ROAD REPAIR AND ACCOUNTABILITY ACT OF 2017 PROJECT BASELINE AGREEMENT Route-27 - Overlay Asphalt Concrete (07-32290)

SHOPP-P-2122-02B Resolution

(will be completed by CTC)

FUNDING PROGRAM 1.

Active Transportation Program

Local Partnership Program (Competitive)

- Solutions for Congested Corridors Program
- State Highway Operation and Protection Program

Trade Corridor Enhancement Program

PARTIES AND DATE 2.

2.1 This Project Baseline Agreement (Agreement) for the Route-27 – Overlay Asphalt Concrete (07-32290),

October 13, 2021 effective on. (will be completed by CTC), is made by and between the California Transportation Commission (Commission), the California Department of Transportation (Caltrans), the Project Applicant,

Caltrans , and the Implementing Agency, Caltrans

, sometimes collectively referred to as the "Parties".

RECITAL 3.

- 3.2 Whereas at its May 13, 2020 meeting the Commission approved the State Highway Operation and Protection Program, and included in this program of projects the Route-27 - Overlay Asphalt Concrete (07-32290), the parties are entering into this Project Baseline Agreement to document the project cost, schedule, scope and benefits, as detailed on the Project Programming Reguest Form attached hereto as Exhibit A and the Project Report attached hereto as Exhibit B, as the baseline for project monitoring by the Commission.
- 3.3 The undersigned Project Applicant certifies that the funding sources cited are committed and expected to be available; the estimated costs represent full project funding; and the scope and description of benefits is the best estimate possible.

4. **GENERAL PROVISIONS**

The Project Applicant, Implementing Agency, and Caltrans agree to abide by the following provisions:

- To meet the requirements of the Road Repair and Accountability Act of 2017 (Senate Bill [SB] 1, Chapter 5, Statutes of 2017) which 4.1 provides the first significant, stable, and on-going increase in state transportation funding in more than two decades.
- 4.2 To adhere, as applicable, to the provisions of the Commission:

	Resolution	Insert Number	"Adoption of Program of Projects for the Active Transportation Program", dated
	Resolution	Insert Number	"Adoption of Program of Projects for the Local Partnership Program", dated
	Resolution	Insert Number	"Adoption of Program of Projects for the Solutions for Congested Corridors Program", dated
\boxtimes	Resolution	G-20-40, "Adopti	on of Program of Projects for the State Highway Operation and Protection Program", dated May 13, 2020
	Resolution	Insert Number	"Adoption of Program of Projects for the Trade Corridor Enhancement Program", dated

- 4.3 All signatories agree to adhere to the Commission's State Highway Operation and Protection Program, Guidelines. Any conflict between the programs will be resolved at the discretion of the Commission.
- 4.4 All signatories agree to adhere to the Commission's SB 1 Accountability and Transparency Guidelines and policies, and program and project amendment processes.
- 4.5 Caltrans agrees to secure funds for any additional costs of the project.
- 4.6 Caltrans agrees to report on a quarterly basis; after July 2019, reports will be on a semi-annual basis on the progress made toward the implementation of the project, including scope, cost, schedule, outcomes, and anticipated benefits.
- 4.7 Caltrans agrees to prepare program progress reports on a quarterly basis; after July 2019, reports will be on a semi-annual basis and include information appropriate to assess the current state of the overall program and the current status of each project identified in the program report.
- 4.8 Caltrans agrees to submit a timely Completion Report and Final Delivery Report as specified in the Commission's SB 1 Accountability and Transparency Guidelines.
- 4.9 All signatories agree to maintain and make available to the Commission and/or its designated representative, all work related documents, including without limitation engineering, financial and other data, and methodologies and assumptions used in the determination of project benefits during the course of the project, and retain those records for four years from the date of the final closeout of the project. Financial records will be maintained in accordance with Generally Accepted Accounting Principles.
- 4.10 The Transportation Inspector General of the Independent Office of Audits and Investigations has the right to audit the project records, including technical and financial data, of the Department of Transportation, the Project Applicant, the Implementing Agency, and any consultant or sub-consultants at any time during the course of the project and for four years from the date of the final closeout of the project, therefore all project records shall be maintained and made available at the time of request. Audits will be conducted in accordance with Generally Accepted Government Auditing Standards.

5. SPECIFIC PROVISIONS AND CONDITIONS

5.1 <u>Project Schedule and Cost</u> See Project Programming Request Form, attached as <u>Exhibit A</u>.

5.2 Project Scope

See Project Report or equivalent, attached as <u>Exhibit B</u>. At a minimum, the attachment shall include the cover page, evidence of approval, executive summary, and a link to or electronic copy of the full document.

5.3 Other Project Specific Provisions and Conditions

Attachments:

Exhibit A:Project Programming Request FormExhibit B:Project Report

SIGNATURE PAGE TO PROJECT BASELINE AGREEMENT

Route 27 Overlay Asphalt Concrete (07-32290)

Resolution

SHOPP-P-2122-02B

David H Mirsancy 08/19/2021 David H. Miraaney Date Project Manager **Project Applicant** Mamar 08/20/2021 Kelly Lamare Date Chief, Office of Program Management Implementing Agency Robert So 08/20/2021 FOR Tony Tavares Date **District Director** California Department of Transportation 9.24.21 Toks Omishakin Date Director California Department of Transportation theh C 10/25/21 Mitchell Weiss Date **Executive Director**

California Transportation Commission

Baseline agreement information was extracted from Caltrans' project data systems. Project description, funding and performance measures are from CTIPS. Project delivery milestones are from PRSM. All information is current and accurate.

BASELINE AGF	REEMENT							Date:	08/09/21	08:31:46 AN	
District	E	Α	Project	ID	PPNO			Projec	oject Manager		
07	07 32290 0716000059		059	5007		MIRAANEY, DAVID H					
County	County Route		Begin Postmile	End Postmile	Implementing			nting Aç	jency		
LA	2	7	0.0	18.6	PA&ED Ca			altrans			
					PS&E			С	altrans		
					Right of V	Vay		С	altrans		
					Construct	tion		С	altrans		
Project Nicknaı	me										
Overlay AC											
Location/Descr	iption										
and upgrade cur		meet Am	ericans with [Disabilities A	Act (ADA) st	andards. (G13 Conting	jency)			
Assembly:	r	, 45, 50	Sena	ito:	26, 27		Congressi	onal		30, 33	
PERFORMANC		· · ·	Sella	ite.	20, 27		Congressi			50, 55	
			ary Asset	Good	Fair	Poor	New	Total		Units	
Existing Co	ndition		vement	0.4	60.5			60.9	La	ne-miles	
Programmed (Pa	vement	60.9				60.9	La	ne-miles	
Project Milesto	ne			<u> </u>					Actual	Planned	
Project Approva	l and Enviro	nmental	Document Mi	lestone					07/30/21		
									0.70072.		
	ertification M	ilestone								04/18/22	
Right of Way Ce Ready to List for			stone							04/18/22 05/01/22	
Right of Way Ce	Advertisem	nent Miles									
Right of Way Ce Ready to List for Begin Construct	Advertisem	nent Miles le (Appro	ve Contract)							05/01/22	
Right of Way Ce Ready to List for	Advertisem	nent Miles le (Appro unts are	ve Contract)							05/01/22	
Right of Way Ce Ready to List for Begin Construct FUNDING (Allo Component	Advertisem ion Mileston cated amou	nent Miles le (Appro unts are s ear	ve Contract) shaded)							05/01/22	
Right of Way Ce Ready to List for Begin Construct FUNDING (Allow Component PA&ED	Advertisem ion Mileston cated amou Fiscal Yo	nent Miles le (Appro unts are s ear	ve Contract) shaded) SHOPP							05/01/22 11/17/22 Total	
Right of Way Ce Ready to List for Begin Construct FUNDING (Allow Component PA&ED PS&E	Advertisem ion Mileston cated amou Fiscal Yo 18/19	nent Miles le (Appro unts are s ear	ve Contract) shaded) SHOPP 1,593							05/01/22 11/17/22 Total 1,593	
Right of Way Ce Ready to List for Begin Construct FUNDING (Allor Component PA&ED PS&E RW Support	Advertiserr ion Mileston cated amou Fiscal Yo 18/19 20/21	ent Miles e (Appro ints are s ear	xe Contract) shaded) SHOPP 1,593 4,205							05/01/22 11/17/22 Total 1,593 4,205	
Right of Way Ce Ready to List for Begin Construct FUNDING (Allow Component PA&ED PS&E RW Support Const Support	Advertisem ion Mileston cated amou Fiscal Yo 18/19 20/21 20/21	e (Appro unts are s ear	ve Contract) shaded) SHOPP 1,593 4,205 389							05/01/22 11/17/22 Total 1,593 4,205 389	
Right of Way Ce Ready to List for Begin Construct FUNDING (Allo	Advertiserr ion Mileston cated amou Fiscal Yo 18/19 20/21 20/21 21/22	ent Miles e (Appro ints are s ear	ve Contract) shaded) SHOPP 1,593 4,205 389 5,540							05/01/22 11/17/22 Total 1,593 4,205 389 5,540	

STATE OF CALIFORNIA • DEPARTMENT OF TRANSPORTATION

07-LA-27 PM 0.0/18.6 322901 -0716000059-5007 20.XX.201.121 July 2021

Project Report

On Route	LA-27
From	Pacific Coast Highway- Route 1 (PM 0.0)
То	Near Devonshire Street, (PM 18.6)

I have reviewed the right-of-way information contained in this report and the right-of-way data sheet attached hereto, and find the data to be complete, current and accurate:

Edward Francis, Deputy District Director, Right of Way

APPROVAL RECOMMENDED:

David A Minsoney

David H. Miraaney, Project Manager

APPROVED:

07/30/2021

Jerrel Kam, Deputy District Director, Division of Design


DATE

This capital preventive maintenance project report has been prepared under the direction of the following registered civil engineer. The registered civil engineer attests to the technical information contained herein and the engineering data upon which recommendations, conclusions, and decisions are based.


Nguyen Hua

REGISTERED CIVIL ENGINEER

07/28/2021



1



Vicinity Map

TABLE OF CONTENTS

1.	INTRODUCTION	. 1
2.	RECOMMENDATION	. 1
3.	BACKGROUND	. 1
4.	PURPOSE AND NEED	. 2
5.	ALTERNATIVES	. 4
6.	CONSIDERATIONS REQUIRING DISCUSSION	. 5
7.	OTHER CONSIDERATIONS AS APPROPRIATE	. 6
8.	FUNDING, PROGRAMMING AND ESTIMATE	. 7
9.	DELIVERY SCHEDULE	. 8
10.	RISKS	. 8
11.	EXTERNAL AGENCY COORDINATION	. 8
12.	PROJECT REVIEWS	. 9
13.	PROJECT PERSONNEL	. 9
14.	ATTACHMENTS	. 9

1. INTRODUCTION

This project is in Los Angeles County, on State Route 27 (SR-27), from Pacific Coast Highway (PM 0.0) to Devonshire Street (PM 18.6). The project proposes to cold plane and overlay the existing asphalt pavement, upgrade the existing curb ramps to meet the requirements of the Americans with Disabilities Act (ADA) standards, construct concrete pads at transit bus stops, upgrade the existing Metal Beam Guard Railing (MBGR) with Midwest Guardrail System (MGS), relocate signals and replace loop detectors due to the proposed improvements, and replace damaged curb and gutters.

Project Limits	07 – LA – 27 PM 0.0/18.6				
	Current Cost	Escalated Cost			
	Estimate:	Estimate:			
Capital Outlay Support	\$12.3	11 million			
Conital Outlaw Construction	(FY2019/20)	(FY2021/22)			
Capital Outlay Construction	\$32.14 million	\$35.55 million			
Conital Outlay Pight of Way	(FY 2017/18)	(FY 2021/22)			
Capital Outlay Right-of-Way	\$1.36 million	\$1.93 million			
Funding Source	SHOPP (Paven	nent Preservation-			
	20.20.201.121)				
Funding Year	FY 2021/22				
Type of Facility	2 to 6 lane Convention	onal Highway			
SHOPP Project Output	Total Lane-Mile: 61				
Environmental Determination	Categorial Exemption/Categorial Exclusion				
or Document					
Legal Description	In Los Angeles County on Topanga Canyon				
	from Route 1 to Devonshire Street				
Project Development Category	5				

Additional information on this project is summarized in the table below:

2. RECOMMENDATION

It is recommended that this Project Report (PR) be approved and that the project proceed to Plans, Specification and Estimate (PS&E) phase of the project.

3. BACKGROUND

The existing pavement has Type B alligator cracking. The last overlay done on this segment of highway was in 1969, 2009, and 2010 for various highway segments with a pavement life of 10 years. Therefore, the pavement needs to be rehabilitated.

There are more than 200 curb ramps that do not meet the latest American Disability Act (ADA) requirements.

4. PURPOSE AND NEED

Purpose:

The purpose of this project is to extend the life of the asphalt pavement, improve ride quality and address the complete street requirements.

Need:

Based on the Pavement Condition Report, there is a need to cold plane and overlay the existing pavement to avoid further deterioration and to improve the ride quality. The Complete Street elements such as ADA ramps, push buttons, signals and bus pads are needed to be upgraded.

Facility Location	Minimum Curve Radius	Throu	ıgh Traff	ic Lanes	Paved Shoulder Width		Median Width	Additional Paved Width for Bicycle Lane or Other
(Post Mile Limits)	Radius (ft)	Number of Lanes	Lane Width (ft)	Type (Flexible, Rigid, or Composite)	Left (ft)	Right (ft)	(ft)	(ft)
*0.0-11.06	110	2	12 and vary	AC	2-10 vary	2-10 vary	0	0
11.06-12.10	300	4	12	AC	4	4	0	0
12.10-18.62	850	6	12 and vary	AC	2	2	12	0

4A. Roadway Geometric Information

*Note-This portion was designated as scenic by the California State Legislature pursuant to Division 1-Chapter 2-Article 2.5-Section 260, which is primarily to protect the social economic values of the natural scenic beauty of California.

Condition of Existing Facility:

1) Traveled Way Data (2015 PAVEMENT DATA)

 PMS Category (1-29)
 10
 Priority Classification (.1-.4)
 0.31

 International Roughness Index (IRI)
 Average 183.3

*Rigid Pavement: *Flexible Pavement: * From latest PMS-Pavement Condition Inventory Survey Data.

3rd Stage Cracking % <u>N/A</u> Alligator B Cracking <u>Average 6.23%</u>

Faulting	N/A	Patching %	0
6		U	

Joint Spalls	N/A	Rutting	Yes	
Pumping	N/A	Bleeding	None	
Corner Breaks %	N/A	Raveling	None	

Locations(s) of subsurface or ponded surface-water problem: N/A

2) Pedestrian Facility Data

Facility Type and Location(s)	Meets ADA Standards (Yes or No for each listed location)	If Facility does not meet ADA Standards, what feature(s) are not ADA compliant? (List features per location)	 Status of Each Noncompliant Location Use the following statements, as appropriate: Will be corrected as part of this project; Will not be corrected to full standard. An Exception to Accessibility Design Standards has been approved.
Curb Ramps See list on Attachment C	No	Slope, width of landing	Will be corrected as part of this project; See Attachment C

Structures Information

Within the project limits, there are 7 structures as shown in the table below. No work is proposed on these structures.

PM	Bridge Number	Location
2.02	53-0143	Topanga Creek
4.20	53-0144	Topanga Creek
6.56	53-0407	Garapito Creek
12.43	53-1064	SR 101/SR-27 Separation
13.93	53-0455	Calabasas Creek
14.27	53-0720	Bell Creek
17.01	53-1832	Santa Susana Creek

This project is not in conflict with the 2012-2035 Regional Transportation Plan (RTP) nor the approved Route 27 Transportation Concept Report (TCR). The City of Los Angeles Department of Transportation (LADOT) had reviewed this CAPM PR and indicated that there are no issues or conflicts with the LADOT plans and operations. The projects listed in the table below are planned within the CAPM PR limits. Their schedule and scope are not in conflict with this project.

EA	Scope	PM Location	Ready to List	Contract Acceptance
27810	Drainage system restoration	2.3/4.0	02/25	04/26
31760	Widening of SR-27 and signal modifications	12.27/15.04	02/20	10/21
30490	Installation of Best Management Practice (BMP) devices -Trash TMDL	0/9.3	06/19	1/21

5. ALTERNATIVES

This project has only one alternative which is described below.

CAPM strategy:

- 1. Overlay all lanes, median and shoulders with 0.15 foot of Rubberized Hot Mix Asphalt Gap-Graded (RHMA-G) and 0.10 foot of Hot Mix Asphalt Type A (HMA Type A) for the segment between PM 0.0 and 4.6.
- 2. Cold plane and overlay all lanes, median and shoulders with 0.15 foot of Rubberized Hot Mix Asphalt Gap-Graded (RHMA-G) and 0.10 foot of Hot Mix Asphalt Type A (HMA Type A) for the segment between PM 4.6 and 18.6.

Additional Work

The project limits from the programming document were expanded to include work between postmiles 4.67/10.11. All work is within the scope of work as approved by the "CAPM Project Report to Request Programming in the 2018 SHOPP" dated 06/01/17, it includes:

- All existing curb ramps and crosswalks at intersections with pedestrian facilities that are either without curb ramps or with non-standard curb ramps will be upgraded to current Americans with Disabilities Act (ADA) standards.
- Relocate traffic signal due to ADA curb ramp modifications and add pedestrian push buttons at ADA curb ramp locations.
- All existing MBGR will be upgraded to MGS within the project limits.
- Two Maintenance Vehicle Pullouts (MVP) will be constructed at PM 0.826 and PM 1.52.
- Replace damaged curb and gutters as needed.
- Portland Cement Concrete bus pads will be provided at transit bus stops to mitigate against AC pavement rutting and shoving.
- Existing drainage inlets grates will be upgraded with bicycle friendly grates as needed.
- Traffic striping and loop detectors will be replaced within paving limits.

Rejected Alternatives: The do nothing alternative is not recommended since the pavement will continue to deteriorate.

6. CONSIDERATIONS REQUIRING DISCUSSION

6A. Hazardous Waste

A full evaluation of potential hazardous waste or contamination issues will be addressed during the PS&E phase of the project. Based on historical information from prior projects within the project vicinity, the following issues may be encountered:

- a. Removal of yellow stripping
- b. Minor Aerially Deposited Lead (ADL) from MBGR posts excavation. See Attachment B.

All materials removed from the job site shall become property of the contractor and disposed of in compliance with Local, State and Federal regulations governing the materials.

6B. Value Analysis

Value Analysis will be completed during the PS&E phrase.

6C. Resource Conservation

The obliterated asphalt concrete may be used in the aggregate base of the new pavement sections. The remainder will become the property of the contractor.

Existing MBGRs and crash cushions will be offered and salvaged if needed to Division of Maintenance.

6D. Right-of-Way Issues

There is no R/W acquisition in this project. The escalated cost for potholing and utility relocation is \$1,927,913 according to right-of-way data sheet. Utilities impacted by the ADA Curb modifications are identified in Attachment D.

6E. Environmental Compliance

The environmental document level is a Categorical Exemption/Categorical Exclusion (CE/CE) per CEQA and NEPA guidelines (see attachment C).

6F. Air Quality Conformity

According to the Environmental Document (CE), this project is deemed classified and is exempt from the requirements to determine conformity.

6G. Title VI Considerations

The proposed project is not expected to negatively affect the low mobility and minority groups.

6H. Noise Abatement Decision Report

The proposed project does not generate additional noise from traffic, and therefore, noise abatement is not a concern.

7. OTHER CONSIDERATIONS AS APPROPRIATE

Public Hearing Process

An CE/CE does not require a Public Hearing.

Route Matters

This project does not require any freeway agreements, new connections, route adoptions, or relinquishments.

Permits

Any city permits required for the construction of curb ramps or traffic signals will be acquired prior to construction.

Cooperative Agreements

No cooperative agreements have been identified for this project.

Other Agreements

No other agreements have been identified for this project.

Transportation Management Plan

A Transportation Management Plan was approved on January 13, 2020 and will consist of the following elements:

- a. Brochures and Mailers
- b. Telephone Hotline
- c. Internet
- d. Changeable Message Signs (Portable)

Stage Construction

Stage construction work will not be needed for this project. All work will be done with typical shoulder and lane closures and all in one phase.

Accommodation of Oversize Loads

Studies for accommodation of oversize loads are not applicable to non-freeway projects.

Graffiti Control

All the elements/components of this projects are not susceptible to graffiti control.

Asset Management

See Attachment H – Performance Output.

Complete Streets

This project proposes to upgrade 235 ADA curb ramps within the project limits. It will also install pedestrian push buttons on locations where this feature is missing.

8. FUNDING, PROGRAMMING AND ESTIMATE

Funding

It has been determined that this project is eligible for Federal-aid funding.

Programming

The proposed program year is 2021/2022. The escalated capital outlay costs for the project is \$37.48 million including R/W cost (Project Estimate see Section 9 and ROW Estimate see Attachment F). Capital outlay support and project cost distributions are provided in the following table:

Fund Source SHOPP		Fiscal Year Estimate							Current Estimate (Escalated)
20.XX.201.121	Prior	20/21	21/22	22/23	23/24	24/25	Future	Programmed Total	At PAED Total
Component			•	In tho	usands	of doll	lars (\$1,	000)	
PA&ED Support	1,593							1,593	1,593
PS&E Support		4,405						4,405	4,405
Right-of-Way Support		576						576	576
Construction Support			5,540					5,540	5,540
Right-of-Way			499					499	1,928
Construction			35,550					35,550	35,550
Total	1,593	4,981	41,589					48,163	49,592

Capital Outlay Support and Project Cost Estimates

9. DELIVERY SCHEDULE

Project Milestones	Milestone Date (Month/Day/ Year)	Milestone Designation (Target/Actual)	
PROGRAM PROJECT	M015	04/26/18	Actual
BEGIN ENVIRONMENTAL	M020	09/28/18	Actual
PA & ED	M200	07/30/21	Target
PRE-60% PS&E		09/01/21	Target
60% QUALITY REVIEW	M313	10/15/21	Target
PRE-95% PS&E		10/20/21	Target
95% PS&E QUALITY REVIEW	M315	12/10/21	Target
PS&E TO DOE	M377	01/20/22	Target
PROJECT PS&E	M380	02/15/22	Target
RIGHT OF WAY CERTIFICATION	M410	03/03/22	Target
READY TO LIST	M460	03/17/22	Target
FUND ALLOCATION	M470	05/13/22	Target
HEADQUARTERS ADVERTISE	M480	06/20/22	Target
AWARD	M495	09/15/22	Target
APPROVE CONTRACT	M500	11/17/22	Target
CONTRACT ACCEPTANCE	M600	11/17/25	Target
END PROJECT	M800	05/17/27	Target

10. RISKS

Refer to attachment G for the list of project Risk Register.

11. EXTERNAL AGENCY COORDINATION

Federal Highway Administration (FHWA)

FHWA has not identified this project for Risk-Based Project Involvement (RBPI).

FHWA review is not needed since it has been delegated as part of the Stewardship Agreement.

This project is an Assigned Project in accordance with the current FHWA and Department of Transportation (Caltrans) Joint Stewardship and Oversight Agreement.

12. PROJECT REVIEWS

Design Manager	Refugio Dominguez	Date 07/22/2021
Program Advisor	MD Musa	Date 07/22/2021
Asset Manager	Roger Yoh	Date 07/22/2021

13. PROJECT PERSONNEL


Name	Title	Phone number
Nguyen Hua	Project Engineer, Design C	(213) 269-1009
Refugio Dominguez	Design Manager, Design C	(213) 269-1762
David Miraaney	Project Manager	(213) 760-6800
Eduado Aguilar	Senior Environmental Planner	(213) 326-1092
Sunny Liem	Storm Water Coordinator	(213) 269-1713

14. ATTACHMENTS

- A. Location and Vicinity Map
- B. Hazardous Waste Assessment
- C. Environmental Document
- D. Right of Way Data Sheet
- E. Storm Water Data Report Cover Sheet
- F. Project Estimate
- G. Risk Register
- H. Performance Output
- I. TMP Data Sheet

ATTACHMENT "A" LOCATION AND VICINITY MAP

LOCATION AND VICINITY MAP



ATTACHMENT "B"

HAZARDOUS WASTE ASSESSMENT

Memorandum

To: REFUGION DOMINGUEZ SENIOR TRANSPORTATION ENGINEER OFFICE OF DESIGN C

Attn: NGUYEN HUA

From: PENNY NAKASHIMA, P.G. Senior Engineering Geologist Hazardous Waste Branch – North Region Office of Environmental Engineering (OEE)

Subject: REVISED HAZARDOUS WASTE ASSESSMENT (PR)

This is in response to your memo dated December 27, 2019, requesting for a revised Hazardous Waste Assessment (HWA) for the above-referenced project. The Office of Design C is presently working on Project Report phase for the Capital Preventive Maintenance (CAPM) project on Route 27. Based on additional funding for the project and community demands, the project limits for EA 322900 have added a segment from PM 4.7 to 10.1. Therefore, the new project limits are from PM 0.0 to 18.6 for continuous CAPM project on Route 27. The purpose of this project is to preserve and extend the life of the existing pavement and improve ride quality. The Major scope of works are as follows:

- 1) Cold plane and overlay 0.20' RHMA-G on all mainline lanes and shoulders.
- 2) Existing curb ramps and crosswalks at intersections with pedestrian facilities that are either without curb ramps or with curb ramps, which do not meet current standards per Design Information Bulletin 82 will be upgraded to current Americans with Disabilities Act (ADA) standards.
- 3) Relocate traffic signal due to ADA Curb modifications and add pedestrian push button at ADA curb ramp locations. Refer to attachment C for signals proposed improvements.
- 4) All existing MBGR will be upgraded to MGS within the project limits.
- 5) Two Maintenance Vehicle Pullouts (MVP) will be constructed at PM 0.826 and PM 1.52,
- 6) Replace damaged curb and gutters as needed.
- 7) Portland Cement Concrete bus pads will be provided at transit bus stops to mitigate against AC pavement rutting and shoving.
- 8) Existing drainage inlets grates will be upgraded with bicycle friendly grates as needed.
- 9) Traffic striping and loop detectors will be replaced within paving limits.
- 10) Digout and replace failed pavements where Alligator B cracking is significant as estimated from the Pavement Condition Survey Report.

ADL concern in unpaved surfaces

Major excavation

The project includes the construction of two MVPs. Based on the previous Site Investigation (SI) report (Task Order No. 07-207001-3Y, 1-01, PM 0.0/11.1, dated December 19, 2003, prepared

"Provide a safe, sustainable, integrated and efficient transportation system to enhance California's economy and livability"

Making Conservation a California Way of Life.

Date: January 17, 2020

 File:
 LA-27

 PM:
 0.0/18.6

 EA:
 07-334-322900

 EFIS:
 0716000059

REFUGION DOMINGUEZ HWA-PR January 17, 2020 Page 2 of 4

by GEOCON), within the project limit, the Total lead concentrations are expected to range from 5.5 mg/kg to 790 mg/kg and soluble lead concentrations (WET citric) range from 1.2 mg/L to 28 mg/L. The soil tested within the project limits was hazardous, because soluble lead concentration was greater than 5 mg/L STLC. Because soil will be excess and disposed, a site investigation will be needed. Once we receive a request to conduct an ADL site investigation (SI) from Design, we will proceed with the SI to determine the actual concentration of lead in soil so that provisions can be made for handling and disposal of the contaminated soils per the Department of Toxic Substances Control (DTSC) Soil Management Agreement with Caltrans. The SI requires four months to complete. For estimating purpose, please consider the top 1 foot of excavated soil in the unpaved areas within 30 feet from the edge of traveled way to be non-RCRA (California) hazardous waste (Type Z-2), per State of California Regulations, with disposal at a California-permitted Class I landfill facility. Please refer to the latest Contract Cost Database (<u>http://sv08web/contractcost/</u>) for the funds that need to be allocated for the removal and disposal of contaminated soil and the lump sum cost of the Contractor's Lead Compliance Plan.

Minor excavation

Removal of guardrail and upgrade some of the curb ramps will be performed in unpaved areas, involving nominal soil excavation, and reuse of all excavated soil at the same location. Based on the Site Investigation (SI) report (Task Order No. 07-207001-3Y, 1-01, PM 0.0/11.1, dated December 19, 2003, prepared by GEOCON), within the project limit, Total lead concentrations ranged from 5.5 mg/kg to 790 mg/kg. Soluble lead concentrations (WET citric) ranged from 1.2 mg/L to 28 mg/L. A lead compliance plan (LCP) will be required for workers health and safety. Please find attached the standard special provisions (SSP 14-11.09) for dealing with minimal disturbance of material containing hazardous waste concentrations of ADL soil for your PS&E package. Please refer to the latest Contract Cost Database (http://sv08web/contractcost/) for the funds that need to be allocated for the lump sum cost of the Contractor's LCP.

Lead and Chromium in Yellow and White Traffic Stripes

Yellow traffic stripes have both lead and chromium in concentrations that exceed threshold levels established by the California Health and Safety Code and Title 22 of the California Code of regulations. The waste generated by the removal of yellow thermoplastic and yellow paint stripes requires disposal at a Class I facility. Please refer to the latest Contract Cost Database (http://sv08web/contractcost/) for the most current estimate for the funds that need to be allocated for the removal and disposal cost of traffic stripes and the lump sum cost of the Contractor's Lead Compliance Plan. During PS&E phase and upon receiving a request for hazardous waste assessment, we will provide appropriate special provisions.

Residue from removing white traffic stripes by itself will not contain hazardous levels of lead.

REFUGION DOMINGUEZ HWA-PR January 17, 2020 Page 3 of 4

However, Lead Compliance Plan (LCP) is required as per Cal-OSHA Title 8 requirements. For cost estimate, for removal of white traffic stripes, please refer to the latest Contract Cost Database (<u>http://sv08web/contractcost/</u>). During PS&E phase and upon receiving a request for hazardous waste assessment, we will provide appropriate special provisions.

Lead and Chromium in Yellow Traffic Stripes

Cold Plane and overlay work will include yellow paint traffic stripes. When the quantity, the volume of AC and the length of the yellow traffic stripe, are available a calculation will be made to determine the total lead and chromium in the removed material. The Contractor shall prepare a project specific Lead Compliance Plan (LCP) to prevent or minimize worker exposure to lead while handling removed yellow and white paint residue. Please refer to the latest Contract Cost Database (http://sv08web/contractcost/) for the funds that need to be allocated for the lump sum cost of the Contractor's LCP. During PS&E phase and upon receiving a request for hazardous waste assessment, we will provide appropriate special provisions.

Treated Wood Waste

The project involves the removal of metal beam guardrail (MBGR) with wood posts. The wood used for the posts are treated with chemical preservatives. Arsenic, chromium, copper, and pentachloro-phenol are among the chemicals added to preserve wood. Once these wood poles are removed and become waste, they are considered as treated wood waste (TWW). TWW is non-RCRA California hazardous waste and the handling, storage, transportation, and disposal are subject to California hazardous waste regulations. During PS&E phase and upon receiving a request for hazardous waste assessment, we will provide appropriate special provisions for handling, storing, transporting, and disposing of TWW. Please refer to the latest Contract Cost Database (http://sv08web/contractcost/) and allocate appropriate funds for disposal of TWW and the Board of Equalization (BOE) fee. Possible asbestos shims on MBGR, need survey.

Electrical Items

There is a potential for exposure of hazardous materials, polychlorinated biphenyl (PCB), associated with the existing electrical components requiring removal. Florescent and/or mercury lamps, ballast and transformer may contain PCB. Therefore, prior to starting construction, the contractor shall inspect the existing electrical components to determine if any hazardous materials are present. All electrical equipment requiring disposal shall be packaged and transported to an appropriate permitted disposal facility. Upon receiving a request for hazardous waste assessment, we will provide appropriate non-standard special provisions for PS&E package.

Asbestos Containing Material (ACM)

Asbestos containing material (ACM) may be encountered during removal of existing metal beam guard railing. The shim between the metal railing and wood block have been found to contain


"Provide a safe, sustainable, integrated and efficient transportation system to enhance California's economy and livability" REFUGION DOMINGUEZ HWA-PR January 17, 2020 Page 4 of 4

asbestos. We will need an asbestos survey to identify ACM. Depending on the survey results we will provide you the appropriate special provision.

This Hazardous Waste Assessment is applicable to the scope of work described above. Any change in the scope of work will require a Hazardous Waste Re-Assessment. If you have any questions or need additional information, please contact me at (213) 897-0670, <u>Penny.Nakashima@dot.ca.gov</u> or contact Saba Tesfayohannes of my staff at (213) 897-8592, <u>Saba.Tesfayohannes@dot.ca.gov</u>.

"Provide a safe, sustainable, integrated and efficient transportation system to enhance California's economy and livability"

ATTACHMENT "C" ENVIRONMENTAL DOCUMENT



Project Information

Project Name (if applicable): LA-27 Roadway Rehabilitation/Safety Improvement Project DIST-CO-RTE: 07-LA-027 PM/PM: EA: 07-32290 / E-FIS 0716000059

0.0/18.6 Federal-Aid Project Number: CE No. 202105009.

Project Description

Caltrans proposes a corridor roadway rehabilitation and safety improvement project on State Route 27 (Topanga Canyon Boulevard) in the City of Los Angeles, in the communities of Topanga (Topanga State Park), Woodland Hills, Warner Center, Canoga Park, and Chatsworth, from post mile 0.0 (Pacific Coast Highway) to post mile 18.6 (Devonshire Street), Los Angeles County. The scope of work includes rubberized pavement overlay from post mile 0.0 to 10.1, cold plane/overlay of pavement from post mile 10.1 to 18.6, replacement of all loop detectors from post mile 10.1 to 18.6, replacement of 235 curb ramps for ADA compliance and the associated relocation of 45 signal poles to accommodate the ADA improvements (post miles 10.1 to 18.5), upgrade of 71 existing Metal Beam Guardrails (MBGR) to Midwest Guardrail System (MGS) [post miles 0.5 to 10.3], and construction of 2 Maintenance Vehicle Pullouts (MVPs) at post miles 0.826 and 1.52 (northbound). Upgrade of MBGR to MGS within the area of Topanga State Park and the community of Topanga shall be painted a color suitable to the scenic highway designation of the area. Reference the continuation sheet starting on Page 3 of this environmental document for additional details/locations of components in scope of work, and reference/adhere to the special provisions that follow (starting on Page 12) as the proposed undertaking exists within environmentally sensitive areas.

Caltrans CEQA Determination (Check one)

□ Not Applicable – Caltrans is not the CEQA Lead Agency

□ Not Applicable – Caltrans has prepared an IS or EIR under CEQA

Based on an examination of this proposal and supporting information, the project is:

□ Exempt by Statute. (PRC 21080[b]; 14 CCR 15260 et seq.)

Categorically Exempt. Class 1(c). (PRC 21084; 14 CCR 15300 et seq.)

oxtimes No exceptions apply that would bar the use of a categorical exemption (PRC 21084 and 14 CCR 15300.2). See the SER Chapter 34 for exceptions.

Covered by the Common Sense Exemption. This project does not fall within an exempt class, but it can be seen with certainty that there is no possibility that the activity may have a significant effect on the environment (14 CCR 15061[b][3].)

Senior Environmental Planner or Environmental Branch Chief

Eduardo Aguilar, SEP

Print Name

Signature

05/19/2021

Date

Project Manager

David H Minaamey

David Miraaney, PM

Print Name

Signature

May 19, 2021 Date



Caltrans NEPA Determination (Check one)

Not Applicable

Caltrans has determined that this project has no significant impacts on the environment as defined by NEPA, and that there are no unusual circumstances as described in 23 CFR 771.117(b). See SER Chapter 30 for unusual circumstances. As such, the project is categorically excluded from the requirements to prepare an EA or EIS under NEPA and is included under the following: 23 USC 326: Caltrans has been assigned, and hereby certifies that it has carried out the responsibility to make this determination pursuant to 23 USC 326 and the Memorandum of Understanding dated April 18, 2019, executed between FHWA and Caltrans. Caltrans has determined that the project is a Categorical Exclusion under:

23 CFR 771.117(c): activity (c)(26)

□ 23 CFR 771.117(d): activity (d)(Enter activity number)

Activity Enter activity number listed in Appendix A of the MOU between FHWA and Caltrans

□ 23 USC 327: Based on an examination of this proposal and supporting information, Caltrans has determined that the project is a Categorical Exclusion under 23 USC 327. The environmental review, consultation, and any other actions required by applicable Federal environmental laws for this project are being, or have been, carried out by Caltrans pursuant to 23 USC 327 and the Memorandum of Understanding dated December 23, 2016 and executed by FHWA and Caltrans.

Senior Environmental Planner or Environmental Branch Chief

Eduardo Aguilar, SEP

Print Name

Signature

05/19/2021 Date

Project Manager

May 19, 2021

Date

Print Name

David Miraaney, PM

Date of Categorical Exclusion Checklist completion (if applicable): 5/18/2021 Date of Environmental Commitment Record or equivalent: 5/18/2021

Briefly list environmental commitments on continuation sheet if needed (i.e., not necessary if included on an attached ECR). Reference additional information, as appropriate (e.g., additional studies and design conditions).

Signature



CONTINUATION SHEET

Scope of Work Covered by This Environmental Document and Subsequent Changes in Scope of Work Subject to Re-Evaluation/Revalidation. This CEQA/NEPA Categorical Exclusion/Categorical Exemption Environmental Document is valid only for the following scope of work as finalized via memorandum on March 24, 2020. <u>Any changes to the scope of work as follows</u> <u>may require re-evaluation/revalidation:</u>

- Pavement overlay of existing pavement from post mile 0.0 to 10.1 with 0.10' HMA Type A asphalt (lower layer), and 0.15' rubberized asphalt (upper layer)
- Cold plane and overlay of existing pavement from post mile 10.1 to 18.6 with 0.10' HMA Type A asphalt (lower layer), and 0.15' rubberized asphalt (upper layer)
- Replacement of all loop detectors from post miles 10.1 to 18.6
- ADA replacement of 235 curb ramps
- Relocate 45 signal poles to accommodate ADA curb ramp replacement
- Upgrade 71 existing Metal Beam Guard Rails (MBGR) with Midwest Guardrail System (MGS)
- Construct 2 Maintenance Vehicle Pullouts (MVPs) at post mile 0.826 post mile 1.52 (northbound). The estimated size of the MVPs at both locations is 12 feet (width) by 85 feet (length), within existing shoulder and Caltrans right-of-way
- Replace 49 bus stop pads

ADA Curb Ramp Upgrade Locations Covered by This Environmental Document. The estimated width of ADA curb ramps is 5 feet by 15 feet maximum. Exact dimensions to be determined during the next project phase. The list of locations of ADA curb ramp upgrade follow:

Location No.	Post Mile	Cross Street	Corner/Direction (N, S, E, W)	Remarks
1	10.111	Woodland Crest Drive	SE	Curb ramp does not lead to anywhere
2	u	u	NE	
3	10.761	Cazanne Avenue	SE	
4	u	u	NE	
5	11.060	Mulholland Drive	SW	
6	"	u	SE	
7	u	u	NW	
8	u	u	NE	
9	11.101	Mulholland Way	SW	
10	u	u	NW	
11	11.171	De LaLux Avenue and	SE	
		Cardenas Avenue		
12	u	u	NE	
13	11.221	Alizondo Drive	SW	
14	u	u	NW	
15	11.291	Independencia Street	SW	
16	u	u	NW	
17	11.361	Ybarra Road	SE	
18	u	u	NW	
19	u	u	NE	
20	11.360	Buenaventura Street	SW	
21	u	u	SE	
22	u	u	NW	
23	u	u	NE	
24	11.420	Viscanio Road	SW	
25	u	u	SE	
26	u	u	NW	
27	u	u	NE	
28	11.470	Dumetz Road	SW	
29	u	u	SE	



Location	Post	Cross Street	Corner/Direction (N, Remarks
No.	Mile		S, E, W)
30	u	u	NW
31	u	u	NE
32	11.531	Providencia Street	SW
33	u	u	SE
34	u	u	NW
35	"	u	NE
36	11.571	San Miguel Street	SW
37	u	u	SE
38	u	u	NW
39	"	u	NE
40	11.641	De la Osa Street	SW
41	"	u	SE
42	"	u	NW
43	"	"	NE
44	11.701	Velicata	SW
45	"	"	SE
46	"	u	NW
47	"	u	NE
48	11.761	Lopez	SW
49	"	u	SE
50	11.761	Lopez	NW
51	u	u	NE
52	11.811	Celes	SW
53	u	u	SE
54	u	u	NW
55	u	u	NE
56	11.871	Martinez	SW
57	u	"	SE
58	"	"	NW
59	u	"	NE
60	11.931 "	Galvez Street	SW
61	<i>u</i>	<i>u</i>	SE
62	<i>u</i>	<i>u</i>	NW
63			NE
64	11.991 "	De la Guerra Street	SW
65	"	<i>u</i>	SE
66	<i>"</i>	" "	NW
67			NE
68	12.051 "	Crespi Street	SW
69			NW
70	12.101	Avenue San Luis	SW
71	 		SE
72	"		NW
73			NE
74	12.161 "	Del Valle Street	SW
75			NW
76	12.211 "	Costanso Street	SW
77	 		SE
78	"	<i>u</i>	NW
79			NE



Location	Post Mile	Cross Street	Corner/Direction (N, Remarks
No.	10.070		S, E, W)
80	12.276	Ventura Boulevard	SW
81 82	"	"	SE
83	u	u	NW NE
84	12.361	Clarendon	SW
85	"	"	SE
86	"	u	NW
87	"	"	NE
88	12.471	SB SR-27/Onramp to SB US-101	SW
89	u	"	NW
90	12.471	NB SR-27/Onramp to SB US-101	SE
91	u	u	NE
92	12.401	NB US-101 Offramp to SB SR-27	SW
93	u	u	NW
94	12.401	NB US-101 Offramp to NB SR-27	SE
95	u	u	NE
96	12.521	Burbank Boulevard	SW
97	u	u	SE
98	u	"	NW
99	12.521	Burbank Boulevard	NE
100	12.681	Collins Street	SW
101	"	"	NW
102	12.741	Marylee Street	SE
103			NW
104 105	12.811	Topanga Canyon	NE SW
	"	Place	
106			NW
107	12.881	Califa Street	SE
108 109		Oxnard Street	NE
109	13.021	"	SWSE
110	u	"	NW
112	u	"	NE
113	13.151	Calvert Street	SW
114	u	u	SE
115	u	"	NW
116	u	u	NE
117	13.271	Erwin Street	SW
118	"	u	SE (1 of 2)
119	u	u	SE (2 of 2)
120	<i>u</i> <i>u</i>	<i>u</i> <i>u</i>	NW
121	<i>u</i>	<i>u</i> <i>u</i>	NE (1 of 2)
122			NE (2 of 2)
123 124	13.551	Victory Boulevard	SW
124	"	<i>u</i>	SE (1 of 2) SE (2 of 2)
125	u	"	NW
120			1444



Location	Post Mile	Cross Street	Corner/Direction (N, Remarks
No.	"	u	S, E, W)
127			NE
128 129	13.711	Topanga Place	
129	13.841	Kittridge Street	SW
130	13.841 "	Kittridge Street	SW SE
131	u	u	NW
132	u	u	NE
133	14.050	Vanowen Street	SW
135	"	"	SE
136	"	"	NW
137	"	u	NE
138	14.161	Bassett Street	SW
139	u	"	SE
140	u	"	NW
141	u	u	NE
142	14.231	Schoolcraft Street	NW
143	u	u	SW
144	14.291	Hart Street	SE
145	u	u	NE
146	14.411	Gault Street	SW
147	u	u	SE
148	14.411	Gault Street	NW
149	u	"	NE
150	14.550	Sherman Way	SW
151	"	и	SE
152	"	"	NW
153	"	"	NE
154	14.601	Cantlay Street	SW
155			NW
156	14.651	Wyandotte Street	SW
<u>157</u> 158	"	"	SENW
158	"	u	NE
160	14.731	Leadwell Street	SW
161	"	"	NW
162	14.791	Valerio	SW
163	"	"	SE
164	"	u	NW
165	u	u	NE
166	14.851	Runnymede Street	SW
167	"	"	NW
168	14.911	Cohasset Street	SW
169	u	u	SE
170	u	u	NW
171	"	"	NE
172	14.981	Covello Street	SW
173	"	u	NW
174	15.041	Saticoy Street	SW
175	"	и	SE
176	"	u	NW
177	"	u	NE
178	15.361	Elkwood Street	SW



Location	Post Mile	Cross Street	Corner/Direction (N, Remarks
No.			S, E, W)
179	u	u	NW
180	15.541	Strathern Street	SW
181	u	u	SE
182	u	u	NW
183	u	u	NE
184	15.651	Lamark Street	SE
185	u	u	NE
186	15.830	Roascoe Boulevard	SW
187	"	u	NE
188	u	"	NW
189	"	"	NE
190	15.911 (79 ft.)	Schoenborn Street	SW
191			SE
192	u	<i>u</i>	NW
193	<i>u</i>	<i>u</i>	NW
194			NE
195	16.141	Chase Street	SW
196	"	"	SE
197	16.141	Chase Street	NW
198			NE
199	16.471	Parthenia Street	SW
200	<i>u</i>	" "	SE
201	<i>u</i> <i>u</i>	" "	SE
202	"	" "	SE
203	" "	" "	NW
204	<i>u</i>	" "	NE
205		 	NE
206			NE
207			NW
208			NE
209 210	16.701	Gresham Street	SW NW
210	17.007	Nordoff Street	SW
211	"	"	SE
212	u	u	NW
213	u	"	NE
215	17.261	Prairie Street/Hanna	SW
215	17.201	Avenue	5
216	"	<i>«</i>	SE
217	и	u	NW
218	и	u	NE
219	17.521	Plummer Street	SW
220	"	"	SE
221	u	u	NW
222	"	u	NE
223	17.871	Marilla Street	SE
224	"	<i>u</i>	NE
225	u	u	NW
226	18.131	Lassen Street	SW
227	"	<i>u</i>	SE
228	u	u	NW
-			



Location No.	Post Mile	Cross Street	Corner/Direction (N, S, E, W)	Remarks
229	u	u	NE	
230	18.381	Mayall Street and	SW	
		Dupont Street		
231	u	u	SE	
232	u	u	NW	
233	u	u	NE	
234	18.501	Craggy View Street	SE	
235	u	u	NE	

Signal Pole Relocations Covered by This Environmental Document

Location	Post Mile	Corner/Direction
No.	1 OSt White	contery birection
1	11.060	SW corner at Mulholland Drive
2	12.361	SW corner at Clarendo Street
3	"	NE corner at Clarendo Street
4	12.521	NW corner at Burbank Boulevard
5	"	SE corner at Burbank Boulevard (1 of 2)
6	"	SE corner at Burbank Boulevard (2 of 2)
7	13.021	SW corner at Oxnard Street (1 of 2)
8	"	SW corner at Oxnard Street (2 of 2)
9	"	NW corner at Oxnard Street
10	"	NE corner at Oxnard Street
11	13.271	SW corner at Erwin Street
12	"	NW corner at Erwin Street
13	13.551	NW corner at Victory Boulevard
14	13.841	SW corner at Kittridge Street
15	"	NW corner at Kittridge Street
16	14.161	SW corner at Bassett Street
17	"	NW corner at Bassett Street
18	14.550	NW corner at Sherman Way
19	"	NE corner at Sherman Way
20	"	SE corner at Sherman Way (1 of 2)
21	"	SE corner at Sherman Way (2 of 2)
22	14.791	SW corner at Valerio Street (1 of 2)
23	u	SW corner at Valerio Street (2 of 2)
24	u	NW corner at Valerio Street
25	"	NE corner at Valerio Street (1 of 2)
26	"	NE corner at Valerio Street (2 of 2)
27	u	SE corner at Valerio Street
28	15.041	SW corner at Saticoy Street
29	u	NW corner at Saticoy Street
30	"	NE corner at Saticoy Street
31	"	SE corner at Saticoy Street (1 of 2)
	"	SE corner at Saticoy Street (2 of 2)
32		
32 33	15.830	SW corner at Roscoe Boulevard
	15.830 "	
33	" 15.911	SW corner at Roscoe Boulevard
33 34	"	SW corner at Roscoe Boulevard NE corner at Roscoe Boulevard
33 34 35	" 15.911	SW corner at Roscoe Boulevard NE corner at Roscoe Boulevard NE corner at Schoenborn Street (1 of 2)



Signal Pole Relocations Covered by This Environmental Document (continued)

Location No.	Post Mile	Corner/Direction
39	u	NE corner at Chase Street
40	u	SE corner at Chase Street
41	17.007	SW corner at Nordhoff Street (1 of 2)
42	u	SW corner at Nordhoff Street (2 of 2)
43	u	NW corner at Nordhoff Street
44	u	SE corner at Nordhoff Street
45	18.131	SW corner at Lassen Street
46	u	NW corner at Lassen Street
47	"	SE corner at Lassen Street

MBGR to MBGS Upgrade Locations Covered by This Environmental Document

Location No.	Post Mile	Length (ft)	Direction	Cross-Street
1	0.527/0.560	220	Northbound	
2	0.737/0.817	379	Southbound	
3	0.972/1.141	600	Southbound	
4	1.356/1.490	700	Southbound	
5	1.917/2.008	493	Southbound	
6	2.103/2.815	3882	Northbound	
7	2.821/2.936	540	Southbound	
8	2.863/2.934	215	Southbound	
9	2.999/3.026	147	Northbound	
10	3.041/3.049	84	Northbound	
11	3.070/3.314	1238	Northbound	
12	3.266/3.312	225	Southbound	
13	3.340/3.390	273	Southbound	
14	3.406/3.454	553	Northbound	
15	3.461/3.454	553	Northbound	
16	3.672/3.726	285	Northbound	
17	3.780/3.821	228	Northbound	
18	3.867/3.916	306	Northbound	
19	4.097/4.197	200	Northbound	
20	4.308		SW Corner	Old Topanga Canyon Road
21	4.308		NW Corner	Old Topanga Canyon Road
22	4.671		Southbound	Entrada Road
23	4.800		NW Corner	Greenleaf Canyon
				Road
24	4.911		SW Corner	Circle Trail
25	4.911		NW Corner	Circle Trail
26	4.946		Southbound	Noah Creek Trail
27	5.089		Northbound	Highvale Trail
28	5.226		Southbound	Private Driveway
29	5.355		Southbound	
30	5.440		Northbound	
31	5.768		Southbound	
32	5.848		Southbound	
33	5.895		Southbound	Hillside Drive
34	6.037		Southbound	Oakwood Drive
35	6.090		Northbound	



MBGR to MBGS Upgrade Locations Covered by This Environmental Document (continued)

36 6.146 Southbound 37 6.203 Southbound 38 6.380 Southbound 39 6.441 Southbound 40 6.527 Northbound 41 6.627 Southbound 42 6.640 Southbound 43 6.696 Southbound 44 6.737 Southbound 45 6.785 Southbound 46 6.832 Southbound 47 6.893 Southbound 48 6.953 Southbound 49 7.101 Southbound 50 7.243 Southbound 51 7.435 Southbound 52 7.493 Southbound 54 7.647 Southbound 55 7.745 Northbound 57 7.947 Southbound 58 8.243 Northbound 59 8.296 Northbound 60 8.316	Location No.	Post Mile	Length (ft)	Direction	Cross-Street
38 6.380 Southbound 39 6.441 Southbound 40 6.527 Northbound Cheney Drive 41 6.627 Southbound Arteique Road 42 6.640 Southbound Arteique Road 43 6.696 Southbound Arteique Road 44 6.737 Southbound 44 45 6.785 Southbound 45 46 6.832 Southbound 48 47 6.893 Southbound 48 48 6.953 Southbound 50 7.101 Southbound 51 7.435 50 7.243 Southbound 52 51 7.493 Southbound 52 52 7.493 Southbound 54 54 7.647 Southbound 55 57 7.947 Southbound 54 58 8.243 Northbound Summit Valey/Edmund D.	36	6.146		Southbound	
39 6.441 Southbound 40 6.527 Northbound Cheney Drive 41 6.627 Southbound Arteique Road 42 6.640 Southbound 43 43 6.696 Southbound 44 43 6.737 Southbound 44 45 6.785 Southbound 44 46 6.832 Southbound 44 47 6.893 Southbound 48 48 6.953 Southbound 49 49 7.101 Southbound 50 50 7.243 Southbound 51 51 7.435 Southbound 53 52 7.493 Southbound 54 54 7.647 Southbound 55 55 7.745 Northbound Summit 58 8.243 Northbound Summit 59 8.296 Northbound 63 60 8.316	37	6.203		Southbound	
40 6.527 Northbound Cheney Drive 41 6.627 Southbound Arteique Road 42 6.640 Southbound 44 43 6.696 Southbound 44 44 6.737 Southbound 44 45 6.785 Southbound 46 46 6.832 Southbound 47 48 6.953 Southbound 48 49 7.101 Southbound 50 50 7.243 Southbound 51 51 7.435 Southbound 740 52 7.493 Southbound 740 53 7.607 Southbound 55 57 7.45 Northbound Private Driveway 56 7.866 Southbound Southound 57 7.947 Southbound Southound 58 8.243 Northbound Southound 60 8.316 Southbound Edelman Park <th>38</th> <td>6.380</td> <td></td> <td>Southbound</td> <td></td>	38	6.380		Southbound	
41 6.627 Southbound Arteique Road 42 6.640 Southbound 43 6.696 Southbound 44 6.737 Southbound 45 6.785 Southbound 46 6.832 Southbound 47 6.893 Southbound 48 6.953 Southbound 49 7.101 Southbound 50 7.243 Southbound 51 7.435 Southbound 52 7.493 Southbound 53 7.607 Southbound 54 7.647 Southbound 55 7.745 Northbound 56 7.866 Southbound 57 7.947 Southbound 58 8.243 Northbound 59 8.296 Northbound 61 8.604 Northbound 62 8.677 Southbound 63 8.939 Southbound 64	39	6.441		Southbound	
42 6.640 Southbound 43 6.696 Southbound 44 6.737 Southbound 45 6.785 Southbound 46 6.832 Southbound 47 6.893 Southbound 48 6.953 Southbound 49 7.101 Southbound 50 7.243 Southbound 50 7.243 Southbound 51 7.435 Southbound 52 7.493 Southbound 54 7.647 Southbound 54 7.647 Southbound 55 7.745 Northbound 56 7.866 Southbound 57 7.947 Southbound 58 8.243 Northbound 60 8.316 Southbound 61 8.604 Northbound 62 8.677 Southbound 63 8.939 Southbound 64 8.969	40	6.527		Northbound	Cheney Drive
43 6.696 Southbound 44 6.737 Southbound 45 6.785 Southbound 46 6.832 Southbound 47 6.893 Southbound 48 6.953 Southbound 49 7.101 Southbound 50 7.243 Southbound 51 7.435 Southbound 52 7.493 Southbound 53 7.607 Southbound 54 7.647 Southbound 55 7.745 Northbound 56 7.866 Southbound 57 7.947 Southbound 58 8.243 Northbound 59 8.296 Northbound 60 8.316 Southbound 61 8.604 Northbound 62 8.677 Southbound 63 8.939 Southbound 64 8.969 Southbound 65 8.997	41	6.627		Southbound	Arteique Road
44 6.737 Southbound 45 6.785 Southbound 46 6.832 Southbound 47 6.893 Southbound 48 6.953 Southbound 49 7.101 Southbound 50 7.243 Southbound 51 7.435 Southbound 52 7.493 Southbound 53 7.607 Southbound 54 7.647 Southbound 55 7.745 Northbound 56 7.866 Southbound 57 7.947 Southbound 58 8.243 Northbound 59 8.296 Northbound 60 8.316 Southbound 61 8.604 Northbound 62 8.677 Southbound 63 8.939 Southbound 64 8.969 Southbound 65 8.997 Southbound 66 9.218	42	6.640		Southbound	
45 6.785 Southbound 46 6.832 Southbound 47 6.893 Southbound 48 6.953 Southbound 49 7.101 Southbound 50 7.243 Southbound 51 7.435 Southbound 52 7.493 Southbound 54 7.607 Southbound 55 7.745 Northbound 55 7.745 Northbound 56 7.866 Southbound 57 7.947 Southbound 58 8.243 Northbound 59 8.296 Northbound 60 8.316 Southbound 61 8.604 Northbound 62 8.677 Southbound 63 8.939 Southbound 64 8.969 Southbound 65 8.997 Southbound 66 9.218 Northbound 67 9.739	43	6.696		Southbound	
46 6.832 Southbound 47 6.893 Southbound 48 6.953 Southbound 49 7.101 Southbound 50 7.243 Southbound 51 7.435 Southbound 52 7.493 Southbound 53 7.607 Southbound 54 7.647 Southbound 55 7.745 Northbound 56 7.866 Southbound 57 7.947 Southbound 58 8.243 Northbound 59 8.296 Northbound 60 8.316 Southbound 61 8.604 Northbound 62 8.677 Southbound 63 8.939 Southbound 64 8.969 Southbound 65 8.977 Southbound 66 9.218 Northbound 67 9.739 Southbound 66 9.218	44	6.737		Southbound	
47 6.893 Southbound 48 6.953 Southbound 49 7.101 Southbound 50 7.243 Southbound 51 7.435 Southbound 52 7.493 Southbound 53 7.607 Southbound 54 7.647 Southbound 55 7.745 Northbound 56 7.866 Southbound 57 7.947 Southbound 58 8.243 Northbound 59 8.296 Northbound 60 8.316 Southbound 61 8.604 Northbound 62 8.677 Southbound 63 8.939 Southbound 64 8.969 Southbound 65 8.997 Southbound 66 9.218 Northbound 67 9.739 Southbound 68 10.008 Northbound 69 0.110/10.258	45	6.785		Southbound	
48 6.953 Southbound 49 7.101 Southbound 50 7.243 Southbound 51 7.435 Southbound 52 7.493 Southbound 53 7.607 Southbound 54 7.647 Southbound 55 7.745 Northbound 56 7.866 Southbound 57 7.947 Southbound 58 8.243 Northbound 59 8.296 Northbound 60 8.316 Southbound 61 8.604 Northbound 62 8.677 Southbound 63 8.939 Southbound 64 8.969 Southbound 65 8.997 Southbound 66 9.218 Northbound 67 9.739 Southbound 68 10.008 Northbound 69 0.110/10.258 782 Southbound Northbound <th>46</th> <td>6.832</td> <td></td> <td>Southbound</td> <td></td>	46	6.832		Southbound	
49 7.101 Southbound 50 7.243 Southbound 51 7.435 Southbound 52 7.493 Southbound 53 7.607 Southbound 54 7.647 Southbound 55 7.745 Northbound 56 7.866 Southbound 57 7.947 Southbound 58 8.243 Northbound 59 8.296 Northbound 60 8.316 Southbound 61 8.604 Northbound 62 8.677 Southbound 63 8.939 Southbound 64 8.969 Southbound 65 8.997 Southbound 66 9.218 Northbound 67 9.739 Southbound 68 10.008 Northbound 69 10.110/10.258 782 Southbound 69 10.110/10.305	47	6.893		Southbound	
50 7.243 Southbound 51 7.435 Southbound 52 7.493 Southbound 53 7.607 Southbound 54 7.647 Southbound 55 7.745 Northbound 56 7.866 Southbound 57 7.947 Southbound 58 8.243 Northbound 59 8.296 Northbound 60 8.316 Southbound 61 8.604 Northbound 62 8.677 Southbound 63 8.939 Southbound 64 8.969 Southbound 65 8.997 Southbound 66 9.218 Northbound 67 9.739 Southbound 68 10.008 Northbound 69 10.110/10.258 782 50 180 Northbound	48	6.953		Southbound	
51 7.435 Southbound 52 7.493 Southbound 53 7.607 Southbound 54 7.647 Southbound 55 7.745 Northbound 56 7.866 Southbound 57 7.947 Southbound 58 8.243 Northbound 59 8.296 Northbound 60 8.316 Southbound 61 8.604 Northbound 62 8.677 Southbound 63 8.939 Southbound 64 8.969 Southbound 65 8.997 Southbound 66 9.218 Northbound 67 9.739 Southbound 68 10.008 Northbound 69 10.110/10.258 782 Southbound 59 10.271/10.305	49	7.101		Southbound	
52 7.493 Southbound Rubicon Road 53 7.607 Southbound 54 7.647 Southbound 54 7.647 Southbound Private Driveway 56 55 7.745 Northbound Private Driveway 56 7.866 Southbound Entrado Drive 58 8.243 Northbound Summit Valley/Edmund D. Edelman Park 59 8.296 Northbound Edelman Park 59 8.296 Northbound Edelman Park 60 8.316 Southbound Edelman Park 61 8.604 Northbound 62 62 8.677 Southbound 63 63 8.939 Southbound 64 64 8.969 Southbound 66 65 8.997 Southbound 66 66 9.218 Northbound 67 67 9.739 Southbound 68 69 10.110/10.258 782 Southbo	50	7.243		Southbound	
53 7.607 Southbound 54 7.647 Southbound 55 7.745 Northbound Private Driveway 56 7.866 Southbound Entrado Drive 57 7.947 Southbound Summit 58 8.243 Northbound Summit 59 8.296 Northbound Edelman Park 59 8.296 Northbound Edelman Park 60 8.316 Southbound Edelman Park 61 8.604 Northbound 63 62 8.677 Southbound 64 63 8.939 Southbound 66 64 8.969 Southbound 66 65 8.997 Southbound 66 66 9.218 Northbound 67 67 9.739 Southbound 68 68 10.008 Northbound 69 69 10.110/10.258 782 Southbound 69	51	7.435		Southbound	
54 7.647 Southbound 55 7.745 Northbound Private Driveway 56 7.866 Southbound Entrado Drive 57 7.947 Southbound Entrado Drive 58 8.243 Northbound Summit Valley/Edmund D. Edelman Park 59 8.296 Northbound Edelman Park 60 8.316 Southbound Edelman Park 61 8.604 Northbound Edelman Park 62 8.677 Southbound Edelman Park 63 8.939 Southbound Edelman Park 64 8.969 Southbound Edelman Park 65 8.997 Southbound Edelman Park 66 9.218 Northbound Edelman Park 67 9.739 Southbound Edelman Park 68 10.008 Northbound Edelman Park 70 10.271/10.305 180 Northbound	52	7.493		Southbound	Rubicon Road
55 7.745 Northbound Private Driveway 56 7.866 Southbound Entrado Drive 57 7.947 Southbound Entrado Drive 58 8.243 Northbound Summit Valley/Edmund D. Edelman Park 59 8.296 Northbound Edelman Park 60 8.316 Southbound Edelman Park 61 8.604 Northbound Edelman Park 62 8.677 Southbound Edelman Park 63 8.939 Southbound Edelman Park 64 8.969 Southbound Edelman Park 65 8.997 Southbound Edelman Park 66 9.218 Northbound Edelman Park 67 9.739 Southbound Edelman Park 68 10.008 Northbound Edelman Park 70 10.271/10.305 180 Northbound	53	7.607		Southbound	
56 7.866 Southbound 57 7.947 Southbound Entrado Drive 58 8.243 Northbound Summit Valley/Edmund D. Edelman Park 59 8.296 Northbound Edelman Park 60 8.316 Southbound Edelman Park 61 8.604 Northbound 62 62 8.677 Southbound 63 63 8.939 Southbound 64 65 8.997 Southbound 66 65 8.997 Southbound 66 67 9.739 Southbound 68 68 10.008 Northbound 69 70 10.271/10.305 180 Northbound	54	7.647		Southbound	
577.947SouthboundEntrado Drive588.243NorthboundSummit Valley/Edmund D. Edelman Park598.296Northbound608.316Southbound618.604Northbound628.677Southbound638.939Southbound648.969Southbound658.997Southbound669.218Northbound679.739Southbound6810.008Northbound7010.271/10.305180Northbound	55	7.745		Northbound	Private Driveway
588.243NorthboundSummit Valley/Edmund D. Edelman Park598.296Northbound608.316Southbound618.604Northbound628.677Southbound638.939Southbound648.969Southbound658.997Southbound669.218Northbound679.739Southbound6810.008Northbound6910.110/10.2587827010.271/10.305180	56	7.866		Southbound	
S9 8.296 Northbound 60 8.316 Southbound 61 8.604 Northbound 62 8.677 Southbound 63 8.939 Southbound 64 8.969 Southbound 65 8.997 Southbound 66 9.218 Northbound 67 9.739 Southbound 68 10.008 Northbound 69 10.110/10.258 782 70 10.271/10.305 180	57	7.947		Southbound	Entrado Drive
59 8.296 Northbound 60 8.316 Southbound 61 8.604 Northbound 62 8.677 Southbound 63 8.939 Southbound 64 8.969 Southbound 65 8.997 Southbound 66 9.218 Northbound 67 9.739 Southbound 68 10.008 Northbound 69 10.110/10.258 782 70 10.271/10.305 180 Northbound	58	8.243		Northbound	Valley/Edmund D.
61 8.604 Northbound 62 8.677 Southbound 63 8.939 Southbound 64 8.969 Southbound 65 8.997 Southbound 66 9.218 Northbound 67 9.739 Southbound 68 10.008 Northbound 69 10.110/10.258 782 Southbound 70 10.271/10.305 180 Northbound	59	8.296		Northbound	
62 8.677 Southbound 63 8.939 Southbound 64 8.969 Southbound 65 8.997 Southbound 66 9.218 Northbound 67 9.739 Southbound 68 10.008 Northbound 69 10.110/10.258 782 Southbound 70 10.271/10.305 180 Northbound	60	8.316		Southbound	
63 8.939 Southbound 64 8.969 Southbound Viewridge Road 65 8.997 Southbound 66 66 9.218 Northbound 67 67 9.739 Southbound 68 68 10.008 Northbound 69 69 10.110/10.258 782 Southbound 70 10.271/10.305 180 Northbound	61	8.604		Northbound	
64 8.969 Southbound Viewridge Road 65 8.997 Southbound 66 9.218 Northbound 66 9.218 Northbound 67 9.739 Southbound 68 10.008 Northbound 69 10.110/10.258 782 Southbound 70 10.271/10.305 180 Northbound 66 9.71 10.271/10.305 180 Northbound 67 </td <th>62</th> <td>8.677</td> <td></td> <td>Southbound</td> <td></td>	62	8.677		Southbound	
65 8.997 Southbound 66 9.218 Northbound 67 9.739 Southbound 68 10.008 Northbound 69 10.110/10.258 782 Southbound 70 10.271/10.305 180 Northbound	63	8.939		Southbound	
66 9.218 Northbound 67 9.739 Southbound 68 10.008 Northbound 69 10.110/10.258 782 Southbound 70 10.271/10.305 180 Northbound	64	8.969		Southbound	Viewridge Road
67 9.739 Southbound 68 10.008 Northbound 69 10.110/10.258 782 Southbound 70 10.271/10.305 180 Northbound	65	8.997		Southbound	
68 10.008 Northbound 69 10.110/10.258 782 Southbound 70 10.271/10.305 180 Northbound	66	9.218		Northbound	
69 10.110/10.258 782 Southbound 70 10.271/10.305 180 Northbound	67	9.739		Southbound	
70 10.271/10.305 180 Northbound	68	10.008		Northbound	
70 10.271/10.305 180 Northbound	69	10.110/10.258	782	Southbound	
71 10.320/10.345 180 Northbound	70	10.271/10.305	180	Northbound	
	71	10.320/10.345	180	Northbound	



Bus Pad Replacement Locations Covered by This Environmental Document

Location No.	Post Mile	Direction (NB/SB)	Intersection
1	11.312	SB	Ybarra
2	11.485	SB	Dumetz Road
3	11.742	SB	Lopez Street
4	11.782	NB	u
5	11.974	SB	De la Guerra Street
6	12.26	SB	Ventura Boulevard
7	12.298	NB	u
8	12.494	SB	Burbank Boulevard
9	12.53	NB	a
10	12.697	SB	Collins Street
11	12.74	SB	Marylee Street
12	12.73	NB	<i>a</i>
13	13.02	SB	Oxnard Street
14	13.002	NB	a
15	12.293	SB	Erwin Street
16	12.272	NB	<i>u</i>
17	13.553	SB	Victory Boulevard
18	13.592	NB	u
19	13.702	SB	Next to America' Tire Store
20	13.746	NB	a a a a a a a a a a a a a a a a a a a
21	13.847	SB	Kittridge Street
22	13.884	NB	
23	14.026	SB	Vanowen Street
24	14.217	SB	Schoolcraft Street
25	14.515	SB	Sherman Way
26	14.563	NB	
27	14.835	SB	Runnymede Street
28	14.871	NB	"
29	15.022	SB	Saticoy Street
30	15.059	NB	
31	15.336	SB	Elkwood Street
32	15.521	SB	Strathem Street
33	15.547	NB	
34	15.803	SB	Roscoe Boulevard
35	15.841	NB	Change Strengt
36 37	16.148	NB SB	Chase Street
37	16.478	NB	Parthenia Street
39	16.505 16.712	SB	Cracham Street
40	16.697	NB	Gresham Street
40	16.982	SB	Nordhoff Street
41 42	17.035	NB	
43	17.26	SB	Prairie Street
44	17.292	NB	
45	18.026	SB	Lassen Street
46	18.305	SB	Mayal Street
47	18.38	SB	Dupont Street
48	18.284	NB	<i>"</i>
49	18.524	SB	Devonshire Street
	10.324	55	



BIOLOGICAL ENVIRONMENT SPECIAL PROVISIONS

Reference Natural Environment Study (Minimal Impacts), April 2020

Subsequent Environmental Reviews at 35%, 65%, 95%, and 100% PS&E. Design shall request additional environmental reviews at 35%, 65%, 95%, and 100% PS&E by submitting the request and any summary of changes to the scope of work since this environmental evaluation by submitting a memorandum and request to Cheryl Henderson, Senior Environmental Planner and Eduardo Aguilar, Senior Environmental Planner at the specified intervals.

Changes in Project Scope of Work Requiring Re-Evaluation/Revalidation. Any changes to the project scope of work as described in this CE/CE environmental document shall be accurately summarized and communicated to the Division of Environmental Planning. These changes may warrant re-evaluation and revalidation prior to environmental certification so that the project is ready-to-list.

Invitation of District Biologist to Pre-Construction Meeting. An invitation shall be submitted to the District Biologist, Celina Oliveri (celina.oliveri@dot.ca.gov) at least two weeks prior to the specified date of the pre-construction meeting for this project.

Avoidance of Habitats/Communities of Concern and Delineation of Environmentally Sensitive Areas (ESAs). Habitats and natural communities of concern will be avoided, such as steelhead critical habitat and southern sycamore/alder riparian woodland, and no work shall take place within the creek. Southern sycamore/alder riparian woodland will be delineated with ESA fencing before construction takes place. ESAs shall be delineated in project plans in coordination with District Biologist, Celina Oliveri (celina.oliveri@dot.ca.gov) and included prior to requesting subsequent environmental reviews at 65%, 95%, and 100% PS&E.

Construction Window for Vegetation Removal and Notification for Pre-Construction Bird Nesting Surveys. It is recommended that all vegetation removal occur outside of bird nesting season which is from February 1 – September 1. Should vegetation need to be removed during this period, the Resident Engineer (RE) shall coordinate with the District Biologist, Celina Oliveri (celina.oliveri@dot.ca.gov), with two weeks notification prior to construction to determine if birds are nesting within the project area. In the event that nesting birds are observed, the RE should pause work until a qualified biologist has determined that fledglings have left the nest. If this is not possible, the RE should coordinate with the District Biologist to minimize the risk of violating the Migratory Bird Treaty Act (MBTA). Most likely, the District Biologist will recommend a buffer of 150 ft. for songbirds and a buffer of 500 ft. for raptors during all phases of Construction. Nesting birds are protected under the MBTA and cannot be impacted by construction activities, including noise and pollution. The District Biologist, Celina Oliveri, must be notified two weeks prior to construction (celina.oliveri@dot.ca.gov), so that preconstruction surveys may be conducted, and exclusionary devices and methods may be discussed, per the following standard specification: 14-6.03 Bird Protection. Construction may proceed within these areas after bird nesting season in order to minimize the risk of violating the Migratory Bird Treaty Act.

Construction Window for Activities with High Noise Levels. Construction activities with high noise levels should be scheduled outside of the bird nesting season (February 1– September 1). If this is not feasible then noise attenuation measures must be in place.

Construction Window for Ground Disturbing/Construction Activities Near/Along Bridges. Ground disturbing activities, and construction activities near or along bridges could impact migratory bird species or bats, therefore it is recommended construction take place outside of the bird nesting season (February 1– September 1).

Restriction of Any Construction Work in Jurisdictional "Waters of the United States" and BMP/Protection Measures. No construction work is authorized within jurisdictional "Waters of the United States," and no equipment is authorized to enter any channel. Additionally, no construction work shall take place during the rainy season. Due to the nature of the project, mitigation measures are not required; however, this project must employ all appropriate Stormwater and Erosion Control Best Management Practices (BMPs) during construction to minimize indirect impact from roadway runoff. Prior to the start of construction all drain inlets and outlets must be protected with BMP's to prevent construction materials and debris from entering drainages. Environmentally Sensitive Area (ESA) fencing will be placed as needed to protect jurisdictional Waters of the United States or Waters of the State. Therefore, this project has very little potential to create water quality impacts. Temporary Construction BMP's will be required such as wind erosion control, sediment tracking control, street sweeping and vacuuming, stabilized construction roadway, spill prevention control, solid waste management, hazardous waste management, sanitary/septic waste management, material delivery and storage, material use, vehicle and equipment cleaning, vehicle and equipment fueling, and vehicle maintenance.



BIOLOGICAL ENVIRONMENT SPECIAL PROVISIONS (continued)

Reference Natural Environment Study (Minimal Impacts), April 2020

Implementation of Stormwater and Erosion Best Management Practices (BMPs). All appropriate storm water and Erosion Best Management Practices will be incorporated into the project PS&E.

Cessation of Construction Work During Rain Events. Construction work shall cease when the chance of rain is more than 30% and is forecasted for the future 72 hours.

Cessation of Construction Work When Encountering Species of Concern. If any species of concern are encountered or observed during construction activities, all work shall immediately cease, and the district biologist, Celina Oliveri (celina.oliveri@dot.ca.gov), shall be immediately notified. Work shall not resume until clearance is given by the district biologist.

Impacts to Native Trees and/or Coastal Sage Scrub. If large native trees or coastal sage scrub species must be impacted, the District Biologist, Celina Oliveri (celina.oliveri@dot.ca.gov), must be notified to determine if the NES needs re-evaluation and if mitigation is required.

Restrictions on Use of Asphalt Grindings Near Any Water Course. No asphalt grindings shall be used within 100 feet of any water course. Water course, for this purpose, is defined as any feature, either natural or man-made, which conveys water during any time of the year.

CULTURAL/ARCHAEOLOGICAL RESOURCES SPECIAL PROVISIONS

Reference Environmentally Sensitive Area (ESA) Action Plan for the LA-27 Corridor Improvement Project, April 2021

Subsequent Environmental Reviews at 35%, 65%, 95%, and 100% PS&E. Design shall request additional environmental reviews at 35%, 65%, 95%, and 100% PS&E by submitting the request and any summary of changes to the scope of work since this environmental evaluation by submitting a memorandum and request to Cheryl Henderson, Senior Environmental Planner and Eduardo Aguilar, Senior Environmental Planner at the specified intervals.

Changes in Project Scope of Work Requiring Re-Evaluation/Revalidation. Any changes to the project scope of work as described in this CE/CE environmental document shall be accurately summarized and communicated to the Division of Environmental Planning. These changes may warrant re-evaluation and revalidation prior to environmental certification so that the project is ready-to-list.

Delineation of Environmentally Sensitive Areas (ESAs)/Archaeologically Sensitive Areas in Project Plans. ESAs for archaeologically sensitive areas shall be delineated in project plans and established during construction in coordination with the Project Archaeologist, Sarah Mattiussi-Gutierrez (sarah.mattiussi-gutierrez@dot.ca.gov) at post mile 4.31 to the west of the SR-27 and Old Topanga Canyon Road intersection within the Project's Area of Direct Impacts (ADI). Additionally, an ESA will be established post mile 4.85/4.9 on the east side of SR-27 within the Project's ADI.

Pre-construction Meeting with Caltrans Resident Engineer and Contractor. The Project Archaeologist, Sarah Mattiussi-Gutierrez (sarah.mattiussi-gutierrez@dot.ca.gov), shall be invited (with at least two weeks' notice) to a pre-construction meeting with the Caltrans Resident Engineer and contractor to discuss ESAs/Archaeologically Sensitive Areas, including access restrictions and maintenance of fencing (or other signage) for protective measures.

Pre-Construction Field Review of ESA Locations by Project Archaeologist. The Resident Engineer will notify Caltrans Archaeologist, Sarah Mattiussi-Gutierrez (sarah.mattiussi-gutierrez@dot.ca.gov) at least three (3) weeks prior to start of construction to allow for a field review of the ESA location and arrangements for monitoring of fence installation or other signage to demarcate the ESA on the ground if feasible. The ESA fencing (or other signage) will be established adjacent to the work sites at the northwest and southwest corners of the Old Topanga Canyon Road and SR-27 intersection where feasible.



CULTURAL/ARCHAEOLOGICAL RESOURCES SPECIAL PROVISIONS (continued)

Reference Environmentally Sensitive Area (ESA) Action Plan for the LA-27 Corridor Improvement Project, April 2021

Installation of ESA Fencing Along Accessible Portions of ESA Boundaries and Access for Monitoring. Temporary orange plastic fencing (or other signage) shall be installed along accessible portions of the ESA boundaries at least one week prior to initiating construction, under the supervision of the RE and/or the Project Archaeologist. Construction/site access shall be granted to the Project Archaeologist to conduct monitoring and photo-documentation throughout project construction to ensure the integrity of the ESA locations.

Governance of Construction Activities by Established ESA Action Plan. All project construction activities shall be governed by the established Environmentally Sensitive Area (ESA) Action Plan for the LA-27 Corridor Improvement Project (April 2021), and the ESA Action Plan shall be included in the Environmental Commitment Record (ECR) and the Resident Engineer (RE) Pending File. The aforementioned ESA Action Plan has been appended to this environmental document.

HAZARDOUS WASTE SPECIAL PROVISIONS

Reference Revised Hazardous Waste Assessment (PR), January 17, 2020

Aerially Deposited Lead (ADL) Concerns in Unpaved Surfaces and Subsequent Site Investigation (SI). For the construction of two (2) Maintenance Vehicle Pullouts (MVPs), total lead concentrations are expected to range from 5.5 mg/kg to 790 mg/kg, and soluble lead concentrations (WET citric) range from 1.2 mg/L to 28 mg/L. Tested soils were deemed hazardous, because soluble lead concentration was greater than 5 mg/L STLC. Because soil will be excess and disposed, a site investigation will be needed. A request must be submitted to conduct an ADL Site Investigation to determine the actual concentration of lead in soil so that provisions can be made for handling and disposal of contaminated soils per the Department of Toxic Substances Control (DTSC). Reference Revised Hazardous Waste Assessment (PR) [January 17, 2020] for additional details.

Lead Compliance Plan (LCP) and Aerially Deposited Lead (ADL) Concerns Regarding Minor Excavation Relating to Removal of Guardrail and Upgrade of Curb Ramps. A Lead Compliance Plan (LCP) will be required for activities relating to minor excavation relating to removal of guardrail and curb ramps. Utilize SSP 14-11.09 for dealing with minimal disturbance of material containing hazardous waste concentrations of ADL soil for PS&E. Reference Revised Hazardous Waste Assessment (PR) [January 17, 2020] for additional details.

Lead and Chromium in Yellow and White Traffic Stripes, Subsequent Site Investigation (SI), and Required Lead Compliance Plan (LCP). Yellow traffic stripes have both lead and chromium in concentrations that exceed threshold levels established by the California Health and Safety Code and Title 22 of the California Code of Regulations. A request must be submitted to conduct an ADL Site Investigation to determine the actual concentration of lead in soil so that provisions can be made for handling and disposal of contaminated soils per the Department of Toxic Substances Control (DTSC). Additionally, a Lead Compliance Plan (LCP) will be required for waste generated by removal of thermoplastic and yellow paint stripes requires disposal at a Class I Facility. The LCP shall also outline provisions to prevent or minimize worker exposer to lead while handling removed yellow and white paint residue. Reference Revised Hazardous Waste Assessment (PR) [January 17, 2020] for additional details.

Handling of Treated Wood Waste (TWW). The proposed project involves removal of Metal Beam Guard Rail (MBGR) with wood posts that have been treated with chemical preservatives. Once wood poles are removed and become waste, they are considered TWW, and its handling, storage, transportation, and disposal are subject to California hazardous waste regulations. A request must be submitted to conduct an additional Hazardous Waste Assessment to determine appropriate special provisions. Reference Revised Hazardous Waste Assessment (PR) [January 17, 2020] for additional details.

Handling of Asbestos Containing Materials (ACM). ACM may be encountered during removal of existing MBGR. A request must be submitted to conduct an asbestos survey to identify ACM, and depending on survey results, the appropriate provisions will be provided.



VISUAL RESOURCES/AESTHETIC SPECIAL PROVISIONS

Reference Visual Impact Analysis Questionnarie, April 3, 2020

Special Paint/Metina for Any Replacement of MBGR/MGS Within Topanga State Park and the Community of Topanga.

Upgrade of MBGR to MGS within the area of Topanga State Park and the community of Topanga shall be painted a color suitable to the scenic highway designation of the area. The paint/metina color and post mile range for special MGS paint/metina shall be determined in coordination with George Olguin, Senior Landscape Architect (george.olguin@dot.ca.gov), and Anthony Baquiran, Associate Environmental Planner (anthony.baquiran@dot.ca.gov) prior to RTL.

ENVIRONMENALLY SENSITIVE AREA ACTION (ESA) PLAN FOR THE LA-27 CORRIDOR IMPROVEMENT PROJECT

LA-27 Post Mile 0.0 to Post Mile 18.6 EA 07-32290 - EFIS 0716000059 Los Angeles County, California

PREPARED BY:

Kourta

Roberta Thomas, Co-Principal Investigator, Prehistoric Archaeology Tiffany Clark, Principal Investigator, Prehistoric Archaeology PaleoWest Archaeology 517 S. Ivy Avenue Monrovia, CA 91016

REVIEWED BY:

Sarah Mattiussi Gutierrez Associate Environmental Planner Co-Principal Investigator (PQS), Prehistoric Archaeology California Department of Transportation, District 7 Environmental Support/Cultural Studies 100 S. Main Street Los Angeles, California 90012

APPROVED BY:

Caprice Harper for

Claudia Harbert Heritage Resources Coordinator California Department of Transportation, District 7 Environmental Support/Cultural Studies 100 S. Main Street Los Angeles, California 90012

April 2021

NADB Data: USGS 7.5' Topanga, CA – T1S, R16W, Sections 6, 7, 18, and Unsectioned Portion and T1N, R16W, Section 31; USGS 7.5' Canoga Park, CA – T1N, R16W, Sections 30, 31, and Unsectioned Portion, T1N, R17W, Section 25 and Unsectioned Portion, T2N, R16W, Unsectioned Portion, and T2N, R17W, Unsectioned Portion; and Oat Mountain T2N, R16W, Unsectioned Portion and T2N, R17W, Unsectioned Portion

Keywords: Los Angeles County, Los Angeles, State Route 27, Topanga Canyon, P-19-000008/CA-LAN-8/H; P-19-004671/CA-LAN-4671H; Multi-component site; Historic-period foundation remnants; Archaeological Survey; 209.5 acres

The environmental review, consultation, and any other actions required by applicable Federal environmental laws for this project are being, or have been carried out by Caltrans pursuant to 23 U.S.C. 327 and the Memorandum of Understanding effective April 18, 2019, and executed by FHWA and Caltrans.

Archaeological and other heritage resources can be damaged or destroyed through uncontrolled public disclosure of information regarding their location. This document contains sensitive information regarding the nature and location of archaeological sites that should not be disclosed to unauthorized persons.

Information regarding the location, character or ownership of a historic resource is exempt from the Freedom of Information Act pursuant to 16 United States Code (U.S.C.) 470w-3 (National Historic Preservation Act), 16 U.S.C. § 470hh (Archaeological Resources Protection Act), and California State Government Code, Section 6254.10.

If any information in this document is to be released for public review, all locational information associated with archaeological resources must be redacted before distribution.

TABLE OF CONTENTS

TABLE OF CONTENTS	L
SECTION 1. SUMMARY OF ESA ACTION PLAN	1
SECTION 2. PROJECT DESCRIPTION	3
SECTION 3. METHODS	5
3.1 Archaeological Monitoring Area	5
SECTION 4. RESPONSIBLE PARTIES	3

APPENDIX

APPENDIX A: ESA and AMA Maps

TABLES

Table 4.1 ESA Action Plan Tasks and Responsible Parties	6
Table 4.2 Responsible Parties and Contact Information as of October 2020	7

SECTION 1. SUMMARY OF ESA ACTION PLAN

The California Department of Transportation (Caltrans) proposes the LA-27 Corridor Improvement Project (Project) (EFIS 0716000059; EA 07-32290) along State Route (SR-) 27 (Topanga Canyon Boulevard) between Post Mile (PM) 0.0 (Pacific Coast Highway) to PM 18.6 (Devonshire Street). The Project lies in the city of Los Angeles and unincorporated areas within Los Angeles County. The proposed improvements include the installation of overlay pavement, loop detector replacement, Americans with Disability Act (ADA) replacement of curb ramps, signal pole relocations, construction of Maintenance Vehicle Pullouts, guard rail upgrades, and bus pad replacements. The Area of Potential Effects Map (APE) for the proposed Project is in Attachment A (Exhibit 3) of the Historic Property Survey Report (HPSR).

The following historic properties will be protected by the designation of an Environmentally Sensitive Area (ESA):

- CA-LAN-8/H (P-19-000008), a multi-component archaeological site previously determined to meet eligibility requirements for listing on the National Register of Historic Places (NRHP) under Criterion D and the California Register of Historical Resources (CRHR) under Criterion 4, located at PM 4.31
- CA-LAN-4671H (P-19-004671), a historic-period archaeological site assumed eligible for listing on the NRHP for the purposes of this Project only, located at PM 4.9

An ESA is being established for the portion of CA-LAN-8/H located at PM 4.31 to the west of the SR-27 and Old Topanga Canyon Road intersection within the Project's Area of Direct Impacts (ADI). Additionally, an ESA will be established for the portion of CA-LAN-4671H located between PM 4.85 and PM 4.9 on the east side of SR-27 within the Project's ADI. A map shown in Appendix A depicts the locations of the ESAs. The ESA boundaries will follow the recorded boundary of each site, and no ground disturbance will be allowed within the area of the ESA.

The following measures are required during each stage of construction for the Project at this location.

Pre-construction:

- The Caltrans Archaeologist will ensure that the boundaries of the ESA are clearly described and illustrated in the Plans, Specifications, and Estimates (PS&E) package.
- This ESA Action Plan will be included in the Environmental Commitment Record (ECR) and the Resident Engineer (RE) Pending File.
- A pre-construction meeting with the Contractor and Caltrans Resident Engineer will be held to discuss the ESA, including access restrictions and maintenance of fencing (or other signage) for protective measures.

The RE will notify Caltrans Archaeologist and Environmental Branch Chief at least three weeks prior to start of construction to allow for a field review of the ESA location and arrangements for monitoring of fence installation or other signage to demarcate the ESA on the ground if feasible. The ESA fencing (or other signage) will be established adjacent to the work sites at the northwest and southwest corners of the Old Topanga Canyon Road and SR-27 intersection where feasible.

• Review ESA location in the field one week prior to start of construction.

During construction:

- Install temporary orange plastic fencing (or other signage) along accessible portions of the ESA boundary for sites CA-LAN-8/H and CA-LAN-4671H at least one week prior to initiating construction, under the supervision of the RE and/or the Caltrans Archaeologist.
- Conduct monitoring and photo-documentation throughout project construction to ensure the integrity of the ESA locations.

Post-construction:

- The Caltrans Environmental Construction-Liaison will notify the Caltrans Archaeologist when construction is complete in the vicinity of the site, so that the temporary fencing (or other signage) can be removed.
- The Caltrans Environmental Construction-Liaison and/or Caltrans Archaeologist will oversee the removal of the fencing (or other signage) from the site.

SECTION 2. PROJECT DESCRIPTION

The Project corridor includes an 18.6-mile-long stretch of SR-27, along with a small portion of Pacific Coast Highway, located within unincorporated Los Angeles County, Topanga State Park, and the city of Los Angeles (see Exhibits 1 and 2 in Attachment A of the HPSR). The southern portion of the Project area intersects is generally suburban and rural in character with more rugged, undeveloped areas within the sections of the Project corridor in the Topanga State Park. The northern portion of the Project area is characterized by suburban and urban with a mix of residential and commercial development. The major geographic features in the area are the Pacific Ocean and Santa Monica Mountains in the south and the Los Angeles River and the San Fernando Valley in the north.

The Project alignment is located within the following USGS 7.5' Maps: Topanga, CA Map (1991) T1S, R16W, Sections 6, 7, 18, and Unsectioned Portion and T1N, R16W, Section 31; USGS 7.5' Canoga Park, CA Map (1952; photorevised 1967) T1N, R16W, Sections 30, 31, and Unsectioned Portion, T1N, R17W, Section 25 and Unsectioned Portion, T2N, R16W, Unsectioned Portion, and T2N, R17W, Unsectioned Portion; and Oat Mountain Map (1952; photorevised 1969) T2N, R16W, Unsectioned Portion, T2N, R17W, Unsectioned Portion, R17W, Unsectioned Portion; and Oat Mountain Map (1952; photorevised 1969) T2N, R16W, Unsectioned Portion, R17W, R17

The proposed LA-27 Corridor Improvement Project includes pavement rehabilitation to comply with the ADA curb ramp upgrades, metal beam guardrail (MBGR) upgrades, construction of maintenance vehicle pullouts (MVPs), relocation of signal poles, and replacement of bus stop pads. Specifically, the work includes:

- Pavement overlay of existing pavement from PM 0.0 to 10.1 with 0.10' HMA type A asphalt (Lower layer) and 0.15' rubberized asphalt (upper layer);
- Cold plane and overlay of existing pavement from PM 10.1 to 18.6 with 0.10' HMA type A asphalt (lower layer);
- Traffic striping and loop detectors will be replaced within paving limits;
- ADA replacement of 235 curb ramps;
- Replacement of damaged curbs and gutters;
- Upgrade 71 existing MBGR with MGS;
- Upgrades to drainage inlet grates;
- Construct 2 MVPs at PM 0.826 (northbound) and PM 1.52 (northbound). The estimated size of the MVPs at both locations is 12 feet (width) by 85 feet (length), within existing shoulder and Caltrans right of way; and
- Replace 49 bus stop pads.

The Area of Potential Effects (APE) that was developed for the Project includes the Area of Direct Impact (ADI), which encompasses all areas of proposed construction activities associated with the installation of the overlay pavement, ADA curb ramps, signal pole relocations, MVP construction, guard rail upgrades, traffic stripping, loop detector, and damaged curb and gutter replacement, drainage inlet grate upgrades, and bus pad replacements. In addition, the ADI includes staging areas and temporary locations of construction sign placements. The entire ADI is located within Caltrans right-of-way.

The APE also encompasses the known boundaries of CA-LAN-8/H (P-19-00008) and CA-LAN-4671H (P-19-004671). CA-LAN-8/H consists of a multi-component site consisting of a prehistoric village and historic trash dump in the community of Topanga. The proposed Project footprint will impact only a limited fraction of the site in the vicinity of PM 4.31. In this area, the proposed Project will upgrade the existing MBGR with MGS at the northwest and southwest corners of the SR-27 and Old Topanga Canyon Road intersection. CA-LAN-4671H consists of historic-era structural remnants, a road, and a cleared graded area, between PM 4.85 and PM 4.9. In this area, the proposed Project will include the installation of pavement overlay of the existing SR-27 roadway. No cold planing or grinding of the existing pavement will take place within the boundary of CA-LAN-4671H as part of the construction activities. As ground disturbance associated with the installation of the pavement overlay would be minimal (less than 4 inches or 10 centimeters) and will not extend into the site boundary, the proposed Project will have no effect on the site.

This ESA Action Plan is prepared as part of a Finding of No Adverse Effect pursuant to the January 2014 *First Amended Programmatic Agreement Among the Federal Highway Administration, the Advisory Council on Historic Preservation, the California State Historic Preservation Officer, and the California Department of Transportation Regarding Compliance with Section 106 of the National Historic Preservation Act, as it Pertains to the Administration of the Federal-Aid Highway Program in California (Section 106 PA) and California Environmental Quality Act (CEQA).*

- CA-LAN-8/H is located on both sides of SR-27. The ESA fencing (or other signage) will be established within the ADI at PM 4.31 at the northwest and southwest corners of the SR-27 and Old Topanga Canyon Road intersection.
- CA-LAN-4671H is located on the east side of SR-27. The ESA fencing (or other signage) will be established within the ADI between PM 4.85 and PM 4.9 along the east side of SR-27 south of the SR-27 and Circle Trail intersection.

SECTION 3. METHODS

This section describes the protocols to be followed for the ESAs established for the Project. The ESAs will be established to prevent inadvertent adverse effects to CA-LAN-8/H and CA-LAN-4671H during Project construction. Additionally, the ESA created for CA-LAN-8/H will be enforced through archaeological and Native American monitoring during Project construction. The ESA for CA-LAN-4671H will be inspected periodically to ensure it is still in place and has not been breached.

An ESA shall be established within the ADI at PM 4.31 to ensure construction-related access will be restricted to the portions of CA-LAN-8/H that contained the proposed work sites at the northwest and southwest corners of the SR-27 and Old Topanga Canyon Road intersection. The ESA will be delineated in the field by the installation of temporary orange fencing or other signage. If ground disturbance breaches the established ESA, construction will be halted until impacts of the breach can be assessed and a course of action approved.

An ESA shall be established within the ADI between PM 4.85 and PM 4.9 to ensure constructionrelated access will be restricted to the existing roadway outside the CA-LAN-4671H boundary south of the SR-27 and Circle Trail intersection. The ESA will be delineated in the field by the installation of temporary orange fencing or other signage. If ground disturbance breaches the established ESA, construction will be halted until impacts of the breach can be assessed and a course of action approved.

The ESA locations will be reviewed in the field one week prior to start of construction. Signs will be placed along the ESA boundaries, where possible, indicating that access is prohibited for construction equipment and personnel.

The ESAs will be established through depiction on the Project plans, by defining it in the PS&E package, and as provided in the Project's RE Pending File. No project-related activities shall occur within the ESA.

A map depicting the locations of the ESAs is found in Appendix A of this ESA Action Plan.

3.1 Archaeological Monitoring Area

Per Caltrans 2018 Standard Specifications Section 14-2.03B (Archaeological Monitoring Area [AMA]), an AMA shall be established within the proposed work locations at the northwest and southwest corners of the SR-27 and Old Topanga Canyon Road intersection within CA-LAN-8/H. An archaeological and Native American monitor will be present for all ground-disturbing activities occurring within the AMA.

A map depicting the location of the AMA is found in Appendix A of this ESA Action Plan.

ATTACHMENT "D" RIGHT OF WAY DATA SHEET

Memorandum

Serious Drought! Help Save Water!

To: Refugio Dominguez , Design Manager Office of Design District 7, Los Angeles Office **Date: 5/14/2021 EA: 32290** Data Sheet ID NO: ds5140 Project ID # 0716000175

From: Dan Murdoch, Office Chief Right of Way Appraisals, and Planning & Management District 7, Los Angeles Office

subject: Current Estimated Right of Way Costs for Project Report

We have completed an estimate of the Right of Way costs for the above referenced project based on information received from Nguyen Hua PE and the following assumptions and limiting conditions apply:

- The mapping did not provide sufficient detail to determine the limits of the right of way required.
- The transportation facilities have not been sufficiently designed, so our estimator could not determine the damages to any of the remainder parcels affected by the project.
- Additional right of way requirements are anticipated, but are not defined due to the preliminary nature of the estimate.
- HIGH RISK: The proposed project schedule does not allow for necessary RW lead time, and therefore a high risk of delivery failure is anticipated. PM has been made aware of the concern. RW is completing the Data Sheet Estimate with the PM's acknowledgment of HIGH RISK

Right of Way Certificate (RWC) lead time will require a minimum of NA after maps to appraisal (MA). Completed Appraisal maps include HMDD, COS, HW Memo, and RE-49. An executed copy of the new freeway agreement if required for the project. When utility relocation is warranted, utility conflict maps will be required. Additionally a minimum of NA will be required after receiving the last revision to the appraisal map. Shorter lead times will require either more right of way resources or an increased number of condemnation suits to be file and present a risk to the RWC project delivery milestone. Due to the passage of Map 21 and the Buy America provision, the Right of Way Certification process will be longer, if Utility Relocation is necessary.

Current Schedule: PRSM

PAED (M 200)	MA (M 224)	RWC (M 410)	RTL (M 460)	CCA (M 600)
7/1/2021	N/A	3/3/2022	3/17/2022	11/17/2025

R/W DATA SHEET

ID NO ds5140

то	Refugio Dominguez
ATTN	Nguyen Hua

SENIOR R/W P&M David Miraaney ROUTE 27

PM_KM 0-18.6 EA 32290 Project ID # ALT
 Date of Data Sheet
 5/14/2021

 Project Description
 CAPM

This cost estimate is valid for the above scoping report only. This is an estimate only and not an appraisal. It may be based on worse case scenarios.

The estimate is subject to change and revision.

The mapping did not provide sufficient nor adequate detail to determine the limits of thr Right of Way required and effects on the improvements.

The transportation facilities have not been sufficiently designed for our estimator to determine the damages to any of the remainder parcels affected by the project.

This cost estimate is pursuant to the following responses supplied by Refugio Dominguez to the Data Sheet Request Form. YES NO Not known at this time

	YES	NO	Not known at this tin
Utilities are depicted on plans	x		
Railroads are depicted on plans		x	
There are Material and/or Disposal Sites Required		x	
Caltrans will do the Right of Way work	x		
There will be a Cooperative Agreement		x	
This is a reimbursable project		x	
There is Hazardous Waste potential		x	

	RW COST ESTIMATE		
	CURRENT VALUE	ESCALATED VALUE	
R/ w acq.(incl.contingency G.w-condemadm.s'tl.)Permits			
Clearance	No Dight	ofMov	
RAP (cont rate.)	No Right	UT Way	
Escrow costs (cont rate.)			
Utility relocation costs	\$1,362,000	\$1,927,913	
Estimate of Reimbursed Appraisal Fee			
Total estimated cost	\$1,362,000	\$1,927,913	
Escalation Rate Rw .07			
Escalation Rate Utilities .08			
Cert.date 3/3/22			

Comment


HIGH RISK: The proposed project schedule does not allow for necessary RW lead time, and therefore a high risk of delivery failure is anticipated. PM has been made aware of the concern. RW is completing the Data Sheet Estimate with the PM's acknowledgment of HIGH RISK



PM_KM 0-18.6

EA ₃₂₂₉₀ ALT

Parcel Count and Py Info



UTILITY INFORMATION

Please See the Utility Conflict Addendum for Complete Utility Information

Are utility easements required? No	Total Current Cost	\$1,362,000
Are Utility agreements required? <u>No</u>	Const. Completion Date	11/17/2025
Utility types , Facilities & Agreements Description:	Utility Escalation Rate	8%
	Total Escalated Cost	\$1,927,913

Data Sheet ID NO: ds5140 ROUTE 27 PM_KM 0-18.6 EA 32290 ALT

RR INFORMATION

	Are RR affected	None	
	Describe affected RR	None, 1/5/21	
	When Branch Line Railroad Facility Be Involved?	s Or Spurs Are Affected ,would Acquisition And Or Payment Of Damages To Businesses More Cost Effective Than Service Contracts ,or Grade Separations Requiring Construction	And Or Industries Served By The on And Maintenance Agreements N/A
	Explain Branch line	s _{N/A}	
	Discuss Types Of A Service Contracts ,c N/A	greements And Rights Required From The Railroads. Are Grade Xing Requiring r Grade Separations Requiring Construction And Maintenance Agreements Involved.	
	RAILROAD COST	PERTAINING TO CONSTRUCTION ACTIVITY	
the RW	/ data sheet, the	lated to project construction activity is a Phase 4 cost (construction e estimated flagging cost is not a RW cost, and is not a part of RW 0 he engineer's estimate for construction the RR flagging estimate i	Capital The estimate is provided

construction activity.

Right of Way Estimate prepared by	Victor Lee	<u>DATE</u> 5/14/21
Railroad Estimate prepared by	Mario Zamorano	5/14/21
Utilities Estimate prepared by	Onyx Smith-Taylor	5/14/21

I have personally reviewed this R/W Data Sheet and all supporting information I certify that the probable highest and best use estimated values and assumptions are reasonable and proper subject to the limiting conditions set forth and I find this Data Sheet complete and current.

This Data Sheet is not to be signed by Chief unless accompanied by final scoping report(PR,PSR,PSSR) for review and/or signature.

chief Jak El 07/21/2021

	EA- 32290 Description	Quantity	\$/Unit	Total Cost
1	Pothole, 1 Du Tel At&t, along NB of LA-27 at pm 8.243 (ea)	2	2000	4000
2	Pothole, 1 Du Tel At&t, along NB of LA-27 at pm 8.296 (ea)	2	2000	4000
3	Pothole, 2 Du Tel At&t, along NB of LA-27 at pm 8.604 (ea)	2	2000	4000
4	Pothole, 2 Du Tel At&t, along NB of LA-27 at pm 9.218 (ea)	2	2000	4000
5	Pothole, 6" Gas SCG, along NB of LA-27 at pm 9.218 (ea)	2	2000	4000
6	Pothole, 9-4" MCD Tel At&t, along NB of LA-27 from pm10.305 to pm	4	2000	8000
7	Pothole, 6" Gas SCG, along NB of LA-27 from pm10.305 to pm	4	2000	8000
8	Pothole, 8" Wtr LADWP, along SB of LA-27 at pm 11.312 - NW of LA	2	2000	4000
9	Pothole, 8" Wtr LADWP, along SB of LA-27 at pm 11.485 - NW of LA	2	2000	4000
10	Pothole, 8" Wtr LADWP, along SB of LA-27 at pm 11.742 - SW of LA	2	2000	4000
11	Pothole, 4" Gas SCG, along NB of LA-27 at pm 11.782 - NE of LA-27	2	2000	4000
12	Pothole, 8" Wtr LADWP, along SB of LA-27 at pm 11.974 - SW of LA	2	2000	4000
13	Pothole, 8" Wtr LADWP, along SB of LA-27 at pm 12.26 - SW of LA	2	2000	4000
14	Pothole, 12" Wtr LADWP, along NB of LA-27 at 12.298 - NE of LA-27	2	2000	4000
15	Pothole, 18 Du Tel At&t, along NB of LA-27 at 12.298 - NE of LA-27	2	2000	4000
16	Pothole, 8 Du Tel AT&T, along NB of LA-27 at 12.298 - NE of LA-27	2	2000	4000
17	Pothole, 8" Wtr LADWP, along SB of LA-27 at pm 12.494 - SW of LA	2	2000	4000
18	Pothole, 20" HP Gas SCG, at SW of LA-27 and Burbank Blvd	2	2000	4000
19	Pothole, 10" HP Gas SCG, SW of LA-27 and Burbank Blvd	2	2000	4000
20	Pothole, 20" HP Gas SCG, at NE of LA-27 and Burbank Blvd	2	2000	4000
21	Pothole, 10" HP Gas SCG, NE of LA-27 and Burbank Blvd	2	2000	4000
22	Pothole, 8 Du Tel AT&T, along NB of LA-27 at 12.53 - NE of LA-27 and	2	2000	4000
23	Pothole, 4" Gas SCG, along NB of LA-27 at 12.53 - NE of LA-27 and	2	2000	4000
24	Pothole, 8" Wtr LADWP, along NB of LA-27 at pm 12.53 - NE of LA-27	2	2000	4000
25	Pothole, 7" Wtr LADWP, along NB of LA-27 at pm 12.53 - NE of LA-27	2	2000	4000
26	Pothole, 8-5" Tel AT&T, along SB of LA-27 at pm 12.697 - NW of LA	2	2000	4000
27	Pothole, 8 Du Tel AT&T, Along NB of LA-27 at pm 12.73 - SE of LA-27	2	2000	4000
28	Pothole, 12" Wtr LADWP, Along NB of LA-27 at pm 12.73 - SE of LA	2	2000	4000
29	Pothole, 12" Wtr LADWP, along NB of LA-27 at pm 13.02 - NE of LA	2	2000	4000
30	Pothole, 21 Du Tel LADWP, along NB of LA-27 at pm 13.02 - NE of LA	2	2000	4000
31	Pothole, 21 Du Tel LADWP, along NB of LA-27 at pm 13.272 - SE of	2	2000	4000
32	Pothole, 12" Wtr LADWP, along NB of LA-27 at pm 13.272 - SE of LA	2	2000	4000
33	Pothole, 12" Wtr LADWP, along NB of LA-27 at pm 13.272 - SE of LA	2	2000	4000
34	Pothole, 6" Gas SCG, along SB of LA-27 at pm 13.293 - NW of LA-27	2	2000	4000
35	Pothole, 23 Du AT&T, along SB of LA-27 at pm 13.293 - NW of LA-27	2	2000	4000

	EA- 32290 Description	Quantity	\$/Unit	Total Cost
36	Pothole, 6" Gas SCG, along SB of LA-27 at pm 13.552 - SW of LA-27	2	2000	4000
37	Pothole, 23 Du AT&T, along SB of LA-27 at pm 13.552 - SW of LA-27	2	2000	4000
38	Pothole, 4 Du AT&T, along SB of LA-27 at pm 13.552 - SW of LA-27	2	2000	4000
39	Pothole, 2 Du AT&T, along SB of LA-27 at pm 13.552 - SW of LA-27	2	2000	4000
40	Pothole, 6-5" & 4-4" Wtr LADWP, at SB of LA-27 and along EB of	2	2000	4000
41	Pothole, 12" Wtr LADWP, along NB of LA-27 at pm 13.592 - NE of LA	2	2000	4000
42	Pothole, 21 Du Tel AT&T, along NB of LA-27 at pm 13.592 - NE of LA	2	2000	4000
43	Pothole, 8 Du Tel AT&T, along NB of LA-27 at pm 13.592 - NE of LA	2	2000	4000
44	Pothole, 23 Du AT&T, along SB of LA-27 at pm 13.702 (ea)	2	2000	4000
45	Pothole, 6" Gas SCG, along SB of LA-27 at pm 13.702 (ea)	2	2000	4000
46	Pothole, 12" Wtr LADWP, along NB of LA-27 at pm 13.746 (ea)	2	2000	4000
47	Pothole, 21 Du Tel AT&T, along NB of LA-27 at pm 13.746 (ea)	2	2000	4000
48	Pothole, 8 Du Tel AT&T, along NB of LA-27 at pm 13.746 (ea)	2	2000	4000
49	Pothole, 23 Du AT&T, along SB of LA-27 at pm 13.847 - SW of LA-27	2	2000	4000
50	Pothole, 6" Gas SCG, along SB of LA-27 at 13.847 - SW of LA-27 and	2	2000	4000
51	Pothole, 4-6" Elect LADWP, along NB of LA-27 at pm 13.884 (ea)	2	2000	4000
52	Pothole, 8 Du Tel AT&T, along NB of LA-27 at pm 13.884 (ea)	2	2000	4000
53	Pothole, 12" Wtr LADWP, along SB of LA-27 at pm 14.026 - SW of LA	2	2000	4000
54	Pothole, 8 Du Tel AT&T, along SB of LA-27 at pm 14.026 - SW of LA	2	2000	4000
55	Pothole, 12" Wtr LADWP, along SB of LA-27 at pm 14.217 - SW of LA	2	2000	4000
56	Pothole, 8 Du Tel AT&T, along SB of LA-27 at pm 14.217 - SW of LA	2	2000	4000
57	Pothole, 12" Wtr LADWP, along SB of LA-27 at pm 14.515 - SW of LA	2	2000	4000
58	Pothole, 20 Du Tel AT&T, along SB of LA-27 at pm 14.515 - SW of LA	2	2000	4000
59	Pothole, 4" Gas SCG, along NB of LA-27 at pm 14.563 - NE of LA-27	2	2000	4000
60	Pothohe, 10 Du Tel AT&T, along NB of LA-27 at pm 14.563 - NE of LA	2	2000	4000
61	Pothole, 12" Wtr LADWP, along SB of LA-27 at pm 14.835 - SW of LA	2	2000	4000
62	Pothole, 20 Du Tel AT&T, along SB of LA-27 at pm 14.835 - SW of LA	2	2000	4000
63	Pothole, 4" Gas SCG, along NB of LA-27 at pm 14.871 (ea)	2	2000	4000
64	Pothole, 8 Du Tel AT&T, along SB of LA-27 at pm 15.022 - SW of LA	2	2000	4000
65	Pothole, 12" Wtr LADWP, along SB of LA-27 at pm 15.022 - SW of LA	2	2000	4000
66	Pothole, Du Tel LADWP, along NB of LA-27 at pm 15.059 - NE of LA	2	2000	4000
67	Pothole, Elect LADWP, along NB of LA-27 at pm 15.059 - NE of LA-27	2	2000	4000
68	Pothole, Gas SCG, along NB of LA-27 at pm 15.059 - NE of LA-27	2	2000	4000
69	Pothole, 12" Wtr LADWP, along SB of LA-27 at pm 15.336 - SW of LA	2	2000	4000
70	Pothole, 6 Du Tel AT&T, along SB of LA-27 at pm 15.336 - SW of LA	2	2000	4000

	EA- 32290 Description	Quantity	\$/Unit	Total Cost
71	Pothole, 2-4" Elect LADWP, crossing LA-27 at pm 15.336 (ea)	2	2000	4000
72	Pothole, 12" Wtr LADWP, along SB of LA-27 at pm 15.521 - SW of LA	2	2000	4000
73	Pothole, 6 Du Tel AT&T, along SB of LA-27 at pm 15.521 - SW of LA	2	2000	4000
74	Pothole, 1" Elect LADWP, along SB of LA-27 at pm 15.521 - SW of LA	2	2000	4000
75	Pothole, 1" Elect LADWP, along NB of LA-27 at pm 15.547 - NE of LA	2	2000	4000
76	Pothole, 4" Gas SCG, along NB of LA-27 at pm 15.547 - NE of LA-27	2	2000	4000
77	Pothole, 12" Wtr LADWP, along SB of LA-27 at pm 15.803 - SW of LA	2	2000	4000
78	Pothole, 6 Du Tel AT&T, along SB of LA-27 at pm 15.803 - SW of LA	2	2000	4000
79	Pothole, 1" Elect LADWP, along SB of LA-27 at pm 15.803 - SW of LA	2	2000	4000
80	Pothole, 4" Gas SCG, along SB of LA-27 at pm 15.803 - SW of LA-27	2	2000	4000
81	Pothole, 8" HP Gas SCG, along EB of Roscoe Blvd at SB of LA-27	2	2000	4000
82	Pothole, 4" Gas SCG, along NB of LA-27 at pm 15.841 - NE of LA-27	2	2000	4000
83	Pothole, 1" Elect LADWP, along NB of LA-27 at pm 15.841 - NE of LA	2	2000	4000
84	Pothole, 8" Wtr LADWP, along NB of LA-27 at pm 16.148 - NE of LA	2	2000	4000
85	Pothole, 4" Gas SCG, along NB of LA-27 at pm 16.148 - NE of LA-27	2	2000	4000
86	Pothole, 9-4" Duct Tel AT&T, along SB of LA-27 at pm 16.478 - NW of	2	2000	4000
87	Pothole, 6" Wtr LADWP, along SB of LA-27 at pm 16.478 - NW of LA	2	2000	4000
88	Pothole, 4" Gas SCG, along SB of LA-27 at pm 16.505 - NE of LA-27	2	2000	4000
89	Pothole, 12" Wtr LADWP, along NB of LA-27 at pm 16.697 (ea)	2	2000	4000
90	Pothole, 4" Gas SCG, along NB of LA-27 at pm 16.697 (ea)	2	2000	4000
91	Pothole, 9-4" Duct Tel AT&T, along SB of LA-27 at pm 16.712 - NW of	2	2000	4000
92	Pothole, 9-4" Duct Tel AT&T, along SB of LA-27 at pm 16.982 - NW of	2	2000	4000
93	Pothole, 8" Wtr LADWP, along SB of LA-27 at pm 16.982 - NW of LA	2	2000	4000
94	Pothole, Elect LADWP, along SB of LA-27 at pm 16.982 - NW of LA	2	2000	4000
95	Pothole, Elect LADWP, along NB of LA-27 at pm 17.035 - NE of LA-27	2	2000	4000
96	Pothole, 12" Wtr LADWP, along NB of LA-27 at pm 17.035 - NE of LA	2	2000	4000
97	Pothole, 12" Wtr LADWP, along SB of LA-27 at pm 17.26 - NW of LA	2	2000	4000
98	Pothole, Elect LADWP, along SB of LA-27 at pm 17.26 - NW of LA-27	2	2000	4000
99	Pothole, 9-4" Du Tel AT&T, along SB of LA-27 at pm 17.26 - NW of LA	2	2000	4000
100	Pothole, 12" Wtr LADWP, along NB of LA-27 at pm 17.292 - NE of LA	2	2000	4000
101	Pothole, Elect LADWP, along NB of LA-27 at pm 17.292 - NE of LA-27	2	2000	4000
102	Pothole, 8" Wtr LADWP, along SB of LA-27 at pm 18.026 - SW of LA	2	2000	4000
103	Pothole, 12-4" Du Tel AT&T, along SB of LA-27 at pm 18.026 - SW of	2	2000	4000
104	Pothole, 8" Wtr LADWP, along NB of LA-27 at pm 18.284 - SE of LA	2	2000	4000
105	Pothole, 4-4" Elect LADWP, along NB of LA-27 at pm 18.284 - SE of	2	2000	4000

	EA- 32290 Description	Quantity	\$/Unit	Total Cost
106	Pothole, 6" Gas SCG, along NB of LA-27 at pm 18.284 - SE of LA-27	2	2000	4000
107	Pothole, 8" Wtr LADWP, along SB of LA-27 at pm 18.38 - NW of LA	2	2000	4000
108	Pothole, 12-4" Du Tel AT&T, along SB of LA-27 at pm 18.38 - NW of	2	2000	4000
109	Pothole, 12-4" Elect LADWP, along SB of LA-27 at pm 18.607 - SW of	2	2000	4000
110	Pothole, 8" Wtr LADWP, along SB of LA-27 at pm 18.607 - SW of LA	2	2000	4000
111	Pothole, 12-4" Du Tel LADWP, along SB of LA-27 at pm 18.607 - SW	2	2000	4000
112	Pothole, 10" Gasoline Shell, crossing LA-27 at SW of LA-27 and	2	2000	4000
113	Pothole, 8" Wtr LADWP, crossing LA-27 at SW of LA-27 and	2	2000	4000
114	Pothole, 12-Cond AT&T, crossing LA-27 at SW of LA-27 and	2	2000	4000
115	Pothole, 6" Wtr LA CO Wtr, along SB of LA-27 at SW of LA-27 and	2	2000	4000
116	Pothole, 6" Du Tel AT&T, along NB of LA-27 at LA-27 and De La Osa	2	2000	4000
117	Pothole, 4" Gas SCG, along NB of LA-27 at LA-27 and De La Osa St	2	2000	4000
118	Pothole, 8" Wtr LADWP, along SB of LA-27 at LA-27 and De La Osa	2	2000	4000
119	Pothole, 2" Gas SCG, cossing LA-27 at LA-27 and De La Osa St	2	2000	4000
120	Pothole, 4" Wte LADWP, cossing LA-27 at LA-27 and De La Osa St	2	2000	4000
121	Pothole, 8" Elect LADWP, along NB of LA-27 at LA-27 and Ventura	3	2000	6000
122	Pothole, 18 Du Tel AT&T, along NB of LA-27 at LA-27 and Ventura	2	2000	4000
123	Pothole, 12 Du Tel AT&T, along NB of LA-27 at LA-27 and Ventura	2	2000	4000
124	Pothole, 4" Gas SCG, along NB of LA-27 at LA-27 and Ventura Blvd	2	2000	4000
125	Pothole, 30 Du Tel AT&T, along EB of Ventura Blvd at LA-27 and	2	2000	4000
126	Pothole, 3" Gas SCG, along EB of Ventura Blvd at LA-27 and Ventura	2	2000	4000
127	Pothole, 16" Wtr LADWP, along EB of Ventura Blvd at LA-27 and	2	2000	4000
128	Pothole, 9 Du Elect, along EB of Ventura Blvd at LA-27 and Ventura	5	2000	10000
129	Pothole, 16" HP Gas SCG, along EB of Ventura Blvd at LA-27 and	4	2000	8000
130	Pothole, 6" Gas SCG, along WB of Ventura Blvd at LA-27 and Ventura	2	2000	4000
131	Pothole, 20 Du Tel AT&T, along WB of Ventura Blvd at LA-27 and	4	2000	8000
132	Pothole, 18 Du Tel AT&T, along NB of LA-27 at LA-27 and Clarendoin	2	2000	4000
133	Pothole, 8 Du Tel AT&T, along NB of LA-27 at LA-27 and Clarendoin	2	2000	4000
134	Pothole, 12" Du Tel AT&T, along NB of LA-27 at LA-27 and Clarendoin	2	2000	4000
135	Pothole, 12" Wtr LADWP, along NB of LA-27 at LA-27 and Clarendoin	2	2000	4000
136	Pothole, 4" Gas SCG, along NB of LA-27 at LA-27 and Clarendoin St	3	2000	6000
137	Pothole, 8" Wtr LADWP, along SB of LA-27 at LA-27 and Clarendoin	2	2000	4000
138	Pothole, 6" Wtr LADWP, along EB of Clarendin St at LA-27 and	2	2000	4000
139	Pothole, 2" Gas SCG, along WB of Clarendin St at LA-27 and	2	2000	4000
140	Pothole, 12" Wtr LADWP, along NB of LA-27 at LA-27 and Burbank	2	2000	4000

	EA- 32290 Description	Quantity	\$/Unit	Total Cost
141	Pothole, 4" Gas SCG, along NB of LA-27 at LA-27 and Burbank Blvd	2	2000	4000
142	Pothole, 18 Du Tel AT&T, along NB of LA-27 at LA-27 and Burbank	4	2000	8000
143	Pothole, 6-4" & 6-5" Elect LADWP, along NB of LA-27 at LA-27 and	4	2000	8000
144	Pothole, 20" HP Gas SCG, along Burbank Blvd at LA-27 and Burbank	4	2000	8000
145	Pothole, 10" HP Gas SCG, along Burbank Blvd at LA-27 and Burbank	4	2000	8000
146	Pothole, 6" Du Tel AT&T, along NB of LA-27 at LA-27 and Martinez St	2	2000	4000
147	Pothole, 4" Gas SCG, along NB of LA-27 at LA-27 and Martinez St	2	2000	4000
148	Pothole, 8" Wtr LADWP, along SB of LA-27 at LA-27 and Martinez St	2	2000	4000
149	Pothole, 2" Gas SCG, cossing LA-27 at LA-27 and Martinez St	2	2000	4000
150	Pothole, 6" Wtr LADWP, cossing LA-27 at LA-27 and Martinez St	2	2000	4000
151	Pothole, 6" Gas SCG, along NB of LA-27 at LA-27 and Erwin St	3	2000	6000
152	Pothole, 12" Wtr LADWP, along NB of LA-27 at LA-27 and Erwin St	2	2000	4000
153	Pothole, 6" Gas SCG, along NB LA-27 at LA-27 and Victory Blvd	2	2000	4000
154	Pothole, 6 Du Tel AT&T, along SB LA-27 at LA-27 and Victory Blvd	2	2000	4000
155	Pothole, 8 Du Tel AT&T, along NB of LA-27 at LA-27 and Kittrige St	2	2000	4000
156	Pothole, 4-6" Elect LADWP, along LA-27 at LA-27 and Kittrige St	6	2000	12000
157	Pothole, 6" Wtr LADWP, along NB of LA-27 at LA-27 and Kittrige St	4	2000	8000
158	Pothole, 6" Gas SCG, along SB of LA-27 at LA-27 and Kittrige St	2	2000	4000
159	Pothole, 6 Du Tel AT&T, along SB of LA-27 at LA-27 and Kittrige St	2	2000	4000
160	Pothole, 2" Gas SCG, cossing LA-27 at LA-27 and School Craft St	2	2000	4000
161	Pothole, 6" Wtr LADWP, along NB LA-27 at LA-27 and School Craft	2	2000	4000
162	Pothole, 4" Gas SCG, along NB of LA-27 at LA-27 and Oxnard St	2	2000	4000
163	Pothole, 12" Wtr LADWP, along NB of LA-27 at LA-27 and Oxnard St	2	2000	4000
164	Pothole, 8-5" Du Tel AT&T, along NB of LA-27 at LA-27 and Oxnard	6	2000	12000
165	Pothole, 6" Gas SCG, along EB of Oxnard St at LA-27 and Oxnard St	4	2000	8000
166	Pothole, 6" Gas SCG, along EB of Sherman St at LA-27 and Sherman	2	2000	4000
167	Pothole, 8" Wtr LADWP, along EB of Sherman St at LA-27 and	2	2000	4000
168	Pothole, 10 Du Tel AT&T, crpssing LA-27 at LA-27 and Sherman St	4	2000	8000
169	Pothole, 12" Wte LADWP, along SB of LA-27 at LA-27 and Valerio St	4	2000	8000
170	Pothole, 20 Du Tel AT&T, along SB of LA-27 at LA-27 and Valerio St	2	2000	4000
171	Pothole, 10 Du Tel AT&T, along NB of LA-27 at LA-27 and Valerio St	2	2000	4000
172	Pothole, 4" Gas SCG, along NB of LA-27 at LA-27 and Valerio St	4	2000	8000
173	Pothole, 6 Du Tel AT&T, along EB of Saticoy St at LA-27 and Saticoy	4	2000	8000
174	Pothole, 6" Wtr LADWP, along EB of Saticoy St at LA-27 and Saticoy	2	2000	4000
175	Pothole, 3" Gas SCG, along WB of Saticoy St at LA-27 and Saticoy St	2	2000	4000

	EA- 32290 Description	Quantity	\$/Unit	Total Cost
176	Pothole, 24" Wtr LADWP, along WB of Saticoy St at LA-27 and	2	2000	4000
177	Pothole, 2-5" and 7-4" Elect LADWP, along WB of Saticoy St at LA-27	2	2000	4000
178	Pothole, 4" Gas SCG, along EB of Strathern St at LA-27 and	2	2000	4000
179	Pothole, 8" Wtr LADWP, along EB of Strathern St at LA-27 and	2	2000	4000
180	Pothole, 6 Du Tel AT&T, at SW of LA-27 and Roscoe Blvd intersection	2	2000	4000
181	Pothole, 4" Gas SCG, cossing LA-27 at LA-27 and Roscoe Blvd	2	2000	4000
182	Pothole, 52" Wtr LADWP, along EB of Roscoe Blvd at LA-27 and	2	2000	4000
183	Pothole, 8" Wtr LADWP, along WB of Roscoe Blvd at LA-27 and	4	2000	8000
184	Pothole, 4" Gas SCG, along NB of LA-27 at LA-27 and Schoenborn St	3	2000	6000
185	Pothole, 1 Du Elect LADWP, along NB of LA-27 at LA-27 and	3	2000	6000
186	Pothole, 1 Du Tel AT&T, corssing LA-27 at LA-27 and Schoenborn St	2	2000	4000
187	Pothole, 4 Du Tel AT&T, along SB of LA-27 at LA-27 and Chase St	2	2000	4000
188	Pothole, 9-4" Elect LADWP, along SB of LA-27 at LA-27 and Chase St	2	2000	4000
189	Pothole, 2 Du Tel AT&T, along WB of Chase St at LA-27 and Chase St	4	2000	8000
190	Pothole, 2" Gas SCG, at NE of LA-27 and Chase St intersection (ea)	2	2000	4000
191	Pothole, 8" Wtr LADWP, along EB of Chase St at LA-27 and Chase St	2	2000	4000
192	Pothole, 4" Gas SCG, along NB of LA-27 at LA-27 and Parthenia St	2	2000	4000
193	Pothole, 8" Wtr LADWP, along NB of LA-27 at LA-27 and Parthenia St	2	2000	4000
194	Pothole, 9-4" Elect LADWP, along NB of LA-27 at LA-27 and	6	2000	12000
195	Pothole, 4 Du Tel AT&T, along WB of Parthenia St at LA-27 and	3	2000	6000
196	Pothole, 4" Gas SCG, along WB of Parthenia St at LA-27 and	5	2000	10000
197	Pothole, 8" Wte LADWP, along WB of Parthenia St at LA-27 and	6	2000	12000
198	Pothole, 12" Wtr LADWP, NB of LA-27 at LA-27 Nordhoff St	9	2000	18000
199	Pothole, Elect LADWP, along EB of Nordhoff St at LA-27 Nordhoff St	3	2000	6000
200	Pothole, 4" Gas SCG, along WB of Nordhoff St at LA-27 Nordhoff St	4	2000	8000
201	Pothole, 8" Wtr LADWP, along NB of LA-27 ate LA-27 and Plummer	3	2000	6000
202	Pothole, 12" Wtr LADWP, along SB of LA-27 ate LA-27 and Plummer	3	2000	6000
203	Pothole, 9-4" Du Tel AT&T, along SB of LA-27 ate LA-27 and Plummer	2	2000	4000
204	Pothole, 8" Wtr LADWP, along NB of LA-27 at LA-27 and Marilla St	3	2000	6000
205	Pothole, 4" Gas SCG, along NB of LA-27 at LA-27 and Marilla St	2	2000	4000
206	Pothole, 9-4" Du Tel AT&T, along SB of LA-27 at LA-27 and Marilla St	2	2000	4000
207	Pothole, 11" Elect LADWP, along SB of LA-27 at LA-27 and Marilla St	2	2000	4000
208	Pothole, 8" Wtr LADWP, along SB of LA-27 at LA-27 and Marilla St	3	2000	6000
209	Pothole, 8" Wtr LADWP, along NB of LA-27 at LA-27 and Lassen St	2	2000	4000
210	Pothole, 4" Gas SCG, along NB of LA-27 at LA-27 and Lassen St	2	2000	4000

	Description	Quantity	\$/Unit	Total Cost
211	Pothole, Elect LADWP, along NB of LA-27 at LA-27 and Lassen St	2	2000	4000
212	Deenergization, Overhead Elect LADWP, along NB of LA-27 and	3	10000	30000
213	Deenergization, Overhead Elect LADWP, along NB of LA-27 and	3	10000	30000
214	Deenergization, Overhead Elect LADWP, along EB of Lassen St at LA	3	10000	30000
215	Deenergization, Overhead Elect LADWP, along NB of LA-27 at LA-27	3	10000	30000
216	Deenergization, Overhead Elect LADWP, along EB of Nordhoff St at	3	10000	30000
217	Deenergization, Overhead Elect LADWP, along SB of LA-27 at LA-27	6	10000	60000
218	Deenergization, Overhead Elect LADWP, along SB of LA-27 at LA-27	3	10000	30000
219	Deenergization, Overhead Elect LADWP, along WB of Saticoy St at	4	10000	40000
220	Deenergization, Overhead Elect LADWP, along WB of Vanowen St at	6	10000	60000
221	Deenergization, Overhead Elect LADWP, along NB of LA-27 at LA-27	3	10000	30000

ATTACHMENT "E" STORM WATER DATA REPORT

Dist-	County-Route: 07-LA-27
Post	Mile Limits: PM 0.0 to 18.6
Туре	of Work: Capital Preventive Maintenance (CAPM)
Proje	ect ID (EA): 0716000059 (322900)
Caltrans [®] Prog	ram Identification: 20.10.201.121
Phas	se: 🗌 PID 🛛 PA/ED 🗌 PS&E
Regional Water Quality Control Board(s): Los Angeles – Region 4
Total Disturbed Soil Area: 7.12 Acre	s PCTA: 0 acres
Alternative Compliance (acres): 0 ac	cres ATA 2 (50% Rule)? Yes □ No ⊠
Estimated Const. Start Date: 06/05/2	Estimated Const. Completion Date: 07/01/2024
Risk Level: RL 1 RL 2] RL 3 🛛 WPCP 🗌 Other:
Is MWELO applicable? Yes 🗌 N	lo 🖂
Is the Project within a TMDL watershe	d? Yes 🖂 No 🗌
TMDL Compliance Units (acres	s): 0 Acres
Notification of ADL reuse (if yes, provid	de date): Yes 🗌 Date: No 🖂

This Report has been prepared under the direction of the following Licensed Person. The Licensed Person attests to the technical information contained herein and the date upon which recommendations, conclusions, and decisions are based. Professional Engineer or Landscape Architect stamp required at PS&E only.

Nguyen Hua

Nguyen Hua, Registered Project Engineer/Landscape Architect

07/15/2021 Date

07/15/2021

I have reviewed the stormwater quality design issues and find this report to be complete, current and accurate:

David H Miraaney, Project Manager

Date

David Lawrence

David Lawrence, Designated Maintenance Representative

Engled Johnmytel

7/16/2021 Date

07/16/2021

Date

for Ron Russak, Designated Landscape Architect Representative

Sunny Lism Sunny Liem, District/Regional Design SW Coordinator 07/16/2021

[Stamp Required at PS&E only]

Date or Designee

PROJECT ESTIMATES

ATTACHMENT "F"

PROJECT

PLANNING COST ESTIMATE ©

EA: 322900 PID: 07-1600-0059

District-County-Route: 07-LA-27

PM: 0.0 - 18.6

PID: 07-1600-0059

EA: 322900

Type of Estimate : Project Report

Program Code : 20.XX.201.121

Project Limits : In Los Angeles County on Topanga Canyon

Project Description: Overlay pavement and upgrade ADA ramps

Scope :

Alternative : Build

SUMMARY OF PROJECT COST ESTIMATE

	TOTAL ROADWAY COST \$ 32 TOTAL STRUCTURES COST \$ 32 SUBTOTAL CONSTRUCTION COST \$ 32 TOTAL RIGHT OF WAY COST \$ 1 TAL CAPITAL OUTLAY COSTS \$ 33,4 PA/ED SUPPORT \$ 1	rrent Year Cost	Es	calated Cost
TOTAL ROADWAY COST	\$	32,135,600	\$	35,550,000
TOTAL STRUCTURES COST	\$	-	\$	-
SUBTOTAL CONSTRUCTION COST	\$	32,135,600	\$	35,550,000
TOTAL RIGHT OF WAY COST	\$	1,362,000	\$	1,927,913
TOTAL CAPITAL OUTLAY COSTS	\$	33,497,600	\$	37,478,000
PA/ED SUPPORT	\$	1,593,000	\$	1,593,000
PS&E SUPPORT	\$	4,405,000	\$	4,405,000
RIGHT OF WAY SUPPORT	\$	576,000	\$	576,000
CONSTRUCTION SUPPORT	\$	5,540,000	\$	5,540,000
TOTAL SUPPORT COST	\$	12,114,000	\$	12,114,000

тот	AL PROJECT COST	\$	45,650,000		\$	49,600,000	
			Programmed Amount		\$	35,550,000	
			Month	/	Year		
	Date of Estimate (Month/Year)		8	/	2020		
	Estimated Construction Start (Month/Year)		11	/	2022		
		N	umber of Working Days =	=	400		
Estima	ed Mid-Point of Construction (Month/Year)			1	2023		
	Estimated Construction End (Month/Year)			/	2025		
	Numbe	er of Pl	ant Establishment Days		0		
	Estimated Project Schedule						
	PID Approval		6/1/17 Actual				
	PA/ED Approval		7/30/2021				
	PS&E		1/20/2022				
	RTL		3/17/2022				
	Begin Construction		11/17/2022				
Reviewed by District O.E. or Cost Estimate Certifier							
-	Project Engineer		Date			Phone	
Approved by Project Manager							
-	Design Manager		Date			Phone	

٦

I. ROADWAY ITEMS SUMMARY

	Section			Cost
1	Earthwork		\$	221,000
2	Pavement Structural Section		\$	12,703,900
3	Drainage		\$	<u> </u>
4	Specialty Items		\$	1,601,000
5	Environmental		\$	66,000
6	Traffic Items		\$	6,866,400
7	Detours		\$	
8	Minor Items		\$	2,145,900
9	Roadway Mobilization		\$	2,360,500
10	Supplemental Work		\$	1,202,200
11	State Furnished		\$	677,100
12	Time-Related Overhead		\$	100,000
13	Roadway Contingency		\$	4,191,600
	TOTAL ROADWAY IT	EMS	\$	32,135,600
Estimate Prepared By	Nguyen Hua	Project Engineer	07/28/2021	(213) 269-1009
· · · · · · · · · · · · · · · · · · ·	Name and Title	-	Date	Phone
Estimate Reviewed By	Rolucio Domina	r. Transp. nuez	Eng. 07/28/2021	(213) 269-1762
	Name and Title	<u> </u>	Date	Phone

By signing this estimate you are attesting that you have discussed your project with all functional units and have incorporated all their comments or have discussed with them why they will not be incorporated.

SECTION 1: EARTHWORK

Item code		Unit	Quantity		Unit Price (\$)		Cost
190101	Roadway Excavation	CY	1,200	х	30.00	=	\$ 36,000
194001	Ditch Excavation	CY		х		=	\$ -
19801X	Imported Borrow	CY/TON		х		=	\$ -
192037	Structure Excavation (Retaining Wall)	CY		х		=	\$ -
193013	Structure Backfill (Retaining Wall)	CY		х		=	\$ -
193031	Pervious Backfill Material (Retaining Wall)	CY		х		=	\$ -
16010X	Clearing & Grubbing	LS/ACRE	1	х	10,000.00	=	\$ 10,000
170101	Develop Water Supply	LS		х		=	\$ -
19801X	Imported Borrow	CY/TON		х		=	\$ -
210130	Duff	ACRE		х		=	\$ -
190105	Roadway Excavation (ADL)_	CY	500	х	350	=	\$ 175,000

TOTAL EARTHWORK SECTION ITEMS \$ 221,000

SECTION 2: PAVEMENT STRUCTURAL SECTION

Mana a -1 -		Unit	Quantity		Unit Price (*)			Cost	
Item code 401050	Jointed Plain Concrete Pavement	CY	1,610	v	Unit Price (\$) 300.00		\$	483,000	
401050	Continuously Reinforced Concrete Pavement	CY	1,010	X	300.00	=	Ф \$	463,000	
400050	Seal Pavement Joint	LF		X X		=	ъ \$	-	
404092		LF				=	ф \$	-	
404093		LF		Х		=		-	
413117		LF		X		=	\$	-	
	Seal Pavement Joint (Asphalt Rubber)			Х		=	\$	-	
280010	Rapid Strength Concrete Base	CY		х		=	\$	-	
410095	Dowel Bar (Drill and Bond)	EA	F1 010	X	00.00	=	\$	-	
390132		TON	51,218	х	90.00	=	\$	4,609,620	
390137		TON	42,327	Х	125.00	=	\$	5,290,875	
39300X	, , , , ,	SQYD		х	~~ ~~	=	\$	-	
260303	Class 3 Aggregate Base	TON/CY	1,610	х	30.00	=	\$	48,300	
290201	Asphalt Treated Permeable Base	CY		х		=	\$	-	
280000	Lean Concrete Base	CY	1,610	х	100.00	=	\$	161,000	
374002	Asphaltic Emulsion (Fog Seal Coat)	TON		х		=	\$	-	
397005	Tack Coat	TON		х		=	\$	-	
377501	Slurry Seal	TON		х		=	\$	-	
	Screenings (Type XX)	TON		х		=	\$	-	
	Asphaltic Emulsion (Polymer Modified)	TON		х		=	\$	-	
370001	Sand Cover (Seal)	TON		х		=	\$	-	
731530	Minor Concrete (Curb and Gutter)	CY	3,000	х	300.00	=	\$	900,000	
731502	Minor Concrete (Miscellaneous Construction)	CY	400	х	700.00	=	\$	280,000	
394075	Place Hot Mix Asphalt Dike (Type D)	LF	0	х	0.00	=	\$	-	
150771	Remove Asphalt Concrete Dike	LF		х		=	\$	-	
420201	Grind Existing Concrete Pavement	SQYD		х		=	\$	-	
150860	Remove Base and Surfacing	SQFT	44,000	х	2.00	=	\$	88,000	
390095	Replace Asphalt Concrete Surfacing	CY	0	х	0.00	=	\$	-	
15312X	Remove Concrete	SQFT	40,000	х	3.00	=	\$	120,000	
394090	Place Hot Mix Asphalt (Miscellaneous Area)	SQYD		х		=	\$	-	
153103	Cold Plane Asphalt Concrete Pavement	SQYD	3,286,800	х	0.22	=	\$	723,096	
39405X	Shoulder Rumble Strip (HMA, X-In Indentations)	STA		х		=	\$	-	
413113	Repair Spalled Joints, Polyester Grout	SQYD		х		=	\$	-	
420102	Groove Existing Concrete Pavement	SQYD		х		=	\$	-	
390136	Minor Hot Mix Asphalt	TON		х		=	\$	-	
394095	Roadside Paving (Miscellaneous Areas)	SQYD		х		=	\$	-	
XXXXXX	Some Item	Unit		х		=	\$	-	
			TOTAL PA	VEN	IENT STRUCTU	JRAI	_ SE	CTION ITEMS	\$ 1
		I							

12,703,900

PROJECT COST ESTIMATE

SECTION 3: DRAINAGE

Item code		Unit	Quantity		Unit Price (\$)			Cost
15080X	Remove Culvert	EA/LF		х		=	\$	-
150820	Modify Inlet	EA	0	х	0.00	=	\$	-
155232	Sand Backfill	CY		х		=	\$	-
15020X	Abandon Culvert	EA/LF		х		=	\$	-
152430	Adjust Inlet	LF		х		=	\$	-
155003	Cap Inlet	EA	0	х	0.00	=	\$	-
510501	Minor Concrete	CY		х		=	\$	-
510502	Minor Concrete (Minor Structure)	CY		х		=	\$	-
5105XX	Minor Concrete (Type XX)	CY		х		=	\$	-
620XXX	XX" Alternative Pipe Culvert (Type X)	LF		х		=	\$	-
	XX" Plastic Pipe	LF		х		=	\$	-
65XXXX	XX" Reinforced Concrete Pipe (Type X)	LF		х		=	\$	-
6650XX	XX" Corrugated Steel Pipe (0.XXX" Thick)	LF		х		=	\$	-
68XXXX	XX" Plastic Pipe (Edge Drain)	LF		х		=	\$	-
69011X	XX" Corrugated Steel Pipe Downdrain (0.XXX" Th	LF		х		=	\$	-
70321X	XX" Corrugated Steel Pipe Inlet (0.XXX" Thick)	LF		х		=	\$	-
70XXXX	XX" Corrugated Steel Pipe Riser (0.XXX" Thick)	LF		х		=	\$	-
7050XX	XX" Steel Flared End Section	EA		х		=	\$	-
703233	Grated Line Drain	LF		х		=	\$	-
72XXXX	Rock Slope Protection (Type and Method)	CY/TON		х		=	\$	-
72901X	Rock Slope Protection Fabric (Class X)	SQYD		х		=	\$	-
721420	Concrete (Ditch Lining)	CY		х		=	\$	-
721430	Concrete (Channel Lining)	CY		х		=	\$	-
750001	Miscellaneous Iron and Steel	LB		х		=	\$	-
710206	Adjust Overside Drain	EA		х		=	\$	-
	•							
					тот	AL D	RAIN	IAGE ITEMS \$

SECTION 4: SPECIALTY ITEMS

i) LS SQFT CY LF/LS LS LB LF LF	1 1 600	x x x x x x	5,000.00	= = =	\$ \$ \$	5,000		
CY LF/LS LS LB LF	-	x x				-		
LF/LS LS LB LF	-	х		=	\$			
LS LB LF	-				Ψ	-		
LB LF	-	х		=	\$	-		
LF	600		5,000.00	=	\$	5,000		
		х	20.00	=	\$	12,000		
IF		х		=	\$	-		
LI	9,800	х	10.00	=	\$	98,000		
EA		х		=	\$	-		
LF		х		=	\$	-		
EA		х		=	\$	-		
LF	39,800	х	30.00	=	\$	1,194,000		30000
LF		х		=	\$	-		
LF		х		=	\$	-		
LF		х		=	\$	-		
EA		х		=	\$	-		
EA		х		=	\$	-		
EA	2	х	40,000.00	=	\$	80,000		
LF		х		=	\$	-		
EA		х		=	\$	-		
LF		х		=	\$	-		
LB		х		=	\$	-		
CY		х		=	\$	-		
SQFT		х		=	\$	-		
SQFT		х		=	\$	-		
SQFT		х		=	\$	-		
SQFT		х		=	\$	-		
SQFT		х		=	\$	-		
EA		х		=	\$	-		
SQFT		х		=	\$	-		
EA		х		=	\$	-		
EA	46	х	4,500.00	=	\$	207,000		
Unit		х		=	\$	-		
	EA LF EA LF LF EA EA EA EA CY SQFT SQFT SQFT SQFT EA SQFT EA EA EA	EA LF EA LF 39,800 LF LF LF EA EA EA 2 LF EA CY SQFT SQFT SQFT SQFT SQFT SQFT EA SQFT EA SQFT EA A SQFT EA SQFT EA SQFT EA SQFT EA SQFT EA SQFT EA SQFT EA SQFT EA SQFT SQFT SQFT EA SQFT SQFT SQFT SQFT EA SQFT SQ SQFT SQ SQ SQFT SQ SQFT SQ SQFT SQFT SQFT SQFT SQ	EA x LF 39,800 x LF 39,800 x LF x L LF x x LF x x LF x x EA x x EA 2 x EA 2 x LF x x EA 2 x SQFT x x EA x x EA x x EA x x EA x6	$\begin{array}{cccccccccccccccccccccccccccccccccccc$	$ \begin{array}{cccccccccccccccccccccccccccccccccccc$	EA x = \$ LF x = \$ LF 39,800 x 30.00 = \$ LF x = \$ \$ \$ LF x = \$ \$ \$ LF x = \$ \$ LF x = \$ \$ EA x = \$ \$ EA 2 x 40,000.00 = \$ EA 2 x 40,000.00 = \$ LF x = \$ \$ \$ EA 2 x 40,000.00 = \$ LF x = \$ \$ \$ SQFT X = \$ \$ \$ SQFT X <td>$\begin{array}{cccccccccccccccccccccccccccccccccccc$</td> <td>EA x = \$ - LF x = \$ - EA x = \$ - LF 39,800 x 30.00 = \$ 1,194,000 LF x = \$ - - - EA x = \$ - - - LF x = \$ - - - LF X = \$ - - - LF X = \$ - - - LF</td>	$ \begin{array}{cccccccccccccccccccccccccccccccccccc$	EA x = \$ - LF x = \$ - EA x = \$ - LF 39,800 x 30.00 = \$ 1,194,000 LF x = \$ - - - EA x = \$ - - - LF x = \$ - - - LF X = \$ - - - LF X = \$ - - - LF

TOTAL SPECIALTY ITEMS \$

\$\$1,601,000

SECTION 5: ENVIRONMENTAL

5A - ENVIRONMENTAL MITIGATION

5A - ENVI	RONMENTAL MITIGATION									
Item code		Unit	Quantity		Unit Price (\$)			Cost		
	Biological Mitigation	LS		х		=	\$	-		
130670	Temporary Reinforced Silt Fence	LF	1,000	х	5.00	=	\$	5,000		
141000	Temporary Fence (Type ESA)	LF		х		=	\$	-		
					Subtotal	Fnv		nental Mitigation	\$	5,000
5P I ANI	DSCAPE AND IRRIGATION				Custota			ionia milgalon	Ψ	0,000
	DSCAPE AND INHIGATION	Unit	Overstitu		Unit Dring (f)			Cont		
Item code		Unit	Quantity		Unit Price (\$)		•	Cost		
	Highway Planting	LS		х	0.00	=	\$	-		
20XXXX	Irrigation System	LS		х	0.00	=	\$	-		
204099	Plant Establishment Work	LS		х	0.00	=	\$	-		
204101	Extend Plant Establishment Work	LS		х		=	\$	-		
20XXXX	Follow-up Landscape Project	LS		х		=	\$	-		
150685	Remove Irrigation Facility	LS		х	0.00	=	\$	-		
	Maintain Existing (Irrigation or Planted Areas)	LS		х		=	\$	-		
	Check and Test Existing Irrigation Facilities	LS		х	0.00	=	\$	-		
	Imported Topsoil (X)	CY/TON		x	0.00	=	\$	-		
	Rock Blanket, Rock Mulch, DG, Gravel Mulch	SQFT/SQYD		x		_	\$	_		
		SQYD						-		
	Weed Germination			Х		=	\$	-		
208304		EA		х		=	\$	-		
2087XX	XX" Conduit (Use for Irrigation x-overs)	LF		х		=	\$	-		
20890X	v ovoro)	LF		х		=	\$	-		
					Subtotal	Land	dscap	pe and Irrigation	\$	-
5C - ERO	SION CONTROL									
Item code		Unit	Quantity		Unit Price (\$)			Cost		
	Move In/Move Out (Erosion Control)	EA	-	х	,	=	\$	_		
210350	Fiber Rolls	LF	\$ 1,000	х	5	=	\$	5,000		
	Compost Sock	LF	φ 1,000	x	0	=	\$	5,000		
	Rolled Erosion Control Product (X)	SQFT		x		_		-		
2102XX 21025X	· · /	SQFT/ACRE					\$	-		
				х		=	\$	-		
210300	-	SQFT		х		=	\$	-		
210420		SQFT		х		=	\$	-		
210430	Hydroseed	SQFT		х		=	\$	-		
210600	Compost	SQFT		х		=	\$	-		
210630	Incorporate Materials	SQFT		х		=	\$	-		
						Sub	total	Erosion Control	\$	5,000
5D - NPD	ES									
Item code		Unit	Quantity		Unit Price (\$)			Cost		
130300	Proporo SW/DPD		1		• •		¢			
	•	LS	I	х	5,000.00	=	\$	5,000		
130200	•	LS		х		=	\$	-		
130100	Job Site Management	LS	1	х	20,000.00	=	\$	20,000		
130330	Storm Water Annual Report	EA	2	х	2,000.00	=	\$	4,000		
130310	Rain Event Action Plan (REAP)	EA	1	х	2,000.00	=	\$	2,000		
130520	Temporary Hydraulic Mulch	SQYD		х		=	\$	-		
130550	Temporary Hydroseed	SQYD		х		=	\$	-		
130505	Move-In/Move-Out (Temporary Erosion Control)	EA		х		=	\$	-		
130570	Temporary Cover	SQYD	400		50.00		\$	2,000		
130640	Temporary Fiber Roll	LF	1,000	х	6.00	=	\$	6,000		
130650	Temporary Gravel Bag Berm	LF	1,000	~	6.00		\$	6,000		
130680	Temporary Silt Fence	LF	100		3.00		\$	3,000		
	Temporary Concrete Washout		2	.,						
130900		LS	2	Х	1,000.00	=	\$	2,000		
130710	Temporary Construction Entrance	EA		х		=	\$			
130610	Temporary Check Dam	LF		х		=	\$	-		
130620	Temporary Drainage Inlet Protection	EA	1	х	1,000.00	=	\$	1,000		
130730	Street Sweeping	LS	1	х	5,000.00	=	\$	5,000		
							S	btotal NPDES	\$	56,000
							00		+	20,000
					T				¢	66.000
. .					101	AL		RONMENTAL	\$	66,000
Sunnlome	ental Work for NPDES									

Cumplamantal	Mark	4	
Supplemental	WORK	IOL	NPDE3

066595	Water Pollution Control Maintenance Sharing*	LS
066596	Additional Water Pollution Control**	LS
066597	Storm Water Sampling and Analysis***	LS
XXXXXX	Some Item	LS

		10	IAL	=NVII	RONMENTAL	\$ 66,000
1	х	5,000.00	=	\$	5,000	
1	х	3,000.00	=	\$	3,000	
1	х		=	\$	5,000	
	х		=	\$	-	
		Subtotal Supp	oleme	ntal V	Vork for NDPS	\$ 13,000

*Applies to all SWPPPs and those WPCPs with sediment control or soil stabilization BMPs.

Applies to both SWPPPs and WPCP projects. * Applies only to project with SWPPPs.

SECTION 6: TRAFFIC ITEMS

6A - Traffic Electrical

Item code		Unit	Quantity		Unit Price (\$)		Cost
860460	Lighting and Sign Illumination	LS	1	х	5,929,400.00	=	\$ 5,929,400
860201	Signal and Lighting	LS		х		=	\$ -
860990	Closed Circuit Television System	LS		х		=	\$ -
86110X	Ramp Metering System (Location X)	LS		х		=	
86070X	Interconnection Conduit and Cable	LF/LS		х		=	\$ -
5602XX	Furnish Sign Structure (Type X)	LB		х		=	\$ -
5602XX	Install Sign Structure (Type X)	LB		х		=	\$ -
498040	XX" CIDHC Pile (Sign Foundation)	LF		х		=	\$ -
86080X	Inductive Loop Detectors	EA/LS		х		=	\$ -
8609XX	Traffic Monitoring Station (Type X)	LS		х		=	\$ -
15075X	Remove Sign Structure	EA/LS		х		=	\$ -
151581	Reconstruct Sign Structure	EA		х		=	\$ -
152641	Modify Sign Structure	EA		х		=	\$ -
860090	Maintain Existing Traffic Management System Elerr	LS		х		=	\$ -
86XXXX	Fiber Optic Conduit System	LS		х		=	\$ -
XXXXX	Some Item	Unit		х		=	\$ -

Subtotal Traffic Electrical \$ 5,929,400

6B - Traffic Signing and Striping

Item code		Unit	Quantity		Unit Price (\$)			Cost	
566011	Roadside Sign - One Post	EA	2	х	1,000.00	=	\$	2,000	
566012	Roadside Sign - Two Post	EA		х		=	\$	-	
5602XX	Furnish Sign	SQFT		х		=	\$	-	
568016	Install Sign Panel on Existing Frame	SQFT		х		=	\$	-	
150711	Remove Painted Traffic Stripe	LF		х		=	\$	-	
141101	Nentove reliow named traine Supe (nazaruous	LF		х		=	\$	-	
150712	Remove Painted Pavement Marking	SQFT		х		=	\$	-	
150742	Remove Roadside Sign	EA		х		=	\$	-	
152320	Reset Roadside Sign	EA	2	х	500.00	=	\$	1,000	
152390	Relocate Roadside Sign	EA		х		=	\$	-	
82010X	Delineator (Class X)	EA		х		=	\$	-	
840502	Thermoplastic Traffic Stripe (Enhanced Wet Night V	LF	394,000	х	0.50	=	\$	197,000	
846012	Thermoplastic Crosswalk and Pavement Marking (I	SQFT		х		=	\$	-	
120090	Construction Area Signs	LS	1	х	2,000.00	=	\$	2,000	
84XXXX	Permanent Pavement Delineation	LS	1	х	5,000.00	=	\$	5,000	
					Subtotal Traf	fic S	igning	and Striping	\$ 207,000

6C - Traffic Management Plan

	general						
Item code		Unit	Quantity	Unit	Price (\$)		Cost
12865X	Portable Changeable Message Signs	EA/LS	20	x \$	1,500	= \$	30,000

Subtotal Traffic Management Plan	\$	30,000
----------------------------------	----	--------

6C - Stage Construction and Traffic Handling

Item code		Unit	Quantity		Unit Price (\$)			Cost	
120199	Traffic Plastic Drum	EA		х		=	\$	-	
12016X	Channelizer (Type X)	EA	1	х		=	\$	-	
120120	Type III Barricade	EA		х		=	\$	-	
129100	Temporary Crash Cushion Module	EA	0	х	0.00	=	\$	-	
120100	Traffic Control System	LS	1	х	700,000.00	=	\$	700,000	
129110	Temporary Crash Cushion	EA		х		=	\$	-	
129000	Temporary Railing (Type K)	LF	0	х	0.00	=	\$	-	
120149	Temporary Pavement Marking (Paint)	SQFT		х		=	\$	-	
82010X	Delineator (Class X)	EA		х		=	\$	-	
XXXXXX	Some Item	Unit		х		=	\$	-	
			Subto	otal S	Stage Constructi	on a	nd Tr	affic Handling \$	700,000

TOTAL TRAFFIC ITEMS \$ 6,866,400

SECTION 7: DETOURS

Includes constructing, maintaining, and removal

Item code		Unit		Quantity		Unit Price (\$)			Cost		
190105 Roadway Excavation (ADL)	1	CY		Quantity 0	х	0.00	=	\$	-		
19801X Imported Borrow	/	CY/TON		0	x	0.00	_	\$	-		
390137 Rubberized Hot Mix Asphal	t (Gap Graded)	TON		0	x	0.00	=	\$	-		
260303 Class 3 Aggregate Base	, i ,	TON/CY		0	х	0.00	=	\$	-		
280000 Lean Concrete Base		CY		0	х	0.00	=	\$	-		
130620 Temporary Drainage Inlet P		EA			х		=	\$	-		
129000 Temporary Railing (Type K))	LF			х		=	\$	-		
128601 Temporary Signal System		LS			х		=	\$	-		
120149 Temporary Pavement Mark	ing (Paint)	SQFT			х		=	\$	-		
80010X Temporary Fence (Type X)		LF			х		=	\$	-		
XXXXXX Some Item		LS			х		=	\$	-		
* Includes constructing, maintaining, and remova	1					ΤΟΤΑΙ	_ DE	TOU	RS	\$	-
						SUBTOTAL SE	ст	IONS	3 1 through 7	\$	21,458,300
SECTION 8: MINOR ITEMS											
8A - Americans with Disabilities Act	Items										
ADA Items						1.0%		\$	214,583		
8B - Bike Path Items											
Bike Path Items						1.0%		\$	214,583		
8C - Other Minor Items Other Minor Items						8.0%	_	\$	1,716,664		
Т	otal of Section 1-7		\$	21,458,300	х	10.0%	=	\$	2,145,830		
						TOTAL	MIN		EMS	\$	2,145,900
										Ψ	
SECTIONS 9: ROADWAY MO	BILIZATION										
Item code											
999990	Total Section 1-8		\$	23,604,200	х	10%	=	\$	2,360,420		
						TOTAL RO	ADV	VAY	MOBILIZATION	\$	2,360,500
SECTION 10: SUPPLEMENT	AL WORK										
Item code		Unit		Quantity		Unit Price (\$)			Cost		
066670 Payment Adjustments For F	Price Index	LS		1	х	2,000.00	=	\$	2,000		
Fluctuations					~		_				
066094 Value Analysis		LS		1	х	10,000.00	=	\$	10,000		
066070 Maintain Traffic		LS		1	х	168,000.00	=	\$	168,000		
066919 Dispute Resolution Board		LS		1	x	15,000.00	=	\$	15,000		
066921 Dispute Resolution Advisor		LS		1	х	10,000.00	=	\$	10,000		
066015 Federal Trainee Program		LS		1	х	5,000.00	=	\$	5,000		
066610 Partnering		LS		1	х	35,000.00	=	\$	35,000		
066204 Remove Rock and Debris		LS		1	х		=	\$	-		
066222 Locate Existing Crossover		LS			х		=	\$	-		
XXXXXX Some Item		Unit			х		=	\$	-		
	Cost of NPL	DES Supp	olem	nental Work sp	ecifie	ed in Section 5D	- =	\$	13,000		
	Total Section 1-8		\$	23,604,200		4%	=	\$	944,168		

SECTION 11: STATE FURNISHED MATERIALS AND EXPENSES

066063 Tra	sident Engineers Office affic Management Plan - Public Information	LS LS	1	х	100,000.00	=		¢100.000	
	affic Management Plan - Public Information	10						\$100,000	
066901 Wa		LO	1	х	10,000.00	=		\$10,000	
	ater Expenses	LS		х		=		\$0	
8609XX Tra	affic Monitoring Station (X)	LS		х		=		\$0	
066841 Tra	affic Controller Assembly	LS		х		=		\$0	
066840 Tra	affic Signal Controller Assembly	LS		х		=		\$0	
066062 CC	DZEEP Contract	LS	1	х	90,000.00	=		\$90,000	
066838 Re	flective Numbers and Edge Sealer	LS		х		=		\$0	
066065 To	w Truck Service Patrol	LS		х		=		\$0	
066916 An	nual Construction General Permit Fee	LS	1	х	5,000.00	=		\$5,000	
XXXXXX Pe	ermits	LS		х		=		\$0	
	Total Section 1-	8	\$ 23,604,200		2%	=	\$	472,084	
					тот	AL S	TATE	FURNISHED	\$677,100

Total of Roadway and Structures Contract Items excluding Mobilization Total Construction Cost (excluding TRO and Contingency)

\$23,604,200 (used to calculate TRO)\$27,844,000 (used to check if project is greater than \$5 million excluding contingency)

4%

Estimated Time-Related Overhead (TRO) Percentage (0% to 10%) =

Item code	Unit	Quantity		Unit Price (\$)		Cost
090100 Time-Related Overhead	WD	200	Х	\$500	=	\$100,000

TOTAL TIME-RELATED OVERHEAD \$100,000

SECTION 13: ROADWAY CONTINGENCY

Total Section 1-12	\$ 27,944,000	x	8% 15%	=	\$4,191,600	\$4,191,600
Hidden Calculations do not print Hidden Calculations do not print	Known risk amount Unknown risks	t	7% 8%		\$2,000,000	

II. STRUCTURE ITEMS

	Bridge 1	Bridge 2	
DATE OF ESTIMATE Bridge Name Bridge Number Structure Type Width (Feet) [out to out] Total Bridge Length (Feet) Total Area (Square Feet) Structure Depth (Feet) Footing Type (pile or spread) Cost Per Square Foot	00/00/00 xxxxxxxxxxxxxxx XX-XXX xxxxxxxxxxxxx	00/00/00 xxxxxxxxxxxxxxxxx 57-XXX xxxxxxxxxxxxxxxxx 0 LF 0 LF 0 SQFT 0 LF xxxxxxxxxxxxxxxxxxxxxxxxxxxxxxxxxxxx	00/00/00 xxxxxxxxxxxxxxxxx 57-XXX xxxxxxxxxxxxxxxxx 0 LF 0 LF 0 SQFT 0 LF xxxxxxxxxxxxxxxxxxxxxxxxxxxxxxxxxxxx
COST OF EACH	\$0	\$0	\$0

	Building 1	Secant Wall 1	Secant wall 2
DATE OF ESTIMATE Building Name Bridge Number Structure Type Width (Feet) [out to out] Total Building Length (Feet) Total Area (Square Feet) Structure Depth (Feet) Footing Type (pile or spread) Cost Per Square Foot	00/00/00 xxxxxxxxxxxxxxxx 57-XXX xxxxxxxxxxxxxxxxx 0 LF 0 LF 0 SQFT 0 LF 0 LF xxxxxxxxxxxxxxxxxxxxxxxxxxxxxxxxxxxx	00/00/00 xxxxxxxxxxxxxxxxx 57-XXX xxxxxxxxxxxxxxxxx 0 LF 0 LF 0 SQFT 0 LF xxxxxxxxxxxxxxxxxxxxxxxxxxxxxxxxxxxx	00/00/00 xxxxxxxxxxxxxxx 57-XXX xxxxxxxxxxxxxxxxxx 0 LF 0 LF 0 SQFT 0 LF xxxxxxxxxxxxxxxxxxxxxxxxxxxxxxxxxxxx
Cost Per Square Foot	\$300	\$U	\$0
COST OF EACH	\$0	\$0	\$0

	TOTAL COST OF BRIDGES	\$0
	TOTAL COST OF BUILDINGS	\$0
STRUCTUF	RES MOBILIZATION 10%	\$0
Recommended Contingency: (Pre-PSR 30%-50%, PSR 25%, Draft PR 20%, PR 15%, after PR app Total recommended percentages includes any quantified risk based contingency from the risk regist	· ,	
	RES CONTINGENCY 10%	\$0
TOTAL COST O	F STRUCTURES	\$0


Estimate Prepared By:

Date

III. RIGHT OF WAY

Fill in all of the available information from the Right of Way Data Sheet.

A)	A1) Acquisition, inc A2) SB-1210	luding Excess Land Purchases, Damages & Goodwill, Fees	\$ \$	0 0
B)	Acquisition of Offsite Mitig	ation	\$	0
C)	C1) Utility Relocation C2) Potholing (Des	on (State Share) ign Phase)	\$ \$	1,362,000 0
D)	Railroad Acquisition		\$	0
E)	Clearance / Demolition		\$	0
F)	Relocation Assistance (R	AP and/or Last Resort Housing Costs)	\$	0
G)	Title and Escrow		\$	0
H)	Environmental Review		\$	0
I)	Condemnation Settlement	s0%_	\$	0
J)	Design Appreciation Factor	or0%_	\$	0
K)	Utility Relocation (Constru	ction Cost)	\$	0



Support Cost Estimate	Victor Lee	
Prepared By	Project Coordinator ¹	Phone
Utility Estimate Prepared	Onyx Smith-Taylor	
Ву	Utility Coordinator ²	Phone
R/W Acquisition Estimate		
Prepared By	Right of Way Estimator ³	Phone
Note: Items G & H applied to	o items A + B	
¹ When estimate has Suppor	rt Costs only ² When estimate has Utility R	elocation ³ When R/W Acquisition is required

ATTACHMENT "G"

RISK REGISTER

RISK REGISTER CERTIFICATION (ACCOUNTABILITY CHECKPOINTS) FORM

PPM-D07-0001 (REV 02/2020)

The risk register is to be approved and signed-off by the District Deputies listed below for all scalability levels. By signing this form, you are certifying that you have reviewed the risks documented in the register and agree that they have been managed to the extent possible by the PDT.

Project Information ECapital Project Major	Maintenance Project(Check One) Total Capital Cost: <u>\$33,498,000</u>
Project ID/District-EA	Project ID: 0716000059/ EA: 07- 322900
Project Description	LA-027-0/18.62-In Los Angeles County on Topanga Canyon between SR-1 & Devonshire Street: AC overlay and ADA Ramps
Project Manager	David Miraaney
Project Risk Manager	Chan Kuoch
No Risk Register Certification Required Check box if pro form with PID, PA&ED, PS&E submittal, and RE Handoff F	ject is less than \$1 million in total cost and risk register not prepared. Sign below and submit this ile (as applicable).
Project Manager Signature	Date:
PID (Recommended for Capital Projects Only ex	cluding Minor Projects)
Project Manager	Date:
Deputy District Director, Planning	Date:
Deputy District Director, Design	Date:
Deputy District Director, Construction	Date:
Deputy District Director, Right of Way	Date:
Deputy District Director, Environmental	Date:
Deputy District Director, Traffic Operations	Date:
Deputy District Director, Maintenance	Date:
Deputy District Director, Project Management	Date:
PA&ED (Required for Capital Projects Only)	
Project Manager	Approved via E-mail- See Attached Approval Tracking Document Date: 6/11/21
Deputy District Director, Design	Approved via E-mail- See Attached Approval Tracking Document Date: 6/11/21
Deputy District Director, Construction	Approved via E-mail- See Attached Approval Tracking Document Date: 6/11/21
Deputy District Director, Right of Way	Approved via E-mail- See Attached Approval Tracking Document Date: 6/11/21
Deputy District Director, Environmental	Approved via E-mail- See Attached Approval Tracking Document Date: 6/11/21
Deputy District Director, Traffic Operations	Approved via E-mail- See Attached Approval Tracking Document Date: 6/13/21
Deputy District Director, Maintenance	Approved via E-mail- See Attached Approval Tracking Document Date: 6/11/21
Deputy District Director, Project Management	Approved via E-mail- See Attached Approval Tracking Document Date: 6/11/21
Prior to PS&E (Required for Capital Projects and	Major Maintenance Projects)
Project Manager	Date:
Deputy District Director, Design	Date:
Deputy District Director, Construction	Date:
Deputy District Director, Right of Way	Date:
Deputy District Director, Environmental	Date:
Deputy District Director, Traffic Operations	Date:
Deputy District Director, Maintenance	Date:
Deputy District Director, Project Management	Date:

ADA Notice For individuals with sensory disabilities, this document is available in alternate formats. For information call (916) 654-6410 or TDD (916) 654-3880 or write to Records and Forms Management, 1120 N Street, MS-89, Sacramento, CA 95814.

From: Sent: To: Subject: Attachments:	Kukla, Dawn E@DOT; Elo, Zoltan@DOT		Iiga, Derek@DOT; So, Robert C H@DOT; ROVAL]
Importance:	High		
Categories: Tracking:	Risk Recipient	Delivery	Response
8	Archuleta, Mark A@DOT	Delivered: 6/11/2021 9:55 AM	Approved as is: 6/11/2021 10:00 AM
	Saadatnejadi, Hamidreza@DOT	Delivered: 6/11/2021 9:56 AM	Approved as is: 6/11/2021 10:47 AM
	Islam, Shafiqul@DOT	Delivered: 6/11/2021 9:55 AM	Approved as is: 6/13/2021 5:05 PM
	Higa, Derek@DOT	Delivered: 6/11/2021 9:55 AM	Approved as is: 6/11/2021 9:56 AM
	So, Robert C H@DOT	Delivered: 6/11/2021 9:55 AM	Approved as is: 6/11/2021 10:02 AM
	Kukla, Dawn E@DOT	Delivered: 6/11/2021 9:55 AM	Approved as is: 6/11/2021 9:56 AM
	Elo, Zoltan@DOT	Delivered: 6/11/2021 9:56 AM	Approved as is: 6/11/2021 2:20 PM
	Miraaney, David H@DOT	Delivered: 6/11/2021 9:55 AM	Approved as is: 6/11/2021 9:56 AM

Attached please find final Risk Register for your approval to proceed via Email Voting Buttons.

- By approving this request via email vote buttons, you are certifying that you have reviewed the risks documented in the
 register and agree that they have been managed to the extent possible by the PDT and you are authorizing the use of the
 Approval Tracking Document printed from this email request in-lieu of the wet signatures on the Risk Register Certification
 (Accountability Checkpoints) Form.
- Wet signature on the project Risk Register Certification (Accountability Checkpoints) form will be replaced with the statement "Approved via Email See attached Approval Tracking Document."
- The Approval Tracking Document from this email will be attached to project Risk Register Certification (Accountability Checkpoints) Form.

Risk Register Summary:

- 1. EA: 322900 / Project ID: 0716000059
- 2. Recommended Contingency @ 70% Confidence: 15%

3. Project Description: LA-027-0/18.62-In Los Angeles County on Topanga Canyon between SR-1 & Devonshire Street: AC overlay and ADA Ramps

- 4. Project Manager: David Miraaney
- 5. Project Risk Manager: Chan Kuoch

Should you have any questions or require additional information, please call me at (213) 760-7756.

Thank You, Mirna Dagher, P.E., PMP Caltrans, District 07 Office of Risk Management

Approving Via Email for: Construction – Mark Archuleta Design – Derek Higa Right of Way – Zoltan Elo

Maintenance – Hamid Saadatnejadi Prog/Proj Mgmt – Robert So Proj Mgr – David Miraaney Traffic Ops – *Shafiqul Islam* Environmental – *Dawn E. Kukla* **Risk Register**

 Duration
 Contacts
 Base RW Cap Est (N):
 51.362
 Risk Based RW Cap Est (N):
 23.971

 CCA
 Con Working Days: 400
 P.M. David H Miraaney
 Base Con Cap Est (N):
 \$7.372
 Risk Based RW Cap Est (N):
 \$2.977

 M6000
 Pant Est Days: 0
 R.M. Can (working Days: 400
 P.M. Can (working Days: 400
 R.M. Cap Est (N):
 \$3.346

 M117/I25
 Total Con Days: 400
 Refugio Domingenz
 Base Total Cap Est (S):
 \$3.349
 Risk Based Total Cap (S):
 \$3.343

 Romeare site sites succes concaped and threak the existion MeRI and RMSCR With MMSKI Gardraf Sites (N):
 \$3.346
 \$4.323 (15%)
 \$4.333 (15%)
 RWC (M410) 03/03/22 Milestones PS&E (M380) 02/15/22 PA&ED (M200) 06/21/21 0 PID F (M010) (06/02/17A 0 322900 - LA-027-0/18.62-In Los Angeles County on Topanga Canyon between SR-1 & Devonshire Street: AC overlay and ADA Ramps

Scope Summar, proposed improv	 y: The proje vements, an 	ect proposes to co id replace damage	ld plane and overlay the existing asphalt pavement, up id curb and gutters.	Scope Summary: The point proposes to cold plane and overlay the existing apphalt pavement, upgrade the existing curb ramps to meet the requirements of the Americans with Disabilities Act (ADA) standards, construct concrete pads at transit bus stops, upgrade the existing MeIel Beam Guard all System (MGS), reforcate signals and replace loop detectors due to the proposed improvements, and replace and overlay the existing apphalt pavement, upgrade the existing apphalt pavement, upgrade the existing activation and replace signals and replace loop detectors due to the proposed improvements, and replace damaged out band guilters.	s of the America	ans with Disabil	Ities Act (ADA) sta	andards, construi	ct concrete pads	at transit bus sto	ops, upgrade the	existing Me	al Beam Gu	ard Ralling (MBGR) with Midwest Guar	rdrail System (N	MGS), relocate signals and replace loo	op detectors	lue to the
								Risk Im	Risk Impact Assessment	ment					c	ä		
			Kisk Identification			Probability		Recommende Risk Impact o	Recommended Contingency (@70th Percentile): Risk Impact on Con Capital (@70th Percentile):	§70th Percentile): \$70th Percentile):	15% \$4,204,733	Risk Impac	Risk Impact on Schedule	Ð	Kesp	Kesponse Strategy		
Risk Status Type No.	pe Category	y Title	Risk Statement	Risk Details with Current Status/Assumptions	Probability of Occurrence	Distribution Type	Distribution Parameter	Low (\$)	Most Likely (\$)	High (\$)	Cost Impact	Low	Most High Likely	Rationale	Strategy	Response Actions	Risk Owner	Updated
- Active Active Threat	50	Missing Items (Assets) Within the Project Limits	If unanticipated items (assets or deficiencies) are discovered within the policed immits a requirement to protect in place, rebrace to remediate these items may be required, which would lead to increased project costs and schedule ciderys.	The current project proposes to improvelorestruct 200 ACA current project proposes to improvelorestruct 200 estimates. There may be additional work immanases such additional curb ramps, MCS, and ITS elements (transpect or gains) conducts, and ITS elements electrical components (topo) detector, pull boxel), electrical components (topo) detector, pull boxel), addinger street elements (transpector), and consult Station), and change systems. Impattor system (trainsing uniques target elements (transpector spate action) econdets attend elements (transpector), uppl corests and the street elements (transpector) and transpector actions etc. that may require repairs, upprades or replacement-	20%			000'000' 15	000'000' 2\$	000'000'ss	1,000,000	9	32	Identifying all items of work improves the stability of the cost estimate. Multiple field visits and consultant reviews confirmed locations of curb ramps is very pow- level. Possibility of needing additional curb ramps is very pw.	Mitigate	Work with all functional units to comprehensively identify work terms.	Design Senior 05/18/21	05/18/21
∽ Active Threat	3	Utby Identification and redocation Needs (PID Risk #1)	Uity (dearrification If impacts on utilities are identified after site investigation, and relocation additional effort tradescaler or protection in glase may be Needs required which would lead to project cost increases and PID Risk #1) schedule delays.	The escalated cost for politicing and utility rehosition is \$1.327.912 per RW data sheet dated (SH 427. Cost) is under in current settimes. Utilitate project LA Water. SCE: City of LV, and AT 75 are within project is updated project requires at PAIP orehead (and proheside) and deterregreed LA DWP orehead lines proper setting and utilities are above \$100, then tam will measure the project requires at PAIP orehead (and project. HWC candid is currently programmed at \$127.913, A documentation PCM represes The advection costs are budget. RWC candid is a rundwite represent optimation PCM represes for all start optimated on project and there are a how \$127.719.13, A documentation PCM represe and all start optimates is a documentation PCM represes and allow for necessary RW people of project schedue does not allow for necessary RW people of the advection of the project schedue does not allow for necessary RW people of the advection of the advection neces. The people of the advection of the advection on the advection and therefore a high risk of deferry failure is anticipated.	20%	Bernoulli		\$750,000	\$975,000	000'000 81'200'000	512,500	ę	12	Identifying all impacted utilities is critical to establishing the cost of utility relocations. Porticing will minimize this risk.	Accept	Rever possible utily conflicts and conducts possible utily conflicts and littlees each in the PSE Phase Once adentified: contact utils the PSE Phase Once adentified: contact utils the companies and monitor progress. Documents Phase Phases 18, 2 and Alexanne batt Statewake W, Annual Alexanne Confrigency has straphs of thinks to coordingtor the straphs of thinks to coordingtor the using O-12 or Supplemental Fund I meeded.	Uithy Engineer 05/18.21	05/18/21
ى Active Threat	50 0 1891111	Survey and Mapping	If surveying data and mapping information are not oncided in a land whanner no consistent with existing field conditions. adjustments and nodification during project development may be required, which would lead to increased project costs and schedule delys.	Survey data received and assume existing conditions will be reflected in the available surveying and mapping the assumed and assume and available between FM 0-10 and the design or MICS. AC overlay, MPC dires, bus pads, etc. was based on Google Map for this section.	20%	Bernoulli		\$1,000,000	\$1,500,000	\$3,000,000	833,333	6	15	Surveys and maps serve as the basis for the design.	Mitigate	Request survey and mapping information as early as possible in the Design Senior 05/1921 PS&E Phase.	Design Senio	05/19/21
م avitaA fisanT	2	Environmental Impact and dearance	If the scope, environmental setting and/or fains change, the project may reque addromal rows and sculars with would hand to increased project costs and schedule delays.	The environmental document level is a Calegorical Exemption/Categorical Exdustion (CE/CE) per CEGA and Exemption/Categorical Exdustion (CE/CE) per CEGA and Caronal disturbing advective and construction advective caronal disturbing advective advective advective therefiere it is recommended construction take place of vids. therefiere it is recommended construction take place of vids.	80 80	Bernoulli		200 [°] 000	000 56 8	\$200,000	31,500	ę	5	Environmental Inspects determine the level of environmental documental documental needor. Neering prior any be prevention in vegetion that is safet for dearing and grubing.	Mitigate	Inform the Division of Environmental Harming of any chargen is sope or measurementory Schedule construction catacities of train results, season or catacities of train results, season references without course within bird disting season. The District Ideal strain results are ablesting afted. Survey to later than three parts before a resolver wat may the and upper later of 11 for somptistic, or 500 and the search and makes the result und flectfungs have left the next. If undeflect claring construction, work shall be halor. In this area until a qualified in the claring construction, work shall be halor. In this area until a qualified find.	Er v Øenior	05/19/21
on Active Threat	2	Hazardous Materials	It additional unanticipated hazardous waste is discovered during the control additional accuracions waste mitigation additionary mun occur, which would lead to design schedule, debys and project cost increases.	Based on revised HVI Assessment dated 01/17/20; the base of hexacted wave in this point or work the final tot 1. Lead based hermovakatis traffic signing and parament methods and the second method of the second wave (MEST possib), 4. Asheretic commining construction material (ACCM) removal of existing metal berm guard railing, 5. (5.12.70) orsave are eccounted for institutes 6.	20%	Bernoulli		000 ['] 05\$	000'36\$	\$200,000	21,000			Effective handling of hezerdous materials on site reduces the cost of disposal.	Accept	Develop an effective and acceptable plan to dispose of inscription ameteriskip per determination of level of contamination effect evening and investigation.	Hazardous Waste South	05/19/21

EA 32290 - 19 Risk Register xlsx: RR_Level_3

Printed: 6/10/2021: 2:37 PM

Page 1 of 3

Risk Register

			Milestones			Duration	Contacts	Base RW Cap Est (k): \$1,36;	52	Risk Based RW Cap Est (k): \$2,977
1) 1 1 1 2 2 2 2 2 2 2	뎹	PA&ED	PS&E	RWC	CCA	Con Working Days: 400	PM: David H Miraaney	Base Con Cap Est (k): \$27,944	A	ljusted Base Con Cap Est (k): \$28,954
22200 - LX-021-0/10:02-111 LOS Anigetes County on Topanga Canyon between SY-1 & Devolution Batter. AC overlay and ADA Ramps	(M010)	(M200)	(M380)	(M410)	(W600)	Plant Est Days: 0	RM: Chan Q. Kuoch	÷	(%)	Risk Impact on Con Cap (k): \$4,205 (15%)
	06/02/17A	06/21/21	02/15/22	03/03/22	11/17/25	Total Con Days: 400	DM: Refugio Dominguez	Base Total Capital Est (k): \$33,498	8	isk Based Total Capital Est (k): \$36,135
Scope Summary: The project proposes to cold plane and overlay the existing asphalt pavement, upgrade the existing curb ramps to meet the requirements of the Ameri	car	ns with Disabilities Act (ADA) stan	idards, construct	t concrete pads a	s at transit bus stops, upgrade the	e existing Metal Beam Guard i	ting Metal Beam Guard Ralling (MBGR) with Midwest Guardrail S	t Guardrail System (MGS), relocate signa	relocate signals and replace loop detectors due t

			fred		121	121	12	\$21	121	823
			Risk Owner Updated	et	6 06/04/21	/ 105/18/21	on 05/18/21	05/18/21	nior 05/18	on 05/18
			Risk Own	in Storm Water	it Traffic Ops Senior / e Hydraulic Senior	te Project Manager / nd Design Senior	Construction Senior	raffic	on Design Ser	Construction Construction Senior Mann. U5/18/21
		kesponse otrategy	Response Actions	Comply with current requirements early in Comply with current requirements early in the are Design Places E.E. will ensure that we are meeting all legislative requirements for storm water.	Schedule adequate time for the permit schedule adequate time for the permit uncertainty. Design to coordinate and ensure the plans submitted to oity are resisten with all regulatory agencies to obtain permits.	Include a coordination clause in the project separationer (PSSE). Coordinate Manager / projects within the same project limits and Design Senior / projects within the same project limits and Design Senior / adlast the construction schedule to avoid the construction schedule to avoid the same project limits and the same project second schedule to avoid the same project second schedule to avoid second	RE to work with Contractor to minimize the non-working days.	A construction staging plan is being approximate the plan of the plan of the plan work wardows and traffic volumes and work wardows and traffic volumes and integet on the condition plans and to develop traffic handling plans and to develop traffic handling plans and the develop traffic handling plans and traffic handling plans and	Schedule adequate time and Design to obtain Design Exception approval as soon Design Senior 05/18/21 as possible.	Before beginning construction achildes. RE will work with ManthemocRingflood. Way to loa desse senaminents and prevention of future encampnents. Includes language in the project specifications for the Contractor to leage activities of the Contractor to leage sector and the Contractor to leage encampnents. Include in Molece to Educes and Exerce of the work for contractor to molefly the Calmans at leage of deps prior to mediang access to areas in the sign of an white contrapents that affect performance of the work for Calmans to transmost externments.
	ć	Kesp	Strategy	Mitigate	Mitigate	Mitigate	Accept	Mitigate	Accept	Mitigate
			Rationale	Storm water requirement must be met. Surveys and maps serve as the basis effort the design. Carlfrim feesblipt of BMP design. Carlfrim feesblipt of BMP design. Carlfrim feesblipt of Stern.	Identity all permits and approvals necessary.	Need coordination to identify conflicting projects to adjust the construction schedule and accept this risk.	Some weather related and non working days are expected (on avg. of 10%)	Poper handing of traffic is necessary to minimize inconvenience to the public in addition to including sufficient funds to cover Public Information Office (PIO) in base estimates.	Developing design fact sheets and exceptions will affect support costs.	Since proper protoce/guidelines are not set in regards to proper handing of the start impact angle multi-set enanyments, the cost impact angle multi-set in the hour angle the cost in the set in the hour angle to and our allocation of resources the total is established.
		chedule	High	52	8	33	33	8	33	
		Risk Impact on Schedule	Most Likely	ŝ	35	ΰ	£	ŝ	15	
		Risk In	Low	9	8	9	9	6	9	
		15% \$4,204,733	Cost Impact	20,500	600,000	21,000	52,000	5,250	75,000	33.333
	ment	270th Percentile) 270th Percentile)	High (S)	\$100,000	\$2,000,000	\$200,000	\$300,000	\$100,000	\$1,000,000	000 [°] 00c \$
	Risk Impact Assessment	Recommended Contingency (@70th Percentile): Risk Impact on Con Capital (@70th Percentile):	Most Likely (\$)	\$65,000	\$1,500,000	\$95,000	\$160,000	\$47,500	\$750,000	\$150,000
	Risk Imp	Recommended Risk Impact o	Low (\$)	\$50,000	\$1,000,000	\$50,000	\$100,000	\$25,000	\$500,000	\$100,000
			Distribution Parameter							
		Probability	Distribution Type	Bernoulli	Bernoulli	Bernoulli	Bernoulli	Bernoulli	Bernoulli	Bernoulli
			Probability of Occurrence	30%	40%	20%	30%	10%	10%	20%
proposed introvenents, and related earlieded cuth and utilities			Risk Details with Current Status/Assumptions	Project requires a Water Palkino chord Porgan MPCD since the disturbed all end (DSA) created by the poject is sent and near. Project is of required to implement, permater ISP and retrienting or proceedings at BPR- cast of \$500,00 is midded in retiments. It allows that near and sector and additional construction site BMPs may be returbed.	City of Los Angeles/County of Los Angeles may require additional season part of constainer to partit approval (20 intersections will be impacted). During COND, Caltrans has experienced significant elabys accessing that Contractor may experience similar delays when obtaining construction parmits.	The indexing projects are planned within this priced inits brokener school and school and in conflict with this project. E. 28960, 5.4.7510, 5.110, and 5.406 sa will as remergany and initiatientic projects. There could be buildly permitted projects scheduled during the same inversion. To provide confids, Traffic Management Plan, TMP) will be represented.	Impacts from indement weather or natural diseater may require subsequent termologitors and repairs faint. Natural diseater such as fire (see of on previous year in the area) may require suspension of work.	Traffic through the construction site must be maintained and all transportation systems must be protected uning construction. Support on the site of the second All work will be done all in one phase with hybrid should and there disare. Per updated approved TMP Data Sheet dete (11/32/202, \$100,000 is induced in cost estimates.	Roadway geometrics must meet mandatory standards. Exsting conditions may not be feasible to install the required length for MOS at various locations and will be explored during PSE phase risk analysis.	1. Established encomponents are and observed at this time. 2. There is a possibility that future encamponents could take place in this action constrained management 3. Limbed encamponent for unshellored action provider uniconnent for unshellored encomponents. 4. Cost for TRO roly will be encounted for in the following Risk (Unshellered / Hondess - TRO)
curb and gutters.		KISK IGENTIFICATION	Risk Statement	It acroments requirements changes or recommended Best Menagement Practices (BMP) focusions and types are found to be morehelds an outfication to the BMP types and Deatoment may be required, which would head to increased project costs and schedule delays.	As a result of securing proper permits and approvals, additional delays and concessions may occur, which would liked to increased project costs and schedule delays.	If other adjacent Calimars and/or local projects are in construction of the same time as the project, directlers in conditing to artific and work activities between the projects may occur, which would lead to increased project costs and duration.	If impacts from weather and natural disaster or non-working Weather related and days are encountered additional contract non-working days Non-working Days and certeration of contract durations may be required, which Non-working Days and be increased project costs and schedule delays.	Because traffic management systems need to be protected and maintained neurophout the compart network zone. Which modifications to the traffic handling plants much zoner, which would result in additional project costs and schedule delays.	As a result of not having geometric design standards fully assessed, additional effort is required on geometric evaluation and approval in PSE phase, which would lead to increase in both COS and capital orsis of the project.	I unshellered or homeless ensempments are encountered with the project area during construction, additional endor may be required for their removal or possible reflocation, which would lead to increased project cost.
proposed improvements, and replace damaged curb and gutters.			Title	Storm Water Requirements	Permits and Approvals	Construction Coordination (PID Risk #5)	Veather related and Non-working Days	Traffic Control and Handling (PID Risk #2)	Roadway Geometrics and Design	Unsheltered / Homeless - non-TRO
ents, and			Category	uŝo	Ę	CO	e S	Ĕ	Dgn	ō
mprovem			Type	fisentT	Threat	Threat	Threat	Тhreat	Threat	Треай
voposed			Risk Status No.	ص Active	ط Active	∞ 9vit>A	co 9vitoA	5 Active	⇒ Active	⊂ Active
-	-					1				

Risk Register

)							
			Milestones			Duration	Contacts	Base RW Cap Est (k):	\$1,362	Risk Based RW Cap Est (k):	\$2,977
222000 1 027 040 CJ L 1- Andrew Construction Construction Construction Construction And Document	뎹	PA&ED	PS&E	RWC	CCA	Con Working Days: 400	PM: David H Miraaney	Base Con Cap Est (k):	\$27,944	Adjusted Base Con Cap Est (k):	\$28,954
22200 - LA-021-010.02-III LOS AUGUES COUNTY ON LOPANGA CANYON DELWEEN SYCT & DEVOUSTIE SUEEL. AC OVERTAY AND AG	(M010)	(M200)	(M380)	(M410)	(W600)	Plant Est Days: 0	RM: Chan Q. Kuoch	Base Contingency (k):	\$4,192 (15%)	Risk Impact on Con Cap (k):	
	06/02/17A	06/21/21	02/15/22	03/03/22	11/17/25	Total Con Days: 400	DM: Refugio Dominguez	Base Total Capital Est (k):	\$33,498	Risk Based Total Capital Est (k):	\$36,135
Scope Summary: The project proposes to cold plane and overlay the existing asphalt pavement, upgrade the existing curb ramps to meet the requirements of the Americans with	nts of the American	s with Disabilities	s Act (ADA) stan	dards, construct	t concrete pads	at transit bus stops, upgrade th	ie existing Metal Beam Guard	Railing (MBGR) with Midwest Gu	uardrail System	with Disabilities Act (ADA) standards, construct concrete pads at transit bus stops, upgrade the existing Metal Beam Guard Ralling (MBGR) with Michaet Guardral System (MGS), relocate signals and replace toop detectors due	op detectors due to the
hronoved improvements and rendare damaged on the and outface											

č	Kesponse Strategy	Strategy Response Actions Risk Owner Updated	Elere e beginning construction activities, Rew Work with Minimemonoch Stription-di- Wory to to address incomprents and prevention of future encompriments and prevention of future encompriments. The stription of the Contractor to beap performance and event dry nonneless to address and synad providents to beap occurator to address and synad providents to address prior to investigations for address prior to investigation across to areas and the application with the calibrane address and address and synad providents to beap address and synad providents that a fiber performance and environ defines for commonent addres. Expect to see contrigents of futures to cover risk.	Follow the Celhrans procees to list and Design Senior 05/18/21 Accept advertes this project for maximum Design Senior 05/18/21 competition.	Balance experienced and IncoMedgetable staff with new staff and Consider succession planming in addition to having succession planming in addition to having in addition to having succession planming in addition to having in ad	Monitor design progress to conform to the OMS process by provide complete admittals for review. Expect to use controgenor funds to pay for work process a fising from indequate project plans.	Conduct an appropriate stite visit and a
		Rationale	Since proper protocol/guiddines are the proper protocol/guiddines are unshaftered/mineters encampments. The cost impact range (cost associated with claims/TTC only hadded in this is assessment is set in the burr argo it is assessment is each the burr argo for this rost range dealered.	A primum, prices will be A	Staffing and productivity contribute Staffing and productivity contribute Interview to the support of however, it may threate the to delay cost as well as cost for potential re-work and repairs,	By following the OMS process the cost and schedule impact on the estimate Can be minimized	
	schedule	High	5	8	53	3	
	Risk Impact on Schedule	Most Likely	ά	£	÷	5	
	Risk	FLOW	5	ę	6	6	
	: 15% : \$4,204,733	Cost Impact	10,080	162,500	43,333	100,000	
ment	Recommended Contingency (@70th Percentile): Risk Impact on Con Capital (@70th Percentile):	High (\$)	\$ 77,000	\$1,000,000	000'008\$	\$750,000	
mpact Assessment	d Contingency ((on Con Capital ((Most Likely (\$)	\$47,600	\$500,000	\$160,000	\$500,000	
KISK IM	Recommende Risk Impact o	Low (\$)	\$35,000	\$250,000	\$100,000	\$250,000	
		Distribution Parameter					
	Probability	Distribution Type	Bernoulli	Bernoulli	Bernoulli	Bernoulli	
		Probability of Occurrence	20%	30%	25%	20%	
		Risk Details with Current Status/Assumptions	 Established encampments are not observed at this time, place in these is provide that future encampments could take place in this area during construction. Julimed encampment spaceforeas which the project limits provided unfavorable and ormert for unshared encampment. Tire sits is accounting only for TRO cost relating removal ent relocation. 	Uncertainty in prices and economic dimite are expected to voltaring the explorement of the paradimeter stars of Certain the COULD-19 paradimeter device California. Stay At event the COULD-19 paradimeter extends California and the California and the stars of an and california economisms may be magatively impacted resulting in economisms and priority california some materials such as sayable, wood (posi for MISS) etc.	Staffing & resources may be different than anticipated, (new test of the contract statistic). As der est through the contract statistic. To charter at through the normal workdway of the COVID-19 Outforeak has changed the normal workdway of the COVID-19 Outforeak has changed the normal workdway of Outer, most staff are exploring the contract the have it and the contract statistic of the test of outer, most staff are exploring the contract the outer. To an any other and the test of an angements. Some staff may not be an antible due to specialist for decircled supput consultant that order will be uters to specialist for decircled supput consultant that order will be uters to specialist which may reque tASE others to supplement.	Although the project plans will go through several iterations of usafity control and assumone in the PSAE phases errors may still occur which will cause the project plans to be indequate and incomplete.	
	KISK Identification	Risk Statement	I unshelpeed or homeless encampments are encountered within the proper and utimy control and disord time may be required for their remond or possible reflocation, which would lead to increased TRO cost and scheduelle depres.	As a result of a dynamic economy, fluctuations in material prices, equipment costs, and alcorr rises may occur, which would baid to increased project cost.	If stating with the proper experience is unattainable, secaring control to augment the effort or delaying project may be required, which would lead to increased project cost and schedule delays.	If errors and omission have been unintentionally overbooked during the quality control (OC) and quality assurance (OA) construction, which would lead to increased project cost and construction, which would lead to increased project cost and schedule delays.	
		Title	Unshellered / Homeless - TRO	Prices and Economic Conditions	Staffing & Resources	Quality Review	
		Category	ē	Con	Wdd	MAA	
		Status Type Category	Threat	Threat	teanT	Threat	
		Risk Statu No.	ස Active	4 evit5A	بن Active	는 Active	

ATTACHMENT "H" PERFORMANCE OUTPUT

7/26/2021

					SHOPP	SHOPP Project - Accomp	Accomplishme	ent - Pe	lishment - Performance Measures - Benefits	Measur	res - Bé	enefits				
	Distr	rict: 07	District: 07 Tool ID: 15937 🗸	15937 🗸	Project ID:	Project ID: 071600059 <	✓ EA: 32290	>	Co-Rte-PM: LA-027-0.0/18.6 (Primary Location) 🗸	LA-027-0.0	^{,/} 18.6 (Prima	Iry Location	>	View/Print	View/Print PIR (Performance) Report	
	B	Bridge	Z Pavement	int Drainage	ge Facilities	ties 🔽 Safety	aty 🛃 Mobility		Roadside Co	Complete Streets	Sustainability /Climate Change		Advance Mitigation Damage	tion Dama	Major Creen- smage house Gases	Relinquishment
							Performanc	ce & Acc	ormance & Accomplishments	its (PPC 🗸	>					
	Act	ActID		Activity Detail	_		Performance Objective	ive	Unit of Measurement	Quantity	Assets in Good Cond	Assets in Fair Cond	Assets in Assets in New Asset Fair Cond Poor Cond Added	Vew Asset Added	Comment	ant
	1 B2	B25 Asphalt P	Pavement Min	Asphalt Pavement Minor Rehab (CAPM)		Pavem	Pavement Class II		Lane Miles	52.685	0.438	52.247				
	2 B2	B25 Asphalt P	Pavement Min	Asphalt Pavement Minor Rehab (CAPM)		Pavem	Pavement Class III		Lane Miles	8.272		8.272				
L	3 EO	E07 Guard Ra	Guard Rail (201.010, .015)	015)		No Per	No Performance Objective in the SHSMP		Linear Feet	39800.000			39800.000		per PR's 11-page estimate	
	4 E1	E19 Traffic Sig	Traffic Signals (201.010, .015)	0, .015)		No Per	No Performance Objective in th	jective in the SHSMP Each	Each	26.000			26.000		per Design Senior	
	5 F2	F24 ADA - Re	epair/Upgrade	ADA - Repair/Upgrade Curb Ramp (201.361)	361)	No Pen	No Performance Objective in the SHSMP Each	he SHSMP	Each	235.000			235.000		per PR	
	6 F2	F26 ADA - Lo	wer Pedestris	ADA - Lower Pedestrian Push Button (201.361)	11.361)	No Pen	No Performance Objective in th	jective in the SHSMP Each	Each	36.000			36.000		per Design Senior	
	7 F4	F43 ADA - De	ADA - Deficient Elements	nts		ADA Pé	ADA Pedestrian Infrastructure		Deficient Elements	271.000			271.000			
	8 G0	07 Worker S	G07 Worker Safety - Safe Access	Access		Roadsi	Roadside Safety Improvements	_	Locations	2.000			2.000			
	9 G1	10 Worker S	G10 Worker Safety - Vegetation Control	ation Control		Roadsi	Roadside Safety Improvements		Locations	22.000			22.000			
	10 H2	27 Transit S:	H27 Transit Stop Improvements	ients		No Per	No Performance Objective in the SHSMP Each	he SHSMP	Each	49.000			49.000		per PR	
	11 H3	H32 Is any Lo	scation Within	is any Location Within the Project Limits Ped/Bike Accessible?	Ped/Bike Accessi		No Performance Objective in th	jective in the SHSMP Yes/No	Yes/No	Yes						
	12 H3	H37 Bicycle-To	Bicycle-Tolerable Drainage Grates	nage Grates		No Per	No Performance Objective in th	jective in the SHSMP Each	Each	2.000				2.000	ET No. 530274000379002 and 530270000356004	nd 530270000356004
	13 NO	02 Quantitat	N02 Quantitative - Proposed Mitigated	d Mitigated		No Pen	No Performance Objective in th	jective in the SHSMP MTCO2e	MTCO2e	7827.000					0% red. GHG Ems due to Con & MT tech.	on & MT tech.
	14 N0	03 Quantitat	N03 Quantitative - Unmitigated	ated		No Pen	No Performance Objective in th	jective in the SHSMP MTCO2e	MTCO2e	7827.000						
	(Last	t Saved - 07/	/25/21 @ 9:26	(Last Saved - 07/25/21 @ 9:26 PM by Roger Yoh)	(-											
4																

1 CALL 1 ċ ŝ ò .

1		
	Post- Total	61.0
	Post- Poor	0.0
	Post-Fair	0.0
	Post Good+New	61.0
	New	0.000
	Post Good	61.0
	Pre-Total	61.0
	lir Pre-Poor	0:0
	Pre-Fair	60.5
	Pre-Good	0.4
	Unit	Lane mile(s)
	Performance Measure	Lane mile(s)
ocations)	Performance Value	61.0
ary (All Lo	Asset	Pavement
e Summa	Asset Class	Primary Pavement
rogramming Performance Summary (All Locations)	Activity Category	Pavement
Programm	Program Code	201.121 Pavement

Notes:

The crosswalk for reporting performance in the "Programming Performance Summary" was developed to assist the districts on performance reporting requirements for CTC and PCRs. For discrepancies or errors, please notify AM Tool admins via e-mail at CT-TAM@dot.ca.gov.

2. The data summarized in the table represents the performance reported or to be reported in CTIPS.

Programming only requires the breakdown of Good, Fair and Poor for Primary and Supplementary Asset Classes.
 Reporting of bridge pre and post conditions may contain errors if the project RTL is before 2024/25.

ATTACHMENT "I" TMP DATA SHEET

TRANSPORTATION MANAGEMENT PLAN DATA SHEET (Preliminary TMP Elements and Costs)

	, 	•
Co/Rte/PM	LA-27, PM 0.0/18.6 EA 07160000	
Project Limit	Route 27 from Pacific Coast Highway (PM 0	
-	in Los Angeles County.	
Project Descrip		plane and overlay the existing
1 roject 2 cherif	asphalt pavement, dig-out damaged paver	
	with new structural sections, upgrade the	
	requirements of the American with Disab	
	construct concrete pads at transit bus stop	
	Midwest Guardrail System (MGS), reloca	
	due to the proposed improvements and re	
		<u> </u>
1) Pub	lic Information	
	a. Brochures and Mailers	\$
	🔀 b. Press Release	
	🔀 c. Paid Advertising	\$10,000
	d. Public Information Center/Kiosk	\$
	e. Public Meeting/Speakers Bureau	
	f. Telephone Hotline	
	🔀 g. Internet	
	h. Others	\$
2) Mot	orists Information Strategies	
	🔀 a. Changeable Message Signs (Fixed)	\$0
	b. Changeable Message Signs (Portable)	\$
	c. Ground Mounted Signs	\$
	🗌 d. Highway Advisory Radio	\$ [.]
	e. Caltrans Highway Information Network	(CHIN)
	f. Others	\$
3) Inci	dent Management	
	a. Construction Zone Enhanced Enforcem	ent
	Program (COZEEP)	\$90,000
	b. Freeway Service Patrol	\$
	c. Traffic Management Team	
	d. Helicopter Surveillance	\$
	e. Traffic Surveillance Stations	
	(Loop Detector and CCTV)	\$
-	f. Others	\$.

4) Construction	Strategies
-----------------	------------

4) Construction Strategies	
🔀 a. Lane Closure Chart	
b. Reversible Lanes	
c. Total Freeway Mainline Closure	
d. Extended Weekend Closure	
e. Contra Flow	
f. Truck Traffic Restrictions	\$
🔀 g. Reduced Speed Zone	\$
h. Connector and Ramp Closures	
i. Incentive and Disincentive	\$
j. Moveable Barrier	\$
k. Others	\$
5) Demand Management	
a. HOV Lanes/Ramps (New or Convert)	\$
b. Park and Ride Lots	\$
c. Rideshare Incentives	\$
d. Variable Work Hours	·
e. Telecommute	
f. Ramp Metering (Temporary Installation)	\$
g. Ramp Metering (Modify Existing)	\$
h. Others	\$
6) Alternative Route Strategies	
a. Add Capacity to Freeway Connector/Ramps	\$
b. Street Improvement (widening, traffic signal etc)	\$
c. Traffic Control Officers	\$
d. Parking Restrictions	
e. Others	\$
7) Other Strategies	
a. Application of New Technology	\$
e. Others	\$

Project Notes:

- 1. This TMP Data Sheet supersedes the previous one dated 02/04/2016.
- 2. The Public Awareness Campaign (PAC) cost estimate of \$10,000 was provided by,
 - Dave White, Caltrans Office of Public Affairs and Media Relations, on January 8, 2020.
- 3. In the "Instruction to RE File", inform RE to Notify Public Affairs prior to construction to ensure that a PIO is assigned for the project.
- 4. The COZEEP cost estimate of \$90,000 was provided by Michael Lopez (Construction Traffic Advisor) on January 13, 2020.
- 5. The following existing fixed Changeable Message Signs (CMS) may be utilized to inform motorists on traffic conditions during construction:
- Northbound Route 101: #108 (De Soto Ave) &
- Southbound Route 101: #114 (Parkway Calabasas).
- 6. It is anticipated that work will be performed in accordance with the Lane Closure Charts provided in the Maintenance Traffic Specifications.
- 7. Any changes in construction strategy that would result in a different type of closures other than indicated here shall require a revision for the TMP Data Sheet.

PREPARED BY

APPROVED BY

Maryam Sarafzade APPROVAL RECOMMENDED BY Γ.E tayan

Morteza Fahrtash. District Traffic Manager

DATE 1/13/2020

DATE DATE