

ROAD REPAIR AND ACCOUNTABILITY ACT OF 2017
PROJECT BASELINE AGREEMENT

Vincent Thomas Bridge Deck Replacement (07-39020)

Resolution SHOPP-P-2425-05B

(to be completed by CTC)

1. FUNDING PROGRAM

- ☐ Active Transportation Program
- ☐ Local Partnership Program (Competitive)
- ☐ Solutions for Congested Corridors Program
- ☒ State Highway Operation and Protection Program
- ☐ Trade Corridor Enhancement Program

2. PARTIES AND DATE

- 2.1 This Project Baseline Agreement (Agreement) effective on March 20, 2025 (will be completed by CTC), is made by and between the California Transportation Commission (Commission), the California Department of Transportation (Caltrans), the Project Applicant, Caltrans, and the Implementing Agency, Caltrans, sometimes collectively referred to as the "Parties".

3. RECITAL

- 3.1 Whereas at its 3/22/2024 meeting the Commission approved the State Highway Operation and Protection Program and included in this program of projects the Vincent Thomas Bridge Deck Replacement (07-39020), the parties are entering into this Project Baseline Agreement to document the project cost, schedule, scope and benefits, as detailed on the Project Programming Request Form attached hereto as **Exhibit A**, the Project Report attached hereto as **Exhibit B**, the Performance Metrics Form, if applicable, attached hereto as **Exhibit C**, as the baseline for project monitoring by the Commission.
- 3.2 The undersigned Project Applicant certifies that the funding sources cited are committed and expected to be available; the estimated costs represent full project funding; and the scope and description of benefits is the best estimate possible.

4. GENERAL PROVISIONS

The Project Applicant, Implementing Agency, and Caltrans agree to abide by the following provisions:

- 4.1 To meet the requirements of the Road Repair and Accountability Act of 2017 (Senate Bill [SB] 1, Chapter 5, Statutes of 2017) which provides the first significant, stable, and on-going increase in state transportation funding in more than two decades.
- 4.2 To adhere, as applicable, to the provisions of the Commission:
- ☐ Resolution , "Adoption of Program of Projects for the Active Transportation Program", dated
- ☐ Resolution , "Adoption of Program of Projects for the Local Partnership Program", dated
- ☐ Resolution , "Adoption of Program of Projects for the Solutions for Congested Corridors Program", dated
- ☒ Resolution G-24-34 , "Adoption of Program of Projects for the State Highway Operation and Protection Program", dated 3/22/2024
- ☐ Resolution , "Adoption of Program of Projects for the Trade Corridor Enhancement Program", dated

- 4.3 All signatories agree to adhere to the Commission's Guidelines. Any conflict between the programs will be resolved at the discretion of the Commission.
- 4.4 All signatories agree to adhere to the Commission's SB 1 Accountability and Transparency Guidelines and policies, and program and project amendment processes.
- 4.5 Caltrans agrees to secure funds for any additional costs of the project.
- 4.6 Caltrans agrees to report to Caltrans on a quarterly basis; on the progress made toward the implementation of the project, including scope, cost, schedule, and anticipated benefits/performance metric outcomes.
- 4.7 Caltrans agrees to prepare program progress reports on a semi-annual basis and include information appropriate to assess the current state of the overall program and the current status of each project identified in the program report.
- 4.8 Caltrans agrees to submit a timely Completion Report and Final Delivery Report as specified in the Commission's SB 1 Accountability and Transparency Guidelines.
- 4.9 Caltrans agrees to submit a timely Project Performance Analysis as specified in the Commission's SB 1 Accountability and Transparency Guidelines.
- 4.10 All signatories agree to maintain and make available to the Commission and/or its designated representative, all work related documents, including without limitation engineering, financial and other data, and methodologies and assumptions used in the determination of project benefits and performance metric outcomes during the course of the project, and retain those records for six years from the date of the final closeout of the project. Financial records will be maintained in accordance with Generally Accepted Accounting Principles.
- 4.11 The Inspector General of the Independent Office of Audits and Investigations has the right to audit the project records, including technical and financial data, of the Department of Transportation, the Project Applicant, the Implementing Agency, and any consultant or sub-consultants at any time during the course of the project and for six years from the date of the final closeout of the project, therefore all project records shall be maintained and made available at the time of request. Audits will be conducted in accordance with Generally Accepted Government Auditing Standards.

5. SPECIFIC PROVISIONS AND CONDITIONS

- 5.1 Project Schedule and Cost
See Project Programming Request Form, attached as Exhibit A.
- 5.2 Project Scope
See Project Report or equivalent, attached as Exhibit B. At a minimum, the attachment shall include the cover page, evidence of approval, executive summary, and a link to or electronic copy of the full document.
- 5.3 Performance Metrics
See Performance Metrics Form, if applicable, attached as Exhibit C.

Attachments:

- Exhibit A: Project Programming Request Form
Exhibit B: Project Report
Exhibit C: Performance Metrics Form (*if applicable*)

SIGNATURE PAGE
TO
PROJECT BASELINE AGREEMENT

Project Name Vincent Thomas Bridge Deck Replacement (07-39020)

Resolution SHOPP-P-2425-05B

(to be completed by CTC)

Rimma Tebeleva

01/15/2025

Rimma Tebeleva

Date

Project Manager

Project Applicant

David Yan

01/17/2025

David Yan

Date

Chief, Office of Program Management

Implementing Agency

Gloria Roberts

01/25/2025

Gloria Roberts

Date

District Director

California Department of Transportation

Tony Tavares

02/27/2025

Tony Tavares

Date

Director

California Department of Transportation

Tanisha Taylor

10/31/2025

Tanisha Taylor

Date

Executive Director

California Transportation Commission

Baseline agreement information was extracted from Caltrans' project data systems. Project description, funding and performance measures are from CTIPS. Project delivery milestones are from PRSM. All information is current and accurate.

STATE OF CALIFORNIA • DEPARTMENT OF TRANSPORTATION

BASELINE AGREEMENT

Date: 01/28/25 09:33:31 AM

District	EA	Project ID		PPNO	Project Manager
07	39020	0722000334		6024	TEBELEVA, RIMMA
County	Route	Begin Postmile	End Postmile	Implementing Agency	
LA	47	R 0.4	2.1	PA&ED	Caltrans
				PS&E	Caltrans
				Right of Way	Caltrans
				Construction	Caltrans

Project Nickname

Vincent Thomas Bridge Deck Replacement

Location/Description

In the city of Los Angeles, near the Port of Long Beach, at Vincent Thomas Bridge No. 53-1471. Replace bridge deck and seismic sensors. This is a Construction Manager/General Contractor (CMGC) project. (G13 Contingency)

Legislative Districts

Assembly: 70 **Senate:** 35 **Congressional:** 44

PERFORMANCE MEASURES

	Primary Asset	Good	Fair	Poor	New	Total	Units
Existing Condition	Bridge Health			352044		352044	Square feet of bridge deck
Programmed Condition	Bridge Health	352044				352044	Square feet of bridge deck

Project Milestone

	Actual	Planned
Project Approval and Environmental Document Milestone	10/24/24	
Right of Way Certification Milestone		07/15/25
Ready to List for Advertisement Milestone		08/15/25
Begin Construction Milestone (Approve Contract)		12/26/25

FUNDING (Allocated amounts are shaded)

Component	Fiscal Year	SHOPP					Total
PA&ED	22/23	17,140					17,140
PS&E	23/24	30,360					30,360
RW Support	23/24	1,683					1,683
Const Support	25/26	46,336					46,336
RW Capital	25/26	3,230					3,230
Const Capital	25/26	618,589					618,589
Total		717,338					717,338

Supplemental Project Report

For Project Approval

On Route 47

Between PM R0.4

And PM 2.1

I have reviewed the right-of-way information contained in this report and the right-of-way data sheet attached hereto, and find the data to be complete, current, and accurate:

Dan Murdoch, Deputy District Director, Right of Way

APPROVAL RECOMMENDED:

Rimma Tebeleva, Project Manager

APPROVAL RECOMMENDED:


Gregory Farr, Deputy District Director, Design

PROJECT APPROVED:

Gloria Roberts, District 7 Director

Date

Vicinity Map



Vincent Thomas Bridge Deck Replacement Project LA-47-PM R0.4/2.1 - EA 39020

This supplemental project report has been prepared under the direction of the following registered civil engineer. The registered civil engineer attests to the technical information contained herein and the engineering data upon which recommendations, conclusions, and decisions are based.

*REGISTERED CIVIL ENGINEER**DATE*

Table of Contents

1. INTRODUCTION	0
2. RECOMMENDATION	1
3. BACKGROUND	1
4. PURPOSE AND NEED.....	1
A. Problem, Deficiencies, Justification.....	1
B. Regional and System Planning.....	1
B. Traffic.....	1
5. ALTERNATIVES.....	1
5A. Viable Alternatives	1
5B. Rejected Alternatives	2
6. CONSIDERATIONS REQUIRING DISCUSSION	2
6A. Hazardous Waste Management.....	2
6B. Value Analysis	3
6C. Resource Conservation.....	3
6D. Right-of-Way Issues	3
6E. Environmental Compliance	3
6F. Air Quality Conformity	3
6G. Title VI Considerations.....	3
6H. Noise Study Analysis.....	3
6I. Life-Cycle Cost Analysis.....	3
6J. Reversible Lanes	3
7. OTHER CONSIDERATIONS AS APPROPRIATE	3
Public Hearing Process	3
Permits	3
Transportation Management Plan	3
Stage Construction and Detour Routes.....	3
Accommodation of Oversize Loads.....	3
Graffiti Control	3
Asset Management.....	3
Complete Streets	3
Broadband and Advanced Technologies	3
8. FUNDING, PROGRAMMING AND ESTIMATES	3

Funding	4
Programming and Cost Estimates	4
9. DELIVERY SCHEDULE.....	4
10. RISKS	5
11. EXTERNAL AGENCY COORDINATION	5
12. PROJECT REVIEWS	5
13. PROJECT PERSONNEL.....	5
14. ATTACHMENTS.....	5

1. INTRODUCTION

Project Description:

This Supplemental Project Report (SPR) to Project Report approved on 10/24/2024 was prepared to a) Extend the east post limit of the project by 0.1 miles, b) Include additional work within the extended limit, c) Make the associated adjustments to the Cost Estimate and Funding Table based on the added scope and other adjustments resulting from the development of the 60% preliminary plans and d) Revise the project Risk Register as needed.

This project proposes to replace the entire bridge deck, bridge railings and fences, median barrier, seismic sensors and upgrade the lighting system of the Vincent Thomas Bridge (VTB) (Bridge #53-1471) on State Route 47 (SR-47) in Los Angeles County as recommended by the Office of Structure Maintenance and Investigations.

The original post-mile limits (PM 0.4/2.0) are being revised to PM R0.4/2.1. The prefix “R,” which is stated correctly in the CTIPS document but missing in the approved Project Report, was added to the lower post-mile limit. This correction did not produce any changes to the original work limit at the west end of the bridge.

On the east end of the bridge, the post-mile was extended by 0.1 miles (PM 2.0 to 2.1) to cover an additional scope consisting of relocating an overhead sign from the east approach (within the bridge limits) to a location outside the bridge limits. This was required to avoid construction conflicts between the heavy crane equipment and the existing overhead sign during the complex construction strategy adopted for the project. The transition of the new bridge section, featuring new ST-75 bridge railing, to the existing roadway section also requires the upgrade of the existing and old metal beam guard railing (MBGR) to the current standard Midwest Guardrail System (MGS), which will protect the relocated overhead sign and existing electroliers within the 0.1-mile extension.

The table below summarizes the revised funding information. The previous figures in the original Project Report are shown crossed out for reference only.

Project Data Summary Table

Project Limits	LA-047, PM R0.4/2.1	
Number of Alternatives	2 – No Build, and Build	
	Current Cost Estimate: (Preferred Alternative)	Escalated Cost Estimate: (Preferred Alternative)
Capital Outlay Support	93,259,600 91,354,000	97,424,000 95,519,000
Capital Outlay Construction	589,479,000 568,160,000	641,800,000 618,589,000
Capital Outlay Right-of-Way	1,730,000 3,230,000	1,730,000 3,230,000
Funding Source	Bridge Formula Program 20.XX.201.116	
Funding Year	2026	
Type of Facility	4-Lane Freeway	

Number of Structures	1
SHOPP Project Output	See Attachment I for SHOPP Performance Measures
Environmental Determination or Document	EIR/EA
Legal Description	In Los Angeles County, in the City of Los Angeles, on Route 47 from PM R0.4 to PM 2.1
Project Development Category	Category 5 - Projects of minimal economic, social, or environmental significance. These projects would include those categorically exempt under CEQA.

2. RECOMMENDATION

It is recommended that this Supplemental Project Report (SPR) be approved, its changes incorporated into the approved Project Report (PR) and adopted in the ongoing development of the project PS&E phase.

The following sections of the approved Project Report remain unchanged.

3. BACKGROUND

4. PURPOSE AND NEED

A. Problem, Deficiencies, Justification

B. Regional and System Planning

B. Traffic

5. ALTERNATIVES

5A. Viable Alternatives

Alternative 1 - No Build alternative.

Alternative 2 – Build Alternative

Alternative 2 -Build Alternative Scope

The following is a list of the major scope items included in Alternative 2. Except for the types of decks referred to above, all the listed items are shared for the different deck materials or deck types analyzed, and therefore, they will apply to the selected preferred alternative. Project scope items added because of the extended post-mile limit from PM 2.0 to 2.1 are listed at the end of the following list with the sub-title: “Extended Post-mile Limit Scope”.

- Removal and replacement of the existing lightweight bridge concrete deck along the approach and suspension spans with new concrete and/or orthotropic deck.
- Removal of the existing metal railing and steel plate curb (suspended spans) and their replacement with a CA ST-75 Bridge Rail.
- Removal of the existing 12’ height chain link fence on each side of the

suspended spans, and its replacement with a 12' height chain link fence.

- Removal of the existing Type 2 Barrier with a 6' barrier-mounted chain link fence along approach spans, and replacement with a CA ST-75 bridge railing with a 9' curb-mounted chain link fence.
- Removal of the existing median concrete barrier Type 50 and replacement with Type 60M concrete barrier or, optionally, a steel barrier.
- Removal and replacement of 18 joint seals along approach spans.
- Remove and replace 11 joint seals on suspension spans.
- Removal of 4 finger joints at four locations on the suspension spans and replacement with seismic joints.
- Removal of existing 26 seismic sensors and replacement with 44 upgraded seismic sensors.
- Removal and replacement of 29 barrier-mounted electroliers along approach spans.
- Upgrading of 160 light fixtures of the "low light system" along suspended spans.
- Installation/Upgrade of signs (one OH sign and approximately 26 barrier and/or pole-mounted roadside signs), pavement delineation, and pavement marking per current standard.
- Installation of 30 power receptacles on the bridge's sub-structure for the maintenance painting crew.

Extended Post-mile Limit Scope (PM 2.0/2.1)

- Removal of concrete curb and MBGR (L=1,050')
- Installation of Midwest Guard Rail (MGS) (L=1,050)
- Removal of asphalt concrete pavement behind the new MGS
- Relocation/Replacement of 8 Electroliers to the back of new MGS.
- Installation of 2 MGS-AGT rail transitions between the ST-75 and MGS railing.
- Removal of the OH Sign across the roadway on the east approach of the bridge.
- Installation of a one-post Overhead Sign (CIDH) at the east end of the bridge (outside the bridge)

Except for Subsection 6D, Subsections 5B through Section 7 of the approved Project Report remain unchanged.

5B. Rejected Alternatives

6. CONSIDERATIONS REQUIRING DISCUSSION

6A. Hazardous Waste Management

6B. Value Analysis**6C. Resource Conservation****6D. Right-of-Way Issues** (a paragraph has been added before sub-section 6E title)

No permanent Right of Way will be required to complete the proposed construction of this project. A Right of Way Data Sheet was prepared and approved on 10/xx/2024 (See Attachment F). Caltrans owns easement rights, which extend 25' beyond the deck drip line or edges of the bridge since the bridge was constructed in 1963.

The CMGC team has expressed the need to install 4 temporary elevators at ground level under the bridge for workers' access during the construction phase. The installation of these elevators may require short temporary use of areas beyond the current State rights of way. The Port of Los Angeles has been contacted, and they are receptive to issuing an entry permit license, which would minimize the interference with tenant operations.

During public meetings, the communities expressed concerns about air quality due to high volumes of heavy traffic along detours crossing residential and sensitive areas during the bridge closures. Funding for \$1.5 million has been included as part of the Right of Way Capital Cost to cover the provision of air filters to the residences along routes being affected as a mitigation measure.

6E. Environmental Compliance**6F. Air Quality Conformity****6G. Title VI Considerations****6H. Noise Study Analysis****6I. Life-Cycle Cost Analysis.****6J. Reversible Lanes****7. OTHER CONSIDERATIONS AS APPROPRIATE****Public Hearing Process****Permits****Transportation Management Plan****Stage Construction and Detour Routes****Accommodation of Oversize Loads****Graffiti Control****Asset Management****Complete Streets****Broadband and Advanced Technologies****8. FUNDING, PROGRAMMING AND ESTIMATES**

Funding

It has been determined that this project is eligible for Federal-aid funding.

Programming and Cost Estimates

The table below provides updated figures reflecting changes supported by this Supplemental Project Report for the selected alternative, the current programmed information for the project cost component, and the updated cost estimate by component. The current cost estimate for support is escalated to the middle of each component at a rate of 3.7% per year for each component. The construction capital cost is escalated to mid-construction at a rate of 4.89% for FY 24/25 and 3.80% for FY 25/26 and beyond. The Right of Way capital is escalated at 8% to 07/30/2027.

Fund Source	Programming by Fiscal Year Preferred Build Alternative (Thousands)								Current Estimate (Escalated)
	Prior	24/25	25/26	26/27	27/28	28/29	Future	Programmed Total	At PAED Total
20.XX.201.116									
Component	In thousands of dollars (\$1,000)								
PA&ED Support	17,140							17,140	17,140*
PS&E Support	20,900							20,900	30,360**
Right-of- Way Support	17							17	1,683**
Construction Support			39,840					39,840	46,336
Right-of- Way			30					30	3,230
Construction			628,464					628,464	618,589
Total	38,057		668,334					706,391	717,338

* Does not include approved G-12 funding, which is \$19,054K

** Voted by CTC in December 2024

9. DELIVERY SCHEDULE

Project Milestones		Milestone Date (Month/Day/Year)	Milestone Designation (Target/Actual)
PROGRAM PROJECT	M015	01/26/2023	A
BEGIN PAED	M020	02/03/2023	A

NOTICE OF PREPARATION (NOP)	M030	04/12/2023	A
CIRCULATE DED EXTERNALLY	M120	04/16/2024	A
PA & ED	M200	10/24/2024	A
START PS&E	M210	12/09/2024	A
PRE-60% PS&E		01/31/2025	T
60% CONST PS&E COMPLETED	M313	03/14/2025	T
PRE-95% PS&E		04/10/2025	T
95% CONST PS&E COMPLETED	M315	05/22/2025	T
PS&E TO DOE	M377	06/20/2025	T
DRAFT STRUCTURES PS&E	M378	05/01/2025	T
PROJECT PS&E	M380	07/15/2025	T
RIGHT-OF-WAY CERTIFICATION	M410	07/15/2025	T
READY TO LIST	M460	08/15/2025	T
FUND ALLOCATION	M470	10/16/2025	T
HEADQUARTERS ADVERTISE	M480	10/31/2025*	T
AWARD	M495	12/01/2025*	T
APPROVE CONTRACT	M500	12/26/2025*	T
CONTRACT ACCEPTANCE	M800	02/29/2028	T
END PROJECT	M800	05/01/2029	T
PROJECT CLOSEOUT	M900	04/01/2030	T

*The schedule reflects the General Contractor (CMGC) program schedule.

10. RISKS

An updated Risk Register is included in the Attachments section, reflecting changes supported by this Supplemental Project Report. The risk impacts of the project have been re-evaluated and the Risk Register has been updated. Refer to Attachment H (Risk Register) for more details included with this Supplemental Project Report.

11. EXTERNAL AGENCY COORDINATION

12. PROJECT REVIEWS

13. PROJECT PERSONNEL


14. ATTACHMENTS (the list of attachments modified is included)

- B. Location map (with revised project PM limits)
- D. Preliminary Layout Plans
- E. Preferred Alternatives Cost Estimate (11-page)
- F. Right of Way Data Sheet
- G. Storm Water Data Report (1)
- H. Risk Register
- I. Approved Project Report (10/24/2024)

ATTACHMENT B

Location Map

LOCATION MAP



Vincent Thomas Bridge Deck Replacement Project
LA-47-PM R0.4/2.1 - EA 39020

ATTACHMENT D

Preliminary Layout Plans

ATTACHMENT F

Right of Way Data Sheet

ATTACHMENT G

Storm Water Data Report (SWDR)

ATTACHMENT H

Risk Register

Project Report

For Project Approval

On Route 47

Between PM 0.4

And PM 2.0

I have reviewed the right-of-way information contained in this report and the right-of-way data sheet attached hereto, and find the data to be complete, current, and accurate:



Dan Murdoch, Deputy District Director, Right of Way

APPROVAL RECOMMENDED:



for **Rimma Tebeleva**, Project Manager

APPROVAL RECOMMENDED:



Gregory Farr, Deputy District Director, Design

PROJECT APPROVED:




Gloria Roberts, District 7 Director

10/24/2024

Date

Vicinity Map



Vincent Thomas Bridge Deck Replacement Project LA-47-PM 0.4/2.0 - EA 390201

This project report has been prepared under the direction of the following registered civil engineer. The registered civil engineer attests to the technical information contained herein and the engineering data upon which recommendations, conclusions, and decisions are based.


REGISTERED CIVIL ENGINEER

10/14/2024
DATE



Table of Contents

1. INTRODUCTION	0
2. RECOMMENDATION	0
3. BACKGROUND	0
4. PURPOSE AND NEED.....	1
A. Problem, Deficiencies, Justification.....	1
B. Regional and System Planning.....	2
B. Traffic.....	2
5. ALTERNATIVES.....	4
5A. Viable Alternatives	4
5B. Rejected Alternatives	11
6. CONSIDERATIONS REQUIRING DISCUSSION	11
6A. Hazardous Waste Management.....	11
6B. Value Analysis	12
6C. Resource Conservation.....	12
6D. Right-of-Way Issues	12
6E. Environmental Compliance.....	13
6F. Air Quality Conformity	13
6G. Title VI Considerations.....	13
6H. Noise Study Analysis.....	13
6I. Life-Cycle Cost Analysis.....	14
6J. Reversible Lanes	14
7. OTHER CONSIDERATIONS AS APPROPRIATE	14
Public Hearing Process	14
Permits	14
Transportation Management Plan.....	15
Stage Construction and Detour Routes.....	15
Accommodation of Oversize Loads.....	16
Graffiti Control	16
Asset Management.....	16
Complete Streets	16
Broadband and Advanced Technologies	16
8. FUNDING, PROGRAMMING AND ESTIMATES	16

Funding	16
Programming and Cost Estimates	17
9. DELIVERY SCHEDULE.....	18
10. RISKS	18
11. EXTERNAL AGENCY COORDINATION	18
12. PROJECT REVIEWS	19
13. PROJECT PERSONNEL.....	19
14. ATTACHMENTS.....	20
A. Final Environmental Impact Report/Environmental Assessment	20
B. Location Map	20
C. Typical Cross Sections	20
D. Preliminary Layout Plans	20
E. Preferred Alternative Cost Estimate (11-page)	20
F. Right of Way Data Sheet	20
G. Storm Water Data Report.....	20
H. Risk Register	20
I. SHOPP – Performance Measures	20
J. Transportation Management Plan Datasheet.....	20
15. REFERENCES – Eng Studies/Technical Reports (available upon request)	20
1. Advance Planning Study (APS) – Feb-2024	20
2. Traffic Operations Analysis Report.....	20
3. Noise Study Report.....	20
4. Bird Deterrent Report	20
5. Type Selection Report	20
6. Asbestos and Lead-Containing Paint Survey Report	20
7. Value Analysis Study	20
8. Design Standard Decision Document.....	20

1. INTRODUCTION

Project Description:

This project proposes to replace the entire bridge deck, bridge railings and fences, median barrier, seismic sensors, and upgrade the lighting system of the Vincent Thomas Bridge (VTB) (Bridge #53-1471) on State Route 47 (SR-47) in Los Angeles County as recommended by the Office of Structure Maintenance and Investigations.

Project Limits	LA-047, PM 0.4/2.0	
Number of Alternatives	2 – No Build, and Build	
	Current Cost Estimate: (Preferred Alternative)	Escalated Cost Estimate: (Preferred Alternative)
Capital Outlay Support	91,355,000	95,520,000
Capital Outlay Construction	550,336,000	599,183,000
Capital Outlay Right-of-Way	1,730,000	1,730,000
Funding Source	Bridge Formula Program 20.XX.201.116	
Funding Year	2026	
Type of Facility	4-Lane Freeway	
Number of Structures	1	
SHOPP Project Output	See Attachment I for SHOPP Performance Measures	
Environmental Determination or Document	EIR/EA	
Legal Description	In Los Angeles County, in the City of Los Angeles, on State Route SR-47 from PM 0.4 to PM 2.0	
Project Development Category	Category 4B. Projects that do not require substantial new right-of-way and do not substantially increase traffic capacity. The project requires an Environmental Impact Report rather than a negative declaration or being categorically exempt under CEQA..	

2. RECOMMENDATION

It is recommended that this Project Report (PR) be approved to adopt the preferred alternative and that the project proceed to the development of the PS&E phase. The affected local agencies have been consulted concerning the recommended plan, their views have been considered, and the local agencies are in general accord with the plan as presented.

3. BACKGROUND

State Route 47 (SR-47) is a freeway that extends from Route I-110 in San Pedro via the Vincent Thomas Bridge to Route I-710. The Vincent Thomas Bridge is a cable-

suspension steel bridge spanning the main channel of Los Angeles Harbor between San Pedro and Terminal Island.

The structure, completed in 1963, has a total length of 6,062 feet. The bridge, which is the main gateway to the Port of Los Angeles, carries an average of 58,000 vehicles daily, of which 6.4% are heavy trucks.

The bridge consists of two concrete approaches (East and West) supported on concrete abutments and bents with span lengths varying between 130' and 230', and three cable-suspended spans of 500', 1500', and 500', comprising the middle portion of the bridge. Two main steel towers combined with massive concrete anchor blocks support these three central suspended spans. The concrete bridge concrete has a variable width between 54.5' for the suspended spans and 58' for the approach spans.

4. PURPOSE AND NEED

Purpose:

The purpose of the project is to restore the structural integrity of the Vincent Thomas Bridge (Bridge #53-1471) deck and improve the overall safety of the facility for the traveling public and maintenance workers.

Need:

There is a need to replace the bridge deck which is rapidly deteriorating due to concrete fatigue caused by heavy truck traffic and the salty marine environment it has been exposed to, throughout the past several decades. The bridge must be often closed for repairs which exposes maintenance crews working next to live traffic. In addition, the existing median barrier and railing do not meet the new Manual for Assessing Safety Hardware (MASH) standards.

A. Problem, Deficiencies, Justification

In 2001, a Structure Maintenance investigation was performed, and it was determined that the bridge deck was 60% to 70% delaminated. A recommendation was made to rehabilitate the bridge deck with a polyester concrete overlay. In 2009, a polyester concrete overlay was applied to the bridge deck to address spalling in the bridge deck. Starting in 2011, new deck spalls began to occur and have been increasing in severity with each subsequent bridge inspection. An in-depth investigation of the bridge deck was performed using ground penetrating radar equipment, rapid automated sounding equipment, and physical and chemical concrete testing. Test results of concrete samples showed that the deck was failing below the polyester overlay causing the subsequent spalling.

A Structure Maintenance and Investigation (SM&I) Bridge Strategy Meeting was held on 09/09/2021 to determine the appropriate remediation strategy to address the accelerated deterioration of the bridge deck. The SM&I Bridge Strategy session recommended that the decks for both the suspended and approaching spans be removed and replaced.

B. Regional and System Planning

The State Route 47, where the Vincent Thomas Bridge is located, is part of the following federal and State systems:

National Highway System (NHS)

The NHS consists of approximately 160,000 miles of highways across the United States, and it includes all interstate routes, a large percentage of urban and rural principal arterials, the defense strategic highway network, and strategic highway connectors. SR-47 is a subset of the National Highway System, categorized under “Other NHS Routes”.

Freeway and Expressway System

SR-47 is part of the State Highway System, according to Section 347 in Article 3 of the Streets and Highway Code.

Federal Surface Transportation Assistance Act (STAA)

The purpose of the STAA is to identify and address issues with highways and bridges included in the Interstate System, such as truck access and operations on highways. SR-47 is a Terminal Access route. A Terminal Access route allows STAA truck access between National Network Routes or a freight terminal facility.

State Planning

The 2015 Transportation Concept Report (TCR) for SR-47 identifies the segment containing the project as Segment 1A (Vincent Thomas Bridge). This segment has a functional classification of expressways and is a Terminal Access Route. Referencing the SCAG’s 2012-2035 Regional Transportation Plan/Sustainable Community Strategy (RTP/SCS), the TCR recommends maintaining the existing facility of two mixed flow lanes in either direction through this segment.

Local Planning

The VTB deck replacement project is in conformance with the different improvement projects of the Port of Los Angeles Waterfront Master Plan which includes Front Street, Harbor Boulevard, and Regan Street to be part of the “Heavy Container Corridor”. The project is also compatible with the San Pedro Waterfront and Promenade Master Plan.

B. Traffic

Current Traffic

Table 4.1 below shows the total traffic and truck traffic volumes for the year 2022 from the Traffic Census Program. It is worth noting that the percentage of type 5 (5 axles or more) trucks make up 41% of the total heavy truck volume.

Table 4.1 - Traffic Volumes and Traffic Composition (Year 2022)

Location	Total AADT	Peak MADT	Peak Hour (vph)	Total Truck AADT (%)	Truck 2 Axle AADT (%)	Truck 3 Axle AADT (%)	Truck 4 Axle AADT (%)	Truck 5 Axle AADT (%)	EAL Mill
SR-47 and Harbor Bl PM 0.43	58,000	64,000	5,800	5,104 (6.4)	1,400 (27.4)	1,387 (27.2)	227 (4.4)	2,091 (41.0)	931

AADT: Annual Average Daily Traffic - MADT: Monthly Average Daily Traffic
 vpd: vehicles per day - vph: vehicles per hour - EAL: Equivalent Axle Load –
 Mill: Millions

Collision Analysis

Tables 4.2 through 4.4 show the number of collisions and their significance, the collision rates, and the collision types along the mainline and within the limits of the project for the period covering the years 2020-2022. The actual collision rates (Table 4.3) are lower than the statewide average for similar facilities. Analysis of collision data shows that rear-end and sideswipe are the most common types of collisions. These types of collisions are typically associated with traffic congestion and narrow shoulders and happen due to unsafe speed, improper turn, and inattention.

Table 4.2 Number of Collisions/Significance (Years 2020-2022)

Location	Total	Fat.	Inj.	F+I	Multi Veh	Collision Conditions		MVM
						Wet	Dark	
SR 47 Mainline Northbound PM 0.2 – 2.0	32	0	4	4	29	0	11	52.97
SR 47 Mainline Southbound PM 0.2 – 2.0	27	0	13	13	23	2	9	52.97

F= Fatal; I= Injury; F+I= Fatal + Injury Pers Kld: Persons Killed - MVM: Millions of Vehicle Miles

Table 4.3 Collision Rates (Years 2020-2022)

Location	Collision Rates					
	Actual			Statewide Average		
	F	F+I	Total	F	F+I	Total
SR 47 Mainline Northbound PM 0.2 – 2.0	0.00	0.13	0.85	0.007	0.37	1.08
SR 47 Mainline Southbound PM 0.2 – 2.0	0.00	0.27	0.65	0.007	0.37	1.08

Table 4.4 Collisions/Types of Collision (Years 2020-2022)

Location	Total	Head-on (%)	Rear-end (%)	Sideswipe (%)	Broadside (%)	Hit Object (%)	Overturn (%)
SR 47 Mainline Northbound PM 0.4 – 2.0	32	0 (0%)	18 (56.2%)	11 (34.4%)	0 (0.0%)	3 (9.4%)	0 (0.0%)
SR 47 Mainline Southbound PM 0.4 – 2.0	27	0 (0%)	13 (48.2%)	9 (33.3%)	0 (0.0%)	5 (18.5%)	0 (0.0%)

To eliminate and/or minimize the occurrence and severity of the collisions, new pavement markings, signage, object markers, and delineators will be installed per the latest standards. The lighting system along the bridge is also being upgraded.

5. ALTERNATIVES

The development of the Project Approval/Environmental Document (PA/ED), the preparation of the Plans, Specifications, and Estimate (PS&E), and the construction phases of this project is being performed under the Construction Manager/General Contractor (CMGC) Program. This is an innovative alternative delivery method that allows Caltrans to receive input on innovative design used in the industry, construction methodology, and staging strategies, from the CMGC technical team throughout the design process with the option to negotiate and become the General Contractor upon an agreed to price.

The following bridge deck replacement alternatives were developed with the close collaboration of the Caltrans Office of Structures Design, the CMGC team, and the participation of a multidisciplinary group composed of professional and technical staff from Caltrans, notably Project Management, Environmental, Roadway Design, Traffic Operations, Traffic and Electrical Design, Transportation Safety, Roadway and Structure Maintenance and Office of Right of Way among others.

5A. Viable Alternatives

Two general alternatives were evaluated for the VTB deck replacement:

Alternative 1 - No Build alternative.

This alternative keeps the existing operation and maintenance conditions of the deck and would not preserve the life of the Vincent Thomas Bridge, and therefore, does not meet the Purpose and Need of the project.

Alternative 2 – Build Alternative

This alternative proposes to replace the entire deck of the bridge with one of these deck-type options: a) Pre-cast Concrete (PC), b) Exodermic Deck Panels (concrete-filled grid), c) Cast-In-Place Concrete (CIP), and d) Orthotropic Steel Deck. Detailed information on the different deck types can be found in the Advance Planning Study Memo/Alternative Design Study.

Alternative 2 -Build Alternative Scope

The following is a list of the major scope items included in Alternative 2. Except for the types of decks referred to above, all the listed items are shared for the different deck materials or deck types analyzed, and therefore, they will apply to the selected preferred alternative.

- Removal and replacement of the existing lightweight bridge concrete deck along the approach and suspension spans with new concrete and/or orthotropic deck.
- Removal of the existing metal railing and steel plate curb (suspended spans) and their replacement with a CA ST-75 Bridge Rail.
- Removal of the existing 12' height chain link fence on each side of the suspended spans, and its replacement with a 12' height chain link fence.
- Removal of the existing Type 2 Barrier with a 6' barrier-mounted chain link fence along approach spans, and replacement with a CA ST-75 bridge railing with a 9' curb-mounted chain link fence.
- Removal of the existing median concrete barrier Type 50 and replacement with Type 60M concrete barrier or, optionally, a steel barrier.
- Removal and replacement of 18 joint seals along approach spans.
- Remove and replace 11 joint seals on suspension spans.
- Removal of 4 finger joints at four locations of the suspension spans and replacement with seismic joints.
- Removal of existing 26 seismic sensors and replacement with 44 upgraded seismic sensors.
- Removal and replacement of 29 barrier-mounted electroliers along approach spans.
- Upgrading of 160 light fixtures of the "low light system" along suspended spans.
- Installation/Upgrade of signs (2 OH signs and approximately 26 barrier and/or pole-mounted roadside signs), pavement delineation, and pavement marking per current standard.
- Installation of 30 power receptacles on the bridge's sub-structure for the maintenance painting crew.

The implementation of Alternative 2 (Build Alternative), considered four construction staging options allowing the design team to find the best option that produced the minimum environmental and traffic impacts.

The project team analyzed 9 construction scenarios, which were generated based on the "build alternative" scope when combined with the 3 deck types (orthotropic, cast-in-place, and precast concrete) and the four construction stages described below.

- **Single-Stage Construction:** This construction staging option consists of a full closure of the bridge that would last 16 or 41 months with detour routes and 24/7 work. The difference in construction timelines depends on the deck type chosen. Orthotropic and Pre-Cast deck types would lead to a construction timeline of approximately 16 months. A Cast-in-Place deck type would lead to a construction timeline of approximately 41 months. Consideration of a hybrid PC deck panel and CIP may be a worthwhile option to analyze during the design phase.
- **Two-Stage Construction:** This construction staging option would leave one lane open in each direction for each stage (two stages). The work would require the installation of a temporary support/bracing system, potentially reduced speeds of approximately 25 miles per hour (mph) due to narrowed lanes, and multiple weekends (55-hour) full closures and overnight full closures of the bridge. Construction would last approximately 25 months.
- **Three-Stage Construction:** This construction staging option would leave one lane open in each direction and would require the installation of a temporary support/bracing system. One lane would be open in each direction for each stage, and multiple weekend (55-hour) full bridge closures and full overnight bridge closures would be required. Construction would last approximately 32 months.
- **Nighttime Bridge Closure:** This construction staging option would leave the bridge fully open during daytime traffic hours (6:00 a.m. to 7:00 p.m.). The work would require the installation of a temporary support/bracing system and fully closing the bridge during nighttime hours (7:00 p.m. to 6:00 a.m.) every day. Construction would last approximately 48 months.

The following sections summarize the build alternative scenarios grouped according to the construction stage under which they were analyzed. Three of these scenarios are associated with the Single-Stage Construction, two with the two-stage Construction, two with the three-stage Construction, and the last two with the Nighttime Bridge Closure.

Single-Stage Construction (Build Alternative - Scenarios 1-3).

This Alternative involves the removal of the existing concrete deck on both the Approach spans and the Suspended span and replacing the existing deck with either, a Pre-Cast (PC) concrete deck on the approach spans or a steel Orthotropic deck on the suspended span (Scenario 1), Precast Concrete only (Scenario 2) or Cast in Place (CIP) throughout the entire bridge length (Scenario 3)

The closure and deck replacement time for the types of deck considered varied from 16 months for the PC-only and PC/Steel-Orthotropic combination (Scenario 1) to 41 months for the CIP-only option (Scenario 3). The preliminary escalated cost estimate of these deck options was, in the same order, \$590M, \$543M, and \$589M. The first two options meet the March 2027 open-to-traffic project requirement. The CIP-only option extends its open-to-traffic date to Nov-2028.

Two-Stage Construction (Build Alternative- Scenarios 4-5)

This two-stage construction alternative involves the removal of the existing concrete deck on both the approach spans and the suspended spans and replacing the deck with either, a Pre-Cast (PC) concrete deck on the approach spans or a steel Orthotropic deck on the Suspended span (Scenario 4) or a Pre-Cast (PC) concrete deck throughout the entire bridge length (Scenario 5).

This alternative entails for the two scenarios considered the closure of half of the bridge and having 2 traffic lanes, one operating in each direction, separated by channelizers, during daytime with full closure of the bridge during nighttime. This will enable the bridge deck to be replaced in 2 stages (East Bound & West Bound) while keeping the bridge operational with one lane in each direction during daytime.

The closure and deck replacement time for the types of deck considered for the two scenarios was 25 months. Both scenarios meet the March 2027 open-to-traffic date timeline requirement. The preliminary escalated cost varied from \$577M, for the Pre-Cast-only option (Scenario 4) to \$541M for the Pre-cast on the approach spans and steel Orthotropic on the suspended spans option (Scenario 5). The current and mandatory 45 mph posted speed will be reduced to 25 mph throughout the construction zone.

Three-Stage Construction (Alternative 2 - Scenarios 6-7)

The Three-Stage involves the removal of the existing concrete deck on both the approach spans and the suspended span and replacing the deck with either, a pre-cast concrete deck throughout the entire length of the bridge (Scenario 6) or a pre-cast concrete deck on the approach spans and a steel Orthotropic deck on the suspended spans (Scenario 7).

This alternative entails the closure of one-third of the bridge having 2 traffic lanes, one operating in each direction during daytime, and full closure of the bridge during nighttime. The difference between the Two-Stage Construction Scenarios and the Three-Stage Construction Scenarios is that in the latter case, the traffic on the operating lanes is separated by a K-rail, while in the Two-Stage Construction Scenarios, the traffic lanes are separated by channelizers. Having a K-rail barrier separating the traffic flowing in opposite directions in a 2-lane configuration requires three stages for the deck replacement, thus requiring an additional time-demanding phase.

The closure and deck replacement time for the types of deck considered for the two scenarios was 32 months, with an estimated open-to-traffic July 2028, which is beyond the desired March 2027 date. The preliminary escalated cost of these two deck options varied from \$581M for the Pre-cast/steel Orthotropic deck combination option to \$532M for the Pre-Cast-only option. The current and mandatory 45 mph posted speed will be reduced to 25 mph throughout the construction zone.

Accelerated Bridge Closure (Build Alternative - Scenarios 8-9)

The Accelerated Bridge Closure alternative is comprised of replacing the bridge deck with either, a Pre-Cast concrete deck throughout the entire length of the bridge (Scenario 8), or a Pre-Cast concrete deck on the Approach spans and a steel Orthotropic

deck on the Suspended spans (Scenario 9).

Both options require a full bridge closure between 7:00 p.m. and 6:00 a.m. and opening the bridge to full traffic outside of these hours. Since the deck replacement on the Approaches will inhibit access to other parts of the bridge, these scenarios will consist of only 2 construction headings.

The actual deck replacement process for the Pre-cast option will be like the previous Alternative 2 Scenarios involving this type of deck, however, due to the limited working hours, this option will require an interim temporary bridge deck panel to be installed before completing the replacement operation with the permanent deck since the deck panel replacement will require multiple shifts. One of the several challenges and concerns with this deck replacement scenario is the difficulty of achieving sufficient concrete strength of the poured haunches over the girders in the limited available work. The preliminary escalated cost of this option (Scenario 8) is \$597M.

For Scenario 9, the Orthotropic deck replacement on the suspended span would require a panel replacement that spans between the floor beams spaced every 30 ft. and the splices occurring in cantilever, a few feet beyond the floor beam. In this situation, it is not feasible to connect the newly placed Orthotropic deck panel to the adjacent existing deck, which would cantilever approximately 28 feet from the adjacent floor beam. This constructability limitation led to the conclusion that Scenario 9 is not constructible and therefore rejected as a potential alternative. No preliminary cost or construction schedule was developed for this scenario.

Build Alternative – Early Work Packages (EWP)

The complexity and size of the project will require the development of the following Early Work Packages which apply to the nine construction scenarios described in the previous sections:

- Installation of 4 elevators at ground level under the bridge for temporary use during construction for the labor force access at 4 convenient locations. These elevators are anticipated to be erected on concrete slabs poured directly on the existing paved areas without excavation or soil removal.
- Installation of a “Quick Deck” system along and under the bridge's sub-structure that will serve as a working platform and shielding for falling debris during construction. This installation will require temporary access to the ground area under the bridge to move crane equipment.
- Repair of local roads, under Early Work Packages (EWP), identified to serve as detour routes during the project's construction phase. The Final Environmental Document has recommended the repair of designated detour roads as a mitigation measure for the anticipated damage to the pavement structure caused by the significant increase in truck traffic during the bridge's full closures.

Selection of the Preferred Alternative

Caltrans has identified and selected the single-stage construction (full bridge closure) as the preferred construction staging option (Scenario 2) within the Build Alternative scenarios analyzed.

The single-stage construction (full bridge closure) option was selected by the Caltrans Project Development Team (PDT) for the following reasons:

- **Stakeholder feedback:** During the 90-day circulation period of the Draft EIR/EA Caltrans received 260 comments, many of which stated their preferred construction staging option. A total of 39 comments stated their preference for the single-stage construction (full bridge closure) option. Important project stakeholders such as the Port of Los Angeles (POLA), the Port of Long Beach (POLB), International Longshore and Warehouse Union (ILWU 13, 63, 94), Harbor Trucking Association, Pacific Merchant Shipping Association, Pacific Maritime Association, Los Angeles Department of Transportation (LADOT), Wilmington Neighborhood Council, Northwest San Pedro Neighborhood Council, Central San Pedro Neighborhood Council, City of Rancho Palos Verdes, and elected official Councilman Tim McOsker (Council District 15) all stated their preference for the single-stage construction (full bridge closure) option.
- **Schedule duration:** A closure of the Vincent Thomas Bridge (partial or full closure) would result in impacts to surrounding communities and facilities for the entire duration of construction. Caltrans, along with the feedback from project stakeholders, determined that a shorter construction duration is important in limiting traffic, economic, and other impacts to surrounding communities and facilities that utilize the Vincent Thomas Bridge. The single-stage construction (full bridge closure) option has the shortest construction schedule of the construction staging options proposed. The single-stage construction (full bridge closure) option with orthotropic or pre-cast deck types would result in a 16-month construction timeline. This timeline is much faster than the 25–48-month timelines for other construction staging options.
- **Worker and driver safety:** A full closure of the Vincent Thomas Bridge would result in no non-construction related vehicular traffic on the bridge for the entire duration of construction. With no vehicular traffic on the bridge, staging measures to separate travel lanes from construction and reduced lane widths would not be needed. This would not only allow for a faster construction timeline but also a safer work environment for construction crews on the bridge and safer for the public not having to drive through a one-lane roadway with no other access for the entire bridge length.

For the type of deck selection, a “type selection report” was prepared, which analyzed the constructability, cost, schedule, traffic handling, material suppliers’ capacity, etc., of the different deck materials originally considered (concrete cast-in-place, orthotropic, and concrete pre-cast slabs). The report recommended the pre-cast slab deck option with a full bridge closure schedule of 16 months.

Non-Standard Design Features

All the alternatives or scenarios discussed above share the same roadway geometric features. This project involves a suspended bridge structure, and the geometry of the roadway within the bridge limits cannot be modified unless the entire bridge superstructure is replaced with a new one, which is well beyond the purpose of this project. Thus, it is unfeasible to bring the existing non-standard roadway geometric features up to current standards.

The removal of the existing metal curb and railing and their replacement with an ST-75 railing along the suspended spans will provide the room to widen the deck 9" on each side (W=54.5' to W=56') for the installation of the new ST-75 railing (W=2') and keep the existing lane/shoulders configuration (2-12' lanes/0.5' inside-outside shoulders).

For the approach spans the existing deck width (W=58') will be maintained with the same lane/shoulder configuration of the suspended spans. The extra foot on each side behind the new ST-75 railing will accommodate the poles of new electroliers and the 9.5' high chain link fence. Currently, both the existing electroliers and chain link fence are mounted on the old Type 2 concrete railing, which is not possible to do on the planned ST-75 railing.

Tables 5.2A and 5.2B below summarize the non-standard geometric features that will be maintained for the reasons stated above and that were addressed by an approved Design Standard Decision Document (DSDD)

Table 5.2A Non-Standard Design Features					
Design Feature	No. of Locations	HDM Index	Standard	Existing	Proposed
Stopping Sight Distance	4	201.1	360 ft (45 mph)	338-360 ft (40-45 mph)	293-360 ft (39-45 mph)
Cross Slope Standards	2	301.3(2) 302.2(3)	1.50%	0.00-0.83%	0.00-0.83%
Shoulder Width & Horizontal Clearance	1**	302.1 309.1(3)(a)	10 ft 5 ft	0.5-0.78 ft 0.5-0.78 ft	0.5-0.78 ft 0.5-0.78 ft
Median Width	1**	305.1(3)(a)	22 ft	5 ft	5 ft

** Full length of the bridge (L=6,060 ft)

Table 5.2B Non-Standard Design Features

Location	HDM Index	Nonstandard Element	Freeway Entrances and Exits		
			Standard	Existing	Proposed
SB SR-47 Off-Ramp From Harbor Blvd	504.2(2)	Departure Angle	4°52'08"	4°01'07.1"	4°01'07.1"
		Deceleration Length	420 ft	101.52 ft	420 ft
	504.2(2) 504.3(6)	Auxiliary Lane	1300 ft	0 ft	0 ft
NB SR-47 On-Ramp From Harbor Blvd.	504.2(2)	Merging Length	1,067.11 ft	409.87 ft	409.87 ft
	504.2(2)	Inlet Nose Radius	3000 ft	1400 ft	1400 ft
	504.2(2)	Lane Taper	1:30 to 1:50	1:21	1:21

5B. Rejected Alternatives

Eight of the nine Build Alternative (Alternative 2) scenarios analyzed in the previous section are viable to be implemented and meet the need and purpose of the project. Although every one of them has its advantages and disadvantages when compared to the others, all of them were offered to the public for their input during the public circulation of the Draft Environmental Document.

Alternative 2 Scenario 9 was considered not viable due to the constructability challenges presented by the connection of Orthotropic panels to the adjacent existing deck, and therefore it was rejected. Similarly, the No-Build-Alternative was rejected since it did not address or resolve the deficiency of the bridge structure.

6. CONSIDERATIONS REQUIRING DISCUSSION

6A. Hazardous Waste Management

The District Hazardous Waste Branch prepared a preliminary Hazardous Waste Reassessment for the project in July of 2023. Recommendations on how to manage potentially hazardous materials on the project site were provided. Notables are the potential presence of Aerially Deposited Lead at locations off the bridge where construction area signs will be installed, asbestos-containing materials (ACM) in the shim plates, weep holes and joint sealants, removed lead base paint (LBP) on the bridge structure, removed yellow and white traffic stripe, pavement marking, and electrical waste disposal produced by the removal of seismic sensors.

6B. Value Analysis

A Value Analysis (VA) Study was completed in December 2023. The purpose of the VA Study was to identify ways to improve the proposed alternatives by reducing their cost, reducing their schedule duration, reducing risks, and minimizing the traffic impacts to the users, stakeholders, and general communities in the vicinity of the project.

At the time of the final VA presentation, the decision-makers accepted 11 of the 16 proposed VA alternatives for project improvement. The net effect of improving upon the baseline design performance by +20.4%, and the anticipated cost impact is roughly \$7,432,000 in initial savings, with no anticipated impact to the construction schedule. When these value elements are combined, they represent an overall value improvement over the baseline design of +20.9%. With the selection of the preferred alternative, two of the 11 accepted VA Alternatives are not applicable, which reduces the overall value improvement to 17% for the remaining 9 accepted VA Alternatives.

The nine VA Alternatives accepted are related and applicable to the design and construction of the structure portion of the bridge. The structure design team will assess their validity from the technical and economic viewpoints as the design progresses and incorporate them into the final PS&E package.

6C. Resource Conservation

The replacement of the deck of the Vincent Thomas Bridge will generate approximately 10,000 CY of concrete debris. This cubic yardage is independent of the alternative selected since the purpose and need of the project is the full replacement of the existing bridge deck. For the alternatives involving the concrete-orthotropic deck options (3), in addition to the cubic yardage of concrete debris generated it would have been necessary to dispose of approximately 20,000 Ft (approx. 680 Tons) of steel stringers (21WF68) that would have to be removed to make room for the orthotropic deck along the suspended spans. The replacement of the existing metal railing and steel plate curb with ST-75 railing along the suspended spans, and the replacement of the chain link fence throughout the length of the bridge will add approximately 100 Tons of reusable chain link fence or recyclable metal.

Following the Department policies regarding the minimization of consumption, destruction, and disposal of nonrenewable resources, it is recommended that cubic yardage of concrete debris be offered to Caltrans projects in the vicinity or to the Port of Los Angeles projects currently under development where it can be processed and used as base, sub-base or structural backfill. Similarly, the footage of the chain link removed will be offered to the Division of Maintenance for the repair of the fences where needed within District 7.

6D. Right-of-Way Issues

No permanent Right of Way will be required to complete the proposed construction of this project. A Right of Way Data Sheet was prepared and approved on 10/04/2024 (See Attachment F). Caltrans owns easement rights, which extend 25' beyond the deck drip line or edges of the bridge since the bridge was constructed in 1963.

The CMGC team has expressed the need to install 4 temporary elevators at ground level under the bridge for workers' access during the construction phase. The installation of these elevators may require short temporary use of areas beyond the current State rights of way. The Port of Los Angeles has been contacted and they are receptive to issuing an entry permit license, which would minimize the interference with tenant operations.

6E. Environmental Compliance

Based on the location and scope of work of the proposed project, an Environmental Impact Report/Environmental Assessment (EIR/EA) (Attachment A) has been prepared for California Environmental Quality Act (CEQA) compliance and an Environmental Assessment (EA) has been prepared for National Environmental Policy Act (NEPA) compliance. Consistent with Caltrans requirements, the document prepared for the proposed project is a combined environmental document (EIR/EA), prepared following Caltrans environmental procedures, as well as with State and Federal environmental regulations.

6F. Air Quality Conformity

This project is exempt from regional (40 CFR 93.126) conformity requirements as it is categorized as “widening narrow pavements or reconstructing bridges (no additional travel lanes). A separate listing of the project in the Regional Transportation Plan and Transportation Improvement Program, and their regional conformity analyses, is not necessary.”

6G. Title VI Considerations

It has been the FHWA’s long-standing policy to actively ensure nondiscrimination under Title VI of the 1964 Civil Rights Act in federally funded activities. The Civil Rights Restoration Act of 1987 clarified the intent of Title VI to include all programs and activities of federal aid recipients, subrecipients, and contractors whether those programs and activities are federally funded or not. The proposed improvements would not cause any disproportionately high or adverse effects on any minority or low-income populations per the provisions of Executive Order 12898.

6H. Noise Study Analysis

The District Division of Environmental prepared a Noise Study Report (2023) to assess the noise impacts on the traveling public and the residential and commercial areas during the periods that the traffic will be detoured to the main arterials within the vicinity of the project, as a result of the implementation of the construction staging associated with the different alternatives. The study analyzed the route segments and intersections identified by the Traffic Operations Analysis Report (TOAR) (2024) as potential alternate routes.

Based on the analysis results, the noise impact for most of the residential areas along all alternate routes during daytime and nighttime resulted in less than a 3 dBA increase in noise levels. Just one area along Willow Street between SR-103 and Santa Fe Avenue would experience a noise increase of up to 5 dBA during the nighttime hours. However,

while this noise increase is considered readily noticeable, it must be noted that the future absolute noise levels of 60 – 65 dBA in this area would not exceed the threshold of 67 dBA. The study concluded that there are no substantial noise increases to the noise-sensitive areas, during daytime or nighttime along any of the detour routes identified due to the construction of the Vincent Thomas Bridge deck replacement project.

6I. Life-Cycle Cost Analysis

The nature of the project, bridge structure deck replacement, does not lean itself to conduct a Life-Cycle Cost Analysis to determine the best option among the different deck materials (or their combination) analyzed. All the deck materials considered, cast-in-place concrete, precast concrete slabs, and steel orthotropic deck, guarantee a deck lifespan of 75 years, which is beyond the end of the remaining useful life of the bridge structure (40 years), which was put in service in 1963.

6J. Reversible Lanes

Per Assembly Bill AB 2542, this project does not qualify as a capacity-increasing or a major street or highway realignment project and reversible lanes will not be considered.

7. OTHER CONSIDERATIONS AS APPROPRIATE

Public Hearing Process

A public circulation of the Draft Environmental Document (DED) and a public hearings process occurred between April 16 and July 15, 2024. The 4 construction staging options covering the 8 scenarios of the build alternative analyzed, were presented to the public in general, stakeholders, communities, and users for their comments and recommendations. Based on the input from the public, the Department's project development process policies, and the technical and economic aspects of the project, the full closure scenario of the build alternative was selected as the preferred alternative, as discussed previously in this document. This full-bridge-closure preferred alternative will advance to the design phase. More details of the Public Hearing Process and its outcome can be found in the Environmental Impact Report/Environmental Assessment (See Attachment A).

Meanwhile, the project team continues to get engaged with the local agencies and communities through regularly scheduled Technical Advisory Committee (TAC) and Community Advisory Committee (CAC) meetings which provide discussion opportunities with the public and stakeholders to focus on the development and implementation of the preferred alternative to better address the concerns of the general public and communities impacted by the project.

Permits

This project will require to secure the following permits before the construction phase:

- US Coast Guard
- California Coastal Commission
- Port of Los Angeles (POLA)
- POLA Coastal Development Permit or exemption

In addition, it will require coordination with Pacific Harbor Line (PHL) the railroad Company operating under the bridge, through the execution of a Flagging Service Contract.

Similarly, with the selection of the detour routes, Cooperative or Service Agreements with the City of Los Angeles, the City of Carson, the City of Wilmington, and the City of Long Beach for the repairs anticipated for the designated detour routes and for the provision of traffic control officers and the signals timing adjustments required along such detours.

Transportation Management Plan

The Transportation Management Plan (TMP) developed for the Project Initiation Document (PID) was revised for the draft project report, then modified to cover the different strategies of the 8 scenarios analyzed, and now re-visited to ensure that it is still valid and applicable to the preferred alternative. This alternative will include a continuous full closure of the bridge for 16 months as well as temporary full closures during weekdays (nighttime) and extended weekends outside the 16-month period. The broad TMP prepared for the 8 scenarios is still applicable to meet the needs, after minor refinements, of the preferred alternative construction strategy.

Some TMP elements incorporated were Incident Management, by the addition of Freeway Service Patrol (FSP), Traffic Management Team (TMT), and Traffic Surveillance Stations (Loop detectors and CCTV) elements; the Construction Strategy, by the addition of Total Mainline Freeway Closures, Extended Weekend Closures and Ramp and Connector Closures elements and last, the Alternative Route Strategy, with the addition of street improvements like detours pavement repair, traffic delineation, traffic signal adjustment and traffic control officers to direct traffic during peak periods at key intersections (see Attachment J)

Stage Construction and Detour Routes

The Traffic Operation Analysis Report (TOAR) presents a comprehensive study of the traffic behavior on the freeways and main arterials within the area of influence (area impacted by the bridge construction traffic closures) of the Vincent Thomas Bridge facility. The study included 21 roadway segments and 61 intersections. Travel demand modeling was used to study traffic patterns near the project, analyzing various closure scenarios of Vincent Thomas Bridge. The study also suggested potential mitigation for 13 intersections to improve operations through delineation modification, lane re-assignment, and signal timing adjustments. The feasibility of the proposals will be further studied and evaluated with partner agencies during the project's design phase.

With the selection of the preferred alternative (full closure of the bridge) and the continuous input of the communities and stakeholders, potential detour routes have been identified. These routes are still preliminary and will be coordinated through the TMP task force, CAC, and TAC through the end of construction. These include the local routes Harry Bridges Bl, Alameda St, Henry Ford Ave, and Sepulveda Bl, which, combined with the freeways I-110, I-710 and the State routes SR-47, SR-103, and SR-1, will conform to the needed detour system. The cities impacted by these detours are

the City of Los Angeles, the City of Wilmington, the City of Long Beach, and the City of Carson.

Accommodation of Oversize Loads

Due to the limited and confined cross-section of the bridge structure, which will not allow the provision of full lane widths or even narrow shoulders during the expected continuous traffic closures, no permit or oversize loads will be allowed on the bridge. Detour routes that can accommodate oversized loads will be properly identified for such purposes.

Graffiti Control

The project is localized in an identified graffiti-prone area. All the proposed alternatives include an item with a dollar amount to cover the Application of Anti-Graffiti Coating.

Asset Management

With the implementation of the improvements recommended in this Project Report, the Department will comply and will be aligned with the California Transportation Asset Management Plan (FY 2021/22 to FY 2031/32), which has set as a goal for the Bridges Asset Class the following: “Not less than 68% (2/3) of bridge area to be in good or fair condition by 2027. Fix not less than an additional of 500 bridges by 2027”. It is expected that the construction phase of this project will conclude by March of 2027 for the preferred alternative.

Complete Streets

Caltrans's "Complete Streets" policies do not apply to this project, as all work will occur within the freeway's prism. Pedestrians, wheelchairs, bicycles, and other forms of non-motorized transportation are prohibited from using this segment. Additionally, the proposed project will not impact public transportation facilities.

Broadband and Advanced Technologies

This project will not include broadband and advanced technology elements. Transportation Management Systems elements will be incorporated into the bridge structure by a separate project (07-36250), which proposes to upgrade the Transportation Management Systems (TMS) on Route 47. Proposed TMS elements include upgrade of fiber optic conduit and cables in both the roadway and bridge (Vincent Thomas Bridge), Closed-Circuit Television Video (CCTV) cameras, California Highway Patrol (CHP) Surveillance Cameras, Vehicle Detection Station (VDS), Traffic Census Station (TCS) and upgrade of existing analog communication equipment to Internet Protocol (IP)

8. FUNDING, PROGRAMMING AND ESTIMATES

Funding

It has been determined that this project is eligible for Federal-aid funding.

Programming and Cost Estimates

The table below provides for the selected alternative the current programmed information for the project cost component and the current cost estimate by component. The current cost estimate for support is escalated to the middle of each component at a rate of 3.5% per year for each component. The construction capital cost is escalated to mid-construction at a rate of 4.89% for FY 24/25 and 3.80% for FY 25/26 and beyond. The Right of Way capital is escalated at 8% to 07/30/2027.

Fund Source	Programming by Fiscal Year Preferred Build Alternative (Thousands)								Current Estimate (Escalated)
		Prior	24/25	25/26	26/27	27/28	Future	Programmed Total	
20.XX.201.116									At PAED Total
Component	In thousands of dollars (\$1,000)								
PA&ED Support		17,140						17,140	17,140
PS&E Support		20,900						20,900	30,360
Right-of-Way Support		17						17	1,684
Construction Support				39,840				39,840	46,336
Right-of-Way				30				30	1,730
Construction				628,464				628,464	599,183
Total		38,057		668,334				706,391	696,433

9. DELIVERY SCHEDULE

Project Milestones		Milestone Date (Month/Day/Year)	Milestone Designation (Target/Actual)
PROGRAM PROJECT	M015	01/26/2023	A
BEGIN PAED	M020	02/03/2023	A
NOTICE OF PREPARATION (NOP)	M030	04/12/2023	A
CIRCULATE DED EXTERNALLY	M120	04/16/2024	A
PA & ED	M200	10/15/2024	T
START PS&E	M210	10/16/2024	T
PRE-60% PS&E		02/05/2025	T
60% PS&E	M313	03/15/2025	T
PRE-95% PS&E		03/30/2025	T
95% PS&E	M315	05/20/2025	T
PS&E TO DOE	M377	05/30/2025	T
DRAFT STRUCTURES PS&E	M378	04/15/2025	T
PROJECT PS&E	M380	06/20/2025	T
RIGHT-OF-WAY CERTIFICATION	M410	06/23/2025	T
READY TO LIST	M460	07/08/2025	T
FUND ALLOCATION	M470	10/16/2025	T
HEADQUARTERS ADVERTISE	M480	10/31/2025	T
AWARD	M495	10/31/2025	T
APPROVE CONTRACT	M500	12/01/2025	T
END PROJECT	M800	01/13/2029	T
PROJECT CLOSEOUT	M900	12/13/2029	T

10. RISKS

The project development team (PDT) conducted re-evaluations of the Risk Register developed during the project initiation phase of the project. The original Risk Register list was modified as the project development progressed. The original Risk Register identified 24 active risks with a Risk Impact on Construction Capital of \$111.8M (@ 70th percentile with 25% Contingency). The re-evaluated Risk Register added 20 active risks (total 41) with a Risk Impact on Construction Capital of \$81.19M (@ 70th percentile with 17% Contingency). See Attachment H for more details on the re-assessed Risk Register.

11. EXTERNAL AGENCY COORDINATION

Federal Highway Administration (FHWA)

This project is considered a Delegated Project in accordance with the current FHWA and California Department of Transportation (Caltrans) Joint Stewardship and

Oversight Agreement. Therefore, this project is not listed on FHWA's list of risk-based project involvement projects.

The project requires the following coordination:

United States Coast Guard

Rivers and Harbors Act of 1899 Section 9

Bridge Permit

California Coastal Commission and/or Local Coastal Program

California Public Resources Code Division 20 (California Coastal Act)

Coastal Development Permit

Local Agency

Coordination with the City of Long Beach, the City of Los Angeles, the Port of Los Angeles, and the Port of Long Beach will continue during the design phase.

Railroads

A Railroad Agreement (Flagging Service Agreement) is anticipated to cover flagging services at railroad tracks crossing under one of the bridge spans.

12. PROJECT REVIEWS

Scoping team field review.

District Bridge Program Advisor Jennifer Man/Shawn Enjily

Headquarters SHOPP Program Advisor Cory Cowden

District Maintenance Shawn Silva

Caltrans Project Delivery Coordinator Robert Navarro

Project Manager Rimma Tebeleva

Structure Design Mina Pezeshpour, Jinrong Wang

District Safety Review Lee Haber

Constructability Review Kyle Kunitake

Skanska Consultant (CMGC Team) Tony Taddeo, Jeff Smith

13. PROJECT PERSONNEL

<u>Name, Title</u>	<u>Functional Unit</u>	<u>Phone #</u>
Rimma Tebeleva	Project Manager	(213) 269 - 1791
Mario Gutierrez	Senior T.E. – Design A	(213) 310 -2603
Jason Roach	Environmental Planning	(213) 310 - 2653
Jennifer Man	Program Advisor – Bridge	(213) 266 - 6911
Jack Liu	Hazardous Waste Unit	(213) 269 - 1109
Kyle Kunitake	Constructability	(213) 269 - 1568
Kenneth Young	District Traffic Manager	(213) 435 - 7916
Zebunnesa Tareke	District Design Liaison	(213) 269 - 0625

Jinrong Wang	Structure Design	(916) 639 - 5891
Wilfred Domingo	Mobility Program Engineer	(213) 266 - 6020
Mohammed Haider	Transp. Safety Engineer	(213) 266 - 6064
Mike Francis	Structure Construction	(310) 766 - 0765
George Saker	Construction	(310) -877 - 4183
Dan Kopulsky	Multimodal System Planning	(213) 317 - 0566
Fatemeh Ansari	Traffic Design Electrical	(213) 266 - 6180
Tony Taddeo	Skanska – CMGC Team	(917) 741 – 8483
Jeffrey D Smith	Skanska – CMGC Team	(951) 232 - 3868

14. ATTACHMENTS

- A. Final Environmental Impact Report/Environmental Assessment
- B. Location Map
- C. Typical Cross Sections
- D. Preliminary Layout Plans
- E. Preferred Alternative Cost Estimate (11-page)
- F. Right of Way Data Sheet
- G. Storm Water Data Report
- H. Risk Register
- I. SHOPP – Performance Measures
- J. Transportation Management Plan Datasheet

15. REFERENCES – Engineering Studies/Technical Reports (available upon request)

- 1. Advance Planning Study (APS) – Feb. 2024
- 2. Traffic Operations Analysis Report – June 2024
- 3. Noise Study Report – Dec. 2023
- 4. Preliminary Bird Abatement Program – Aug. 2024
- 5. Bridge Type Selection Report – July 2024
- 6. Asbestos and Lead-Containing Paint Survey Report – June 2024
- 7. Value Analysis Study – May-2024
- 8. Design Standard Decision Document – Oct. 2024

ATTACHMENT A

Final Environmental Impact Report/Environmental Assessment

Vincent Thomas Bridge Deck Replacement Project

LOS ANGELES, CALIFORNIA
DISTRICT 7 – LA – 47 (PM 0.4/2.0)
39020/0722000334



Final Environmental Impact Report/Environmental Assessment with Finding of No Significant Impact

Prepared by the
State of California, Department of Transportation

The environmental review, consultation, and any other actions required by applicable Federal environmental laws for this project are being, or have been, carried out by Caltrans pursuant to 23 USC 327 and the Memorandum of Understanding dated May 27, 2022, and executed by FHWA and Caltrans.



October 2024

This page intentionally left blank

General Information About This Document

What's in This Document

The California Department of Transportation (Caltrans), as assigned by the Federal Highway Administration (FHWA), has prepared this Final Environmental Impact Report/Environmental Assessment (EIR/EA) with Finding of No Significant Impact for the proposed project located on the Vincent Thomas Bridge (State Route-47 [SR-47]) in the Port of Los Angeles (POLA) in Los Angeles County. Caltrans is the lead agency under the National Environmental Policy Act (NEPA). Caltrans is the lead agency under the California Environmental Quality Act (CEQA). The document tells you why the project is being proposed, what alternatives we have considered for the project, how the existing environment could be affected by the project, the potential impacts of each of the alternatives, and the proposed avoidance, minimization, and/or mitigation measures. The Draft EIR/EA circulated to the public for 90 days between April 16, 2024 and July 15, 2024. Comments received during this period are included in Appendix F. Elsewhere throughout this document, a vertical line in the margin indicates a change made since the draft document circulation. Minor editorial changes and clarifications are not shown.

- This document may be viewed and downloaded at the following website:
www.virtualeventroom.com/caltrans/vtb/.

Alternative Formats

For individuals with sensory disabilities, this document can be made available in Braille, in large print, on audiocassette, or on computer disk. To obtain a copy in one of these alternate formats, please call or write to the California Department of Transportation, Attn: Alex Brown, Environmental Planning, 100 S. Main St., Los Angeles, CA 90012; (213) 310-2590 (Voice), or use the California Relay Service 1 (800) 735-2929 (TTY to Voice), 1 (800) 735-2922 (Voice to TTY), 1 (800) 855-3000 (Spanish TTY to Voice and Voice to TTY), 1-800-854-7784 (Spanish and English Speech-to-Speech) or 711.

FHWA Highway ID No.

SCH# 2023040301
07-LA-47-PM 0.4/2.0
39020
0722000334

Vincent Thomas Bridge Deck Replacement Project
(Postmile 0.4 to Postmile 2.0) in the Port of Los Angeles,
Los Angeles County, California

**Final Environmental Impact Report/Environmental Assessment
with Finding of No Significant Impact**

Submitted Pursuant to: (State) Division 13, California Public Resources Code
(Federal) 42 USC 4332(2)(C)]

THE STATE OF CALIFORNIA
Department of Transportation

Responsible Agency: California Transportation Commission



Gloria Roberts
District Director
California Department of Transportation
NEPA Lead Agency

9/27/2024

Date

The following person may be contacted for more information about this document:

Jason Roach
California Department of Transportation
100 South Main Street, MS-16A
Los Angeles, CA, 90012-3712
Phone No.: (213) 310-2653

Finding of No Significant Impact (FONSI)



CALIFORNIA DEPARTMENT OF TRANSPORTATION FINDING OF NO SIGNIFICANT IMPACT (FONSI)

FOR

Vincent Thomas Bridge Deck Replacement Project

The California Department of Transportation (Caltrans) has determined that alternative (2: Build Alternative) will have no significant impact on the human environment. This FONSI is based on the attached Environmental Assessment (EA) which has been independently evaluated by Caltrans and determined to adequately and accurately discuss the need, environmental issues, and impacts of the proposed project and appropriate mitigation measures. It provides sufficient evidence and analysis for determining that an Environmental Impact Statement is not required. Caltrans takes full responsibility for the accuracy, scope, and content of the attached EA.

The environmental review, consultation, and any other actions required by applicable Federal environmental laws for this project are being, or have been, carried out by Caltrans pursuant to 23 USC 327 and the Memorandum of Understanding dated May 27, 2022, and executed by FHWA and Caltrans.

A handwritten signature in blue ink, likely of the Caltrans District Director.

Caltrans District Director

09/27/2024

Date

Revised May 2022

This page intentionally left blank

Summary


NEPA Assignment

California participated in the “Surface Transportation Project Delivery Pilot Program” (Pilot Program) pursuant to 23 United States Code (USC) 327 for more than 5 years, beginning July 1, 2007, and ending September 30, 2012. The Moving Ahead for Progress in the 21st Century Act (MAP-21) (P.L. 112-141), signed by President Obama on July 6, 2012, amended 23 USC 327 to establish a permanent Surface Transportation Project Delivery Program. As a result, Caltrans entered into a Memorandum of Understanding (MOU) pursuant to 23 USC 327 (National Environmental Policy Act [NEPA] Assignment MOU) with the Federal Highway Administration (FHWA). The NEPA Assignment MOU became effective October 1, 2012, and was renewed on May 27, 2022, for a term of 10 years. In summary, Caltrans continues to assume FHWA responsibilities under NEPA and other federal environmental laws in the same manner as was assigned under the Pilot Program, with minor changes. With the NEPA Assignment MOU, the FHWA assigned and Caltrans assumed all of the United States Department of Transportation (USDOT) Secretary’s responsibilities under NEPA. This assignment includes projects on the State Highway System and Local Assistance Projects off the State Highway System within the State of California, except for certain categorical exclusions that FHWA assigned to Caltrans under the 23 USC 326 Categorical Exclusion (CE) Assignment MOU, projects excluded by definition, and specific project exclusions.

Project Description

Caltrans is proposing to replace the deteriorated bridge deck, upgrade seismic sensors, and improve the existing median barrier and railings on the Vincent Thomas Bridge (State Route 47 [SR-47]) in the Port of Los Angeles (POLA). A regional location map is included on Figure S-1. The bridge deck is deteriorating due to concrete fatigue caused by heavy truck traffic over six decades of use. In 2009, a polyester concrete overlay was applied to the bridge deck to address spalling in the bridge deck; however, in 2011, new deck spalls began to occur and have been increasing in severity with each subsequent bridge inspection.

Figure S-1: Regional Location Map



Source: Community Impact Assessment (2024)

In-depth investigation of the bridge deck has been ongoing using ground-penetrating radar equipment, rapid automated sounding equipment, and physical and chemical concrete testing. Concrete test samples showed that the deck is failing below the polyester overlay causing the subsequent spalling. According to the latest bridge inspection (2022), the deck conditions have deteriorated from 'fair' to 'poor.' As a result of the evident grade of deterioration of the deck and the results of the physical and chemical testing performed, a technical team of the Office of Structure Maintenance and Investigation determined and recommended that the best strategy to extend the life of the bridge and provide a safe operation for the traveling public was to remove and replace the deck of both the suspended and approach spans of the Vincent Thomas Bridge.


The Vincent Thomas Bridge Deck Replacement Project is located at the southern end of SR-47 in Los Angeles County at the POLA in California, spans the Main Channel, and connects Smith Island to Terminal Island.

A No Build Alternative (Alternative 1) and a Build Alternative (Alternative 2) to replace the existing bridge deck on the Vincent Thomas Bridge are being evaluated as part of the proposed project. Additionally, four construction staging options for closure of the bridge were evaluated in the Build Alternative:

- **Single-Stage Construction:** This construction staging option consists of a full closure of the bridge that would last 16 or 41 months with detour routes and 24/7 work. The difference in construction timelines depends on the deck type chosen. Orthotropic and Pre-Cast deck types would lead to a construction timeline of approximately 16 months. A Cast-in-Place deck type would lead to a construction timeline of approximately 41 months.
- **Two-Stage Construction:** This construction staging option would leave one lane open in each direction for each stage (two stages). The work would require the installation of a temporary support/bracing system, potentially reduced speeds of approximately 25 miles per hour (mph) due to narrowed lanes, and multiple weekend (55-hour) full closures and overnight full closures of the bridge. Construction would last approximately 25 months.
- **Three-Stage Construction:** This construction staging option would leave one lane open in each direction and would require installation of a temporary support/bracing system. One lane would be open in each direction for each stage, and multiple weekend (55-hour) full bridge closures and full overnight bridge closures would be required. Construction would last approximately 32 months.
- **Nighttime Bridge Closure:** This construction staging option would leave the bridge fully open during daytime traffic hours (6:00 a.m. to 7:00 p.m.). The work would require the installation of a temporary support/bracing system and fully close the bridge during nighttime hours (7:00 p.m. to 6:00 a.m.) every day. Construction would last approximately 48 months.

The Build Alternative would include upgrading seismic sensors and improving the existing median barrier and railings on the bridge. The project limits are illustrated on Figure S-2.

Figure S-2: Project Limits Map



Source: Community Impact Assessment (2024).

The Build Alternative is necessary to preserve the life of the Vincent Thomas Bridge deck and ensure the safety of the traveling public. The No Build Alternative would not preserve the life of the bridge deck and would likely lead to emergency repair work and unplanned closures of the bridge.

The proposed project is a joint project by Caltrans and the Federal Highway Administration (FHWA) and is subject to State and federal environmental review requirements. Project documentation, therefore, has been prepared in compliance with both the California Environmental Quality Act (CEQA) and NEPA. Caltrans is the lead agency under both NEPA and CEQA. In addition, FHWA's responsibility for environmental review, consultation, and any other actions required by applicable federal environmental laws for this project are

being, or have been, carried out by Caltrans pursuant to 23 USC Section 327 and the MOU dated May 27, 2022, and executed by the FHWA and Caltrans.

Some impacts determined to be significant under CEQA may not lead to a determination of significance under NEPA. Because NEPA is concerned with the significance of the project as a whole, often a “lower level” document is prepared for NEPA. One of the most common joint document types is an Environmental Impact Report/Environmental Assessment (EIR/EA).

After receiving comments from the public and reviewing agencies, a Final EIR/EA has been prepared. The Final EIR/EA includes responses to comments received on the Draft EIR/EA and identifies the Preferred Alternative. A Notice of Determination (NOD) has been published for compliance with CEQA, and Caltrans has issued a Finding of No Significant Impact (FONSI) for compliance with NEPA. A Notice of Availability (NOA) of the FONSI has been sent to the affected units of federal, State, and local government, and to the State Clearinghouse in compliance with Executive Order 12372.

Project Impact

The proposed project requires closing the Vincent Thomas Bridge for a bridge deck replacement. The extent and duration of the closure would depend on the construction staging option that is chosen. In all staging options in the Build Alternative, there would be traffic impacts and the necessity for designated detour route(s), primarily through the neighborhood of Wilmington and the city of Carson, which are located north of the POLA.

The project’s primary impacts are due to construction and affect the community and traffic. All the closure options of the Vincent Thomas Bridge in the Build Alternative would require the use of detour route(s) to divert traffic to and from Terminal Island and away from the project site. The use of the detour route(s) by vehicular and port truck traffic could temporarily impact the community through increased traffic. A summary of anticipated project impacts for each construction staging option is shown in Table S-1.

Table S-1: Anticipated Project Impacts

Project Impacts for Each Construction Staging Option	Single-Stage Construction	Two-Stage Construction	Three-Stage Construction	Nighttime Bridge Closure
Traffic	All Construction Options: Temporary impacts that are less than significant with mitigation incorporated. (CEQA Determination) The following mitigation measures and project feature will be implemented to help alleviate traffic impacts: MM-TR-1, MM-TR-2, and PF-TR-1. More information on these measures and project feature can be found in Section 2.10 Traffic and Transportation/Pedestrian and Bicycle Facilities under Avoidance, Minimization, and Mitigation Measures.			
Biology	All Construction Options: Temporary impacts that are less than significant with mitigation incorporated. (CEQA Determination) Mitigation includes MM-BIO-1 through MM-BIO-7 include exclusionary devices on the bridge for peregrine falcons, bird surveying, and the construction of artificial nesting. More information on these measures can be found in Section 2.19 Animal Species under Avoidance, Minimization, and Mitigation Measures.			
Environmental Justice	Single-Stage Construction: Temporary disproportionately high and adverse effect on minority or low-income populations in accordance with EO 12898 for cumulative traffic and air quality impact. (NEPA Determination) Mitigation includes MM-EJ-1 and MM-EJ-2 include regular and ongoing coordination with agencies and the community to coordinate construction schedules and to address community concerns. More information on these measures can be found in Section 2.8 Environmental Justice under Avoidance, Minimization, and Mitigation Measures.	Two-Stage, Three-Stage, and Nighttime Closure Options: No temporary disproportionately high and adverse effects on minority or low-income populations. Mitigation MM-EJ-1 and MM-EJ-2 would be implemented for these staging options (if selected).		
Cumulative	Single-Stage Construction: Temporary significant and unavoidable impacts to environmental justice communities for cumulatively considerable impacts to traffic and air quality. (CEQA Determination) The following mitigation measures will be implemented to help alleviate these impacts: MM-EJ-1 and MM-EJ-2, which include regular and ongoing coordination with agencies and the community to coordinate construction schedules and to address community concerns. The following mitigation measures and project feature will also be implemented: MM-TR-1, MM-TR-2, and PF-TR-1,	Two-Stage, Three-Stage, and Nighttime Closure Options: Temporary less than significant impact with mitigation incorporated to environmental justice communities for cumulatively considerable impacts to traffic and air quality. (CEQA Determination) Impacts will be less than significant with the implementation of these mitigation measures: MM-EJ-1 and MM-EJ-2, which include regular and ongoing coordination with agencies and the community to coordinate construction schedules and to address community concerns. The following mitigation measures and project feature will also be implemented: MM-TR-1, MM-TR-2, and PF-TR-1, which include potential temporary modification of project area intersections to alleviate traffic increases, repair of detour routes, and changeable message signs to alert drivers of bridge closures and detour routes. More information on these measures can be found under Avoidance, Minimization, and Mitigation Measures in Section 2.8 Environmental Justice and Section 2.10 Traffic and Transportation/Pedestrian and Bicycle Facilities.		

Table S-1: Anticipated Project Impacts

Project Impacts for Each Construction Staging Option	Single-Stage Construction	Two-Stage Construction	Three-Stage Construction	Nighttime Bridge Closure
	which include potential temporary modification of project area intersections to alleviate traffic increases, repair of detour routes, and changeable message signs to alert drivers of bridge closures and detour routes.			

Source 1: Traffic and Operations Analysis Report (2023).

Source 2: Natural Environment Study (2023).

Source 3: Community Impact Assessment (2024).


The project will require coordination with the public and other agencies. Other agency coordination will include, but not be limited to, consultation with the California Department of Fish and Wildlife (CDFW), the United States Coast Guard, and the California Coastal Commission (CCC). Necessary permits include a Harbor Development Permit (or Harbor Development Permit exemption) with the POLA, which will satisfy the requirements of a Coastal Development Permit with the CCC if the CCC agrees to the merits of the permitting application and decision. A full list of agency coordination and permits is available at the end of Section 1.3 Project Description.

Since the project's scoping period, Caltrans has engaged neighborhood councils, union organizations, chambers of commerce, councils of governments, other project area organizations, and the public to encourage feedback and solicit comments on the proposed project. Caltrans has also formed a Community Advisory Committee (CAC) and a Technical Advisory Committee (TAC) to facilitate feedback from interested stakeholders throughout the life of the project until the open-to-traffic date. The main concern raised by the public and project area organizations is regarding the potential detour route(s) and the impacts related to heavy truck traffic near neighborhoods. Another primary concern is the traffic impacts caused by the different construction staging options proposed on the Vincent Thomas Bridge.

ATTACHMENT B

Location Map

LOCATION MAP




Vincent Thomas Bridge Deck Replacement Project
LA-47-PM 0.4/2.0 - EA 390201

ATTACHMENT C


Typical Cross Sections

STATE OF CALIFORNIA - DEPARTMENT OF TRANSPORTATION	DESIGN	MARIO GUTIERREZ	WILFRIDO MORALES	DATE REVISIED	
		FUNCTIONAL SUPERVISOR	KENNY DUONG	REVISIED BY	

- NOTE:
- FOR COMPLETE R/W AND ACCURATE ACCESS DATA, SEE R/W RECORD MAPS AT DISTRICT OFFICE.
 - BRIDGE DECK TYPE TO BE DETERMINED FROM THE FOLLOWING OPTIONS:
 - CAST IN PLACE/STRESSED DECK (PC/PS)
 - PRECAST/PRESTRESSED DECK (PC/PS)
 - CAST IN PLACE/REINFORCED DECK (CIP/RC)



EXISTING TYPICAL SECTION - APPROACH SPANS
Sta 51+52.00 TO Sta 69+42.00
Sta 94+54.50 TO Sta 111+97.50
ROUTE 47



PROPOSED TYPICAL SECTION - APPROACH SPANS
Sta 51+52.00 TO Sta 69+42.00
Sta 94+54.50 TO Sta 111+97.50
ROUTE 47

Attachment C - Typical Cross Sections

TYPICAL CROSS SECTION
NO SCALE

X - 1

DIST	COUNTY	ROUTE	POST MILES TOTAL PROJECT	SHEET NO.	TOTAL SHEETS


REGISTERED CIVIL ENGINEER	DATE
PLANS APPROVAL DATE	

NO.	DATE	BY	REVISION


THE STATE OF CALIFORNIA OR ITS OFFICERS OR AGENTS SHALL NOT BE RESPONSIBLE FOR THE ACCURACY OR COMPLETENESS OF THE INFORMATION SHOWN ON THIS PLAN SHEET.

STATE OF CALIFORNIA - DEPARTMENT OF TRANSPORTATION	FUNCTIONAL SUPERVISOR	DESIGNED BY Kenny Duong	DATE REVISID
	MARIO GUTIERREZ	WILFRIDO MORALES	DATE REVISID

NOTE:
1. FOR COMPLETE R/W AND ACCURATE ACCESS DATA, SEE R/W RECORD MAPS AT DISTRICT OFFICE.
2. BRIDGE DECK TYPE TO BE DETERMINED FROM THE FOLLOWING OPTIONS:
A. ORTHOTROPIC STEEL DECK
B. PRECAST/PRESTRESSED DECK (PC/PS)
C. CAST IN PLACE/REINFORCED DECK (CIP/RC)



EXISTING TYPICAL SECTION - SUSPENDED SPANS
Sta 69+42.00 TO 94+54.50
ROUTE 47



TYPICAL SECTION - SUSPENDED SPANS
Sta 69+42.00 TO 94+54.50
ROUTE 47


ATTACHMENT D

Preliminary Layout Plans

INDEX OF PLANS

STATE OF CALIFORNIA
DEPARTMENT OF TRANSPORTATION
PROJECT PLANS FOR CONSTRUCTION ON
STATE HIGHWAY
IN LOS ANGELES COUNTY
IN LOS ANGELES
AT VINCENT THOMAS BRIDGE

TO BE SUPPLEMENTED BY STANDARD PLANS DATED 2022



Dist	COUNTY	ROUTE	POST MILES TOTAL PROJECT	SHEET NO. TOTAL SHEETS
07	LA	47	RO. 4/2.0	

LOCATION MAP

THE CONTRACTOR SHALL POSSESS THE CLASS (OR CLASSES) OF LICENSE AS SPECIFIED IN THE "NOTICE TO BIDDERS."

BORDER LAST REVISED 9/17/2018 CALTRANS WEB SITE IS: [HTTP://WWW.DOT.CA.GOV/](http://www.dot.ca.gov/)

RELATIVE BORDER SCALE IS IN INCHES

3

USERNAME => 6146431
DWG FILE => 1390201d0001.dgn

UNIT 1796

PROJECT NUMBER & PHASE 07220003341

CONTRACT No.	07-390204
PROJECT ID	0722000334

PLANS APPROVAL DATE
THE STATE OF CALIFORNIA OR ITS
OFFICERS OR AGENTS SHALL NOT BE
LIABLE FOR ANY ERRORS OR OMISSIONS
OR INCOMPLETENESS OF THIS PLAN SHEET.



PROJECT ENGINEER
REGISTERED CIVIL ENGINEER

DATE

PROJECT ENGINEER
REGISTERED CIVIL ENGINEER

DATE

PROJECT ENGINEER
REGISTERED CIVIL ENGINEER

DATE

STATE OF CALIFORNIA - DEPARTMENT OF TRANSPORTATION	DESIGN	FUNCTIONAL SUPERVISOR	DESIGNED BY	KENNY DUONG	REVISD BY	
			CALCULATED- CHECKED BY	WILFRIDO MORALES	DATE REVISED	

BORDER LAST REVISED 8/5/2020

USERNAME => s146431
DON FILE => 739207ee004.dgn

LAYOUT

L-4

PROJECT NUMBER & PHASE

UNIT

RELATIVE BORDER SCALE
IS IN INCHES

0 1 2 3

DATE PLOTTED => 10-SEP-2024

LAST REVISION


- NOTE:
- FOR COMPLETE R/W AND ACCURATE ACCESS DATA, SEE R/W RECORD MAPS AT DISTRICT OFFICE.
 - BRIDGE DECK TYPE TO BE PRECAST/PRESTRESSED DECK (PC/PS)

DIST	COUNTY	ROUTE	POST MILES TOTAL PROJECT	SHEET TOTAL NO. SHEETS

REGISTERED CIVIL ENGINEER	DATE

PLANS APPROVAL DATE	NO.	EXP.	NO.


THE STATE OF CALIFORNIA OR ITS OFFICIALS THESE PLANS HAVE BEEN REVIEWED AND THE ACCURACY OR COMPLETENESS OF SAME COPIES OF THIS PLAN SHEET.
--



DIS+ COUNTY	ROUTE	POST MILES	SHEET TOTAL
		TOTAL PROJECT	NO. SHEETS
REGISTERED CIVIL ENGINEER		DATE	
PLANS APPROVAL DATE			
THE STATE OF CALIFORNIA OR ITS OFFICIALS		NO. CIVIL	
THE AUTHORITY OR COMPLETENESS OF SEAWARD		STATE OF CALIFORNIA	
COPIES OF THIS PLAN SHEET			



NOTE:
1. FOR COMPLETE R/W AND ACCURATE ACCESS DATA,
SEE R/W RECORD MAPS AT DISTRICT OFFICE.
2. BRIDGE DECK TYPE TO BE PRECAST/PRESTRESSED DECK (PC/PS)



LAYOUT

ATTACHMENT E

Cost Estimate of Preferred Alternative

39020 - Cost Estimate

Project ID: 0722000334

Type of Estimate : Project Report
Program Code : SHOPP
Project Limits : LA-47-PM 0.4/2.0
Description: Vincent Thomas Bridge Deck Replacement
Scope : Replace Bridge Deck, Replace Seismic Sensors, Replace Bridge Railings and Median Concrete Barrier, Replace Chain Link Fence, Upgrade Lighting System
Alternative : Option # 2 Full Closure PC Approach and PC Main Span

	Current Total Cost	Escalated Cost
ROADWAY ITEMS	\$ 154,566,169	\$ 168,285,184
STRUCTURE ITEMS	\$ 395,770,200	\$ 430,898,051
SUBTOTAL CONSTRUCTION COST	\$ 550,336,000	\$ 599,183,000
RIGHT OF WAY	\$ 1,730,000	\$ 1,730,000
TOTAL CAPITAL OUTLAY COST	\$ 552,066,000	\$ 600,913,000
PA/ED SUPPORT	\$ 17,140,000	\$ 17,140,000
PS&E SUPPORT	\$ 29,333,000	\$ 30,360,000
RIGHT OF WAY SUPPORT	\$ 1,627,000	\$ 1,684,000
CONSTRUCTION SUPPORT	\$ 43,255,000	\$ 46,336,000
TOTAL CAPITAL OUTLAY SUPPORT COST*	\$ 91,355,000	\$ 95,520,000
TOTAL PROJECT COST	\$ 643,421,000	\$ 696,433,000

If Project has been programmed enter Programmed Amount

Date of Estimate (Month/Year)	Month / Year 8 / 2024
Estimated Date of Construction Start (Month/Year)	1 / 2026
Number of Working Days	352 Working Days
Estimated Mid-Point of Construction (Month/Year)	10 / 2026
Estimated Construction End (Month/Year)	7 / 2027

Estimated Project Schedule


PID Approval	10/20/22
PA/ED Approval	10/01/24
PS&E	06/20/25
RTL	07/08/25
Begin Construction	01/26/26

Reviewed by Design Manager Mario Gutierrez, Design Manager (213) 310-2603

Approved by Project Manager Rimma Tebeleva, Project Manager (213) 269-1791

I. ROADWAY ITEMS SUMMARY

Section		Cost
1	Earthwork	
2	Pavement Structural Section	\$ 47,000
3	Drainage	\$ 1,000,000
4	Specialty Items	\$ 17,300,685
5	Environmental	\$ 8,684,834
6	Traffic Items	\$ 22,650,754
7	Detours	\$ 24,231,500
8	Minor Items	\$ 4,434,900
9	Roadway Mobilization	\$ 11,752,500
10	Supplemental Work	\$ 6,128,497
11	State Furnished	\$ 3,296,704
12	Contingencies	\$ 18,283,828
13	Overhead	\$ 36,754,967
TOTAL ROADWAY ITEMS		\$ 154,566,169

Estimate Prepared By :	 Wilfrido Morales, Project Engineer	10/14/2024	(213) 266-6239
	Name and Title	Date	Phone
Estimate Reviewed By :	 Mario Gutierrez, Design Manager	10/14/2024	(213) 310-2603
	Name and Title	Date	Phone

By signing this estimate you are attesting that you have discussed your project with all functional units and have incorporated all their comments or have discussed with them why they will not be incorporated.

SECTION 1: EARTHWORK

Item code	Unit	Quantity		Unit Price (\$)		Cost
160101 Clearing & Grubbing	LS		x		= \$	-
170101 Develop Water Supply	LS	1	x	0.00	= \$	-
190101 Roadway Excavation	CY		x		= \$	-
190103 Roadway Excavation (Type Y) ADL	CY		x		= \$	-
190105 Roadway Excavation (Type Z-2) ADL	CY		x		= \$	-
192037 Structure Excavation (Retaining Wall)	CY		x		= \$	-
193013 Structure Backfill (Retaining Wall)	CY		x		= \$	-
193031 Pervious Backfill Material (Retaining Wall)	CY		x		= \$	-
194001 Ditch Excavation	CY		x		= \$	-
198001 Impored Borrow	CY		x		= \$	-
198007 Imported Material (Shoulder Backing)	TON		x		= \$	-
XXXXXX	ls	1	x	0.00	= \$	-

TOTAL EARTHWORK SECTION ITEMS	\$	-
-------------------------------	----	---

SECTION 2: PAVEMENT STRUCTURAL SECTION

Item code	Unit	Quantity		Unit Price (\$)		Cost
398100 Remove Asphalt Concrete Dike	LF		x		= \$	-
150860 Remove Base and Surfacing	CY		x		= \$	-
153103 Cold Plane Asphalt Concrete Pavement	SQYD	130	x	85.26	= \$	11,084
1532XX Remove Concrete (type)	CY		x		= \$	-
250401 Class 4 Aggregate Subbase	CY		x		= \$	-
260303 Class 3 Aggregate Base	CY		x		= \$	-
280000 Lean Concrete Base	CY		x		= \$	-
290201 Asphalt Treated Permeable Base	CY		x		= \$	-
365001 Sand Cover	TON		x		= \$	-
374002 Asphaltic Emulsion (Fog Seal Coat)	TON		x		= \$	-
374492 Asphaltic Emulsion (Polymer Modified)	TON		x		= \$	-
3750XX Screenings (Type XX)	TON		x		= \$	-
377501 Slurry Seal	TON		x		= \$	-
390095 Replace Asphalt Concrete Surfacing	CY		x		= \$	-
390132 Hot Mix Asphalt (Type A)	TON	22	x	1,632.52	= \$	35,915
390136 Minor Hot Mix Asphalt	TON		x		= \$	-
390137 Rubberized Hot Mix Asphalt (Gap Graded)	TON		x		= \$	-
393003 Geosynthetic Pavement Interlayer	SQYD		x		= \$	-
39405X Shoulder Rumber Strip (HMA, Type XX Inden	STA		x		= \$	-
394074 Place Hot Mix Asphalt Dike	LF		x		= \$	-
394090 Place Hot Mix Asphalt (Misc. Area)	SQYD		x		= \$	-
397005 Tack Coat	TON		x		= \$	-
398001 Remove Asphalt Concrete Pavement	SQYD		x		= \$	-
401000 Concrete Pavement	CY		x		= \$	-
401050 Jointed Plain Concrete Pavement	CY		x		= \$	-
401108 Replace Concrete Pavement (Rapid Strength	CY		x		= \$	-
404092 Seal Pavement Joint	LF		x		= \$	-
404094 Seal Longitudinal Isolation Joint	LF		x		= \$	-
413112A Repair Spalled Joints (Polyester Grout)	SQYD		x		= \$	-
413115 Seal Existing Concrete Pavement Joint	LF		x		= \$	-
420102 Groove Existing Concrete Pavement	SQYD		x		= \$	-
420201 Grind Existing Concrete Pavement	SQYD		x		= \$	-
731502 Minor Concrete (Stamped Concrete)	SQFT		x		= \$	-
03998X No.4 Wired Mesh	SQFT		x		= \$	-

SECTION 3: DRAINAGE

Item code	Unit	Quantity	Unit Price (\$)	Cost
150206 Abandon Culvert	LF	x	= \$	-
150805 Remove Culvert	LF	x	= \$	-
150820 Modify Inlet	EA	x	= \$	-
152430 Adjust Inlet	LF	x	= \$	-
155003 Cap Inlet	EA	x	= \$	-
193114 Sand Backfill	CY	x	= \$	-
510502 Minor Concrete (Minor Structure)	CY	x	= \$	-
510512 Minor Concrete (Box Culvert)	CY	x	= \$	-
62XXXX XXX" APC Pipe	LF	x	= \$	-
64XXXX XXX" Plastic Pipe	LF	x	= \$	-
65XXXX XXX" RCP Pipe	LF	x	= \$	-
66XXXX XXX" CSP Pipe	LF	x	= \$	-
68XXXX Edge Drain	LF	x	= \$	-
69XXXX XXX" Pipe Downdrain	LF	x	= \$	-
70XXXX XXX" Pipe Inlet	LF	x	= \$	-
70XXXX XXX" Pipe Riser	LF	x	= \$	-
70XXXX XXX" Flared End Section	EA	x	= \$	-
703233 Grated Line Drain	LF	x	= \$	-
72XXXX Rock Slope Protection (Type and Method)	CY	x	= \$	-
721420 Concrete (Ditch Lining)	CY	x	= \$	-
721430 Concrete (Channel Lining)	CY	x	= \$	-
729010 Rock Slope Protection Fabric	SQYD	x	= \$	-
750001 Miscellaneous Iron and Steel	LB	x	= \$	-
XXXXXX Additional Drainage	LS	1	x 1,000,000.00	= \$ 1,000,000
XXXXXX Some Item		x	= \$	-

TOTAL DRAINAGE ITEMS \$ 1,000,000

SECTION 4: SPECIALTY ITEMS

Item code	Unit	Quantity	Unit Price (\$)	Cost
70012 Progress Schedule (Critical Path Method)	LS	1	x 957,102	= \$ 957,102
150662 Remove Metal Beam Guard Railing and Curb	LF	12,226	x 92.86	= \$ 1,135,312
150668 Remove Terminal Systems	EA	x	= \$	-
153221 Remove Barrier (Type 50)	LF	6,113	x 70.20	= \$ 429,106
153250 Remove Sound Wall	SQFT	x	= \$	-
190110 Lead Compliance Plan	LS	1	x 1,203,901	= \$ 1,203,901
49XXXX CIDH Concrete Piling (<i>Insert Diameter</i>)	LF	x	= \$	-
510060 Structural Concrete (Retaining Wall)	CY	x	= \$	-
510133 Class 2 Concrete (Retaining Wall)	CY	x	= \$	-
510524 Minor Concrete (Sound Wall)	CY	x	= \$	-
5110XX Architectural Treatment (<i>Insert Type</i>)	SQFT	x	= \$	-
511048 Apply Anti-Graffiti Coating	SQFT	1	x 0.00	= \$ -
5136XX Reinforced Concrete Crib Wall (<i>Insert Type</i>)	SQFT	x	= \$	-
518002 Sound Wall (Masonry Block)	SQFT	x	= \$	-
520103 Bar Reinf. Steel (Retaining Wall)	LB	x	= \$	-
80XXXX Fence (<i>Insert Type</i>)	LF	x	0.00	= \$ -
800360 Chain Link Fence	LF	12,226	x 225.73	= \$ 2,759,793
832001 Metal Beam Guard Railing	LF	x	= \$	-
832005 Install Midwest Guardrail System	LF	x	= \$	-
839310 Double Midwest Guardrail System	LF	x	= \$	-
839521 Minor Concrete (Curb and Gutter)	LF	x	= \$	-
83954X Transition Railing (<i>Insert Type</i>)	EA	x	= \$	-
8395XX Alternative In-line Terminal System (MASH)	EA	x	= \$	-
8395XX Alternative Flared Terminal System	EA	x	= \$	-
8395XX End Anchor Assembly (<i>Type SFT</i>)	EA	x	= \$	-
839561 Rail Tensioning Assembly	EA	x	= \$	-
839XXX Crash Cushion (<i>Insert Type</i>)	EA	x	= \$	-
83XXX1 Concrete Median Barrier (<i>Type 60MA</i>)	LF	6,122	x 526.71	= \$ 3,224,500
83XXX2 Bridge Rail (CA ST-75)	LF	12,184	x 526.71	= \$ 6,417,397
83XXX3 Concrete Barrier (<i>ST-70SM (Mod2)</i>)	LF	x	= \$	-
83XXX4 Concrete Barrier (<i>ST-70SM (Mod1)</i>)	LF	x	= \$	-
190113 Asbestos Compliance Plan	LS	1	x 188,110	= \$ 188,110
83XXXX Install Compression Rail End Treatment	EA	x	= \$	-
XXXXXX Develop Water Supply	LS	1	x 485,463.00	= \$ 485,463
Relocate utility	LS	1	500,000.00	= \$ 500,000

TOTAL SPECIALTY ITEMS \$ 17,300,685

SECTION 5: ENVIRONMENTAL

5A - ENVIRONMENTAL MITIGATION

Item code	Unit	Quantity	Unit Price (\$)	Cost
XXXXXX Coastal Development Permit Filing Fee	LS	1	x 20,000.00	= \$ 20,000
071325 TEMPORARY REINFORCED SILT FENCE	LF		x	= \$ -
XXXXXX Bird Deterrent	LS	1	x 2,802,860.81	= \$ 2,802,861
Remove/handle asbestos material	LS	1	1,000,000.00	\$ 1,000,000
Contractor supply Biologist	LS	1	1,500,000.00	\$ 1,500,000
Subtotal Environmental				\$ 5,322,861

5B - LANDSCAPE AND IRRIGATION

Item code	Unit	Quantity	Unit Price (\$)	Cost
200001 Highway Planting	LS		x	= \$ -
20XXXX XXX" (Insert Type) Conduit (Use for	LF		x	= \$ -
20XXXX Extend XXX" (Insert Type) Conduit	LF		x	= \$ -
201700 Imported Topsoil	CY		x	= \$ -
2030XX Erosion Control (Type __)	SQYD		x	= \$ -
13064x Fiber Rolls	LF		x	= \$ -
203026 Move In/ Move Out (Erosion Control)	EA		x	= \$ -
204099 Plant Establishment Work	LS		x	= \$ -
204101 Extend Plant Establishment (X Years)	LS		x	= \$ -
208000 Irrigation System	LS		x	= \$ -
208304 Water Meter	EA		x	= \$ -
209801 Maintenance Vehicle Pullout	EA		x	= \$ -
XXXXXX Some Item			x	= \$ -
Subtotal Landscape and Irrigation				\$ -

5C - NPDES

Item code	Unit	Quantity	Unit Price (\$)	Cost
130100 Job Site Management	LS	1	x 1,305,883.00	= \$ 1,305,883
74017 Prepare WPCP	LS	1	x 37,590.00	= \$ 37,590
130200 Prepare SWPPP	LS		x	= \$ -
74023 Temporary Erosion Control	SQYD		x	= \$ -
130330 Storm Water Annual Report	EA		x	= \$ -
130640 Temporary Fiber Roll	LF	12,500	x 8.00	= \$ 100,000
130900 Temporary Concrete Washout	LS	1	x 75,000.00	= \$ 75,000
130710 Temporary Construction Entrance	EA	4	x 48,939.97	= \$ 195,760
74035 Temporary Check Dam	LF		x	= \$ -
74037 Move In/ Move Out (Temporary Erosion Cont	EA		x	= \$ -
130620 Temp. Drainage Inlet Protection	EA	10	x 1,000.00	= \$ 10,000
74041 Street Sweeping	LS	1	x 1,196,811	= \$ 1,196,811
74042 Temporary Concrete Washout (Portable)	LS	1	x 65,030.00	= \$ 65,030
74018 Natural Resources Protection Plan	LS	1	x 375,899.00	= \$ 375,899

Supplemental Work for NPDES

(These costs are not accounted in total here but under Supplemental Work on sheet 7 of 11).

66595 Water Pollution Control Maintenance Sharing*	LS	1	x 50,000.00	= \$ 50,000
66596 Additional Water Pollution Control**	LS	1	x 50,000.00	= \$ 50,000
66597 Storm Water Sampling and Analysis***	LS	1	x 50,000.00	= \$ 50,000
66916 Annual Construction General Permit Fee	LS	1	x 20,000.00	= \$ 20,000

Subtotal NPDES (Without Supplemental Work) \$ 3,361,973

*Applies to all SWPPPs and those WPCPs with sediment control or soil stabilization BMPs.

**Applies to both SWPPPs and WPCP projects.

*** Applies only to project with SWPPPs.

TOTAL ENVIRONMENTAL \$ 8,684,834

SECTION 6: TRAFFIC ITEMS

6A - Traffic Electrical

Item code	Unit	Quantity	Unit Price (\$)	Cost
150760 Remove Sign Structure	EA	1	105,262.00	= \$ 105,262
151581 Reconstruct Sign Structure	EA			= \$ -
152641 Modify Sign Structure	LS	1	1,127,806.00	= \$ 1,127,806
870009 Maintain Existing Traffic Management System Elements During Construction	LS	1	100,000.00	= \$ 100,000
5602XX Install Sign Structure	LS	1	187,968.00	= \$ 187,968
872XXX Maintain Existing Electrical System	LS	1	225,561.00	= \$ 225,561
872130 Modify Existing Electrical System	LS			= \$ -
872134 Modify Ramp Metering System	LS	1	250,000.00	= \$ 250,000
86055X Lighting & Sign Illumination	LS	1	450,000.00	= \$ 450,000
8607XX Interconnection Facilities	LS			= \$ -
8609XX Traffic Monitoring Stations	LS			= \$ -
860XXX Modify Signals & Lighting	LS	1	500,000.00	= \$ 500,000
8611XX Ramp Metering System (Location X)	LS			= \$ -
8611XX Fiber Optic Testing and Documentation	LS			= \$ -
871900 Install Fiber Optic Conductor on Exist Conduit	LS	6,200	50.00	= \$ 310,000
XXXXXX Vandal Resistant Pullbox	EA			= \$ -
Subtotal Traffic Electrical				\$ 3,256,597

6B - Traffic Signing and Striping

Item code	Unit	Quantity	Unit Price (\$)	Cost
120090 Construction Area Signs	LS	1	\$ 1,202,606	= \$ 1,202,606
150701 Remove Yellow Painted Traffic Stripe	LF	12,600	4.00	= \$ 50,400
150710 Remove Traffic Stripe	LF			= \$ -
150713 Remove Pavement Marking	SQFT			= \$ -
150742 Remove Roadside Sign	LS	1	37,594	= \$ 37,594
152320 Reset Roadside Sign	LS			= \$ -
150761 Overhead Signage and Structure	LS		0	= \$ -
566011 Roadside Sign (One Post)	LS	1	225,561	= \$ 225,561
566012 Roadside Sign (Two Post)	EA			= \$ -
560XXX Furnish Sign Panels	LB	51,000	17.00	= \$ 867,000
562002 Barrier Mounted Sign	LS	1	150,374	= \$ 150,374
84050X Thermoplastic Traffic Stripe	LF	48,480	5.81	= \$ 281,886
840515 Thermoplastic Pavement Marking	LS	1	15,037	= \$ 15,037
560XXX Install Sign Panels	SQFT			= \$ -
820XXX Gore Area Striping	EA			= \$ -
XXXXXX Modified Changeable message sign	LS	1	200,000.00	= \$ 200,000
Subtotal Traffic Signing and Striping				\$ 3,030,458

6C - Stage Construction and Traffic Handling

Item code	Unit	Quantity	Unit Price (\$)	Cost
120100 Traffic Control System	LS	1	7,565,418	= \$ 7,565,418
120103 Impact Attenuator Vehicle	EA			= \$ -
xxxxxx Contractor's Office	LS	1	1,540,000.00	= \$ 1,540,000
12016X Channelizer	EA			= \$ -
128651 Portable Changeable Message Signs	LS	1	822,862	= \$ 822,862
129000 Temporary Railing (Type K)	LF	14,400	40.00	= \$ 576,000
129100 Temp. Crash Cushion Module	EA	6	1,749.00	= \$ 10,494
120204 Portable Radar Speed Feedback Sign	EA			= \$ -
839603A Temporary Crash Cushion (ADIEM)	EA			= \$ -
120101 Traffic Control Supervisor	LS	1	263,460	= \$ 263,460
Temporary elevators	EA	4	1,315,616	= \$ 5,262,465
Public Campaign awareness	LS	\$ 1	\$ 323,000	= \$ 323,000
Subtotal Stage Construction and Traffic Handling				\$ 16,363,699

TOTAL TRAFFIC ITEMS \$ 22,650,754

SECTION 7: DETOURS

Include constructing, maintaining, and removal

Item code	Unit	Quantity	Unit Price (\$)	Cost
0713XX Temporary Fence (Type X)	LF	x	= \$	-
07XXXX Temporary Drainage	LS	x	= \$	-
12014x Temporary Pavement Delineation	LF	1	= \$	-
1286XX Temporary Signals	EA	1	= \$	-
12900X Temporary Railing (Type K)	LF	x	= \$	-
190101 Roadway Excavation	CY	x	= \$	-
198001 Imported Borrow	CY	x	= \$	-
198050 Embankment	CY	x	= \$	-
250401 Class 4 Aggregate Subbase	CY	x	= \$	-
260201 Class 2 Aggregate Base	CY	x	= \$	-
39013X Hot Mix Asphalt (Type A)	TON	31,022	x 240.00	= \$ 7,445,280
390137 RHMA	TON	23,270	285.00	\$ 6,631,950
398200 Cold Plane	SQYD	233,057	x 12.50	= \$ 2,913,213
Remove and Replace JPCP Paving	CY	3,315	1,400.00	\$ 4,641,000
XXXX Signs ,Pavement Delineation	LS	1	1,000,000.00	\$ 1,000,000
SWPPP, BMP's, Sweeping		1	400,000.00	\$ 400,000
120100 Traffic Control	LS	1	1,200,000.00	\$ 1,200,000

TOTAL DETOURS \$ 24,231,500

SUBTOTAL SECTIONS 1-7 \$ 73,914,773

SECTION 8: MINOR ITEMS

8A - Americans with Disabilities Act Items

ADA Items

0.2%

8B - Bike Path Items

Bike Path Items

0.2%

8C - Other Minor Items

Other Minor Items

3.0%

Total of Section 1-7 \$ 73,914,773 x 6.0% = \$ 4,434,886

TOTAL MINOR ITEMS \$ 4,434,900

SECTIONS 9: MOBILIZATION

Item
code

999990 Total Section 1-8 \$ 78,349,673 x 15% = \$ 11,752,451

TOTAL MOBILIZATION \$ 11,752,500

SECTION 10: SUPPLEMENTAL WORK

Item code	Unit	Quantity	Unit Price (\$)	Cost
66015 Federal Trainee Program	LS	1	x 100,000.00	= \$ 100,000
6606x Traffic Management Plan - Public Informati	LS	1	x 1,000,000.00	= \$ 1,000,000
66090 Maintain Traffic	LS	1	x 1,000,000.00	= \$ 1,000,000
66094 Value Analysis	LS	1	x 50,000.00	= \$ 50,000
66204 Remove Rock & Debris	LS	x	= \$	-
66061A RR Agreement and Flagging Service	LS	1	x 2,000,000.00	= \$ 2,000,000
66670 Payment Adjustments For Price Index Fluct	LS	1	x 300,000.00	= \$ 300,000
66700 Partnering	LS	1	x 100,000.00	= \$ 100,000
66866 Operation of Existing Traffic Management S	LS	1	x 300,000.00	= \$ 300,000
66920 Dispute Review Board	LS	1	x 126,829.27	= \$ 126,829
90205 Dispute Resolution Board On-Site Meeting	LS	1	x 198,170.73	= \$ 198,171

Cost of NPDES Supplemental Work specified in Section 5C = \$ 170,000

Total Section 1-8 \$ 78,349,673 1% = \$ 783,497

TOTAL SUPPLEMENTAL WORK \$ 6,128,497

SECTION 11: STATE FURNISHED MATERIALS AND EXPENSES

Item code		Unit	Quantity		Unit Price (\$)		Cost
66063	Public Information	LS	1	x	73,598	= \$	73,598
66105	RE Office	LS	1	x	1,223,106	= \$	1,223,106
66803	Padlocks	LS		x		= \$	-
66838	Reflective Numbers and Edge Sealer	LS		x		= \$	-
66901	Water Expenses	LS		x		= \$	-
066062A	COZEEP Expenses	LS	1	x	2,000,000	= \$	2,000,000
06684X	Ramp Meter Controller Assembly	LS		x		= \$	-
06684X	TMS Controller Assembly	LS		x		= \$	-
06684X	Traffic Signal Controller Assembly	LS		x		= \$	-
XXXXXX	Railroad Flagging	LS		x		= \$	-

Total Section 1-8 \$ 78,349,673 0% = \$ -

TOTAL STATE FURNISHED	\$ 3,296,704
------------------------------	------------------------

SECTION 12: TIME-RELATED OVERHEAD

Estimated Time-Related Overhead (TRO) Percentage (0% to 10%) = 10% \$36,754,967

Item code		Unit	Quantity		Unit Price (\$)		Cost	
				Total of All Contract Items Only		\$	367,549,673	(used to calculate TR
				Total Project Cost		\$	495,297,574	(used to check if proje
70018	Time-Related Overhead	LS	1	x	36,754,967.30	= \$	36,754,967	

TOTAL TIME-RELATED OVERHEAD	\$36,754,967
------------------------------------	---------------------

SECTION 13: CONTINGENCY

(Pre-PSR 30%-50%, PSR 25%, Draft PR 20%, PR 15%, after PR approval 10%, Final PS&E 5%)

Total Section 1-11 \$ 96,230,670 x 19% = \$18,283,828

TOTAL CONTINGENCY	\$18,283,828
--------------------------	---------------------

II. STRUCTURE ITEMS

	<u>Bridge 1</u>	<u>Seismic Sensors</u>	<u>Bridge 3</u>
DATE OF ESTIMATE	08/12/24	08/12/24	08/12/24
Bridge Name	Vincent Thomas	Vincent Thomas	XXXXXXXXXXXXXXXXXXXX
Bridge Number	53-1471	53-1471	XXXXXXXXXXXXXXXXXXXX
Structure Type	Over Cross Bridge	Over Cross Bridge	Over Cross Bridge
Width (Feet) [out to out]	58.00 LF	0.00 LF	0.00
Total Bridge Length (Feet)	6062.00 LF	0.00 LF	0.00
Total Area (Square Feet)	351596 SQFT	0 QFT	0
Structure Depth (Feet)	0.00 LF	44.00 units	0.00
Footing Type (pile or spread)	XXXXXXXXXXXXXXXXXXXX	XXXXXXXXXXXXXXXXXXXX	XXXXXXXXXXXXXXXXXXXX
Cost Per Square Foot		\$0.00	\$0.00

COST OF EACH STRUCTURE	\$289,200,000.00		\$0.00
-------------------------------	-------------------------	--	---------------

DATE OF ESTIMATE	00/00/00	00/00/00	00/00/00
Building Name	XXXXXXXXXXXXXXXXXXXX	XXXXXXXXXXXXXXXXXXXX	XXXXXXXXXXXXXXXXXXXX
Bridge Number	57-XXX	57-XXX	57-XXX
Structure Type	XXXXXXXXXXXXXXXXXXXX	XXXXXXXXXXXXXXXXXXXX	XXXXXXXXXXXXXXXXXXXX
Width (Feet) [out to out]	100.00 LF	0.00 LF	0.00
Total Building Length (Feet)	150.00 LF	0.00 LF	0.00
Total Area (Square Feet)	15000 SQFT	0.00 QFT	0.0
Structure Depth (Feet)	0.00 LF	0.00 LF	0.00
Footing Type (pile or spread)	XXXXXXXXXXXXXXXXXXXX	XXXXXXXXXXXXXXXXXXXX	XXXXXXXXXXXXXXXXXXXX
Cost Per Square Foot	\$0.00	\$0.00	\$0.00

COST OF EACH STRUCTURE	\$0.00	\$0.00	\$0.00
-------------------------------	---------------	---------------	---------------

TOTAL COST **\$289,200,000**

TOTAL COST **\$0**

Time-Related Overhead 10% **\$0**

STRUCTURES MOBILIZATION 15% **\$43,380,000**

STRUCTURES CONTINGENCY* 19% **\$63,190,200**

TOTAL COST OF STRUCTURES¹	\$395,770,200.00
---	-------------------------

Estimate Review By: Jinrong Wang Date: _____
Jinrong Wang - Division of Structures

¹Structure's Estimate includes Overhead and Mobilization, and it is an average cost estimate between the price provided by the Independent Cost Estimate (ICE) and the Construction Manager (CM) amount.

III. RIGHT OF WAY

Fill in all of the available information from the Right of Way data sheet.

A)	A1) Acquisition, including Excess Land Purchases, Damages & Goodwill,	\$	1,642,510
	A2) SB-1210	\$	0
B)	Acquisition of Offsite Mitigation	\$	0
C)	C1) Utility Relocation (State Share)	\$	
	C2) Potholing (Design Phase)	\$	0
D)	Railroad Acquisition	\$	0
E)	Clearance / Demolition	\$	0
F)	Relocation Assistance (RAP and/or Last Resort Housing Costs)	\$	0
G)	Title and Escrow	\$	0
H)	Environmental Review	\$	0
I)	Condemnation Settlements <u>0%</u> (Items G & H applied to items A + B)	\$	0
J)	Design Appreciation Factor 0%	\$	0
K)	Utility Relocation (Construction Cost)	\$	0

L)

TOTAL RIGHT OF WAY ESTIMATE	\$1,642,510
------------------------------------	--------------------

(Excluding Item #8 - Hazardous Waste)

M)

TOTAL R/W ESTIMATE: Escalated	\$1,699,998
--------------------------------------	--------------------

N)

Right of Way Support	\$ 1,683,000
-----------------------------	---------------------

Support Cost Estimate Prepared By	Wayne Lee Project Coordinator ¹	213-269-0509 Phone
Utility Estimate Prepared By	Wael Alshami Utility Coordinator ²	805-748-9988 Phone
R/W Acquisition Estimate Prepared By	Tracie Banks Right of Way Estimator ³	213-897-2063 Phone

¹ When estimate has Support Costs only

² When estimate has Utility Relocation

³ When R/W Acquisition is required

ATTACHMENT F

Right of Way Data Sheet

A

DEPARTMENT OF TRANSPORTATION

M e m o r a n d u m

*Serious Drought!
Help Save Water!*

To: Mario Gutierrez, Design Manager
Office of Design
District 7, Los Angeles Office

Date: 10/11/2024

EA: 39020

From: Zoltan Elo, Office Chief
Right of Way Appraisals, and Planning & Management
District 7, Los Angeles Office

Data Sheet ID NO: ds6574

Project ID # 0722000334

Subject: Current Estimated Right of Way Costs for **Project Report**

We have completed an estimate of the Right of Way costs for the above referenced project based on information received from Wilfrido Morales, PE and the following assumptions and limiting conditions apply:

- The mapping did not provide sufficient detail to determine the limits of the right of way required.
- The transportation facilities have not been sufficiently designed, so our estimator could not determine the damages to any of the remainder parcels affected by the project.
- Additional right of way requirements are anticipated, but are not defined due to the preliminary nature of the estimate.

Right of Way Certificate (RWC) lead time will require a minimum of 24 months after maps to appraisal (MA). Completed Appraisal maps include HMDD, COS, HW Memo, and RE-49. An executed copy of the new freeway agreement is required for the project. When utility relocation is warranted, utility conflict maps will be required. Additionally a minimum of 18 months will be required after receiving the last revision to the appraisal map. Shorter lead times will require either more right of way resources or an increased number of condemnation suits to be filed and present a risk to the RWC project delivery milestone. Due to the passage of Map 21 and the Buy America provision, the Right of Way Certification process will be longer, if Utility Relocation is necessary.

Current Schedule: PRSM

PAED (M 200)	MA (M 224)	RWC (M 410)	RTL (M 460)	CCA (M 600)
10/15/2024	1/2/2025	6/23/2025	7/8/2025	7/30/2027

TO Mario Gutierrez
ATTN Wilfrido Morales
SENIOR R/W P&M Rimma Tebeleva
ROUTE 47
PM_KM 0.4/2.0
EA 39020
Project ID # 0722000334
ALT

R/W DATA SHEET

ID NO ds6574

Date of Data Sheet 10/11/2024
Project Description Vincent Thomas Bridge Deck Replacement

This cost estimate is valid for the above scoping report only. This is an estimate only and not an appraisal. It may be based on worse case scenarios.

The estimate is subject to change and revision.

The mapping did not provide sufficient nor adequate detail to determine the limits of the Right of Way required and effects on the improvements.

The transportation facilities have not been sufficiently designed for our estimator to determine the damages to any of the remainder parcels affected by the project.

This cost estimate is pursuant to the following responses supplied by Mario Gutierrez to the Data Sheet Request Form.

	YES	NO	Not known at this time
Utilities are depicted on plans		x	
Railroads are depicted on plans	x		
There are Material and/or Disposal Sites Required		x	
Caltrans will do the Right of Way work	x		
There will be a Cooperative Agreement			x
This is a reimbursable project	x		
There is Hazardous Waste potential		x	

RW COST ESTIMATE

	CURRENT VALUE	ESCALATED VALUE
R/ w acq.(incl.contingency G.w-condem.-adm.s'tl.)Permits	\$1,730,000	\$1,730,000
Clearance		
RAP (cont rate.)		
Escrow costs (cont rate.)		
Utility relocation costs		
Estimate of Reimbursed Appraisal Fee		
Total estimated cost	\$1,730,000	\$1,730,000

Escalation Rate Rw .07
Escalation Rate Utilities .08
Cert.date 6/23/25

Parcel Count and Py Info

PARCEL DUAL
TYPES APPR.

A		
B		
C	6	
D		
F		

RIGHTS
NEEDED

FEE

EASE

TCE

6

TAKES

FULL

PART

TOTAL

0
6
6

DISPLACEMENT
OF UNITS

SFR

BUS

MULTI

PARCELS WITH
RAP

--

POTENTIAL
CLEARANCE
PARCELS

--

POTENTIAL
CONDEMNATION
PARCELS

--

POTENTIAL
EXCESS
PARCELS

--

UTILITY IMPACTS

u4-1	
u4-2	
u4-3	
u4-4	
u5-7	
u5-8	
u5-9	

Estimate Of Right Of Way Support Hours

Activity Codes	Function	Hours
225 & 245	Appraisals	
225 & 245	Acquisitions	10,361
200	Utilities	
185.20.40	Utility Potholing	
205	Railroads	
225 & 245	Condemnation	
225 & 245	Clearance	
225 & 245	Relocation	
220 & 300	RW Engineering	2,590
	Total	12,951

UTILITY INFORMATION

Are utility easements required? _____
Are Utility agreements required? _____

Total Cu Ent Cost _____
Const. Completion Date 7/30/2027
Utility Escalation Rate 8%
Total Escalated Cost _____

RR INFORMATION

Are RR affected YES

Describe the RR facilities affected, and ownership: PHL Primary Track Operator but fee is owned by L.A. City (i.e. RR name, RR spurs, branch lines, at grade crossings?)

Will construction work be performed in RR right of way? Y/N If yes, describe:

What types of agreements are anticipated to be required from the RR?

Will Temporary Construction Easement (TCE) rights be required for the project construction? If yes, explain.

Phase 4 costs: RR Flagging related to construction activity. This cost is a phase 4 construction contract cost. Though noted on the RW datasheet, the estimated flagging cost is not a RW cost, and not a part of the RW Capital. This estimate is provided so it can be added to the engineer's estimate for construction – RR flagging estimate is based on the number of days flagging is needed for construction activity.

Phase 9 costs: Purchase of rights for construction, agreements, Preliminary Engineering Contracts, RR re-arrangement costs. This figure is included in the RW Capital estimate total.

		<u>DATE</u>
Right of Way Estimate prepared by	Victor Lee	<u>10/4/24</u>
Estimate prepared by	Victor Lee	<u>10/4/24</u>
Utilities Estimate prepared by	Victor Lee	<u>10/4/24</u>

I have personally reviewed this R/W Data Sheet and all supporting information I certify that the probable highest and best use estimated values and assumptions are reasonable and proper subject to the limiting conditions set forth and I find this Data Sheet complete and current.

This Data Sheet is not to be signed by Chief unless accompanied by final scoping report(PR,PSR,PSSR) for review and/or signature.

CHIEF	<u>Wayne D. Lee</u>	<u>10/11/24</u>
-------	---------------------	-----------------

ATTACHMENT G

Storm Water Data Report (SWDR)



Dist-County-Route: 07-LA-47

Post Mile Limits: 0.4/2.0

Project Type: Bridge Rehabilitation

Project ID (EA): 0722000334 (390200)

Phase: ☐ PID ☒ PA/ED ☐ PS&E

Regional Water Quality Control Board(s): Los Angeles – Region 4

- | | | |
|--|------------------------------|--|
| 1. Does the project disturb 5 or more acres of soil? | Yes ☐ | No ☒ |
| 2. Does the project disturb 1 or more acres of soil and not qualify for the Rainfall Erosivity Waiver? | Yes ☐ | No ☒ |
| 3. Is the project required to implement Treatment BMPs? | Yes ☐ | No ☒ |
| 4. Does the project impact existing Treatment BMPs? | Yes ☐ | No ☒ |

If the answer to any of the preceding questions is “Yes”, prepare a Long Form – Stormwater Data Report.
Unless otherwise agreed upon by the District/Regional Design Stormwater Coordinator.

Applicable Caltrans Permit Post Construction Treatment Requirement: 2012 ☐ 2022 ☒
Total Disturbed Soil Area: 0.0 acre New Impervious Surface: 0.0 acre
Estimated Const. Start Date: 11/4/2025 Estimated Const. Completion Date: 07/30/2027

Risk Level: RL 1 ☐ RL 2 ☐ RL 3 ☐ Not Applicable ☒
Is (M)WEL0 applicable? Yes ☐ No ☒

This Short Form – Stormwater Data Report has been prepared under the direction of the following Licensed Person. The Licensed Person attests to the technical information contained herein and the data upon which recommendations, conclusions, and decisions are based. Professional Engineer or Landscape Architect stamp required at PS&E only.

 10/8/2024
Mario Gutierrez, Registered Project Engineer Date

I have reviewed the stormwater quality design issues and find this report to be complete, current, and accurate:

[Stamp Required at PS&E only]  10/09/2024
Shao-Chiang Liu, District/Regional Design SW Coordinator Date
or Designee

1. Project Description

- This project proposes to remove and replace the existing CIP lightweight bridge deck at the approach and suspension spans with a new pre-cast concrete deck at Vincent Thomas Bridge (Bridge Number 53-1471). The columns and abutments will be intact.
- Remove the existing metal railing and steel plate curb at suspended spans and replace it with CA ST-75 Bridge Rail.
- Remove the existing 12' height chain link fence at suspended spans and replace it with 12' height chain link fence.
- Remove the existing Type 2 barrier and 6' chain link at approach spans and replace it with CA ST-75 bridge railing with a 6' chain link fence (Mounted on ST-75 railing curb).
- Remove the existing median concrete barrier Type 50 and replace it with Type 60M.
- Remove and replace 18 joint seals at approach spans, 11 joint seals at suspension spans.
- Remove 4 finger joints at suspension spans and replace with seismic joints.
- Remove existing 26 seismic sensors and replace with 44 ungraded seismic sensors.
- Removed and replace 29 barrier-mounted electroliers at approach spans.
- Upgrade 160 light fixtures of "low light system" along the suspended spans.
- Install 30 painter's receptacle on the sub-structure of the bridge for maintenance paint crew.
- Install and upgrade signs (2 OH signs and approximately 26 barrier and /or pole-mounted roadside signs), and pavement marking per current standard.
- Remove and re-install an OH sign truss across the main line (East approach span).
- Removed and replace cantilever OH sign (West approach span).
- Install 8 temporary elevators at ground level under the bridge before construction phase and dismantle 8 temporary elevators after construction phase. (No excavation anticipated).
- Install a "Quick Deck" system along and under the bridge's sub-structure.
- Repair of local roads, under Early Work Packages (EWP).
- Construction will be entirely within the State's right of way. Therefore, no additional right of way will be needed.
- This project is not a new facility or major reconstruction. There will be no change in line /grade or hydraulic capacity. The project will not create new slopes or modify existing slopes. In addition, construction site BMPs will be implemented during construction. All construction activities, including the contractor's staging areas, will be done on paved areas. Therefore, this project does not have the potential to create water quality impacts.
- This project's limits fall within Los Angeles County. This project is in an urban MS4 area.
- There is no soil being disturbed. The Disturbed Soil Area (DSA) = 0 acre.
- Replaced Impervious Surface (RIS) = 0 acres
- New Net Impervious Surface (NNI) = 0 acre
- New Impervious Surface (NIS) = NNI + RIS = 0 + 0 = 0 acre
- Post Construction Treatment Area (PCTA) = NIS + ATA = 0 + 0 = 0 acre.
- The total cost of this project is \$648,251,000.

- Additional information will be provided during the PS&E phase.

2. Site Data and Stormwater Quality Design Issues

- This project limits are within the Hydrological Unit Dominguez Channel and Hydrological Sub-Area number #411.02, 411.03, 411.04.
- The 2022-2022 303 (d) listed receiving waterbody within the project is Los Angeles/ Long Beach Inner Harbor. Pollutant of concern are as follows: Benthic Community Effects, Benzo(a) Pyrene, Chrysene (C1-C4), Dichlorodiphenyl- Trichloroethane (DDT), Polychlorinated Biphenyls (PCBs), and Metal (Cu, Zn), Toxicity.
- There are no drinking water reservoirs or recharge facilities within the project limits.
- This project fall within Los Angeles County, in urban MS4 area.
- This project does not require 401 certification.
- The project limits are in the Dominguez channel watershed. The Total Maximum Daily Loads (TMDLs) are as follow:

1 Dominguez Channel

Pollutant(s)	Effective Date	LA RWQB Resolution No.	Categorical Implementation Requirements ^{1 2}
Title: Dominguez Channel and Greater Los Angeles and Long Beach Harbor Waters Toxic Pollutants TMDL			
Toxic pollutants (dichlorodiphenyl-trichloroethane (DDT), polycyclic aromatic hydrocarbons (PAHs), total polychlorinated biphenyls (PCBs), metals (Cu, Pb, Zn))	03/23/2012	R11-008	Targeted pollutants are to be monitored in the water column in the channel and harbors as well as the sediment in the harbors. The TMDL requires the dischargers of the Los Angeles River and the San Gabriel River to monitor water quality at the mouth of each river. Caltrans shall implement control measures and/or treatment BMPs to prevent the discharge of sediments which may contain toxic pollutants as listed in the TMDL. Possible treatment options include the interception and infiltration of runoff which will allow water to percolate into soil.

1 Refer to §4 of the PPDG to determine the specific impervious threshold for stormwater Treatment BMP requirements.

2 General TMDL Requirements can be found in Attachment IV of the NPDES Statewide Storm Water Permit.

- Additional information will be provided during the PS&E phase.

3. Construction Site BMPs

- This project requires Water Pollution Control Program (WPCP) since the total Disturbed Soil Area (DSA) created by the project is less than 1 acre.
- The following BMPs are included in the lump sum bid item for Job Site Management:
 - Vehicle and Equipment Fueling and Maintenance

- Paving, Sealing, Saw Cutting, Grooving, and Grinding Activities
 - Material Delivery and Storage
 - Water Conservation Practices
 - Material Use
 - Spill Prevention and Control
 - Hazardous Waste Management
 - Sanitary and Septic Waste
 - Solid Waste Management
 - Illegal Connection and Illegal Discharge Detection Reporting
 - Street Sweeping
- The following cost items will be required for the implementation of Construction Site BMP strategies:
 - Supplemental Work Items
 - Water Pollution Maintenance Sharing
 - Additional Water Pollution Control
 - Bid Items
 - Job Site Management
 - Temporary Drainage Inlet Protection
 - Temporary Concrete Washout
 - Water Pollution Control Program
- Project specific BMP measures will be specified and quantified during the PS&E phases.
- Temporary construction site BMPs cost has been estimated at \$2,957,792 accordance with the guidelines of Appendix F, 2023 PPDG.
- Additional information will be provided during the PS&E phase.
- On October 13, 2023 Arthur Hedayati, District 7 Construction Stormwater Coordinator, concurred to the temporary construction site BMP strategy used (at PA/ED phase) for the scope of work for this project.

Required Attachments¹

- Vicinity Map
- Evaluation Documentation Form
- SWDR Summary Spreadsheets

¹ Additional attachments may be required as applicable or directed by the District/Regional Design Stormwater Coordinator. (e.g., BMP line item estimate, SW, DPP, and CS Checklists).



VICINITY MAP

LA 47 - VINCENT THOMAS BRIDGE
(BR #53-1471) EA 390200 (0722000334)

Evaluation Documentation Form

No.	Criteria	Yes ✓	No ✓	Supplemental Information for Evaluation
1.	Begin Project evaluation regarding requirement for implementation of Treatment BMPs	✓		Continue to 2.
2.	Is the scope of the Project to install Treatment BMPs (e.g., Alternative Compliance or TMDL requirement)?		✓	If Yes , go to 8. If No , continue to 3.
3.	Is there a direct or indirect discharge to surface waters?	✓		If Yes , continue to 4. If No , go to 9.
4.	As defined in the WQAR or ED, does the project: a. discharge to Areas of Special Biological Significance (ASBS), or b. discharge to a TMDL watershed where Caltrans is named stakeholder, or c. have other pollution control requirements for surface waters within the project limits (e.g. STGA)?		✓	If Yes to any , contact the District/Regional Design Stormwater Coordinator or District/Regional NPDES Coordinator to discuss the Department's obligations, go to 8 or 5. <u>SL</u> (Dist./Reg. Coordinator initials) If No to all, continue to 5.
5.	Are any existing Treatment BMPs partially or completely removed? (ATA Condition 1, Section 4.3.1)		✓	If Yes , go to 8 AND continue to 6. If No , continue to 6.
6.	Is this a Routine Maintenance Project?		✓	If Yes , go to 9. If No , continue to 7.
7.	Does the project result in an increase of <u>10,000 ft² or more</u> (or <u>5,000 ft²</u> for "non-highway facilities projects") of new impervious surface (NIS)?		✓	If Yes , go to 8. If No , go to 9.
8.	Project is required to implement Treatment BMPs.	Complete Checklist T-1, Part 1.		
9.	Project is not required to implement Treatment BMPs. <u>SL</u> (Dist./Reg. Design SW Coord. Initials) <u>MG</u> (Project Engineer Initials) <u>10/7/2024</u> (Date)	Document for Project Files by completing this form and attaching it to the SWDR.		

SWDR Summary Spreadsheet

[illegible]

ATTACHMENT H

Risk Register

EA-07-390200, EFIS ID: 0722000334							Milestones				Duration				Base Con Cap Est: \$507,274,349		PM: Rimma Tebedeva			
Route & Post Mile: LA 47 PM 0.420							PD	PA&ED	PS&E	RTL	CCA	Con Working Days: 352				Base Contingency: \$81,185,700		DM: Mario Gutierrez		
							(M010)	(M200)	(M380)	(M460)	(M600)	Plant Est Days: 0				Base Total Construction Capital Est: \$588,460,049		RM: May Fung		
							11/29/22	10/01/24	06/20/25	07/08/25	07/30/27	Total Con Days: 352								
Project Description: Vincent Thomas Bridge Deck Replacement (Bridge No. 53-1471)																				
Scope Summary: The project proposes to replace the existing 1965-year-built CIP lightweight concrete on the cable suspension span and east/west approach spans of the bridge. Items will also include replacing appurtenances such as barrier rails, seismic joints, chainlink fences, joint seals, and seismic instrumentation.																				
Risk Identification							Risk Impact Assessment								Response Strategy					
							Contingency (@70th Percentile):			17%		Risk Impact on Working Days* (@70th Percentile):								1257
Risk No.	Status	Type	Category	Risk Title	Risk Statement	Risk Details with Current Status/Assumptions	Probability of Occurrence	Low (\$)	Most Likely (\$)	High (\$)	Cost Impact	Low	Most Likely	High	Time Impact	Rationale	Strategy	Response Actions	Risk Owner	Updated
7	Active	Threat	DGN	Quality, Constructability & Safety Review	As a result of challenging project site (i.e., steep hillside, over open water), or missing crucial project information (Plans, Specs, Quantities, or Construction Details) uncovered during construction, additional items that were unintentionally overlooked or omitted during project design may be added, which would lead to contract change orders, potential claims, and schedule delays during construction.	The proposed work involves working within limited working space and unusual field condition that is high above over the Los Angeles Harbor. Further, since the project is above the ocean channel, maritime guidelines, or quality requirement, and other mitigations may be triggered. More detailed information will be available in the PS&E phase.	25%	\$5,000,000	\$7,000,000	\$10,000,000	\$1,791,667	30	40	50	10	By following the Quality Management System (QMS) process, the cost and schedule impacts on the project can be minimized.	Mitigate	Monitor design progress to conform to the QMS process and ensure complete submittals are provided for review. In addition, the CMGC process (which allows the Contractor to access the project site before bidding) will help to develop necessary mitigation in the PS&E phase.	Project Engineer	August 29, 2024
8	Active	Threat	ROW	Agreements	As a result of work that impacts local agencies and utilities, agreements addressing additional project requirements and constraints may be needed, which would lead to increased project costs and duration.	Various agreements will be developed in the subsequent phase. The project team will need to verify if the deck replacement impacts any utilities since the utility may be attached to the girders below. The track owner is the Port of Los Angeles, with UPRR and others as tenants. Agreements may be required with the City of Los Angeles, Long Beach and Carson to construct the proposed project.	50%	\$2,000,000	\$3,000,000	\$4,000,000	\$1,500,000	21	28	35	14	Coordination of the Department's effort, along with cooperation from utility companies, is necessary to start relocation promptly.	Mitigate	Identify all utilities and local agencies impacted, contact companies and stakeholders, and monitor progress.	Project Manager, Design and Utility Engineers	August 29, 2024
9	Active	Threat	CON	Labor Productivity	As a result of work progress or production rate is not as anticipated, additional costs may be incurred, which would lead to increased project costs and schedule delays.	If the proposed work is not progressing as initially carried in the Estimate, additional labor costs may be incurred to improve productivity and maintain the schedule.	50%	\$1,500,000	\$2,500,000	\$5,000,000	\$1,375,000	38	63	125	35	Depending on the types of work, adding extra work crew to help may be feasible.	Transfer	If necessary, CMGC will evaluate opportunities to accelerate the work progress using overtime or add an additional labor force to improve the production rate.	CMGC	August 29, 2024
10	Active	Threat	STR	Unanticipated Painting of Steel Members	As a result of bracing installation, unanticipated painting work may be required, which would lead to increased project costs and schedule delays.	Bracing will be required to be installed on both the Approaches and Suspension Spans. If the existing stringers are retained on the Suspension Span while the deck is being replaced, there is a possibility that substantial re-painting of the stringers and other steel members (that have not been included in the cost nor the schedule of the project) may be needed after the bridge deck replacement.	50%	\$500,000	\$2,500,000	\$5,000,000	\$1,291,667	15	63	125	33	Some re-painting may be required on other bridge components due to incidental damage caused by construction activities.	Mitigate	Protective measures will be developed in the PS&E phase to protect the existing bridge components in place and minimize incidental damage.	Project Engineer	August 29, 2024
11	Active	Threat	DGN	FHWA and CTC Approvals	As a result of securing proper approvals from external agencies, additional delays and concessions may occur, which would lead to increased project costs and schedule delays.	The Early Works Packages have been scheduled with the anticipated approval of CTC and FHWA. If the approvals could not be obtained in anticipated time-frame, both the project's schedule and cost will be impacted.	50%	\$100,000	\$2,500,000	\$5,000,000	\$1,250,333	15	63	125	33	Consensus and approval from external agencies will usually take some time.	Transfer	Coordinate with the agencies as early as possible in the PS&E phase and allow adequate time for the approval process and plan for uncertainty.	Project Engineer and Project Manager	August 29, 2024
12	Active	Threat	STR	Relocation of Safe Span Access Platform System	As a result of the proposed structural work, unanticipated work that was not part of the project design may be triggered during construction, which would lead to increased project costs and schedule delays.	Due to the installation of the bracing on the Suspension Span, the suspender hangers of the Safe span access platform system may need to be temporarily relocated, which could potentially impact the project schedule and costs.	50%	\$100,000	\$2,500,000	\$5,000,000	\$1,250,333	15	63	125	33	Some bridge members (hangers, platform) may need to be relocated temporary to perform other work.	Transfer	CMGC will evaluate various construction operations during the design phase in detail and plan the work accordingly.	CMGC	August 29, 2024
13	Active	Threat	STR	Unanticipated Bridge Behavior	As a result of unanticipated design changes or construction procedure changes needed to maintain the structural integrity of the existing structure, additional retrofit work may be required, which would lead to increased project costs and schedule delays.	Changes in design or construction procedures due to unanticipated bridge behavior and maintaining stability, could result in longer schedule and higher project costs. Additional work may lead to inefficient construction sequence, and longer construction durations.	25%	\$3,000,000	\$5,000,000	\$7,000,000	\$1,250,000	75	125	175	31	How the proposed bridge deck replacement activities will affect the structural integrity of the bridge during construction is unknown at this time.	Accept	CMGC will evaluate the condition during construction and develop the appropriate optimizations to address the situation accordingly.	Caltrans/CMGC	August 29, 2024
14	Active	Threat	STR	Tightening of Cable Bands and Bolt Replacement	As a result of the bridge deck replacement, unplanned work/additional work such as cable bands tightening and bolts replacement may be triggered which would lead to increase project costs and extended project duration.	The current phases assumes 100% of bolts will be tightened and 10% bolts and cable bands will be replaced. The bolts and cable bands have not been checked and tightened since their initial installation. Industry recommended to test and tighten the cable bands every 25 yrs. Unknown amount of cable band disengagement could occur. If bolts are not easily to remove and/or tighten, additional work to jack out the bolts may be necessary. Testing is on-going and bolt tensile testing are being performed currently at random locations.	50%	\$	\$2,500,000	\$5,000,000	\$1,250,000	0	63	125	31	Bolt replacement and cable tightening, if necessary, will be done during the Pre-construction phase.	Mitigate	Perform field investigation and evaluate the test results during the design phase to produce a more reliable estimate.	Project Engineer	August 29, 2024
15	Active	Threat	STR	Stringer Replacement	As a result of changes made to the project scope during its development, additional work may be required, which would lead to increased project costs and duration.	The current scope of work does not propose to replace the existing stringers. The current estimate does not include stringer replacement or repairs. However, if the existing condition of the stringers is worse than expected, there is a possibility that additional repairs or replacement may increase the initial estimates.	50%	\$	\$2,500,000	\$5,000,000	\$1,250,000	0	63	125	31	Some existing stringer members may need to be replaced.	Mitigate	Perform field investigation during the design phase to produce a more reliable estimate.	Project Engineer	August 29, 2024

*Risk impact on construction schedule is estimated using Monte Carlo simulation without consideration of overlapping concurrent activities.

EA-07-390200, EFIS ID: 0722000334										Milestones			Duration		Base Con Cap Est: \$507,274,349		PM: Rimm Tadejona
Route & Port MILE: LA 47 PM 0.420										PD	PAEED	PSLE	CCA	Con Working Days: 352	Base Contingency: \$81,195,700		DM: Mario Guerez
Project Description: Vincent Thomas Bridge Deck Replacement (Bridge No. 634171)										(M016)	(M200)	(M380)	(M460)	Plant Est Days: 0	Base Total Construction Capital Est: \$588,460,049		PM: May Jung
										11/29/22	10/01/24	06/20/25	07/29/27	Total Con Days: 352			

Scope Summary: The project proposes to replace the existing 1951-year-built C/P I/glyweight concrete on the cable suspension span and east/west approach spans of the bridge. Items will also include replacing appurtenances such as barrier rail, seismic joints, chainlink fences, joint seals, and seismic instrumentation.

Risk Identification						Risk Impact Assessment				Response Strategy										
Risk No.	Status	Type	Category	Risk Title	Risk Statement	Risk Details with Current Status/Assumptions	Probability of Occurrence	Contingency (@70th Percentile):			Risk Impact on Working Days* (@70th Percentile):			Time Impact	Rationale	Strategy	Response Actions	Risk Owner	Updated	
								Low (\$)	Most Likely (\$)	High (\$)	Cost Impact	Low	Most Likely							High
16	Active	Threat	CON	Design Delays (Structure)	As a result of the time needed to secure the concurrence of stakeholders, get design approvals and permits, and complete the design work, the project may experience delays in the design phase, which may impact the project schedule.	Present panel has been selected as the preferred alternative for bridge deck replacement work. The Panel of Los Angeles recently reviewed a \$20 Million project and will work on the project early start date. The design is in progress.	30%	\$3,000,000	\$4,000,000	\$5,000,000	\$1,200,000	21	43	65	13	As more information becomes available, this risk diminishes.	Mitigate	Perform field investigation and design analysis during the following phases to minimize this risk.	Project Manager & Project Engineer	August 25, 2024
17	Active	Threat	STR	Temporary Shoring Instability	If the Wind Tunnel Analysis results require additional significant steel work to strengthen the bridge components, the project may experience delays in the construction phase, which may impact the project schedule.	The wind tunnel analysis will be performed in the subsequent phase. Depending on the wind tunnel analysis results, additional work or strengthening work may be needed, such as redesigning protective shielding which may affect construction access of the project.	10%	\$5,000,000	\$10,000,000	\$20,000,000	\$1,003,333	30	50	100	6	Wind tunnel analysis results are currently unknown. Potential test results may only allow a limited length or height of shielding.	Mitigate	The project engineer will evaluate the test results and develop a stabilized procedure to address the condition accordingly.	Project Engineer	August 25, 2024
18	Active	Threat	STR	Wind Tunnel Analysis Results	If the Wind Tunnel Analysis results require additional significant steel work to strengthen the bridge components, the project may experience delays in the construction phase, which may impact the project schedule.	The wind tunnel analysis will be performed in the subsequent phase. Depending on the wind tunnel analysis results, additional work or strengthening work may be needed, such as wind fairings or the outside of the bridge, median barrier strengthening, and redesign of protective shielding.	20%	\$1,000,000	\$5,000,000	\$10,000,000	\$1,033,333	25	125	250	26	Wind tunnel analysis results are currently unknown. Potential test results may trigger additional strengthening work.	Mitigate	The project engineer will evaluate the test results and determine what other work is required during the design phase.	Project Manager & Project Engineer	August 25, 2024
19	Active	Threat	TIF	Interference with Other Projects	As a result of the construction of the project within the limits of the existing infrastructure, the project may experience delays in the construction phase, which may impact the project schedule.	There are locally-sponsored and Caltrans projects scheduled during the same time frame. The Port of Los Angeles recently reviewed a \$20 Million project and will work on the project early start date. The design is in progress.	15%	\$5,000,000	\$7,000,000	\$8,000,000	\$1,020,000	50	100	150	15	Coordination efforts with all necessary parties will help minimize the impacts of this risk. TIO may cost up to \$10,000/day.	Mitigate	Coordinate with permitting agencies to identify local and/or other Caltrans projects within the same project limit and adjust the construction schedule to avoid conflicts.	Construction Engineer, Project Engineer, Traffic Engineer (OTM)	August 25, 2024
20	Active	Threat	TIF	Temporary Traffic Closures (CMAA Activities)	If temporary traffic or bridge closures are not granted by the local or state agencies in a timely manner, Early Work may occur, which will lead to increased project costs and schedule delays.	Some EWP works activities will require bridge closure or full of the bridge. The project will be completed during the construction phase. The completion schedule will be impacted. Project duration may be extended and additional costs may be incurred.	25%	\$1,000,000	\$3,000,000	\$10,000,000	\$668,333	25	75	250	24	Early planning should mitigate the impact of this risk.	Mitigate	Coordinate with permitting agencies ahead of time to identify local and/or other Caltrans projects within the same project limit and adjust the construction schedule to avoid conflicts.	Caltrans/CMAA	August 25, 2024
21	Active	Threat	CON	Missing Items (Assets) Within the Project Limits	As a result of unexpected items (assets) within the project limits, a requirement to perform work on these items (assets) may occur, which will lead to increased project costs and schedule delays.	Unforeseen issues may arise that affect the components of the abutment, bridge transfers, and seismic seating systems that are attached to the deck and are required for the bridge to function properly. The project will be completed during the construction phase. The completion schedule will be impacted. Project duration may be extended and additional costs may be incurred.	10%	\$5,000,000	\$7,000,000	\$10,000,000	\$716,667	30	40	50	4	Identifying all items of work, improve the reliability of the cost estimate.	Mitigate	Work with all functional units to comprehensively identify work items. Include funds in the cost estimate to cover the additional expenses. During construction, technicians should be available to maintain and check transfer daily to ensure that they are prepared when necessary for work.	Project Manager	August 25, 2024
22	Active	Threat	STR	Construction Methods (Pre-Cast Panels) Caused Delays (Cost Overrun)	As a result of unexpected outcomes resulting from planned construction means or methods, delays during construction, which may impact the project schedule.	With the installation of the precast panels, (especially the inner deck) on the Suspension Span, cracking might occur due to the shrinkage and settlement of the concrete during the construction. The bridge transfers at the approach span are not operational at the moment and may be too small for construction work. The project will be completed during the construction phase. The completion schedule will be impacted. Project duration may be extended and additional costs may be incurred.	20%	\$2,500,000	\$3,500,000	\$5,000,000	\$716,667	63	88	125	18	Precast panel may crack due to unknown reasons (temperature, lifting, movement) during the construction phase. The project team should be aware of the impact of this risk.	Transfer	CMAA will work with Construction Engineer, EOR, & Precast Manufacturer to develop plans to mitigate potential of panel cracking.	Caltrans/CMAA	August 25, 2024

*Risk impact on construction schedule is estimated using Monte Carlo simulation without consideration of overdesign/contingency activities.


EA - 07-390200
Vincent Thomas Bridge Deck Replacement (Bridge No. 53-1471)

Construction Capital Cost \$ 588,460,049

Base Construction Capital Cost (w/o Contingency) \$ 507,274,349


Base No. of Working Days 352

Confidence Level	Construction Capital Risk-Based Estimate (\$)	Contingency %	Contingency (\$)
1%	\$ 523,835,820	3.3%	\$ 16,561,471
5%	\$ 532,122,366	4.9%	\$ 24,848,017
10%	\$ 538,708,579	6.2%	\$ 31,434,230
15%	\$ 543,397,479	7.1%	\$ 36,123,130
20%	\$ 546,858,254	7.8%	\$ 39,583,905
25%	\$ 550,353,295	8.5%	\$ 43,078,946
30%	\$ 553,667,957	9.1%	\$ 46,393,608
35%	\$ 556,625,958	9.7%	\$ 49,351,609
40%	\$ 560,581,196	10.5%	\$ 53,306,847
45%	\$ 564,140,523	11.2%	\$ 56,866,174
50%	\$ 567,789,486	11.9%	\$ 60,515,137
55%	\$ 572,371,950	12.8%	\$ 65,097,601
60%	\$ 577,957,720	13.9%	\$ 70,683,371
65%	\$ 584,806,740	15.3%	\$ 77,532,391
70%	\$ 591,969,705	16.7%	\$ 84,695,356
75%	\$ 602,986,586	18.9%	\$ 95,712,237
80%	\$ 636,390,201	25.5%	\$ 129,115,852
85%	\$ 694,619,583	36.9%	\$ 187,345,234
90%	\$ 732,012,089	44.3%	\$ 224,737,740
95%	\$ 776,377,671	53.0%	\$ 269,103,322
99%	\$ 841,519,765	65.9%	\$ 334,245,416



Construction Capital Risk Based estimate is based on the project cost estimate as well as the PDT's input on the risk register.

Confidence Level	Construction Working Days Risk-Based Estimate	% Change in Working Days	Working Days Delay
1%	755	114.5%	403
5%	912	159.0%	560
10%	1,036	194.5%	684
15%	1,110	215.3%	758
20%	1,174	233.4%	822
25%	1,223	247.4%	871
30%	1,269	260.5%	917
35%	1,309	272.0%	957
40%	1,347	282.5%	995
45%	1,393	295.9%	1,041
50%	1,435	307.6%	1,083
55%	1,483	321.3%	1,137
60%	1,522	332.5%	1,174
65%	1,562	343.7%	1,210
70%	1,609	357.0%	1,257
75%	1,659	371.4%	1,307
80%	1,722	389.3%	1,370
85%	1,800	411.3%	1,444
90%	1,896	438.7%	1,544
95%	2,021	474.2%	1,669
99%	2,219	530.3%	1,867





*Risk impact on construction schedule is estimated using Monte Carlo simulation without consideration of overlapping/concurrent activities.

EA - 07-390200
Vincent Thomas Bridge Deck Replacement (Bridge No. 53-1471)

Construction Capital Cost \$ 588,460,049

Base Construction Capital Cost (w/o Contingency) \$ 507,274,349
Base No. of Working Days 352



ATTACHMENT I

SHOPP - Performance Measures

District: 07

Tool ID: 23488

Project ID: 0722000334

Co-Rte-PM: LA-047-R0-42.0 (Primary Location)

View/Print PIR (Performance) Report

Multi-Objective Worksheet

Bridge

B

Pavement

Drainage

Facilities

Signs and Lighting

EA:

39020

Mobility

Roadside Infrastructure

Greenhouse Gases

Major Damage & Incidents

Advance Mitigation

Relinquishment

Performance & Accomplishments (IPC)

ActID	Activity Detail	Performance Objective	Unit of Measurement	Quantity	Pre-Good	Pre-Fair	Pre-Poor	New	Post-Good	Post-Fair	Post-Poor	HQ Program Review - (All Districts?)	HQ Comment	Review Date	Performance Change Date After Review	Comment
1 A03	Bridge Rail (201.112)	Bridge Rail Replacement and Upgrade	Linear Feet	18306.000	18306.000				18306.000							
2 A04	Bridge Rehabilitation (201.110, 111, 113, 322)	Bridge and Tunnel Health	Square Feet	352044.000		352044.000	352044.000									Artificially, E55 is at approach and 11 joint seals at suspension spans. Remove 4 finger joints and replace with seismic joints.
3 A08	Number of Bridges	No Performance Objective in the SHSMP	Each	1.000												
4 E01	Median Barrier (201.010, 015)	No Performance Objective in the SHSMP	Linear Feet	9153.000		9153.000	9153.000		9153.000							
5 E23	Collisions Reduced (201.015)	Collision Severity Reduction	Fatal/Serious Injury Collisions	9.000			9.000	9.000								Based upon the new methodology-S/14/23
6 E55	Proactive Safety Vehicles	Annual Fatal & Serious Injury Collisions	Annual Fatal & Serious Injury Collisions	0.530			0.530	0.530								Based upon the new methodology-S/14/23
7 H32	Is any Location Within the Project Limits Ped/Bike Accessible?	Proactive Safety	Yes/No	No												
8 H55	Justification for Bicycle and Pedestrian Infrastructure Not Applicable/Bike/Ped Prohib	No Performance Objective in the SHSMP	1,2,3													

(Last Saved - 02/28/24 @ 4:04 PM by Mara Chaudhatri)

Programming Performance Summary (All Locations)

Program Code	Activity Category	Asset Class	Asset	Performance Value	Performance Measure	Unit	Pre-Good	Pre-Fair	Pre-Poor	Pre-Total	Post-Good	New	Post-Fair	Post-Poor	Post-Total
201.116	Bridge - Formula Program	Primary	Bridge	1.0	Bridges(s)	Square Feet	0.0	0.0	352.044.0	352.044.0	352.044.0	0.0	0.0	0.0	352.044.0

Bridge/Tunnel Number	Pre-Health	Post-Health	Area
53 471	Poor	Good	352044

Notes:

- The crosswalk for reporting performance in the "Programming Performance Summary" was developed to assist the districts on performance reporting requirements for CTC and PCRs. For discrepancies or errors, please notify AM Tool admins via e-mail at CT-TAM@dot.ca.gov.
- The data summarized in the table represents the performance reported or to be reported in CTIPS.
- Programming only requires the breakdown of Good, Fair and Poor for Primary and Supplementary Asset Classes.
- Reporting of bridge pre and post conditions may contain errors if the project RTL is before 2024/25.
- Reporting drainage pre-total and post good may differ whenever projects contain abandoned/removed culverts as the culvert no longer exists at post construction. It is deleted from the pre-total value for posting of the post good value, and gets deleted from the statewide CIP inventory database.
- Reactive Safety projects will temporarily use the same performance outputs of Safety Improvement projects. When the reporting requirements for CTC changes, the logic in the AM Tool will change.
- During the transition to the new Proactive Safety objective, the performance output for projects with a primary activity category of Proactive Safety (under program codes 015, 112, or 235) will continue to be presented here in the units of measure corresponding to the activities historically reported to date. A change in units to "Annual Fatal and Serious Injury Collisions" for future programming requests is being planned.

ATTACHMENT J

Transportation Management Plan Data Sheet

TRANSPORTATION MANAGEMENT PLAN DATA SHEET

(Preliminary TMP Elements and Costs)

County/Route/PM LA-47; PM 0.4/2.0 EA 390200 Alternative No. See Project Notes
 E-FIS 0722000334 Project Phase: PAED
 Project Limit At Vincent Thomas Bridge
 Project Description Replace Entire Bridge Deck and Seismic Sensors

1) Public Information

- ☐ a. Brochures and Mailers _____
- ☒ b. Press Release _____
- ☒ c. Paid Advertising \$ 150,000
- ☐ d. Public Information Center/Kiosk _____
- ☒ e. Public Meeting/Speakers Bureau _____
- ☒ f. Telephone Hotline _____
- ☒ g. Internet _____
- ☐ h. Others: _____

Sub-Total (1) \$ 150,000

2) Motorists Information Strategies

- ☒ a. Changeable Message Signs (Fixed) See notes
- ☒ b. Changeable Message Signs (Portable) \$ 690,000
- ☐ c. Ground Mounted Signs _____
- ☐ d. Highway Advisory Radio _____
- ☒ e. Caltrans Highway Information Network (CHIN) _____
- ☐ f. Others: _____

Sub-Total (2) \$ 690,000

3) Incident Management

- ☒ a. Construction Zone Enhanced Enforcement Program (COZEEP) \$ 340,000
- ☒ b. Freeway Service Patrol (FSP) \$ 962,000
- ☒ c. Traffic Management Team (TMT) _____
- ☐ d. Helicopter Surveillance _____
- ☒ e. Traffic Surveillance Stations (Loop Detector and CCTV) See notes
- ☐ f. Others: _____

Sub-Total (3) \$ 1,302,000

4) Construction Strategies

- ☒ a. Lane Closure Charts
- ☐ b. Reversible Lanes
- ☒ c. Total Mainline Freeway Closure
- ☒ d. Extended Weekend Closure
- ☐ e. Contra Flow
- ☐ f. Truck Traffic Restrictions
- ☒ g. Reduced Speed Zone
- ☐ h. Connector and Ramp Closures
- ☒ i. Incentive and Disincentive
- ☐ j. Moveable Barrier
- ☐ k. Others: _____

See notes

See notes

Sub-Total (4) \$ -

5) Demand Management

- ☐ a. HOV Lanes/Ramps (New or Convert)
- ☐ b. Park and Ride Lots
- ☐ c. Rideshare Incentives
- ☐ d. Variable Work Hours
- ☐ e. Telecommute
- ☐ f. Ramp Metering (Temporary Installation)
- ☐ g. Ramp Metering (Modify Existing)
- ☐ h. Others: _____

Sub-Total (5) \$ -

6) Alternative Route Strategies

- ☐ a. Add Capacity to Freeway Connector/Ramps
- ☒ b. Street Improvement (widening, traffic signal, etc.)
- ☒ c. Traffic Control Officers
- ☐ d. Parking Restrictions
- ☐ e. Others: _____

See notes

\$ 340,000

Sub-Total (6) \$ 340,000

7) Other Strategies

- ☒ a. Application of New Technology
- ☐ b. Others: _____

See notes

Sub-Total (7) \$ -

TOTAL ESTIMATED COST OF TMP ELEMENTS: \$ 2,482,000

Project Notes:

General notes.

- * This TMP is updated for PAED phase based on Two-Stage Construction (Scenarios 4-5) Alternative of the Draft PR (as of 02/11/2024).
- ** Closure duration: 25 months.
- ** Strategy: Closure of half of the bridge and having 2 traffic lanes, one operating in each direction during daytime with full closure of the bridge during nighttime and weekends.
- * Construction shall notify Office of Media / Public Affairs a minimum of one month prior to the start of construction to initiate the Public Awareness Campaign (PAC). Similarly, Media Affairs shall be notified a minimum of one month prior to each change in the construction phase. Note that during the PS&E phase, there may be a need for Construction to notify Office of Media / Public Affairs sooner than 1 month to allow sufficient time to disseminate advanced notifications to the Port of Long Beach (PoLB), Port of Los Angeles (PoLA), local cities and other entities.
- * Any changes in the scope of the project (including traffic handling) will require a re-evaluation of the TMP cost and strategies.
- * The number of traffic lanes will be maintained throughout the construction duration, except as allowed in the lane requirement charts of the Maintaining Traffic Specifications.
- * The engineer should identify and coordinate with other projects (both Caltrans and local cities) that will be in construction at the same time with this project to avoid conflicts in planned lane closures.
- * Any strategies that involve long-term closures (than 55-hour extended weekend closures) will require inputs and concurrence from Office of Mobility Program.
- * Similarly, traffic circulation and safety along the local streets along detour/alternates routes will require inputs and concurrence from Office of Mobility Program and Traffic Safety.

Notes for Specific TMP Elements.

- (1) Public Information: was provided by Public Information Officer - Media Relations on 02/01/2024.
- (2a) CMS: Utilize existing CMS to provide notification to public traffic in advance of and during closures to encourage voluntary diversion from the construction zone and to notify the public of the closures.
- (2b) Propose PCMS to be utilized 24/7 during 25 months of closure.
- (3a) COZEEP was provided by Construction Traffic Advisor on 02/05/2024.
- (3b) Propose FSP to assist with disable vehicles during the weekdays when there are only 2 lanes open to traffic (one in each direction). Because the current FSP contract for Los Angeles area does not include Route 47, it is required that a Cooperative Agreement will be prepared between Caltrans and MTA, to be prepared by Office of PPM and Design during the PS&E phase. Office of DTM will assist with providing inputs.
- (3c) Deploy TMT as needed during closures to assist with traffic queueing monitor and record traffic delay. Note that the TMT is only additional to the Contractor's responsibility to provide "End of Queue Monitoring and Warning" as shown in SSP section 12-4.02C(10).
- (3e) Propose to install temporary Traffic Surveillance Stations during lane closure where the permanent ones are disabled due to work related to roadway excavation. Estimate cost will be calculated in the

PS&E phase by Office of ITS.

- (4a) Lane closure charts will include closures for mainline freeway and ramps leading to the construction zone as shown in the Maintaining Traffic Specifications during the PS&E phase.
- (4d) Extended Weekend Closure (EWC) of 55-hour is needed to provide more work space for construction. During PS&E phase, EWC strategies will be developed in details along with Motorist Information Plans showing detour/alternates routes for public traffic.
- (4g) See Maintaining Traffic Specifications section 12-4.02C(12) Construction Work Zone Speed Limit Reduction. The cost will be included in other section of the BEES and proposed by office of Design during the PS&E phase.
- (4i) Incentive/Disincentive should be considered for this project to encourage the Contractor to complete the project quicker, resulting in a shorter closure duration. This requires a Cooperative Agreement to be prepared by Office of Design during the PS&E phase. Note that the Incentive/Disincentive clause should be considered carefully to avoid unnecessary and costly reimbursement to the Contractor. It should only be considered after accurate number of working days for each construction staging have been calculated with acceptable production rates of the work items.
- (6b) Proposed Street Improvement which includes:
 - * Install new/temporary traffic signal.
 - * Local street improvement (pavement, striping, etc.)
 - * Roadway widening to accommodate big truck turning at intersections.Estimate cost for this item will be calculated during the PS&E phase by Office of Traffic Design, ITS, and Design. A Coop Agreement may be needed between Caltrans and local cities and the Ports to secure fundings.
- (6c) Proposed Traffic Control Officers (TCO) to manage traffic at intersections on local streets that are not under CHP jurisdictions. The TCO hourly rate is similar to that of CHP in COZEEP. A detailed calculation will be done during the PS&E phase. For PAED phase, it is estimated to be similar to COZEEP estimate, thus the dollar amount is the same as Item 3a.
- (7a) Better construction methods are encouraged utilizing the latest technology and available advanced equipment in order to shorten duration of construction, which in turn shorten closure duration and return the entire bridge surface for use by public traffic. The cost will be calculated during the PS&E phase.

TMP cost for BEES.

The TMP costs to be included in the BEES under State Furnished Materials and Expenses section are shown below in the same order as the TMP elements:


066063 - Traffic Management Plan - Public Information	\$ 150,000
066578 - Portable Changeable Message Signs	\$ 690,000
066062 - COZEEP Contract	\$ 340,000
066065 - Tow Truck Service Patrol	\$ 962,000
066074 - Traffic Control	\$ 340,000


Note:

- (a) The BEES code 066578 for Portable Changeable Message Sign was based on the TMP Guidelines. The Design Engineer may select to program another Item Code in BEES for this

PCMS estimate. The purpose is that funding for PCMS proposed in this TMP is included in the project cost estimates. If Design decides to include this amount in the Traffic Control or PMCS in another section of BEES, then a note needs be included in Notes to the RE records to indicate that the total amount includes PCMS-TMP cost.

(b) Item Traffic Control (066074) is used for Traffic Control Officer.

PREPARED BY  DATE 03/06/2024
Duke M. Huynh,
Transportation Engineer

APPROVAL RECOMMENDED BY  DATE 03/06/2024
Julio Valdez,
Acting Senior Transportation Engineer

APPROVED BY  DATE 03/07/2024
Kenneth Young,
District Traffic Manager,
Division of Traffic Operations

[REQUEST FOR DISTRICT DIRECTOR APPROVAL] Project Report for EA 07-39020

Final Audit Report

2024-10-25

Created:	2024-10-18
By:	Maxwell Verkuilen (s154383@dot.ca.gov)
Status:	Signed
Transaction ID:	CBJCHBCAABAAHICLy6j5wauGJnq7ZD5ES9Q_pEtmDwsG

"[REQUEST FOR DISTRICT DIRECTOR APPROVAL] Project Report for EA 07-39020" History

-  Document created by Maxwell Verkuilen (s154383@dot.ca.gov)
2024-10-18 - 8:56:01 PM GMT- IP address: 149.136.33.250
-  Document emailed to Monica Benavides (monica.benavides@dot.ca.gov) for approval
2024-10-18 - 9:04:48 PM GMT
-  Email viewed by Monica Benavides (monica.benavides@dot.ca.gov)
2024-10-18 - 9:08:23 PM GMT- IP address: 104.28.111.146
-  Document approved by Monica Benavides (monica.benavides@dot.ca.gov)
Approval Date: 2024-10-24 - 11:17:42 PM GMT - Time Source: server- IP address: 149.136.17.253
-  Document emailed to Gloria Roberts (gloria.roberts@dot.ca.gov) for signature
2024-10-24 - 11:17:52 PM GMT
-  Email viewed by Gloria Roberts (gloria.roberts@dot.ca.gov)
2024-10-25 - 1:59:59 AM GMT- IP address: 172.226.3.167
-  Document e-signed by Gloria Roberts (gloria.roberts@dot.ca.gov)
Signature Date: 2024-10-25 - 2:04:13 AM GMT - Time Source: server- IP address: 174.243.209.29
-  Agreement completed.
2024-10-25 - 2:04:13 AM GMT