CTC-0001 (REV. 03/2023)

1.

2.

2.1

3.3.1

3.2

4.

4.1

4.2

ROAD REPAIR AND ACCOUNTABILITY ACT OF 2017 PROJECT BASELINE AGREEMENT

SR-213 Roadway Preservation (07-34660)

Resolution: SHOPP-P-2425-02B

(to be completed by CTC)

FUNDING PROGRAM
D Active Transportation Program
D Local Partnership Program (Competitive)
D Solutions for Congested Corridors Program
O State Highway Operation and Protection Program
D Trade Corridor Enhancement Program
PARTIES AND DATE
This Project Baseline Agreement (Agreement) effective on October 16, 2025 (will be completed by CTC), is made by and between the California Transportation Commission (Commission), the California Department of Transportation (Caltrans), the Project Applicant, Caltrans and the Implementing Agency, Caltrans sometimes collectively referred to as the "Parties".
RECITAL
Whereas at its 3/22/2024 meeting the Commission approved the StateHighwayOperafonandProtectionProgram and included in this program of projects the SR-213 Roadway Preservation (07-34660), the parties are entering into this Project Baseline Agreement to document the project cost, schedule, scope and benefits, as detailed on the Project Programming Request Form attached hereto as <i>Exhibit A</i> , the Project Report attached hereto as <i>Exhibit B</i> , the Performance Metrics Form, if applicable, attached hereto as <i>Exhibit C</i> , as the baseline for project monitoring by the Commission.
The undersigned Project Applicant certifies that the funding sources cited are committed and expected to be available; the estimated costs represent full project funding; and the scope and description of benefits is the best estimate possible.
GENERAL PROVISIONS
The Project Applicant, Implementing Agency, and Caltrans agree to abide by the following provisions:
To meet the requirements of the Road Repair and Accountability Act of 2017 (Senate Bill [SB] 1, Chapter 5, Statutes of 2017) which provides the first significant, stable, and on-going increase in state transportation funding in more than two decades.
To adhere, as applicable, to the provisions of the Commission:
D Resolution , "Adoption of Program of Projects for the Active Transportation Program", dated
D Resolution , "Adoption of Program of Projects for the Local Partnership Program", dated
D Resolution , "Adoption of Program of Projects for the Solutions for Congested Corridors Program", dated
Ii] Resolution G-24-34, "Adoption of Program of Projects for the State Highway Operation and Protection Program", dated 312212024
D Resolution , "Adoption of Program of Projects for the Trade Corridor Enhancement Program", dated

Project Baseline Agreement Page I of3

4.3	All signatories agree to adhere to the Commission's Guidelines. Any conflict between the programs will be resolved at the discretion of the Commission.
4.4	All signatories agree to adhere to the Commission's SB 1 Accountability and Transparency Guidelines and policies, and program and project amendment processes.
4.5	Caltrans agrees to secure funds for any additional costs of the project.
4.6	Caltrans agrees to report to Caltrans on a quarterly basis; on the progress made toward the implementation of the project, including scope, cost, schedule, and anticipated benefits/performance metric outcomes.
4.7	Caltrans agrees to prepare program progress reports on a on a semi-annual basis and include information appropriate to assess the current state of the overall program and the current status of each project identified in the program report.
4.8	Caltrans agrees to submit a timely Completion Report and Final Delivery Report as specified in the Commission's SB 1 Accountability and Transparency Guidelines.
4.9	m Caltrans agrees to submit a timely Project Performance Analysis as specified in the Commission's SB 1 Accountability and Transparency Guidelines.
4.10	All signatories agree to maintain and make available to the Commission and/or its designated representative, all work related documents, including without limitation engineering, financial and other data, and methodologies and assumptions used in the determination of project benefits and performance metric outcomes during the course of the project, and retain those records for six years from the date of the final closeout of the project. Financial records will be maintained in accordance with Generally Accepted Accounting Principles.
4.11	The Inspector General of the Independent Office of Audits and Investigations has the right to audit the project records, including technical and financial data, of the Department of Transportation, the Project Applicant, the Implementing Agency, and any consultant or sub-consultants at any time during the course of the project and for six years from the date of the final closeout of the project, therefore all project records shall be maintained and made available at the time of request. Audits will be conducted in accordance with Generally Accepted Government Auditing Standards.
5.	SPECIFIC PROVISIONS AND CONDITIONS
5.1	Project Schedule and Cost See Project Programming Request Form, attached as Exhibit A.
5.2	Project Scope See Project Report or equivalent, attached as Exhibit B. At a minimum, the attachment shall include the cover page, evidence of approval, executive summary, and a link to or electronic copy of the full document.
5.3	Performance Metrics See Performance Metrics Form, if applicable, attached as Exhibit C.
5.4	Additional Provisions and Conditions (Please attach an additional page if additional space is needed.)
Att	achments:
	nibit A: Project Programming Request Form nibit B: Project Report

Project Baseline Agreement Page 2 of3

Exhibit C: Performance Metrics Form (if applicable)

SIGNATURE PAGE TO PROJECT BASELINE AGREEMENT

ProjectName IsR-213 Roadway Preservation (07-34660)

Resolution

SHOPP-P-2425-02B

(to be completed by CTC)

Carlos beerg ugi l, 202510:59:43 PDT)	08/11/2025
Nader Abdelmalek	Date
Project Manager	
Project Applicant	
David Yan	08/18/2025
V	Date
David Yan	Bute
Chief, Office of Program Management	
Implementing Agency	
DO ALL PONTO	
de d'hrbeite	09/04/2025
Gloria Roberts	Date
District Director	
California Department of Transportation	
Dina El-Taw anay (c ep 22, 2025 13:01:52 PDT)	09/22/2025
Dina EI-Tawansy	Date
Director	
California Department of Transportation	
Nal Har	
Paul Golaszewski for	10/31/2025
Tanisha Taylor	Date
Executive Director	
California Transportation Commission	

Project Baseline Agreement Page 3 of3

Date:

08/11/25 10:04:19 AM

BASELINE AGREEMENT

FUNDING (Allocated amounts are shaded)

Fiscal Year

22/23

22/23

22/23

25/26

25/26

25/26

Component

PA&ED

PS&E

RW Support

RW Capital

Total

Const Capital

Const Support

SHOPP

910

3,751

900

7,200

1,286

46,179

60,226

Baseline agreement information was extracted from Caltrans' project data systems. Project description, funding and performance measures are from CTIPS. Project delivery milestones are from PRSM. All information is current and accurate.

STATE OF CALIFORNIA • DEPARTMENT OF TRANSPORTATION

District		EA	Project ID			PPNO	PPNO				Project Manager		
07		34660	07	7180000	076	5371		A	ABDELI	MALE	K, NADEF	RH	
County		Route		egin stmile	End Postmile			Implem	enting /	Agency			
LA		213	(0.0	9.984	PA&ED)			Caltr	Caltrans		
						PS&E				Caltr	ans		
						Right of V	Vay			Caltr	ans		
						Construct	ion			Caltr	ans		
Project Nicknam	ie												
SR-213 Roadway	/ Presei	rvation & AD	A Ramps										
Location/Descrip	otion												
In and near the c upgrade guardrai		•										itate pavement, curb ramps and	
	l, install	complete s	treets eleme	ents, ind	cluding bike l							·	
upgrade guardrai signal to America Legislative Distr	l, install	complete s	treets eleme Act (ADA) s	ents, ind	cluding bike I		valk improv		sidewa		d upgrade	·	
upgrade guardrai signal to America Legislative Distr Assembly:	I, install ns with ricts	complete si Disabilities 64, 66,	treets eleme Act (ADA) s	ents, ind	cluding bike I	anes, crossv	valk improv	ements, new	sidewa		d upgrade	curb ramps and	
upgrade guardrai signal to America Legislative Distr Assembly:	I, install ns with ricts	complete si Disabilities 64, 66,	treets eleme Act (ADA) s	ents, indetandard	cluding bike I	anes, crossv	valk improv	ements, new	sidewa	lk, and	d upgrade	curb ramps and	
upgrade guardrai signal to America	I, install ns with ricts MEAS	complete si Disabilities 64, 66,	treets eleme Act (ADA) s	Senat	cluding bike I	26, 35	valk improv	Congression	sidewal	lk, and	d upgrade	33, 43, 44	
upgrade guardrai signal to America Legislative Distr Assembly: PERFORMANCE	I, install ns with ricts E MEAS	complete si Disabilities 64, 66,	treets eleme Act (ADA) s 70 Primary Ass	sents, indetandard	cluding bike I	26, 35	valk improv	Congression	onal:	al 9	d upgrade	curb ramps and 33, 43, 44 Units	
upgrade guardraisignal to America Legislative Distr Assembly: PERFORMANCE Existing Co	ns with	complete si Disabilities 64, 66,	Act (ADA) s 70 Primary Ass	sents, indetandard	ds. Good 0.0	26, 35 Fair 42.9	Poor 0.0	Congression	onal: Tot	al 9	d upgrade	curb ramps and 33, 43, 44 Units Lane-miles	
upgrade guardraisignal to America Legislative Distr Assembly: PERFORMANCE Existing Co Programmed Project Mileston	I, install ns with ricts E MEAS andition Condition	Complete si Disabilities de G4, 66, iures	Act (ADA) s 70 Primary Ass Pavement Pavement	Senat	ds. te: Good 0.0 42.9	26, 35 Fair 42.9	Poor 0.0	Congression	onal: Tot	al 9	d upgrade	curb ramps and 33, 43, 44 Units Lane-miles Lane-miles	
upgrade guardraisignal to America Legislative Distr Assembly: PERFORMANCE Existing Co	I, install ns with ricts E MEAS andition Condition e and Env	complete si Disabilities 64, 66, URES Pon	Act (ADA) s 70 Primary Ass Pavement Pavement	Senat	ds. te: Good 0.0 42.9	26, 35 Fair 42.9	Poor 0.0	Congression	onal: Tot	al 9	d upgrade	curb ramps and 33, 43, 44 Units Lane-miles Lane-miles	
upgrade guardraisignal to America Legislative Distr Assembly: PERFORMANCE Existing Co Programmed Project Mileston Project Approval	I, install ns with ricts MEAS andition Condition e and Envitification	complete si Disabilities 64, 66, GURES P on vironmental n Milestone	Act (ADA) s 70 Primary Ass Pavement Pavement	Senat	ds. te: Good 0.0 42.9	26, 35 Fair 42.9	Poor 0.0	Congression	onal: Tot	al 9	d upgrade	curb ramps and 33, 43, 44 Units ane-miles Planned	

https://qmrs.dot.ca.gov/qmrs/f?p=148:5:::::P5_DISTRICT,P5_EA,P5_BASELINEDATE:07,34660,08%2F11%2F2025 10%3A04:19 AM&cs=3kUM4XOc...

Total

910

3,751

900

7,200

1,286

46,179

60,226

Memorandum

To: Kelly Lamare Date: August 11, 2025

Deputy District Director

Program/Project Management File: 07-346601
District 7 07-LA-213

PID: 0718000076

From: NADER ABDELMALEK

Project Manager

District 7

Subject: SB1 BASELINE AGREEMENT CLARIFICATION MEMORANDUM

This memorandum is written to accompany the SB-1 Baseline Agreement for this Roadway Preservation & ADA Ramps project on State Route 213 Los Angeles County. The purpose of this memorandum is to update the Post Miles, project milestones, and Funding table in the Project Report (PR) and:

- The Post Miles are updated as shown in the PPR and PRSM as follows: 0.0/9.984
- The Performance Measures as shown in the PR as follows: 42.9 Lane Miles
- The project milestones are updated as shown in the PPR and PRSM as follows:

0	M200	Planned	09/27/2024 (PR)
		Actual	11/15/2024 (PPR/PRSM)
0	M410	Planned	05/06/2026 (PPR/PRSM) 03/02/2026 (PR)
0	M460	Planned	05/20/2026 (PPR/PRSM) 04/06/2026 (PR)
0	M500	Planned	01/09/2027 (PPR/PRSM) 12/07/2026 (PR)

Fund Source		Fiscal Year Estimate									
20.XX.201.121	Prior	23/24	24/25	25/26	26/27	27/28	Future	Programmed Total	Total At PA&ED		
Component				In th	ousands of	dollars (\$	1,000)				
PA&ED Support		\$1,620						\$1,620	\$1,620 \$910		
PS&E Support			\$2,420					\$2,420	\$3,751		
Right-of-Way Support			\$775					\$775	\$900		
Construction Support				\$4,828				\$4,828	\$7,200		
Right-of-Way				\$999				\$999	\$1,286		
Construction				\$26,441				\$26,441	\$45,879 \$46,179		
Total		\$1,620	\$3,195	\$32,268				\$37,083	\$60,636 \$60,226		

If you have any questions, please contact me at (213) 598-6/89.

Nader Abdelmalek


08/11/2024

Project Report

For Project Approval

	On Route	213	
	Between	West 25 th Street	
	And	Junction Route 405	
		nformation contained in this red find the data to be complete,	-
		Dan Mondrel	
		Dan Murdoch, Deputy Distric	ct Director, Right of Way
APPROVAL I	RECOMMENDED:	Nader Abdelmalek,	N.
		Gregory Jann	
		Greg Farr, Deputy Dis	strict Director, Design
PROJECT AP	PROVED:		
	Il Alphate		10/09/2024
	Gloria Rober	ts, District Director	Date

Vicinity Map



Route 213 Project Limits PM 0.0/10.0

This project report has been prepared under the direction of the following registered civil engineer. The registered civil engineer attests to the technical information contained herein and the engineering data upon which recommendations, conclusions, and decisions are based.

Kin Seng Wong
KIN SENG WONG, REGISTERED CIVIL ENGINEER

06/26/2024

DATE



Table of Contents

1.	INTRODUCTION	1
2.	RECOMMENDATION	1
3.	BACKGROUND	2
4.	PURPOSE AND NEED	3
	4C. Traffic	4
5.	ALTERNATIVES	5 6
6.	CONSIDERATIONS REQUIRING DISCUSSION	
	6A. Hazardous Waste	6 7
	6E. Right-of-Way Issuses	
	6F. Railroad Involvement	8
	6G. Environmental Compliance	
	6H. Air Quality Conformity	
	6J. Noise Abatement Decision Report	
	6K. Life-Cycle Cost Analysis	
	6L. Stormwater Compliance	
	6M. Utilities Information	
7.	6N. Geotechnical Information OTHER CONSIDERATIONS	
	7A. Corridor and System Coordination	
	7B. Transportaion Management Plan	
	7C. Climate Change Considerations	
	7E. Transit Facilities	
8.	FUNDING, PROGRAMMING AND ESTIMATE	10
9.	DELIVERY SCHEDULE	
10.	RISKS	12
11.	EXTERNAL AGENCY COORDINATION	
12.	PROJECT REVIEWS	
13.	PROJECT PERSONNEL	13
14.	ATTACHMENTS (Number or Pages)	

1. INTRODUCTION

Project Description:

This project report (PR) presents a roadway preservation project on State Route 213 in and near the cities of Los Angeles, Rancho Palos Verdes, Lomita, and Torrance, from West 25th Street to Route 405. This project was originally programmed in the 2022 State Highway Operation and Protection Program (SHOPP) under 20.XX.201.121 Roadway Preservation Program for delivery in the 2025/2026 fiscal year (FY). The project proposes to rehabilitate pavement (cold plane and overlay), upgrade guardrail, upgrade existing nonstandard ADA curb ramps facilities to Americans with Disabilities Act (ADA) standards, construct concrete bus pads at transit stops, construct retaining walls for the addition of sidewalk segments, relocate traffic signals, upgrade pedestrian push-buttons, replace vehicle loop detectors, reduce lane widths & medians to allow for the placement of Class II bike lanes, install bicycle loop detectors, upgrade existing drainage inlet grates with bicycle friendly grates, and install guide, warning and bicycle signs.

Project Limits	07-LA-213-PM 0.0/10.0					
Number of Alternatives	2					
	Current Cost Estimate:	Escalated Cost Estimate:				
Capital Outlay Support	\$12,093,000	\$13,471,000				
Capital Outlay Construction	\$38,381,000	\$45,879,000				
Capital Outlay Right-of-Way	\$949,000	\$1,286,000				
Funding Source	SHOPP (20.XX.201.12	21)				
Funding Year	2026					
Type of Facility	4 to 6 lane conventiona	l highway				
Number of Structures	None					
SHOPP Project Output	42.87 lane miles CAPN 64 ADA Curb Ramps,					
	complete list of perform					
	Attachment M.					
Environmental Determination	Categorical Exemption	/Categorical Exclusion				
or Document	(CE/CE)					
Legal Description	In Los Angeles County Angeles, between West					
Project Development Category	5					

2. RECOMMENDATION

It is recommended that the project be approved with the preferred alternative and that the project proceed to the PS&E phase.

3. BACKGROUND

State Route 213 (SR-213) is a conventional highway in the cities of Los Angeles, Rancho Palos Verdes, Lomita, and Torrance. SR-213 is a north and south route which connects SR-1 to I-405 and provides access to the South Bay area. The highway consists of two lanes in each direction from West 25th St. to Carson St. where it then widens to three lanes in the southbound direction, and then becomes 3 lanes in each direction from Carson St. to Junction Route 405. The existing lane widths throughout SR-213 range from 11 to 12 feet, the raised median widths measure between 4 to 17 feet, and the shoulder widths along the segments of Western Ave. vary from 0 to 7 feet.

Federal-aid funding provisions allow for projects to accomplish preventative maintenance activities of the pavement. This work provides cost effective treatments to an existing roadway system without increasing pavement structural capacity. Geometric enhancements are not included, and the work cannot degrade any existing safety devices, complete streets, and asset management. Additionally, State law and policies have amended the process for management and selection of State Highway Operation and Protection Program (SHOPP) projects for Caltrans.

The Project Initiation Report (PIR) was approved on June 27, 2018, and recommended to be programmed into the State Highway Operation and Protection Program (SHOPP) for delivery in the 2023/2024 fiscal year (FY). Due to other competing priorities, the project was not programmed in the 2024 FY. Subsequently, the 1st Supplemental PIR, approved in 2019, adjusted the project cost. Later, the project scope and support cost were updated in the 2nd Supplemental PIR and approved on June 22, 2021. The project was programmed into the 2022 SHOPP with the use of the 2nd Supplemental PIR for delivery in the 2025/2026 FY.

In the summer of 2022, the District received SHOPP Complete Street Reservation funds to implement Class II bike lanes on SR-213 from PM 0.0 to PM 8.0 under EA 30661. Due to roadway width limitations, Caltrans implemented a combination of Class II bike lanes and Class III bike lines and would defer the study for the replacement of Class III bike lanes with Class II lanes to the upcoming project EA 34660. In July of 2023, the District received funding from the Infrastructure Investment and Jobs Act (IIJA) to incorporate additional complete streets items. This project, EA 34660, proposes continuous Class II bike lanes in both directions of SR-213 from PM 0.0 to PM 10.0. On June 12, 2024, Caltrans held a community outreach meeting to present the project to the public and city personnel at the City of Los Angeles, Lomita, Torrance, and Rancho Palos Verdes.

4. PURPOSE AND NEED

Purpose:

The purpose of the project is to rehabilitate the existing pavement, improve public safety, and enhance mobility for all users of the facility.

Need:

There is a need to rehabilitate the existing deteriorating roadway, upgrade non-standard ADA curb ramps to meet current standards, and to implement Class II bike lanes to improve safety for all users and maintenance workers.

The 2021 Pavement Condition Detailed Report (Pave M) states the average International Ride Index is 179. This pavement condition meets the requirements for preventative maintenance. See Attachment J for the Pavement Condition Survey. ADA curb ramps, not already upgraded, will be brought to current ADA curb ramp standards. The existing bikeway along Western Ave. is intermittent and in need for continuity.

4A. Problem, Deficiencies, and Justification

In addition to the need for pavement rehabilitation, ADA curb ramps are required to meet current ADA curb ramp standards.

Pedestrian Facility

A total of 64 existing ADA curb ramps will be upgraded to current ADA standards. This includes replacing existing crosswalks with continental crosswalk markings using enhanced wet night high visibility paint. Additionally, a sidewalk segment (1,125 ft.) will be constructed to provide a continuous pedestrian path. See Attachment B and R.

Bicycle Facility

SR-213 currently has limited segments of dedicated bike lanes. Project 07-306614, currently in construction, will add Class II bike lanes from West 25th St. to Palos Verdes Dr. North. This project, EA 34660, proposes to complete the Class II bikeway along the route by filling-in the gaps from West 25th St. to Palos Verdes Dr. North and extending Class II bike lanes north of Palos Verdes Dr. North.

Median reduction along segments of SR-213 are proposed to allow for the integration of Class II bike lanes. The reconstruction of these medians includes replacing the existing cracked asphalt concrete surfacing within the median with minor concrete (stamped concrete) and/or concrete pavers in keeping with the corridor design.

4B. Regional and System Planning

Identify Systems

SR-213 is a north and south route and is classified as a "Principal Arterial" in an urbanized corridor {Federal Highway Administration (FHWA) bases functional classification on a roadway's primary purpose}. SR-213 provides access to the community of San Pedro and the cities of Los Angeles, Rolling Hills Estates, Lomita, Torrance, and Rancho Palos Verdes.

State Planning

The Transportation Concept Report (TCR) is the Department of Transportation's (Caltrans) long-range planning document that identifies the existing and future route conditions and needs for each route on the State Highway System and establishes a twenty-year planning concept. The proposed improvements do not impact any transportation planning concepts in the TCR for State Route 213 (District 7, December 2016). There are no capacity enhancement projects proposed for SR-213 in the TCR.

Local Planning

It is anticipated that the proposed improvements would have little impact on local planning and other development efforts.

Transit Operation Planning

The project proposes to construct several new bus pads. It is anticipated that the construction of these improvements would have some temporary impacts to bus transit operations during construction.

4C. Traffic

Current and Forecasted Traffic

The following traffic data was obtained from the Traffic Census Program and summarized below.

Table 4.1 - Traffic Data

Project Limits (PM)	PHV	AADT	AADT	TRUCK	%
 		(Year 2022)	(Year 2045)	AADT	TRUCKS
25 th Avenue – Avenida Aprenda 0.00 – 3.46	1800	29,000	37,500	496	1.71
Avenida Aprenda – Palos Verdes Dr. North 3.46 – 4.31	2,200	36,000	46,500	496	1.71
Palos Verdes Dr. North – PCH 4.31 – 5.09	1,300	21,500	28,000	496	1.71
PCH – Lomita Blvd. 5.09 – 5.67	1,200	20,000	26,000	596	2.98
Lomita Blvd. – Sepulveda Blvd. 5.67 – 7.00	1,650	27,000	35,000	596	2.98
Sepulveda Blvd – I-405 7.00 – 9.98	1,850	30,000	39,000	1,140	3.80

^{*}Linear Projection by 1.25% per year

Collision Analysis

The Caltrans Traffic System Network (TSN) provides available detailed collision data for all highways in the State of California. The Traffic Selective Accident Rate (TSAR) and Table B were provided by Caltrans District 7 on SR-213 between the project limits for the three-year period between October 1, 2020, and September 30, 2023. The Analysis of the TASAS Table B records a total of 54 collisions.

Table 4.2 - Collision Rates - TASAS Table B (October 1, 2020 - September 30, 2023)

Post	Numbe	er of Col	lisions	Total	Collision Rates (No. of Collisions/MVM)					
Mile	Fatal	Fatal	Total	Million		Actual			wide Ave	erage
		+		Vehicle	Fatal	Fatal	Total	Fatal	Fatal	Total
		Injury		Miles		+			+	
				(MVM)		Injury			Injury	
0.00-	1	36	54	267.34	0.004	0.13	0.20	0.013	0.45	0.96
8.90										

5. ALTERNATIVES

5A. Viable Alternatives

Alternative 1 - Programmable Project Alternative -

The scope of work for the programmable project alternative is as follows:

- Cold plane 0.20 feet of the existing asphalt concrete pavement and overlay with 0.20 feet of rubberized hot mix asphalt gap graded (RHMA-G).
- Dig-outs: Dig-out and replace failed pavement with hot mix asphalt type A (HMA-Type A).
- Upgrade 64 existing ADA curb ramps to the current American Disabilities Act standards. Ramps are located at various locations within project limits. See Attachment R.
- Add Class II Bike lanes to fill in the gaps in Ranchos Palos Verdes and continue from Palos Verdes Dr. North to Del Amo Blvd. (PM 4.31 to PM 9.05)
- Reconstruct/reduce various median islands to accommodate Class II Bike lanes (includes new pavement where needed).
- Upgrade existing 478 ft. Metal Beam Guardrail (MBGR) with Midwest Guardrail System (MGS) located between Bynner Dr. and S. Weymouth Ave. (PM 1.37 to PM 1.46)
- Construct 42 new concrete bus pads (JPCP-RSC).
- Modify Caltrans fiber optic cable systems impacted by installation of bus pads (7 bus pad locations). See Attachment T.
- Construct 2 retaining walls to accommodate new sidewalk: total combined retaining wall length is 533 ft. The retaining walls are located between Bynner Dr. and 0.2 miles south of S. Weymouth Ave.
- Construct 1,125 LF of sidewalk located between Bynner Dr. and 0.2 miles south of S. Weymouth Ave.

- Install 38 accessible pedestrian pushbuttons at various ADA curb ramp upgrade locations.
- Upgrade 11 existing drainage inlets with bicycle friendly grates.
- Replace all traffic loop detectors within limits of pavement rehabilitation.
- Install bicycle loop detectors at all signalized intersections.
- As required due to ADA curb ramp upgrades at intersections; replace 7 traffic signal poles and relocate 5 electrical boxes. See Attachment Q.
- Place bicycle, guide, and warning signs in both directions of travel.
- Upgrade crosswalks and pavement markings and replace traffic striping and pavement markers.
- Construct two BMPs.

5B. Rejected Alternatives

Alternative 2 - No Build Alternative

The no build alternative was rejected since it does not address the purpose and need of the project.

5C. Nonstandard Design Features

For the build alternative, there are 3 boldface nonstandard features associated with nonstandard shoulder width and 9 underlined nonstandard design features associated with nonstandard median width located along Route 213. Both nonstandard features will allow enough horizontal clearance to implement a 5' bicycle lane along Route 213. A Design Standard Decision Document (DSDD) was developed for this project.

6. CONSIDERATIONS REQUIRING DISCUSSION

6A. Hazardous Waste

The project requires roadway excavation for the reconstruction of medians, construction of new bus pads, retaining walls, sidewalks, ADA curb ramps and traffic signal poles. Included in the project is the installation of signpost, and Midwest guardrail which generally contributes to minimal soil disturbance.

An assessment of known or likely hazardous materials and contamination that may be encountered during the construction of this project is attached in Attachment D. A full evaluation of potentially hazardous waste or contamination issues will be addressed during the design phase of the project. See Attachment D for Hazardous Waste Assessment.

6B. Value Analysis

The VA Sprint process is a virtual workshop available to federally non-mandated projects under \$50 million in construction costs (and bridge projects under \$40

million). The Caltrans VA Sprint process was designed to leverage innovative solutions from previous VA studies using a condensed workshop format to maximize the opportunity for value while reducing the time and expense of conducting standard VA studies on smaller, less complex projects.

A Value Analysis Sprint was conducted since it is a project requirement for projects costing over \$25 million. As a result of the study, savings for the project were estimated at \$4.4 M. See attachment K for the Final Value Analysis Sprint Report.

6C. Complete Streets

The Infrastructure Investment and Jobs Act (IIJA) is a bill which provides new funding for various infrastructure projects including highway and pedestrian safety projects. This project was selected and approved for IIJA federal funding for the following Complete Street elements: Addition of Class II bike lanes, conflict zone green paint, enhanced visibility paint crosswalks, bicycle detection loops, and bicycle and pedestrian signage. The Project Change Request (PCR) documents the additional complete street scope and associated cost to this 2022 State Highway Operation and Protection Program (SHOPP) project. See Attachment O. The Complete Streets Decision Document was revalidated. See Attachment S.

6D. Resource Conservation

The project will not increase roadway capacity and therefore not increase Green House Gas Emissions (GHG). Where available, the following strategies are recommended:

- i. Material within a local radius of the project area and/or locally available building material be utilized to reduce GHG emissions.
- ii. Promote the use of low-carbon footprint materials such as warm mix asphalt, or concrete (fly ash, limestone).
- iii. Construction incentives to use clean energy; Tier 4 or greater equipment emissions standards as a goal.

6E. Right-of-Way Issues

While most work will be completed within the existing R/W, additional right of way is required for the construction of two retaining walls and an ADA curb ramp. Positive identification/potholing of utilities will be conducted in the next phase to determine the need for any utility relocations. The R/W Data Sheet was prepared on June 24, 2024. See Attachment E.

Temporary Construction Easements (TCE) will be necessary to construct the new retaining wall and sidewalk located along southbound Route 213 between Bynner Dr. and Weymouth Ave.

A highway easement is required for the proposed ADA curb ramp at the southeast corner of 228th St. and Western Ave. Additional Right of Way needs will be assessed early in the PS&E phase.

6F. Railroad Involvement

The following railroad facilities cross SR-213:

- 1) Burlington Northern Santa Fe (BNSF) crosses Western Ave. at PM 6.88. BNSF also crosses Sepulveda Blvd. which is located within 1.5 miles of the project limits. The proximity of this crossing will also require coordination with BNSF to prevent vehicular back-up near railroad crossings.
- 2) Union Pacific Railroad (UPRR) runs along Torrance Blvd. and crosses SR-213 at PM 8.45. Coordination with UPRR is anticipated beginning in the PS&E phase and through construction.

Caltrans will be working with the California Public Utilities Commission (CPUC), UPRR, and BNSF to assess improvements within these crossings.

6G. Environmental Compliance

The project is Categorically Exempt under Class 1(c) and Categorically Excluded under the National Environmental Policy Act (NEPA) 23 CFR 771.117 (c): activity (c)(26). A Categorical Exemption/Categorical Exclusion Determination Form was signed on April 10, 2024. See Attachment F.

6H. Air Quality Conformity

This project is not a Congestion Mitigation and Air Quality Program (CMAQ) recipient. Air quality conformity is not required.

6I. Title VI Considerations

Title VI of the Civil Rights Act of 1964 and related statutes requires that there is no discrimination in federally assisted program on the basis of race, color, national origin, age, sex, or disability (religion is a protected category under the Fair Housing Act of 1968). There have been no findings of adverse impacts within the project area on minority groups, the elderly, handicapped, or other special interest groups.

6J. Noise Abatement Decision Report

This project does not meet Type I criteria; therefore, a detailed noise impact study is not required. Type I projects are proposed Federal or Federal-aid highway projects for the construction of a highway on a new location, the physical alteration of an existing highway where there is substantial horizontal or vertical roadway realignment, addition of through and auxiliary lanes, and the addition or relocation of an interchange or

ramps.

6K. Life-Cycle Cost Analysis

Per Appendix 8 of the Life Cycle Cost Analysis Manual (LCCA), CAPM projects are exempt from the LCCA requirement.

6L. Stormwater Compliance

Two permanent treatment BMP will be included in this CAPM project. An Alternative Compliance Plan will be needed for this project if the BMP(s) are not feasible. See Attachment G for SWDR.

6M. Utilities Information

Scope of work involving excavation will require potholing to positively identify the location of utilities. The Right of Way Data sheet has accounted for the necessary potholes along with the proposed utility relocations. For detailed information See Attachment E.

6N. Geotechnical Information

The Office of Geotechnical Design is in the process of testing soil from borings for the proposed retaining walls. Further testing will also be conducted for the proposed traffic signal poles during PS&E phase. See Attachment N and Q.

7. OTHER CONSIDERATIONS AS APPROPRIATE

7A. Corridor and System Coordination

The following are projects in the vicinity of this project:

EA	Danta	Begin	End	Description	Current	Construction	
EA	Route	PM	PM	Description	Phase	Begin	End
32160	1	0	18.0	Cold plane and overlay AC pavement, & install curb ramps	3	12/5/2023	9/17/2027
34610	1	7	7.4	Structures Seismic Retrofit	1	1/30/25	9/28/28
39020	47	0.4	2.0	Vincent Thomas Bridge Deck Replacement	0	10/17/2025	7/30/2027
0W670	103	0	1.8	0.15 ft. HMA-A Cold plane and overlay and dig-outs	1	7/15/2024	12/05/2028
37540	405	13.6	29.5	Replace and line various culverts	0	11/6/2026	5/30/2028
35310	405	16.4	20.2	Construct transition lane	1	12/3/2025	3/10/2027

7B. Transportation and Management Plan

A Transportation Management Plan (TMP) was prepared for handling traffic during construction. The key elements of TMP are Press Release, Internet, Lane Closure and

COZEEP. See Attachment H for TMP Data Sheet dated 3/22/2024.

7C. Climate Change Considerations

Caltrans' Standard Specifications in Section 14-9 (2018) require reducing air quality impacts during construction activities. Section 14-9.02 specifically requires compliance by the contractor with all applicable laws and regulations related to air quality, including air pollution control district and air quality management district regulations and local ordinances.

7D. Stage Construction

The scope of work will be performed in stages. In general, work commences with concrete work prior to roadway resurfacing and paving. This would include construction of medians, bus pads, traffic signal poles, drainage, curb and gutters, sidewalks, and ADA curb ramps in the first phase. Temporary pedestrian access will be provided during the construction of ADA curb ramps. Construction of retaining walls may occur concurrently. Pavement repairs and, cold plane and overlay operations would be next, followed by the placement of loop detectors, pavement delineation, and pavement markers.

7E. Transit Facilities

An integral part of the SR-213 multi-modal system includes bus transit offered by the local agencies. The implementation of new bus pads at bus stops will enhance the services along this route. Furthermore, the opportunity to construct the missing bus pads along Rte. 213 at one time will minimize future interruptions to transit services. See Attachment B.

8. FUNDING, PROGRAMMING AND ESTIMATE

Funding

It has been determined that this project is eligible for Federal-aid funding.

Programming

The table below provides the current programmed information for the project cost component, and the current cost estimate by component. The current cost estimate for support is escalated to the middle of each component at a rate of 3.5% per year. The construction capital cost is escalated to the middle of construction at a rate of 4.89% for FY 24/25 and 3.80% for FY 25/26 and beyond. The Right of Way capital is escalated at 8% to 2028.

Fund Source	Fiscal Year Estimate							Current Estimate (Escalated)	
20.XX.201.121	Prior	23/24	24/25	25/26	26/27	27/28	Future	Programmed Total	Total At PA&ED
Component		In thousands of dollars (\$1,000)							
PA&ED Support		\$1,620						\$1,620	\$1,620
PS&E Support			\$2,420					\$2,420	\$3,751
Right-of-Way Support			\$775					\$775	\$900
Construction Support				\$4,828				\$4,828	\$7,200
Right-of-Way				\$999				\$999	\$1,286
Construction				\$26,441				\$26,441	\$45,879
Total		\$1,620	\$3,195	\$32,268				\$37,083	\$60,636

Estimate

The estimated capital cost for the project as of June 2024 is \$39.33 M, including R/W. The escalated capital cost is \$47.17 M. The total escalated project cost is \$60.64 M which exceeds the programmed amount by \$23.55 M. The project cost increase is largely due to the increase of bid item cost, quantities, and price index fluctuation from the PID approval date to the present. SHOPP variance will cover these capital and support cost increases. For the itemized cost comparison of the Project Initiation Report scope vs. the PA&ED scope, see Attachment P. For the Preliminary Project Cost Estimate, see Attachment C.

A Project Change Request (PCR) will be prepared for approval after the Project Report approval.

9. DELIVERY SCHEDULE

Project Milestones	Milestone Date (Month/Day/Year)	Milestone Designation (Target/Actual)	
PROGRAM PROJECT	M015	6/30/22	Actual
BEGIN ENVIRONMENTAL	M020	1/04/23	Actual
PA & ED	M200	9/27/24	Target
START PS&E	M210	8/01/24	Target
BEGIN STRUCTURE	M215	8/09/24	Target
60% PS&E	M313	7/21/25	Target
PRE-95% PS&E		9/02/25	Target
95% PS&E	M315	11/3/25	Target
PS&E TO DOE	M377	12/01/25	Target
DRAFT STRUCTURES PS&E	M378	9/02/25	Target
PROJECT PS&E	M380	2/02/26	Target
RIGHT OF WAY CERTIFICATION	M410	3/02/26	Target
READY TO LIST	M460	4/06/26	Target
FUND ALLOCATION	M470	7/06/26	Target
HEADQUARTERS ADVERTISE	M480	8/10/26	Target
AWARD	M495	11/09/26	Target
APPROVE CONTRACT	M500	12/07/26	Target
CONTRACT ACCEPTANCE	M600	7/09/29	Target
END PROJECT	M800	1/06/31	Target

10. RISKS

A Level 3 Risk Register was prepared and approved on June 19, 2024. A total of 39 risks included the following risk: 16 Design related, 5 Right of Way related, 2 Environmental related, 2 Traffic related, 2 Program/Project Management related, and 12 Construction related risk all identified as shown in Attachment L.

11. EXTERNAL AGENCY COORDINATION

Federal Highway Administration (FHWA)

This project is an Assigned Project in accordance with the current FHWA and State of California, Department of Transportation (Caltrans) Joint Stewardship and Oversight Agreement Federal Highway Administration (FHWA).

The project requires the following coordination:

Railroads

Railroad Agreement are anticipated for the at-grade crossing(s).

12. PROJECT REVIEWS

Scoping team field review Kin Seng Wong, Suzie Kearns, Kevin Nguyen Date 6/06/24

District SHOPP Program	Advisor	Md Musa	Date _	6/06/24
District ADA Program Ac	Wilfred Domingo	Date _	6/06/24	
Headquarters SHOPP Pro	gram Advisoı	Long K. Huynh	Date _	6/06/24
District Maintenance		Eric Chau	Date _	6/06/24
Headquarters Project Deli	very Coordin	ator Robert Navarro	Date _	6/06/24
Project Manager	Nader Al	odelmalek	Date _	6/06/24
District Safety Review		Kevin Ferrer	Date _	6/06/24
Constructability Review _		Kyle Kunitake	Date _	6/06/24
Transportation Planning _	Benjamin	Medina	Date _	6/06/24

13. PROJECT PERSONNEL


Joseph Reynoza	Design Manager	213-266-6121
Kin Seng Wong	Project Engineer	213-266-3705
Suzie Kearns	Project Engineer	213-266-3729
Nader Abdelmalek	Project Manager	213-598-6789
Md Musa	SHOPP Program Advisor	213-269-1252
Benjamin Medina	Sr. Transportation Planner, Office of Complete Streets	213-760-7740
Ryan Nai	AGPA, Project Management, Office of Risk Management	213-269-1433
Karl Price	Sr. Environmental Planner	213-266-3822
Anna Johnson	Environmental Scientist	213-310-2536
Wayne Lee	Sr. Right of Way Agent, Right of Way Project Coordination	213-264-9044
Stephanie Chew	Sr., R/W Engineering	213-266-3605
Shao-Chiang Liu	Sr. Transportation Engineer - Stormwater Compliance	213-269-1662
Fariborz Gahvari	Sr. Division of Engineering Services, Office of	213-200-4073
	Geotechnical Design South	
Kenneth Young	Sr. Transportation Engineer, Office of DTM-TMP (South)	213-639-5923
Julio C. Valdez	Transportation Engineer - TMP (South)	213-266-6238
Fatemeh Ansari	Sr. Transportation Electrical Engineer, Office of Traffic	213-266-6180
	Design	
Erick Morales	Transportation Electrical Engineer, Office of Traffic Design	213-269-1509
Candace Fung	Sr. Transportation Electrical Engineer, Office of ITS	213-266-3997
Benjamin Medina	Sr. Transportation Planner	213-760-7740
Joe A. Hernandez	Construction Traffic/Safety Coordinator	213-793-9065
Wayne Liu	Sr. Transportation Engineer Construction	562-860-5963
Syed Huq	Risk Manager	213-266-6630

14. ATTACHMENTS

- A. Vicinity map (1)
- B. Project Plans (38)
- C. Preliminary Project Cost Estimate (10)
- D. Hazardous Waste Assessment (7)
- E. Right of Way Data Sheet (8)
- F. Environmental Document (CE/CE) (7)
- G. Stormwater Data Report (32)
- H. Transportation Management Plan Data Sheet (5)
- I. Materials Engineering Recommendation (3)
- J. Pavement Condition Survey (1)
- K. Value Analysis Sprint Report (58)
- L. Risk Register (7)
- M. SHOPP Project Performance Output Worksheet (1)
- N. Geotechnical Services Subsurface Information (2)
- O. Project Change Request (12)
- P. PIR/PAED Cost Estimate Comparison (4)
- Q. Traffic Electrical Work (1)
- R. ADA Curb Ramp List (2)
- S. Complete Streets Decision Document (5)
- T. Fiber Optic Cable Systems Modification Table (1)


VICINITY MAP – Attachment A


Vicinity Map





Route 213 Project Limits PM 0.0/10.0


PROJECT PLANS– Attachment B



























LAST REVISION DATE PLOTTED => 10-JUN-2024
TIME PLOTTED => 12:23 00000000000 POST MILES TOTAL PROJECT 0.01/0.0 LAYOUT SCALE: 1" = 50' DATE REGISTERED CIVIL ENGINEER ROUTE 213 Dist COUNTY 07 LA PROJECT NUMBER & PHASE 1797 UNIT 1797 2 TANTA CRUZ ST OUR OUR 羅羅 RELATIVE BORDER SCALE IS IN INCHES NOTE: FOR ACCURATE RIGHT OF WAY DATA, CONTACT RIGHT OF WAY ENGINEERING AT THE DISTRICT OFFICE. 90 +S 1SI BORE LAST REVISED OF TRANSPORTED OF TRANSPORTION


THE CALLFORNIA - DEPRIMENT OF TRANSPORTED OF T CINE C-6 MATCH KINZENC MONC DATE REVISED CHECKED BA 10SEPH REYNOZA CALCULATED-REVISED BY КЕЛІИ ИСПЛЕИ FUNCTIONAL SUPERVISOR
















































































PRELIMINARY PROJECT COST ESTIMATE – Attachment C

PROJECT

PLANNING COST ESTIMATE©

EA: DS-34660 PAED:

PAED: District-County-Route: 07-LA-213

PM: 00.0 - 10.0

Type of Estimate : Project Report **Program Code :** 20.XX.201.121

EA: DS-34660

Project Limits: SR -213, PM 0.0/PM 10.0

Project Description: In Los Angeles County, in the City of Los Angeles, between W. 25th St. and I-405.

Scope: Pavement Capital Preventative Maintenance project

Alternative: Alternative # 1

SUMMARY OF PROJECT COST ESTIMATE

	Cı	ırrent Year Cost	Escalated Cost	
TOTAL ROADWAY COST	\$	38,380,700	\$	45,878,924
TOTAL STRUCTURES COST	\$	-	\$	-
SUBTOTAL CONSTRUCTION COST	\$	38,380,700	\$	45,878,924
TOTAL RIGHT OF WAY COST	\$	948,960	\$	1,285,717
TOTAL CAPITAL OUTLAY COSTS	\$	39,330,000	\$	47,165,000
PA/ED SUPPORT	\$	1,620,000	\$	1,620,000
PS&E SUPPORT	\$	3,659,000	\$	3,751,000
RIGHT OF WAY SUPPORT	\$	775,000	\$	900,000
CONSTRUCTION SUPPORT	\$	6,039,000	\$	7,200,000
TOTAL SUPPORT COST	\$	12,093,000	\$	13,471,000
TOTAL PROJECT COST	\$	51,423,000	\$	60,636,000

Programmed Amount

	Date of Estimate (Month/Year)	Month 3	/	<u>Year</u> 2024	
	Estimated Construction Start (Month/Year)	11	/	2026	
		Number of Working Days	=	600	
Estir	nated Mid-Point of Construction (Month/Year)	1	/	2028	
	Estimated Construction End (Month/Year)	1	/	2029	
	Numbe	er of Plant Establishment Days		0	
	Estimated Project Schedule				
	PID Approval	6/27/2018			
	PA/ED Approval	6/28/2024			
	PS&E	12/1/20256			
	RTL	3/30/2026			
	Begin Construction	12/7/2026			
Reviewed by District O.E. or Cost Estimate Certifier	Samy Ragy	5/17/2024		(213) 269-1218	
_	Office Engineer / Cost Estimate Certifier	Date		Phone	
Approved by Project Manager	Nader Abdelmalek	6/24/2024		(213) 598-6789	
_	Project Manager	Date		Phone	

I. ROADWAY ITEMS SUMMARY

	Section		Cost
1	Earthwork	\$	2,209,500
2	Pavement Structural Section	\$	15,040,000
3	Drainage	\$	27,500
4	Specialty Items	\$	1,357,400
5	Environmental	\$	302,900
6	Traffic Items	\$	7,019,100
7	Detours	\$	540,000
8	Minor Items	\$	397,500
9	Roadway Mobilization	\$	2,689,400
10	Supplemental Work	\$	989,000
11	State Furnished	\$	1,457,500
12	Time-Related Overhead	\$	1,344,700
13	Total Roadway Contingency	\$	5,006,200
	TOTAL ROADWAY ITEMS	\$	38,380,700
	TOTAL NOADWAT TILMO	"	00,000,700
mate Prepared By	:	6/18/2024	(213) 266-3705
	Kin Seng Wong, P.E.	Date	Phone
imate Reviewed By	:	6/20/2024	(213) 266-6121
	Joseph Reynoza, Senior T.E.	Date	Phone

By signing this estimate you are attesting that you have discussed your project with all functional units and have incorporated all their comments or have discussed with them why they will not be incorporated.

SECTION 1: EARTHWORK

Item code		Unit	Quantity		Unit Price (\$)		Cost
190101	Roadway Excavation	CY	3,380	Х	200.00	=	\$ 676,000
19010X	Roadway Excavation (Insert Type) ADL	CY	250	Х	250.00	=	\$ 62,500
19801X	Imported Borrow	CY/TON		Х		=	\$ =
194001	Ditch Excavation	CY		Х		=	\$ -
192037	Structure Excavation (Retaining Wall)	CY	3,660	Х	225.00	=	\$ 823,500
192053	Structure Excavation (Type Z-2)	CY	640	Х	450.00	=	\$ 288,000
193013	Structure Backfill (Retaining Wall)	CY	3,320	Х	100.00	=	\$ 332,000
193031	Pervious Backfill Material (Retaining Wall)	CY	50	Х	250.00	=	\$ 12,500
17010X	Clearing & Grubbing	LS/ACRE	1	Х	15,000.00	=	\$ 15,000
100100	Develop Water Supply	LS		Х		=	\$ -
19801X	Imported Borrow	CY/TON		Х		=	\$ =
21012X	Duff	ACRE/SQFT		Х		=	\$ -

TOTAL EARTHWORK SECTION ITEMS	\$	2,209,500
-------------------------------	----	-----------

SECTION 2: PAVEMENT STRUCTURAL SECTION

Item code		Unit	Quantity		Unit Price (\$)			Cost
401055	Jointed Plain Concrete Pavement (RSC)	CY	1,560	х	850.00	=	\$	1,326,000
400050	Continuously Reinforced Concrete Pavement	CY	.,	х		=	\$	-
390132	Hot Mix Asphalt (Type A)	TON		х		=	\$	_
280015	Lean Concrete Base Rapid Setting	CY	900	х	280.00	=	\$	252,000
	Class 2 Aggregate Base	TON/CY		х		=	\$,
260303	Class 3 Aggregate Base	CY	2.040	х	175.00	=	\$	357,000
	Base Bond Breaker	SQYD	5,490	x	3.00	=	\$	16,470
153103	Cold Plane Asphalt Concrete Pavement	SQYD	427,900	x	5.00	=	\$	2,139,500
414240	Isolation Joint Seal (Asphalt Rubber)	LF	,,,,,	x	0.00	=	\$	-,,
414241	Isolation Joint Seal (Silicone)	LF		х		=	\$	-
280010	Rapid Strength Concrete Base	CY		х		=	\$	_
	Drill and Bond (Dowel Bar)	EA		х		=	\$	_
390137	Rubberized Hot Mix Asphalt (Gap Graded)	TON		х		=	\$	-
	Asphalt Binder (Geosynthetic Pavement Interlayer)	TON		х		=	\$	_
290201	Asphalt Treated Permeable Base	CY		x		=	\$	_
	Asphaltic Emulsion (Fog Seal Coat)	TON		х		_	\$	_
397005	Tack Coat	TON	100	x	800.00	_	\$	80,000
377501	Slurry Seal	TON	100	Х	000.00	=	\$	-
374493	Polymer Asphaltic Emulsion (Seal Coat)	TON		X		_	\$	_
370001	Sand Cover (Seal)	TON		Х		=	\$	_
731530	Minor Concrete (Textured Paving)	CY		Х		=	\$	_
731502	,	CY		X		=	\$	_
731521	Minor Concrete (Sidewalk)	CY	60	X	1,500.00	=	\$	90.000
731504	Minor Concrete (Curb and Gutter)	CY	70	X	100.00	_	\$	7,000
	Remove Concrete (Curb and Gutter)	LF	500	X	30.00	=	\$	15,000
7310340	,	CY	900	X	1,000.00	_	\$	900,000
	Place Hot Mix Asphalt Dike (Insert Type)	LF	300	X	1,000.00	_	\$	500,000
398100	Remove Asphalt Concrete Dike	LF		X		_	\$	
420201	Grind Existing Concrete Pavement	SQYD		X		_	\$	_
398300	Remove Base and Surfacing	CY		X		=	\$	_
390095	Replace Asphalt Concrete Surfacing	CY	100	X	450.00	=	\$	45,000
	Remove Concrete Pavement	SOYD/CY	100	X	430.00	_	\$	43,000
394090	Place Hot Mix Asphalt (Miscellaneous Area)	SQYD		X		=	\$	-
398200	Cold Plane Asphalt Concrete Pavement	SQYD		X		_	\$	-
846046	6" Rumble Strip (Asphalt Concrete Pavement)	STA		X		_	\$	-
	6" Rumble Strip (Concrete Pavement)	STA				=	\$	-
846051	12" Rumble Strip (Asphalt Concrete Pavement)	STA		X X		=	\$ \$	-
	12" Rumble Strip (Aspirali Concrete Pavement)	STA		X			э \$	-
420102	,	SQYD				-	э \$	-
	Groove Existing Concrete Pavement	SQYD		X		=	\$ \$	-
394095	Roadside Paving (Miscellaneous Areas)	TON		X				-
	Minor Hot Mix Asphalt	TON		X		=	\$	-
	Hot Mix Asphalt (Type A)		57 OOO	X	150.00	=	\$	- 9 670 000
	Rubberized Hot Mix Asphalt (Gap Graded)	TON	57,800	X	150.00	=	\$	8,670,000
	ADA Curb Ramps	EA	64 630	X	13,000.00	=	\$	832,000
	Lean Concrete Base Some Item	CY Unit	620	X	500.00	=	\$ \$	310,000
^^^^	Sume item	UTIIL		Х		=	Þ	-

TOTAL PAVEMENT STRUCTURAL SECTION ITEMS	\$	15,040,000
---	----	------------

EA: DS-34660 PAED:

SECTION 3: DRAINAGE

Item code		Unit	Quantity		Unit Price (\$)		Cost
71013X	Remove Culvert	EA/LF		х		=	\$ -
710240	Modify Inlet	EA		х		=	\$ -
710370	Sand Backfill	CY		х		=	\$ -
71010X	Abandon Culvert	EA/LF		х		=	\$ -
710196	Adjust Inlet	LF		х		=	\$ -
710262	Cap Inlet	EA		х		=	\$ -
510501	Minor Concrete	CY		х		=	\$ -
510502	Minor Concrete (Minor Structure)	CY		х		=	\$ -
731627	Minor Concrete (Curb, Sidewalk, and Curb Ramp)	CY		х		=	\$ -
6101XX	XX" Alternative Pipe Culvert (Insert Type)	LF		х		=	\$ -
6411XX	XX" Plastic Pipe	LF		х		=	\$ -
65XXXX	XX" Reinforced Concrete Pipe (Insert Type)	LF		х		=	\$ -
6811XX	XX" Plastic Pipe (Edge Drain)	LF		х		=	\$ -
6901XX	XX" Corrugated Steel Pipe Downdrain (0.XXX" Thick)	LF		х		=	\$ -
7006XX	XX" Corrugated Steel Pipe Inlet (0.XXX" Thick)	LF		х		=	\$ -
7032XX	XX" Corrugated Steel Pipe Riser (0.XXX" Thick)	LF		х		=	\$ -
7050XX	XX" Steel Flared End Section	EA		х		=	\$ -
703233	Grated Line Drain	LF		х		=	\$ -
72XXXX	Rock Slope Protection (Type and Method)	CY/TON		х		=	\$ -
72901X	Rock Slope Protection Fabric (Insert Class)	SQYD		х		=	\$ -
721420	Concrete (Ditch Lining)	CY		х		=	\$ -
721430	Concrete (Channel Lining)	CY		х		=	\$ -
750001	Miscellaneous Iron and Steel	LB		х		=	\$ -
150820	Modify Inlet	EA	11	х	2,500.00	=	\$ 27,500
XXXXXX	Additional Drainage	LS		х		=	\$ =

TOTAL DRAINAGE ITEMS \$ 27,500

SECTION 4: SPECIALTY ITEMS

Item code		Unit	Quantity		Unit Price (\$)		Cost		
520103	Bar Reinforced Steel (Retaining Wall)	LB	33,020	х	3.00	=	\$ 99,060	PR	SM quantity input for Loo
5100XX	Structural Concrete	CY		х		=	\$ -	PR	SM quantity input for Loo
510060	Structural Concrete, Retaining Wall	CY		х		=	\$ -	PR	SM quantity input for Look
5201XX	Bar Reinforcing Steel	LB		х		=	\$ -	PR	SM quantity input for Look
080050	Progress Schedule (Critical Path Method)	LS		х		=	\$ -		
582001	Sound Wall (Masonry Block)	SQFT		х		=	\$ -		
510530	Minor Concrete (Wall)	CY	380	х	2,500.00	=	\$ 950,000		
60005X	Remove Sound Wall	LF/LS/SQFT		Х		=	\$ -		
190110	Lead Compliance Plan	LS	1	х	20,000.00	=	\$ 20,000		
141120	Treated Wood Waste	LB		Х		=	\$ -		
839750	Remove Barrier	LF		х		=	\$ -		
839752	Remove Guardrail	LF	478	х	20.00	=	\$ 9,560		
710167	Remove Flared End Section	EA		Х		=	\$ -		
8000XX	Chain Link Fence (Insert Type)	LF		Х		=	\$ -		
80XXXX	XX" Chain Link Gate (Type CL-X)	EA		х		=	\$ -		
832007	Midwest Guardrail System	LF	478	Х	75.00	=	\$ 35,850		
839301	Single Thrie Beam Barrier	LF		Х		=	\$ -		
839310	Double Thrie Beam Barrier	LF		Х		=	\$ -		
839521	Cable Railing	LF		х		=	\$ -		
839566	Terminal System (Type CAT)	EA		х		=	\$ -		
839584	Alternative In-line Terminal System	EA		х		=	\$ -		
839585	Alternative Flared Terminal System	EA		Х		=	\$ -		
4906XX	XX" Cast-In-Drilled-Hole Concrete Piling	LF		Х		=	\$ -		
8396XX	Crash Cushion (Insert Type)	EA		Х		=	\$ -		
8331XX	Concrete Barrier (Insert Type)	LF		Х		=	\$ -		
839701	Concrete Barrier (Type 60)	LF	144	Х	350.00	=	\$ 50,400		
839749	Concrete Barrier (Type 842 Mod)	LF	150	Х	550.00	=	\$ 82,500		
780460	Anti-Graffiti Coating	SQFT		х		=	\$ -		
780450	Rock Stain	SQFT		х		=	\$ -		
	Reinforced Concrete Crib Wall (Insert Type)	SQFT		х		=	\$ -		
83954X	Transition Railing (Insert Type)	EA		х		=	\$ -		
780440	Prepare and Stain Concrete	SQFT		х		=	\$ -		
839561	Rail Tensioning Assembly	EA		х		=	\$ -		
839581	End Anchor Assembly (Type SFT)	EA	4	х	2,500.00	=	\$ 10,000		
XXXX	Side Walk, Raised island and Curb repair	LS	1	х	100,000.00	=	\$ 100,000		

Effective immediately, districts must input estimated item quantities in blue text above in the PRSM database for the pay items listed in the Design Memo, dated April 9, 2018, when Project Report is approved (Milestone 200).

Page 4 7/9/2024

SECTION 5: ENVIRONMENTAL

	PONMENTAL MITIGATION								
Item code	RONMENTAL MITIGATION	Unit	Quantity		Unit Price (\$)			Cost	
itom couc	Biological Mitigation (on-site)	LS	quantity	х	O 1.100 (4)	=	\$	-	
80010X	Temporary Fence (Insert Type)	LF		Х		=	\$	_	
	Temporary Reinforced Silt Fence	LF		Х		=	\$	_	
	,				Subtotal E	≣nvi	ronm	ental Mitigation	\$ -
5B - LANI	DSCAPE AND IRRIGATION							<u> </u>	-
Item code		Unit	Quantity		Unit Price (\$)			Cost	
20XXXX	Permanent BMP #1	LS	1	х	73,440.00	_	\$	73,440	
20XXXX	Permanent BMP #2	LS	1	х	30,150.00	=	\$	30,150	
20XXXX	Highway Planting	LS		х		=	\$	· -	
20XXXX	Irrigation System	LS		х		-	\$	-	
204099	Plant Establishment Work	LS		х		=	\$	-	
20XXXX	Follow-up Landscape Project	LS		х		=	\$	-	
206405	Remove Irrigation Facility	LS		Х		=	\$	-	
204096	Maintain Existing Planted Areas	LS		Х		=	\$	-	
206400	Check and Test Existing Irrigation Facilities	LS		Х		=	\$	-	
	Imported Topsoil	CY/TON		Х		=	\$	-	
200114	Rock Blanket	SQFT/SQYD		Х		=	\$	-	
	Vegetation Control (Minor Concrete)	SQYD	300	Х	47.00	=	\$	14,100	
	XX" Conduit (Use for Irrigation x-overs)	LF		Х		=	\$	-	
20890X	Extend X" Conduit (Use for Extension of Irrigation	LF		Х		=	\$	-	
					Subtotal L	and	Iscap	e and Irrigation	\$ 117,690
	SION CONTROL	11	O		Unit Duine (A)			04	
Item code	B	Unit	Quantity	.,	Unit Price (\$)			Cost	
211111	Permanent Erosion Control Establishment Work	LS		X		=	\$	-	
210010	Move-In/Move-Out (Erosion Control)	EA	1 000	X X	5.00	=	\$	- -	
210350	Fiber Rolls	LF	1,000	X	3.00	=	\$	5,000	
210360	Compost Sock	LF		X		=	\$ \$	-	
	Rolled Erosion Control Product (Insert Type)	SQFT		X		_	\$ \$	-	
21025X 210300	Bonded Fiber Matrix Hydromulch	3QFT/ACRE SQFT		X		_	\$ \$	-	
210300	Straw	SQFT		X		=	э \$	-	
210420	Hydroseed	SQFT		х		=	\$	-	
210430	Compost	CY		Х		=	\$	_	
	Incorporate Materials	SQFT					Ψ		
					,				
5D - NPD						Sub	total i	Erosion Control	\$ 5,000
	ES					Sub	total i	Erosion Control	\$ 5,000
Item code		Unit	Quantity		Unit Price (\$)	Sub		Erosion Control Cost	\$ 5,000
Item code 130300	Prepare SWPPP	LS	Quantity	x		<u>Sub</u> =	\$		\$ 5,000
130300 130200	Prepare SWPPP Prepare WPCP	LS LS	1	x x	Unit Price (\$) 10,000.00		\$	Cost 10,000	\$ 5,000
130300 130200 130100	Prepare SWPPP Prepare WPCP Job Site Management	LS LS LS	1		Unit Price (\$) 10,000.00 10,000.00	=	\$ \$ \$	Cost 10,000 - 10,000	\$ 5,000
130300 130200 130100 130330	Prepare SWPPP Prepare WPCP Job Site Management Storm Water Annual Report	LS LS LS EA	1 1 2	x x x	Unit Price (\$) 10,000.00 10,000.00 3,000.00	= = =	\$ \$ \$	Cost 10,000 - 10,000 6,000	\$ 5,000
130300 130200 130100 130330 130310	Prepare SWPPP Prepare WPCP Job Site Management Storm Water Annual Report Rain Event Action Plan	LS LS LS EA	1 1 2 10	x x x x	Unit Price (\$) 10,000.00 10,000.00 3,000.00 1,000.00	= = = =	\$ \$ \$ \$	Cost 10,000 - 10,000 6,000 10,000	\$ 5,000
130300 130200 130100 130330 130310 130320	Prepare SWPPP Prepare WPCP Job Site Management Storm Water Annual Report Rain Event Action Plan Storm Water Sampling and Analysis Day	LS LS LS EA EA	1 1 2	x x x x	Unit Price (\$) 10,000.00 10,000.00 3,000.00	= = = = = =	\$ \$ \$ \$	Cost 10,000 - 10,000 6,000	\$ 5,000
130300 130200 130100 130330 130310 130320 130520	Prepare SWPPP Prepare WPCP Job Site Management Storm Water Annual Report Rain Event Action Plan Storm Water Sampling and Analysis Day Temporary Hydraulic Mulch	LS LS LS EA EA EA SQYD	1 1 2 10	x x x x x	Unit Price (\$) 10,000.00 10,000.00 3,000.00 1,000.00	= = = = =	\$ \$ \$ \$ \$	Cost 10,000 - 10,000 6,000 10,000	\$ 5,000
130300 130200 130100 130330 130310 130320 130520 130550	Prepare SWPPP Prepare WPCP Job Site Management Storm Water Annual Report Rain Event Action Plan Storm Water Sampling and Analysis Day Temporary Hydraulic Mulch Temporary Hydroseed	LS LS LS EA EA SQYD SQYD	1 1 2 10	x x x x x x	Unit Price (\$) 10,000.00 10,000.00 3,000.00 1,000.00	= = = = = =	\$ \$ \$ \$ \$ \$ \$ \$	Cost 10,000 - 10,000 6,000 10,000	\$ 5,000
130300 130200 130100 130330 130310 130320 130520 130550 130505	Prepare SWPPP Prepare WPCP Job Site Management Storm Water Annual Report Rain Event Action Plan Storm Water Sampling and Analysis Day Temporary Hydraulic Mulch Temporary Hydroseed Move-In/Move-Out (Temporary Erosion Control)	LS LS LS EA EA SQYD SQYD EA	1 1 2 10 1	x x x x x x x	Unit Price (\$) 10,000.00 10,000.00 3,000.00 1,000.00 3,200.00	= = = = = = =	\$ \$ \$ \$ \$ \$ \$ \$ \$ \$	Cost 10,000 - 10,000 6,000 10,000 3,200	\$ 5,000
130300 130200 130100 130330 130310 130320 130520 130550 130505	Prepare SWPPP Prepare WPCP Job Site Management Storm Water Annual Report Rain Event Action Plan Storm Water Sampling and Analysis Day Temporary Hydraulic Mulch Temporary Hydroseed Move-In/Move-Out (Temporary Erosion Control) Temporary Fiber Roll	LS LS EA EA SQYD SQYD EA LF	1 1 2 10 1	x x x x x x x x	Unit Price (\$) 10,000.00 10,000.00 3,000.00 1,000.00 3,200.00	= = = = = = = =	\$ \$ \$ \$ \$ \$ \$ \$ \$	Cost 10,000 - 10,000 6,000 10,000 3,200 5,000	\$ 5,000
130300 130200 130100 130330 130310 130320 130520 130550 130505 130640 130900	Prepare SWPPP Prepare WPCP Job Site Management Storm Water Annual Report Rain Event Action Plan Storm Water Sampling and Analysis Day Temporary Hydraulic Mulch Temporary Hydroseed Move-In/Move-Out (Temporary Erosion Control) Temporary Fiber Roll Temporary Concrete Washout	LS LS EA EA SQYD SQYD EA LF LS	1 1 2 10 1	x x x x x x x x x	Unit Price (\$) 10,000.00 10,000.00 3,000.00 1,000.00 3,200.00	= = = = = = = = = = = = = = = = = = = =	\$ \$ \$ \$ \$ \$ \$ \$ \$ \$	Cost 10,000 - 10,000 6,000 10,000 3,200	\$ 5,000
130300 130200 130100 130330 130310 130320 130520 130550 130505 130640 130900 130710	Prepare SWPPP Prepare WPCP Job Site Management Storm Water Annual Report Rain Event Action Plan Storm Water Sampling and Analysis Day Temporary Hydraulic Mulch Temporary Hydroseed Move-In/Move-Out (Temporary Erosion Control) Temporary Fiber Roll Temporary Concrete Washout Temporary Construction Entrance	LS LS EA EA SQYD SQYD EA LF LS EA	1 1 2 10 1	x x x x x x x x x	Unit Price (\$) 10,000.00 10,000.00 3,000.00 1,000.00 3,200.00	= = = = = = = = = = = = = = = = = = = =	\$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$	Cost 10,000 - 10,000 6,000 10,000 3,200 5,000	\$ 5,000
130300 130200 130100 130330 130310 130320 130520 130550 130505 130640 130900 130710 130610	Prepare SWPPP Prepare WPCP Job Site Management Storm Water Annual Report Rain Event Action Plan Storm Water Sampling and Analysis Day Temporary Hydraulic Mulch Temporary Hydroseed Move-In/Move-Out (Temporary Erosion Control) Temporary Fiber Roll Temporary Concrete Washout Temporary Construction Entrance Temporary Check Dam	LS LS LS EA EA SQYD SQYD EA LF LS EA LF	1 2 10 1 1,000	x x x x x x x x x x	Unit Price (\$) 10,000.00 10,000.00 3,000.00 1,000.00 3,200.00 5.00 35,000.00		\$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$	Cost 10,000 - 10,000 6,000 10,000 3,200 5,000 35,000	\$ 5,000
130300 130200 130100 130330 130310 130320 130520 130550 130505 130640 130900 130710 130610 130620	Prepare SWPPP Prepare WPCP Job Site Management Storm Water Annual Report Rain Event Action Plan Storm Water Sampling and Analysis Day Temporary Hydraulic Mulch Temporary Hydroseed Move-In/Move-Out (Temporary Erosion Control) Temporary Fiber Roll Temporary Concrete Washout Temporary Construction Entrance Temporary Check Dam Temporary Drainage Inlet Protection	LS LS LS EA EA SQYD SQYD EA LF LS EA LF EA	1 2 10 1 1,000 1	x x x x x x x x x x x	Unit Price (\$) 10,000.00 10,000.00 3,000.00 1,000.00 3,200.00 5.00 35,000.00		\$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$	Cost 10,000 - 10,000 6,000 10,000 3,200 5,000 35,000 - 30,000	\$ 5,000
130300 130200 130100 130330 130310 130320 130520 130550 130505 130640 130900 130710 130610 130620 130730	Prepare SWPPP Prepare WPCP Job Site Management Storm Water Annual Report Rain Event Action Plan Storm Water Sampling and Analysis Day Temporary Hydraulic Mulch Temporary Hydroseed Move-In/Move-Out (Temporary Erosion Control) Temporary Fiber Roll Temporary Concrete Washout Temporary Construction Entrance Temporary Drainage Inlet Protection Street Sweeping	LS LS LS EA EA SQYD SQYD EA LF LS EA LF EA LS	1 2 10 1 1,000 1	x x x x x x x x x x x x x x x x x x x	Unit Price (\$) 10,000.00 10,000.00 3,000.00 1,000.00 3,200.00 5.00 35,000.00		* * * * * * * * * * * * * * * * * * * *	Cost 10,000 - 10,000 6,000 10,000 3,200 5,000 35,000 - 30,000 50,000	\$ 5,000
130300 130200 130100 130330 130310 130320 130520 130550 130505 130640 130900 130710 130610 130620	Prepare SWPPP Prepare WPCP Job Site Management Storm Water Annual Report Rain Event Action Plan Storm Water Sampling and Analysis Day Temporary Hydraulic Mulch Temporary Hydroseed Move-In/Move-Out (Temporary Erosion Control) Temporary Fiber Roll Temporary Concrete Washout Temporary Construction Entrance Temporary Check Dam Temporary Drainage Inlet Protection	LS LS LS EA EA SQYD SQYD EA LF LS EA LF EA	1 2 10 1 1,000 1	x x x x x x x x x x x	Unit Price (\$) 10,000.00 10,000.00 3,000.00 1,000.00 3,200.00 5.00 35,000.00		\$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$	Cost 10,000 - 10,000 6,000 10,000 3,200 5,000 35,000 - 30,000	\$ 5,000
130300 130200 130100 130330 130310 130320 130520 130550 130505 130640 130900 130710 130610 130620 130730	Prepare SWPPP Prepare WPCP Job Site Management Storm Water Annual Report Rain Event Action Plan Storm Water Sampling and Analysis Day Temporary Hydraulic Mulch Temporary Hydroseed Move-In/Move-Out (Temporary Erosion Control) Temporary Fiber Roll Temporary Concrete Washout Temporary Construction Entrance Temporary Drainage Inlet Protection Street Sweeping	LS LS LS EA EA SQYD SQYD EA LF LS EA LF EA LS	1 2 10 1 1,000 1	x x x x x x x x x x x x x x x x x x x	Unit Price (\$) 10,000.00 10,000.00 3,000.00 1,000.00 3,200.00 5.00 35,000.00		\$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$	Cost 10,000 - 10,000 6,000 10,000 3,200 5,000 35,000 - 30,000 50,000	\$ 5,000
130300 130200 130100 130330 130310 130320 130520 130550 130505 130640 130900 130710 130610 130620 130730	Prepare SWPPP Prepare WPCP Job Site Management Storm Water Annual Report Rain Event Action Plan Storm Water Sampling and Analysis Day Temporary Hydraulic Mulch Temporary Hydroseed Move-In/Move-Out (Temporary Erosion Control) Temporary Fiber Roll Temporary Concrete Washout Temporary Construction Entrance Temporary Drainage Inlet Protection Street Sweeping	LS LS LS EA EA SQYD SQYD EA LF LS EA LF EA LS	1 2 10 1 1,000 1	x x x x x x x x x x x x x x x x x x x	Unit Price (\$) 10,000.00 10,000.00 3,000.00 1,000.00 3,200.00 5.00 35,000.00 300.00 50,000.00 7.00		\$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$	Cost 10,000 - 10,000 6,000 10,000 3,200 5,000 35,000 - 30,000 50,000 21,000	
130300 130200 130100 130330 130310 130320 130520 130550 130640 130900 130710 130610 130620 130730 130570	Prepare SWPPP Prepare WPCP Job Site Management Storm Water Annual Report Rain Event Action Plan Storm Water Sampling and Analysis Day Temporary Hydraulic Mulch Temporary Hydroseed Move-In/Move-Out (Temporary Erosion Control) Temporary Fiber Roll Temporary Concrete Washout Temporary Construction Entrance Temporary Drainage Inlet Protection Street Sweeping	LS LS LS EA EA SQYD SQYD EA LF LS EA LF EA LS	1 2 10 1 1,000 1	x x x x x x x x x x x x x x x x x x x	Unit Price (\$) 10,000.00 10,000.00 3,000.00 1,000.00 3,200.00 5.00 35,000.00 300.00 50,000.00 7.00		\$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$	Cost 10,000 - 10,000 6,000 10,000 3,200 - 5,000 35,000 - 30,000 50,000 21,000	\$ 180,200
130300 130200 130100 130330 130310 130320 130520 130550 130640 130900 130710 130610 130620 130730 130570	Prepare SWPPP Prepare WPCP Job Site Management Storm Water Annual Report Rain Event Action Plan Storm Water Sampling and Analysis Day Temporary Hydraulic Mulch Temporary Hydroseed Move-In/Move-Out (Temporary Erosion Control) Temporary Fiber Roll Temporary Concrete Washout Temporary Construction Entrance Temporary Drainage Inlet Protection Street Sweeping Temporary Cover	LS LS LS EA EA SQYD SQYD EA LF LS EA LF EA LS	1 2 10 1 1,000 1	x x x x x x x x x x x x x x x x x x x	Unit Price (\$) 10,000.00 10,000.00 3,000.00 1,000.00 3,200.00 5.00 35,000.00 300.00 50,000.00 7.00		\$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$	Cost 10,000 - 10,000 6,000 10,000 3,200 - 5,000 35,000 - 30,000 50,000 21,000	\$ 180,200
130300 130200 130100 130330 130310 130320 130520 130555 130640 130900 130710 130610 130620 130730 130570	Prepare SWPPP Prepare WPCP Job Site Management Storm Water Annual Report Rain Event Action Plan Storm Water Sampling and Analysis Day Temporary Hydraulic Mulch Temporary Hydroseed Move-In/Move-Out (Temporary Erosion Control) Temporary Fiber Roll Temporary Concrete Washout Temporary Construction Entrance Temporary Drainage Inlet Protection Street Sweeping Temporary Cover	LS LS LS EA EA EA SQYD SQYD EA LF LS EA LF EA LS SQYD	1 1 2 10 1 1,000 1 100 1 3,000	x x x x x x x x x x x x x x x x x x x	Unit Price (\$) 10,000.00 10,000.00 3,000.00 1,000.00 3,200.00 5.00 35,000.00 300.00 50,000.00 7.00	= = = = = = = = = = = = = = = = = = =	\$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$	Cost 10,000 - 10,000 6,000 10,000 3,200 - 5,000 35,000 - 30,000 50,000 21,000 btotal NPDES	\$ 180,200
130300 130200 130100 130330 130310 130320 130520 130550 130640 130900 130710 130620 130730 130570 Suppleme 066595 066596	Prepare SWPPP Prepare WPCP Job Site Management Storm Water Annual Report Rain Event Action Plan Storm Water Sampling and Analysis Day Temporary Hydraulic Mulch Temporary Hydroseed Move-In/Move-Out (Temporary Erosion Control) Temporary Fiber Roll Temporary Concrete Washout Temporary Construction Entrance Temporary Drainage Inlet Protection Street Sweeping Temporary Cover	LS LS LS EA EA EA SQYD SQYD EA LF LS EA LF EA LS SQYD	1 1 2 10 1 1,000 1 100 1 3,000	x x x x x x x x x x x x x x x x x x x	Unit Price (\$) 10,000.00 10,000.00 3,000.00 1,000.00 3,200.00 5.00 35,000.00 300.00 50,000.00 7.00	= = = = = = = = = = = = = = = = = = =	\$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$	Cost 10,000 - 10,000 6,000 10,000 3,200 - 5,000 35,000 - 30,000 50,000 21,000 btotal NPDES RONMENTAL	\$ 180,200
130300 130200 130100 130330 130310 130320 130550 130555 130640 130900 130710 130620 130730 130570 Suppleme 066595 066596 066597	Prepare SWPPP Prepare WPCP Job Site Management Storm Water Annual Report Rain Event Action Plan Storm Water Sampling and Analysis Day Temporary Hydraulic Mulch Temporary Hydroseed Move-In/Move-Out (Temporary Erosion Control) Temporary Fiber Roll Temporary Concrete Washout Temporary Construction Entrance Temporary Drainage Inlet Protection Street Sweeping Temporary Cover	LS LS LS EA EA EA SQYD SQYD EA LF LS EA LF EA LS SQYD	1 1 2 10 1 1,000 1 100 1 3,000	x x x x x x x x x x x x x x x x x x x	Unit Price (\$) 10,000.00 10,000.00 3,000.00 1,000.00 3,200.00 5.00 35,000.00 300.00 50,000.00 7.00 TOTA	= = = = = = = = = = = = = = = = = = =	\$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$	Cost 10,000 - 10,000 6,000 10,000 3,200 - 5,000 35,000 - 30,000 50,000 21,000 bitotal NPDES RONMENTAL 100,000 10,000 5,000	\$ 180,200 302,900
130300 130200 130100 130330 130310 130320 130550 130555 130640 130900 130710 130610 130620 130730 130570 Suppleme 066595 066596 066597 XXXXXX	Prepare SWPPP Prepare WPCP Job Site Management Storm Water Annual Report Rain Event Action Plan Storm Water Sampling and Analysis Day Temporary Hydraulic Mulch Temporary Hydroseed Move-In/Move-Out (Temporary Erosion Control) Temporary Fiber Roll Temporary Concrete Washout Temporary Construction Entrance Temporary Drainage Inlet Protection Street Sweeping Temporary Cover	LS LS LS EA EA EA SQYD SQYD EA LF LS EA LS LS LS LS LS LS	1 1 2 10 1 1,000 1 100 1 3,000	x x x x x x x x x x x x x x x x x x x	Unit Price (\$) 10,000.00 10,000.00 3,000.00 1,000.00 3,200.00 5.00 35,000.00 300.00 50,000.00 7.00 TOTA	= = = = = = = = = = = = = = = = = = =	\$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$	Cost 10,000 - 10,000 6,000 10,000 3,200 - 5,000 35,000 - 30,000 50,000 21,000 bitotal NPDES RONMENTAL 100,000 10,000 5,000	\$ 180,200

 $^{{}^*\!\}mathsf{Applies} \text{ to all SWPPPs and those WPCPs with sediment control or soil stabilization BMPs}.$

Page 5 7/9/2024

^{**}Applies to both SWPPPs and WPCP projects.

^{***} Applies only to project with SWPPPs.

SECTION 6: TRAFFIC ITEMS

6A - Traff	fic Electrical								
Item code		Unit	Quantity		Unit Price (\$)			Cost	
870200	0 0 3	LS		Х		=	\$	-	
870300	Sign Illumination System	LS		Χ		=	\$	-	
870400	Signal and Lighting System	LS		Х		-	\$	-	
870510	Ramp Metering System	LS		Х		=	\$	-	
	Interconnection Conduit and Cable	LF/LS		Х		=	\$	-	
	Furnish Sign Structure (Insert Type)	LB		Х		=	\$	-	
	Install Sign Structure (Insert Type)	LB		Х		=	\$	-	
	XX" CIDHC Pile (Sign Foundation)	LF EA/LC		Х		=	\$	-	
	Inductive Loop Detector	EA/LS LS		Х		=	\$	-	
870600	Traffic Monitoring Station System	EA/LS		X		=	\$	-	
56804X 568054	Remove Sign Structure Reconstruct Sign Structure	EA/LS		X		=	\$ \$	-	
568060	Modify Sign Structure	EA		X		=	\$	-	
	Traffic Census Station Systems	LS	1	X	225,000.00	=	\$	225,000	
870009	During Construction	LS	1	X	10,000.00	_	\$	10,000	
	Modifying Fiber Optic Cable System (Relocate f/o)	LS	1	X X	400,000.00	=	\$	400,000	
872133		LS	1	X	1,186,152.00	=	\$	1,186,152	
	Relocate Signal Structures/ Pull Boxes, and Loop Detectors	LS	1	X	740,000.00	=	\$	740,000	
	Modifying Wireless Magnetometer Vehicle Detection Systems	LS	1	Х	80,000.00	_	\$	80,000	
OTAXXX	Wilders was received vericle betection by stems	LO	'	^	00,000.00	_	Ψ	00,000	
					S	ubto	tal Ti	raffic Electrical	\$ 2,641,152
6B - Traff	fic Signing and Striping								
Item code		Unit	Quantity		Unit Price (\$)			Cost	
820840	Roadside Sign -(One Post & Two Post)	LS	1	Х	820,000.00	=	\$	820,000	
5602XX	Furnish Sign Structure (Insert Type)	SQFT		Х		=	\$	-	
820890	Install Sign Panel on Existing Frame	SQFT		X		=	\$	-	
846020	Remove Painted Traffic Stripe	LF		Х		=	\$	-	
141102	Remove Yellow Painted Traffic Stripe (Hazardous Waste)	LF	104,060	Х	2.00	=	\$	208,120	
846025	Remove Painted Pavement Marking	SQFT		Х		=	\$	-	
820250	Remove Roadside Sign	EA		Х		=	\$	-	
820530	Reset Roadside Sign	EA		Х		=	\$	-	
820610	Relocate Roadside Sign	EA		Х		=	\$		
820101	Delineator (Marker)	EA	970	Х	10.00	=	\$	9,700	
840501	Temporary Traffic Stripe	LF	200,000	Х	1.50	=	\$	300,000	
840502	Thermoplastic Traffic Stripe (Enhanced Wet Night Visibility) ттегтторгазис стозъматк ана Рачеттел главкиту (Еппансеи	LF	400,000	Х	3.00	=	\$	1,200,000	
846012	Mot Night Vicibility)	SQFT	4	X	100 000 00	=	\$	100.000	
120090 84XXXX	Construction Area Signs Permanent Pavement Delineation	LS LS	1	X X	100,000.00	=	\$ \$	100,000	
0177707	Termanent avenient beimeaten	23		^					
					Subtotal Tra	ffic S	Signir	ng and Striping	\$ 2,637,820
	fic Management Plan		0		Hale Del (#)			2	
12065V	Portable Changeable Message Sign	Unit	Quantity		Unit Price (\$)		ď	Cost	
12865X	Portable Changeable Message Sign	LS	1	Х	\$ 185,500	=	\$	185,500	
					Subtotal Ti	raffic	Mar	nagement Plan	\$ 185,500
6C - Stag	e Construction and Traffic Handling								
Item code		Unit	Quantity		Unit Price (\$)			Cost	
120198		EA		Х		=	\$	-	
12016X	31 .	EA	100	Х	50.00	=	\$	5,000	
120116	Type II Barricade	EA		Х		=	\$	-	
	Type III Barricade	EA		Х	600.55	=	\$	-	
129100	Temporary Crash Cushion Module	EA	42	Х	260.00	=	\$	10,920	
	Traffic Control System	LS	1	X	1,500,000.00	=	\$	1,500,000	
129110	Temporary Parrier System	EA	30	X	350.00	=	\$	10,500	
120320	Temporary Payament Marking (Paint)	LF	740 600	X	30.00	=	\$	22,200	
	Temporary Payement Marking (Paint)	SQFT	600	X	10.00	=	\$ \$	6,000	
	Temporary Pavement Marking (Tape) Delineator (Insert Class)	SQFT EA		X X		=	\$ \$	-	
GIUIAA	Delinicator (Illocit Oldos)	LA	Subt		Stage Constructi			raffic Handling	\$ 1,554,620
					Т.	ОТА	L TR	AFFIC ITEMS	\$ 7,019,100
			ļ		•				 .,,,,,,,

EA: DS-34660 PAED:

SECTION 7: DETOURS

Includes constructing, maintaining, and removal

Item code		Unit	Quantity	L	Init Price (\$)		Cost
190101	Roadway Excavation	CY		Х		=	\$ -
19801X	Imported Borrow	CY/TON		х		=	\$ -
390132	Hot Mix Asphalt (Type A)	TON		х		=	\$ -
26020X	Class 2 Aggregate Base	CY/TON		Х		=	\$ -
250401	Class 4 Aggregate Subbase	CY		Х		=	\$ -
130620	Temporary Drainage Inlet Protection	EA		Х		=	\$ -
129000	Temporary Railing (Type K)	LF	18,000	Х	30.00	=	\$ 540,000
128601	Temporary Signal System	LS		Х		=	\$ -
120149	Temporary Pavement Marking (Paint)	SQFT		Х		=	\$ -
80010X	Temporary Fence (Insert Type)	LF		Х		=	\$ -
XXXXXX	Some Item	LS		Х		=	\$ -

TOTAL DETOURS \$ 540,000

SUBTOTAL SECTIONS 1 through 7 \$ 26,496,400

SECTION 8: MINOR ITEMS

8A - Americans with Disabilities Act Items

ADA Items 0.0% \$
8B - Bike Path Items
Bike Path Items 0.0% \$

8C - Other Minor Items

TOTAL MINOR ITEMS \$ 397,500

SECTIONS 9: ROADWAY MOBILIZATION

Item code

999990 Total Section 1-8 \$ 26,893,900 x 10% = \$ 2,689,390

TOTAL ROADWAY MOBILIZATION \$ 2,689,400

SECTION 10: SUPPLEMENTAL WORK

Item code		Unit	Quantity		Unit Price (\$)		Cost
066670	Payment Adjustments For Price Index Fluctuations	LS	1	х	350,000.00	=	\$ 350,000
066094	Value Analysis	LS	1	Х	10,000.00	=	\$ 10,000
066070	Maintain Traffic	LS	1	Х	150,000.00	=	\$ 150,000
066919	Dispute Resolution Board	LS	1	Х	25,000.00	=	\$ 25,000
066921	Dispute Resolution Advisor	LS	1	Х	10,000.00	=	\$ 10,000
066015	Federal Trainee Program	LS	8	Х	5,000.00	=	\$ 40,000
066610	Partnering	LS	1	Х	20,000.00	=	\$ 20,000
066204	Remove Rock and Debris	LS		Х		=	\$ -
066222	Locate Existing Crossover	LS		Х		=	\$ -
XXXXXX	Some Item	Unit		х		=	\$ -

Cost of NPDES Supplemental Work specified in Section 5D = \$ 115,000

Total Section 1-8 \$ 26,893,900 1% = \$ 268,939

TOTAL SUPPLEMENTAL WORK \$ 989,000

SECTION 11: STATE FURNISHED MATERIALS AND EXPENSES

Item code		Unit	Quantity		Unit Price (\$)		Cost
66020	Railroad Work (Flagging)	LS	1	Х	300,000.00	=	\$300,000
66020	Railroad Work (Pedestrian Gates)	LS	1	Х	500,000.00	=	\$500,000
066105	Resident Engineers Office	LS	1	Х	150,000.00	=	\$150,000
066063	Traffic Management Plan - Public Information	LS	1	Х	150,000.00	=	\$150,000
066901	Water Expenses	LS		Х		=	\$0
8609XX	Traffic Monitoring Station (X)	LS		Х		=	\$0
066841	Traffic Controller Assembly	LS		Х		=	\$0
066840	Traffic Signal Controller Assembly	LS		Х		=	\$0
066062	COZEEP Contract	LS	1	Х	85,000.00	=	\$85,000
066838	Reflective Numbers and Edge Sealer	LS		Х		=	\$0
066065	Tow Truck Service Patrol	LS		Х		=	\$0
066916	Annual Construction General Permit Fee	LS	1	Х	3,500.00	=	\$3,500
XXXXXX	Some Item	Unit		Х		=	\$0
	Total Section 1-8		\$ 26,893,900		1%	=	\$ 268,939

TOTAL STATE FURNISHED \$1,457,500

SECTION 12: TIME-RELATED OVERHEAD

Total of Roadway and Structures Contract Items excluding Mobilization

\$26,893,900 (used to calculate total TRO)

Estimated Time-Related Overhead (TRO) Percentage (0% to 10%) =

Item code	Unit	Quantity		Unit Price (\$)		Cost
090100 Time-Related Overhead	WD	600	Х	\$2,241	=	\$1,344,700

TOTAL TIME-RELATED OVERHEAD \$1,344,700

SECTION 13: ROADWAY CONTINGENCY*

Risk Amount from Risk Register		(for Known Risks)		13%		\$2,000,000	
Additional or Residual Contingency	(for Unknow	wn/Undefined Risks)		2%		\$667,490	
Total Section 1-12	\$	33,374,500	х	15%	=	\$5,006,175	

TOTAL CONTINGENCY* \$5,006,200

II. STRUCTURE ITEMS

	Bridge 1	Bridge 2	
DATE OF ESTIMATE Bridge Name Bridge Number Structure Type Width (Feet) [out to out] Total Bridge Length (Feet) Total Area (Square Feet) Structure Depth (Feet) Footing Type (pile or spread) Cost Per Square Foot	00/00/00 xxxxxxxxxxxxxxxxxxxxxxxxxxxxx	00/00/00 xxxxxxxxxxxxxxxxxxxxxxxxxxxxx	00/00/00 xxxxxxxxxxxxxxxxxxxxxxxxxxxxx
COST OF EACH	\$0	\$0	\$0
DATE OF ESTIMATE Building Name Bridge Number Structure Type Width (Feet) [out to out] Total Building Length (Feet) Total Area (Square Feet) Structure Depth (Feet) Footing Type (pile or spread) Cost Per Square Foot	Building 1 00/00/00 xxxxxxxxxxxxxxxxxxxxxxxxxxx	00/00/00 xxxxxxxxxxxxxxxxx 57-XXX xxxxxxxxxxxxxxxx 0 LF 0 LF 0 SQFT 0 LF xxxxxxxxxxxxxxxxxxxxxxxxxxxxxxxxxxx	00/00/00 xxxxxxxxxxxxxxxxxxxxxxxxxxxxx
COST OF EACH	\$0	\$0	\$0
1			
		TOTAL COST OF	BRIDGES \$0
		TOTAL COST OF E	BUILDINGS \$0
		Time-Related Overhead	10% \$0
		STRUCTURES MOBILIZATION	10% \$0
		STRUCTURES CONTINGENCY*	25% \$0
	٦	TOTAL COST OF STRUCTURES	\$0
Estimate Prepared By: XXXXXXXXX	XXXXXXXX Division of Structure		\$0

Page 9 7/9/2024

EA: DS-34660 PAED:

III. RIGHT OF WAY

Fill in all of the available information from the Right of Way Data Sheet.

			3	C	Current Value Future Use		Escalated Value
A)	A1)	Acquisition, including	Excess Land, Fees,	\$	r utare eee	\$	ruide
	A2)	Damages, Goodwill SB-1210		\$	235,250	\$	255,479
B)	B1)	Utility Relocation (Stat	e Share)	\$		\$	
	B2)	Potholing (Design Pha		\$	696,500	\$	1,011,800
C)		vance Engineering Esti r with State Only Fund		\$	0	\$	0
D)	RAP and/o	or Last Resort Housing		\$	0	\$	0
E)	Clearance	& Demolition		\$	0	\$	0
F)	Relocation	n Assistance (RAP and/	or Last Resort Housing Cost	s) \$	0	\$	0
G)	Title and E Reimburse	Escrow ed Appraisal Fee		\$ \$	8,210 9,000	\$ \$	9,438 9,000
H)	Environme	ental Review		\$	0	\$	0
I)	Condemna	ation Settlements	0%	\$	0	\$	0
J)	Design Ap	preciation Factor	0%	\$	0	\$	0
K)	Utility Relo	ocation (Construction C	ost)	\$	0	\$	0
L)			TOTAL RIGH	T OF WAY E	STIMATE		\$948,960
M)			TOTAL R/W	ESTIMATE:	Escalated		\$1,285,717
N)			RIGHT	OF WAY SUP	PORT		\$44,721
	Cost Estimate pared By	Project C	oordinator ¹		Phone		_
Utility Esti	mate Prepared						_
	Ву	Utility Co	ordinator ²		Phone		
	isition Estimate pared By		y Estimator ³		Phone		_

Note: Items G & H applied to items A + B

Page 10 7/9/2024

¹ When estimate has Support Costs only

² When estimate has Utility Relocation ³ When R/W Acquisition is required

HAZARDOUS WASTE ASSESSMENT – Attachment D

Memorandum

Making Conservation a California Way of Life.

March 25, 2024

Joseph Reynoza, STE To:

Office of Design A Division of Design

Kin Seng Wong, PE Attn: File:

Project Engineer

07-LA-213

Date:

PM 0.0/10.0 Western Ave

CAPM/ADA Curb Ramps Project in Los **Angeles County**

1846-0718000076-0

PN: 07-333-346600 EA:

DEPARTMENT OF TRANSPORTATION From:

OEE-HAZARDOUS WASTE BRANCH, SOUTH REGIONS

DIVISION OF ENVIRONMENTAL PLANNING

Subject: PROJECT REPORT (PR) PRELIMINARY HAZARDOUS WASTE ASSESSMENT

The Office of Environmental Engineering (OEE) is in receipt of your memorandum, dated October 31 2023 and update February 16, 2024 requesting a Preliminary Hazardous Waste Assessment for the above-mentioned CAPM/ADA Curb Ramps Project (refer to herein as the "Project") along Western Avenue (State Route SR-213) in Los Angeles County. OEE also received an update draft right of way plan from your office on March 21, 2024 as reference.

The Project proposes to cold plane and overlay of Asphalt Concrete pavement for pavement rehabilitation on SR-213. In addition to construct/reconstruct 64 curb ramps to meet the current Americans with Disabilities Act (ADA) standards. The purpose of the Project is to accomplish preventative maintenance activities of the payement, and to improve continuity to pedestrian accessibility along the State facilities on Western Avenue (SR-213) within the said Project limits for pedestrians with disabilities.

Based on the submittals/emails received on 10/31/23, 2/16/24, and 03/21/2024, the specific scope of work for this Project consists of the following:

- Cold plane 0.20' of existing AC pavement and overlay with AC pavement.
- Dig-out failed segments of roadway and replace with pavement structure.
- Reconstruct existing 64 curb ramps to comply with the current ADA standards.
- Upgrade 478' of MBGR with MGS. Replace 144' of MBGR with Concrete Barrier.
- Place 42 Concrete Bus Pads.
- Place 11 bicycle friendly drainage grates to replace existing non-grid type.
- Incorporate addition of Class II/Class II Buffered Bike lanes, include median width reductions.
- **Enhanced Visibility Paint Crosswalks**

EA: 07-346600 (PN: 1846-0718000076-0) PAED Preliminary Hazardous Waste Assessment March 25, 2024 Page 2 of 4

- Conflict zone green paint approaching intersections.
- Bicycle and Pedestrian Signage.
- Installation of pedestrian push buttons (APS).
- Upgrade 7 traffic signal poles and 5 pull boxes located at six intersections.
- Install new loops and bicycle loops.
- Install sidewalk segment (PM 1.256 to PM 1.47) from Bynner Dr to Weymouth Place.
- Remove existing and install new pavement delineations.
- Reconstruct new structural section under the existing curb & gutter along the existing & new curb ramps, and
- Acquire new Right of Way (R/W) and/or Temporary Construction Easements (TCEs) for 5 parcels to accommodate the improvements.

In reviewing the draft Project plans and discussion with the Project Engineer, the followings are potential hazardous waste concerns that require special handling and waste management during construction:

Material Containing Hazardous Waste Concentrations of Aerially Deposited Lead (ADL):

Per OEE's review of the Project scope of work, excess soil, potentially containing hazardous waste concentrations of ADL, will be generated from said improvements/excavation work at unpaved areas. Based on OEE's reviewed of relevant reports/data obtained for ADL site investigations at/near the Project vicinity, elevated ADL concentrations exist at the upper shallow soil layer at the unpaved areas due to particulate emissions from historical leaded gasoline usage. The excess soil suspects to have elevated lead and other heavy metals concentrations that may exceed the California and/or Federal hazardous waste threshold Special handling and/or waste management may be required from the Project excavation activities. OEE recommends a Project-specific Aerially Deposited Lead (ADL) site investigation (SI) to be conducted in PS&E phase to evaluate and to determine the extent of the ADL contamination. Furthermore, the ADL SI data will assist the General Contractor (GC) to develop task-specific Lead Compliance Plans (LCPs) and to implement lead awareness trainings in conformance with 8CCR, Section 1532.1, "Lead" and Cal-OSHA Construction Safety Order prior to commencement of ADL excavation work. For the PR Cost Estimate, it is recommended to assume all excess excavated soils at the unpaved areas to be classified as California hazardous waste (Roadway/Structural Excavation Type Z-2) and shall be disposed at a permitted Class I hazardous waste disposal facility within the State of California.

Minimum Disturbance of Material Containing Hazardous Waste Concentrations of Aerially Deposited Lead (ADL):

The Project will require installation of temporary stationary mounted construction area signposts and minor landscape/irrigation restoration at existing unpaved areas. These works are considered "minimal soil disturbance" and will not generate excess/surplus potential ADL soil that requires special handling and/or waste management. According to Caltrans' ADL guidance document (2010), US EPA allows certain discrete areas of generally dispersed contamination to be considered as individual waste management unit. These discrete areas

EA: 07-346600 (PN: 1846-0718000076-0) PAED Preliminary Hazardous Waste Assessment March 25, 2024 Page 3 of 4

are defined as Areas of Contamination (AOCs). An AOC is equated to a single unit, and therefore movement, consolidation, or in-situ treatment of hazardous waste within the AOC does not create a new point of hazardous waste generation. For an AOC, contamination must be contiguous but can have various concentrations. The Department of Toxic Substances Control (DTSC) allows Caltrans to apply AOC approach to projects that will only cause minimal disturbances of soil containing hazardous waste concentrations of aerially deposited lead. All soil disturbed must remain in the immediate area of disturbance and not be transported elsewhere. Health and safety precautions and dust control for hazardous waste must be implemented. It is important to notify the General Contractor (GC) that lead is present and allow for preparation of a task-specific Lead Compliance Plan (LCP) and implement lead awareness training as required by Title 8, Section 1532.1 of the California Code of Regulations (8CCR) and Cal-OSHA Construction Safety Order.

Remove Existing Yellow Traffic Stripes and Pavement Marking With Hazardous Residue:

Yellow traffic paint used prior to 1999 in District 1 and prior to 1997 in all other districts contained high concentrations of lead. Application of yellow thermoplastic material containing high concentrations of lead was phased out during 2004 to 2006. The lead concentrations in the older yellow paint and yellow thermoplastic are high enough to make these materials hazardous wastes when they are removed. In addition, in many areas there are new low lead concentration paints on top of older yellow high lead concentration paints. The GC is required to properly manage removed stripe and pavement marking as a hazardous waste and to have and implement a LCP prepared by a Certified Industrial Hygienist (CIH). The LCP shall be prepared in conformance with 8CCR, Section 1532.1 and Cal-OSHA Construction Safety Order. The GC is also required to submit a work plan for the removal, containment, storage, and disposal of yellow thermoplastic and yellow painted traffic stripe and pavement marking.

Remove Existing Traffic Stripes and Pavement Markings Containing Lead (Non-Yellow And Non-Hazardous):

Residues from the removal of existing white (non-yellow) thermoplastic and lead-based painted traffic stripe/pavement marking can be classified as non-hazardous and does not require disposal at a permitted Class I hazardous waste disposal facility. The GC is required to develop a task-specific LCP as required in 8CCR, section 1532.1, Cal-OSHA Construction Safety Order, and training program to ensure worker safety at the construction site prior to commencement of work.

For Project preliminary cost estimate, refer to http://sv08doweb1/contractcost/ for the latest bid costs per the hazardous waste conditions/items stated above.

Temporary Construction Easements, Highway Easements, and Partial Fee Acquisition:

Based on OEE's discussion with the Project Engineer, two locations/5 parcels will require temporary construction easements (TCEs), highway easements (HEs) and/or partial fee (F) acquisitions. Refer to the attached map locations with potential new right of way (R/W) acquisitions. Initial site assessments (ISAs) may/will be required to assess all new

EA: 07-346600 (PN: 1846-0718000076-0) PAED Preliminary Hazardous Waste Assessment March 25, 2024 Page 4 of 4

commercial/industrial parcels/properties that will be acquire for the Project. The objective of the ISA is to identify recognized environmental conditions (RECs) presence or likely presence of nay hazardous substances or petroleum products in, on, or at a property (1) due to any release to the environment; (2) under conditions indicative of a release to the environment; or (3) under conditions that pose a material threat of a future release to the environment.

OEE RESOURCE ESTIMATE FOR PROJECT (CC 1846):

WBS 235.10 = 700 hours (200 PY hours (SI Support) + 500 PYE hours (ADL Site Investigation and ISA Consultant Work)

WBS 255.05 = 120 hours (PS&E Support)

WBS 270.66 = 80 hours (Construction Support)

WBS 280.10 = 24 hours (Project Close Out)

Upon completion of the final draft PR, please provide a copy to OEE for review. Please note that this preliminary hazardous waste assessment is only applicable to limited scope of work provided with the Project request and it is not applicable for a final hazardous waste assessment/clearance of the project.

If you have any questions, I can be reached at tuanchi.liu@dot.ca.gov (213) 269-1109, or contact Avery Chan of my staff at avery.chan@dot.ca.gov, (213) 897-0936.

Jack Liu, P.E., STE

District Hazardous Waste Branch (South Region)

Office of Environmental Engineering (OEE)

Jumle Lus

Division of Environmental Planning

Reference:


draft Project Repot, January 2014; HWA request memo 10/31/23, Scope Update memo 2/16/24, draft Plan, and draft Right of Way Maps March/2024.

Attachment:


draft ROW Cost Estimate Map (Pertaining to Sidewalk and ADA locations with New R/W Acquisition)

File:

D7EnvPlngDocs Cheryl Henderson - Division of Environmental Planning Karl Price - Division of Environmental Planning Nader Abdelmalek - Division of Project Management







RIGHT OF WAY DATA SHEET – Attachment E

Memorandum

Serious Drought! Help Save Water!

To: Joseph Reynoza, Design Manager

Office of Design

From:

District 7, Los Angeles Office

Zoltan Elo, Office Chief

Right of Way Appraisals, and Planning & Management

District 7, Los Angeles Office

Date: 6/24/2024 EA: 34660

Data Sheet ID NO: ds6502 Project ID # 0718000076

Subject: Current Estimated Right of Way Costs for **Project Report**

We have completed an estimate of the Right of Way costs for the above referenced project based on information received from Suzie Kearns, PE and the following assumptions and limiting conditions apply:

- The mapping did not provide sufficient detail to determine the limits of the right of way required.
- The transportation facilities have not been sufficiently designed, so our estimator could not determine the damages to any of the remainder parcels affected by the project.
- Additional right of way requirements are anticipated, but are not defined due to the preliminary nature of the estimate.

Right of Way Certificate (RWC) lead time will require a minimum of 24 months after maps to appraisal **(MA).** Completed Appraisal maps include HMDD, COS, HW Memo, and RE-49. An executed copy of the new freeway agreement if required for the project. When utility relocation is warranted, utility conflict maps will be required. Additionally a minimum of 18 months will be required after receiving the last revision to the appraisal map. Shorter lead times will require either more right of way resources or an increased number of condemnation suits to be file and present a risk to the RWC project delivery milestone. Due to the passage of Map 21 and the Buy America provision, the Right of Way Certification process will be longer, if Utility Relocation is necessary.

Current Schedule: PRSM

PAED (M 200)	MA (M 224)	RWC (M 410)	RTL (M 460)	CCA (M 600)
6/7/2024	6/30/2024	3/20/2026	4/20/2026	2/28/2029

TO Joseph Reynoza
ATTN Suzie Kearns

R/W DATA SHEET

ID NO ds6502

Date of Data Sheet 6/24/2024

ROUTE 213

PM_KM 0/10

SENIOR R/W P&M Nader Abdelmalek

EA 34660

Project ID # 0718000076

ALT

Project Description In Los Angeles Co., in the City of Los Angeles, between 25th St. and I-405. Pavement Capital Preventative Maintenance

This cost estimate is valid for the above scoping report only. This is an estimate only and not an appraisal. It may be based on worse case scenarios.

The estimate is subject to change and revision.

The mapping did not provide sufficient nor adequate detail to determine the limits of the Right of Way required and effects on the improvements.

The transportation facilities have not been sufficiently designed for our estimator to determine the damages to any of the remainder parcels affected by the project.

This cost estimate is pursuant to the following responses supplied by Joseph Reynoza to the Data Sheet Request Form.

YES NO Not known at this time

	YES	NO	Not known	at this time
Utilities are depicted on plans		х		
Railroads are depicted on plans	х			
There are Material and/or Disposal Sites Required			x	
Caltrans will do the Right of Way work	х			
There will be a Cooperative Agreement			х	
This is a reimbursable project			х	
There is Hazardous Waste potential			x	

RW COST ESTIMATE

	CURRENT VALUE	ESCALATED VALUE
R/ w acq.(incl.contingency G.w-condemadm.s'tl.)Permits	\$235,250	\$255,479
Clearance		
RAP (cont rate.)		
Escrow costs (cont rate.)	\$8,210	\$9,438
Utility relocation costs	\$696,500	\$1,011,800
Estimate of Reimbursed Appraisal Fee	\$9,000	\$9,000
Total estimated cost	\$948,960	\$1,285,717

Escalation Rate Rw .07
Escalation Rate Utilities .08

Cert.date 3/20/26

ALT

Parcel Count and Py Info

P	ARCEL TYPES	DUAL APPR.		RIGHTS NEEDED	_	TAKES	DISPLAC OF UI		PARCELS RA		POTENTIAL CLEARANCE PARCELS	POTENTIAL CONDEMNATION PARCELS	POTENTIAL EXCESS PARCELS	UTILITY II	MPACTS
Α			FEE		FULL		SFR							u4-1	
В	6		EASE	2	PART	6	BUS		<u>-</u>			1.8		u4-2	
С			TCE	4	TOTAL	6	MULTI							u4-3	
D					'									u4-4	3
F						Estir	mate Of	Right C	of Way	Support	Hours			u5-7	
						Ac	tivity Codes	Funct	tion	Hours				u5-8	
							225 & 245	Appra	isals	1,050				u5-9	3
							225 & 245	Acquis	itions	1,230					

1,290 570

790

756

1,800

7,486

Utilities

Utility Potholing

Railroads

Condemnation

Clearance

Relocation

RW Engineering

Total

UTILITY INFORMATION

200

185.20.40

225 & 245

225 & 245

225 & 245

220 & 300

Please See the Utility Conflict Addendum for Complete Utility Information

	Total Current Cost	Ψ030,300
Are utility easements required? No	_	
Are Utility agreements required? Yes	Const. Completion Date	2/28/2029
Utility types , Facilities & Agreements Description:	Utility Escalation Rate	8%
Not all as-builts information received from ROWU	Total Escalated Cost	\$1,011,800

Data Sheet ID NO: ds6502

ROUTE 213

PM_KM 0/10

EA 34660

ALT

RR INFORMATION

Are RR affected		
Describe affected RR BNSF A UPRR A	BNSF At-Grade Crossing at PM 6.88 At-Grade Crossing at PM 8.45	
When Branch Lines Or Sp Railroad Facility Be More Co Involved?	ours Are Affected ,would Acquisition And Or Payment Of Damages To lost Effective Than Service Contracts ,or Grade Separations Requiring	Businesses And Or Industries Served By The g Construction And Maintenance Agreements 100,000
Explain Branch lines Pla	an Review and Inspection	
	nts And Rights Required From The Railroads. Are Grade Xing Requirir Separations Requiring Construction And Maintenance Agreements In	
Flagging and Inspection duri construction. Compensating	ing Railroad for Safety Enhancements.	
RAILROAD COST PERTAIN	NING TO CONSTRUCTION ACTIVITY \$800,000	<u></u>
construction activity.	gineer's estimate for construction the RR flagging e	ostimate is based on days needed to
Right of Way Estimate prepared by	Carly Corona	DATE 6/24/24
Right of Way Estimate prepared by	Carly Corona Mario Zamorano	
		6/24/24
Railroad Estimate prepared by Utilities Estimate prepared by	Mario Zamorano Michele Graves R/W Data Sheet and all supporting information I certinptions are reasonable and proper subject to the limit	6/24/24 4/24/24 4/24/24 ify that the probable highest and best
Railroad Estimate prepared by Utilities Estimate prepared by have personally reviewed this F se estimated values and assum his Data Sheet complete and cu	Mario Zamorano Michele Graves R/W Data Sheet and all supporting information I certinptions are reasonable and proper subject to the limit	ify that the probable highest and best iting conditions set forth and I find
Railroad Estimate prepared by Utilities Estimate prepared by have personally reviewed this F se estimated values and assum his Data Sheet complete and cu	Mario Zamorano Michele Graves R/W Data Sheet and all supporting information I certinptions are reasonable and proper subject to the limiturrent.	ify that the probable highest and best iting conditions set forth and I find

	EA- 34660 Description	Quantity	\$/Unit	Total Cost
1	Pothole 10" SCG line along Western Ave near Summerland St (ea)	2	2000	4000
2	Pothole 12" SCG line along Western Ave near Summerland St (ea)	2	2000	4000
3	Pothole 12" California Water water line along Western Ave near	2	2000	4000
4	Pothole AT&T conduit along Western Ave near Park Western Dr (ea)	2	2000	4000
5	Pothole 8" California Water water line along Western Ave near Park	2	2000	4000
6	Pothole 12" SCG line along Western Ave near Trudie Dr (ea)	2	2000	4000
7	Pothole 8" SCG line along Western Ave near Trudie Dr (ea)	2	2000	4000
8	Pothole 8" California Water water line along Western Ave near Trudie	2	2000	4000
9	Pothole 6" California Water water line along Western Ave near	2	2000	4000
10	Pothole 8" California Water water line along Western Ave near	2	2000	4000
11	Pothole AT&T conduit along Western Ave near Caddington Dr (ea)	2	2000	4000
12	Pothole 12" SCG line along Western Ave near Caddington Dr (ea)	2	2000	4000
13	Pothole 8" SCG line along Western Ave near Caddington Dr (ea)	2	2000	4000
14	Pothole AT&T conduit along Western Ave near Toscanini Dr (ea)	2	2000	4000
15	Pothole 12" SCG line along Western Ave near Toscanini Dr (ea)	2	2000	4000
16	Pothole 8" SCG line along Western Ave near Toscanini Dr (ea)	2	2000	4000
17	Curb Ramp 1 and 2 Relocate Firehydrant (ea)	1	25000	25000
18	Curb Ramp 1 and 2 adjust to grade manhole (ea)	1	7500	7500
19	Curb Ramp 1 and 2 Pothole 20" Philips Pipeline along Western Ave	2	2000	4000
20	Curb Ramp 1 and 2 Pothole 6" Plains All American Oil Line along	2	2000	4000
21	Curb Ramp 1 and 2 Pothole SCE along Sepulveda Blvd (ea)	2	2000	4000
22	Curb Ramp 1 and 2 Pothole 8" SCG along Sepulveda Blvd (ea)	2	2000	4000
23	Curb Ramp 3 Relocate Firehydrant (ea)	1	25000	25000
24	Curb Ramp 3 adjust to grade pullbox (ea)	1	5000	5000
25	Curb Ramp 3 Pothole 8" SCG along Western Ave (ea)	2	2000	4000
26	Pothole 8" Marathon Pipeline along 228th St (ea)	2	2000	4000
27	Pothole 6" Crimson oil line along Western Ave (ea)	2	2000	4000
28	Pothole 10" PBF Energy oil line along Western Ave at 228th St (ea)	2	2000	4000
29	Pothole 8" SCG along 228th St (ea)	2	2000	4000
30	Pothole 2" SCG along Plaza Del Amo (ea)	2	2000	4000
31	Pothole 10" PBF Energy oil line along Western Ave at 224th St (ea)	2	2000	4000
32	Pothole SCE along Western Ave at 223rd St (ea)	2	2000	4000
33	Pothole 10" PBF Energy oil line along Western Ave at 223rd St (ea)	2	2000	4000
34	Pothole 4" SCG along Western Ave at 223rd St (ea)	2	2000	4000
35	Pothole 10" PBF Energy oil line along Western Ave at 220th St (ea)	2	2000	4000
		·	·	·

	EA- 34660 Description	Quantity	\$/Unit	Total Cost
36	Pothole 4" SCG along Western Ave at 220th St (ea)	2	2000	4000
37	Curb Ramp 4 Pothole 8" SCG along Western Ave (ea)	6	2000	12000
38	Curb Ramp 10 Pothole 8" SCG along Western Ave (ea)	2	2000	4000
39	Curb Ramp 12 Pothole SCE along Western Ave (ea)	2	2000	4000
40	Curb Ramp 12 Pothole 10" PBF Energy oil line along Western Ave (ea)	2	2000	4000
41	Curb Ramp 12 Pothole 12" PBF Energy oil line along Western Ave (ea)	2	2000	4000
42	Curb Ramp 19 and 20 adjust to grade pullbox (ea)	3	5000	15000
43	Curb Ramp 19 and 20 Pothole Frontier line along Torrance Blvd (ea)	2	2000	4000
44	Curb Ramp 19 and 20 Pothole 10" PBF Energy oil line along Western	2	2000	4000
45	Curb Ramp 21 adjust to grade pullbox (ea)	1	5000	5000
46	Curb Ramp 21 Pothole 10" PBF Energy oil line along Western Ave (ea)	3	2000	6000
47	Curb Ramp 21 Pothole 12" PBF Energy oil line along Western Ave (ea)	3	2000	6000
48	Curb Ramp 21 Pothole SCE along Western Ave (ea)	3	2000	6000
49	Curb Ramp 22 Pothole AT&T conduit along Torrance Blvd (ea)	2	2000	4000
50	Curb Ramp 22 Pothole Lumen conduit along Torrance Blvd (ea)	2	2000	4000
51	Curb Ramp 22 Pothole 10" PBF Energy oil line along Western Ave (ea)	2	2000	4000
52	Curb Ramp 23 Pothole SCE along Western Ave (ea)	3	2000	6000
53	Curb Ramp 23 Pothole 8" SCG along 209th St (ea)	2	2000	4000
54	Curb Ramp 24 Pothole AT&T conduit along Western Ave (ea)	2	2000	4000
55	Curb Ramp 24 Pothole 2" SCG along 209th St (ea)	2	2000	4000
56	Curb Ramp 24 Pothole 4" SCG along Western Ave (ea)	2	2000	4000
57	Curb Ramp 26 Pothole AT&T conduit along Western Ave (ea)	2	2000	4000
58	Curb Ramp 26 Pothole 8" PBF Energy Oil Line along Western Ave (ea)	2	2000	4000
59	Curb Ramp 26 Pothole Lumen conduit along 208th St (ea)	2	2000	4000
60	Curb Ramp 26 Pothole 4" SCG along Western Ave (ea)	3	2000	6000
61	Curb Ramp 26 Pothole 12" PBF Energy oil line along Western Ave (ea)	2	2000	4000
62	Curb Ramp 28 Pothole AT&T conduit along 208th St (ea)	2	2000	4000
63	Curb Ramp 28 Pothole SCE along Western Ave (ea)	2	2000	4000
64	Curb Ramp 28 Pothole 10" gas Line along Western Ave (ea)	2	2000	4000
65	Curb Ramp 28Pothole MWD line along Western Ave	2	2000	4000
66	Curb Ramp 29 Pothole AT&T conduit along Western Ave (ea)	2	2000	4000
67	Curb Ramp 29 Pothole 8" PBF Energy Oil Line along Western Ave (ea)	2	2000	4000
68	Curb Ramp 29 Pothole 4" SCG along Western Ave (ea)	2	2000	4000
69	Curb Ramp 29 Pothole 2" SCG along 207th St (ea)	2	2000	4000
70	Curb Ramp 31 Pothole AT&T conduit along Western Ave (ea)	2	2000	4000
		·	·	·

	Description	EA- 34660	Quantity	\$/Unit	Total Cost
71	Curb Ramp 31 P	othole 8" PBF Energy Oil Line along Western Ave (ea)	2	2000	4000
72	Curb Ramp 31 P	othole 4" SCG along Western Ave (ea)	2	2000	4000
73	Curb Ramp 32 a	djust to grade pullbox (ea)	1	5000	5000
74	Curb Ramp 34 P	othole AT&T conduit along 205th St (ea)	2	2000	4000
75	Curb Ramp 34Po	othole 10" PBF Energy oil line Line along Western Ave	2	2000	4000
76	Curb Ramp 34 P	othole SCE along 205th St (ea)	4	2000	8000
77	Curb Ramp 35 P	othole AT&T conduit along Western Ave (ea)	2	2000	4000
78	Curb Ramp 35 P	othole 8" PBF Energy Oil Line along Western Ave (ea)	2	2000	4000
79	Curb Ramp 35 P	othole 4" SCG along Western Ave (ea)	2	2000	4000
80	Curb Ramp 35 P	othole 2" SCG along 205th St (ea)	4	2000	8000
81	Curb Ramp 37 a	nd 38 Pothole AT&T conduit along Western Ave (ea)	2	2000	4000
82	Curb Ramp 37 a	nd 38 Pothole 8" PBF Energy Oil Line along Western	2	2000	4000
83	Curb Ramp 37 a	nd 38 Pothole 4" SCG along Western Ave (ea)	2	2000	4000
84	Curb Ramp 39 a	nd 40 adjust to grade pullbox (ea)	2	5000	10000
85	Curb Ramp 39 a	nd 40 Pothole 20" Chevron oil line along Western Ave	2	2000	4000
86	Curb Ramp 39 a	nd 40 Pothole AT&T conduit along Western Ave (ea)	2	2000	4000
87	Curb Ramp 39 a	nd 40 Pothole 8" PBF Energy Oil Line along Western	2	2000	4000
88	Curb Ramp 39 a	nd 40 Pothole 16" Plains All American Oil Line along	2	2000	4000
89	Curb Ramp 39 a	nd 40 Pothole 4" SCG along 190th St (ea)	4	2000	8000
90	Curb Ramp 41 a	nd 42 adjust to grade pullbox (ea)	1	5000	5000
91	Curb Ramp 41 a	nd 42 Pothole SCE along Del Amo Blvd (ea)	3	2000	6000
92	Curb Ramp 41 a	nd 42 Pothole 10" PBF Energy oil line along Western	2	2000	4000
93	Curb Ramp 41 a	nd 42 Pothole 12" PBF Energy oil line along Western	2	2000	4000
94	Curb Ramp 41 a	nd 42 Pothole AT&T conduit along Western Ave (ea)	2	2000	4000
95	Curb Ramp 44 a	djust to grade pullbox (ea)	1	5000	5000
96	Curb Ramp 44 P	othole Shell Oil Line along Western Ave (ea)	2	2000	4000
97	Curb Ramp 44 P	othole 16" Plains All American Oil Line along Western	2	2000	4000
98	Curb Ramp 46 a	djust to grade pullbox (ea)	1	5000	5000
99	Curb Ramp 46 P	othole SCE along Western Way (ea)	2	2000	4000
100	Curb Ramp 47 a	nd 48 adjust to grade pullbox (ea)	1	5000	5000
101	Curb Ramp 47 a	nd 48 Pothole Lumen conduit along Fransisco St (ea)	2	2000	4000
102	Curb Ramp 47 a	nd 48 Pothole AT&T conduit along Western Ave (ea)	2	2000	4000
103	Curb Ramp 47 a	nd 48 Pothole 4" SCG along Western Ave (ea)	4	2000	8000
104	Curb Ramp 49 a	nd 50 adjust to grade pullbox (ea)	1	5000	5000
105	Curb Ramp 49 a	nd 50 Pothole SCE along Western Way (ea)	2	2000	4000
				•	

	Description	Quantity	\$/Unit	Total Cost
106	Curb Ramp 51 adjust to grade pullbox (ea)	2	5000	10000
107	Curb Ramp 52 adjust to grade pullbox (ea)	1	5000	5000
108	Curb Ramp 53 and 54 adjust to grade pullbox (ea)	2	5000	10000
109	Curb Ramp 55 and 56 adjust to grade pullbox (ea)	2	5000	10000
110	Curb Ramp 55 and 56 Pothole SCE along Western Ave (ea)	4	2000	8000
111	Curb Ramp 57 and 58 adjust to grade pullbox (ea)	5	5000	25000
112	Curb Ramp 57 and 58 Pothole Lumen conduit along 190th St (ea)	2	2000	4000
113	Curb Ramp 59 and 60 adjust to grade pullbox (ea)	3	5000	15000
114	Curb Ramp 59 and 60 Pothole AT&T conduit along 190th St (ea)	2	2000	4000
115	Curb Ramp 59 and 60 Pothole SCE along Western Ave (ea)	3	2000	6000
116	Curb Ramp 59 and 60 Pothole 36" SCG along 190th St (ea)	2	2000	4000
117	Curb Ramp 59 and 60 Pothole 2" SCG along 190th St (ea)	2	2000	4000
118	Curb Ramp 61 and 62 adjust to grade pullbox (ea)	4	5000	20000
119	Curb Ramp 61 and 62 Relocate Firehydrant (ea)	1	25000	25000
120	Curb Ramp 61 and 62 pothole 10" Air Products gas line in 16" csg	2	2000	4000
121	Curb Ramp 61 and 62 Pothole AT&T conduit along 190th St (ea)	2	2000	4000
122	Curb Ramp 61 and 62 Pothole SCE along 190th St (ea)	4	2000	8000
123	Curb Ramp 61 and 62 Pothole 6" SCG along Western Ave (ea)	2	2000	4000
124	Curb Ramp 3 Relocate 6" Crimson oil line (If)	60		0

$\begin{array}{c} ENVIRONMENTAL\ DOCUMENT-\\ Attachment\ F \end{array}$



CEQA EXEMPTION / NEPA CATEGORICAL EXCLUSION DETERMINATION FORM (rev. 06/2022)

Project Information			
Project Name (if applicat	ole): Roadway Rehabilitation		
DIST-CO-RTE: 07-LA-213	PM/PM: 0.0/10.0		
EA : 34660 Feder	al-Aid Project Number: 07180000	076	
Project Description			
guardrail, upgrade existing Disabilities Act standards, retaining walls for the addit upgrade some pedestrian to allow for placement of C	chabilitate pavement (cold plane and nonstandard ADA curb ramp facility construct concrete bus pads at transtion of sidewalk segments, relocated push buttons, replace loop detectorals. Il bike lanes, place Class II bike tight drainage inlet grates with bic bicycle signs.	ties to Americans with nsit stops, construct e some traffic signals, rs, reduce some medians ke lanes, install bicycle	
Caltrans CEQA Determin	ation (Check one)		
 □ Not Applicable – Caltra □ Based on an examination of Exempt by Statute. (Pf □ Categorically Exempt. □ No exceptions app 21084 and 14 CCF □ Covered by the Comm exempt class, but it can activity may have a sign 	ans is not the CEQA Lead Agency ans has prepared an IS or EIR under of this proposal and supporting information (Cass 1(c)). (PRC 21084; 14 CCR oly that would bar the use of a cate (Cass 15300.2). See the SER Chapter on Sense Exemption. This project has be seen with certainty that there is nificant effect on the environment (Canner or Environmental Branch (Canner or Environmental	ormation, the project is: (1.) 15300 et seq.) gorical exemption (PRC 34 for exceptions. et does not fall within an s no possibility that the 14 CCR 15061[b][3].)	
Karl Price	Karl Price	4/10/2024	
Print Name Signature Date			
Project Manager			
Nader Abdelmalek		4/10/2024	
Print Name Signature Date			



Caltrans NEPA Determination (Ch	eck one)			
□ Not Applicable				
Caltrans has determined that this proas defined by NEPA, and that there a CFR 771.117(b). See <u>SER Chapter</u> is categorically excluded from the reand is included under the following:	are no unusual circumstances as de 30 for unusual circumstances. As s	escribed in 23 auch, the project		
 ≥ 23 USC 326: Caltrans has been at the responsibility to make this determined the management of the caltrans. Caltrans has determined the caltrans. ≥ 23 CFR 771.117(c): activity 	nination pursuant to 23 USC 326 an ed April 18, 2022, executed betweer nat the project is a Categorical Exclu	nd the n FHWA and		
☐ 23 CFR 771.117(d): activity	• • • • • • • • • • • • • • • • • • • •			
□ Activity Enter activity num FHWA and Caltrans	ber listed in Appendix A of the MO	3U between		
□ 23 USC 327: Based on an examir Caltrans has determined that the proof The environmental review, consultat Federal environmental laws for this part Caltrans pursuant to 23 USC 327 and May 27, 2022, and executed by FHV	oject is a Categorical Exclusion under ion, and any other actions required project are being, or have been, carr and the Memorandum of Understanding	er 23 USC 327. by applicable ried out by		
Senior Environmental Planner or I	Environmental Branch Chief			
Karl Price	Karl Price	4/10/2024		
Karl PriceKarl Price4/10/2024Print NameSignatureDate				
Project Manager/ DLA Engineer				
Nader Abdelmalek		4/10/2024		
Print Name	Signature	Date		

Date of Categorical Exclusion Checklist completion (if applicable): 4/4/24 Date of Environmental Commitment Record or equivalent: 4/4/24

Briefly list environmental commitments on continuation sheet if needed (i.e., not necessary if included on an attached ECR). Reference additional information, as appropriate (e.g., additional studies and design conditions).

EA: 34660 Page **2** of **7**



Continuation sheet:

Biological Resources

This project will have no impacts to biological resources. There will be minor removal of vegetation (mostly grass) with no removal of trees. All work is within the prism of the roadway or the unvegetated shoulder only. There will be no effect to federal/state threatened/endangered species.

Avoidance and Minimization Measures:

- 1. All work will be limited to the prism of the roadway, or the edge of the unvegetated roadway for purposes of equipment maneuvering and traffic control.
- 2. There will be no clearing or grubbing of vegetation as a result of this project. There will be minor removal of vegetation (mostly non-native invasive grasses) with no removal of trees.
- 3. All appropriate Stormwater and Erosion Best Management Practices will be incorporated into the project specifications.
- 4. All pollution and litter laws and regulations will be followed by the contractor.
- 5. If this project scope should change for any reason, this Division will be notified to determine whether current environmental documentation is adequate.
- 6. This Division will be provided the Project Specifications & Expenditures Review Package for review and comments.
- 7. No asphalt grindings shall be used within 100 feet of any water course. Water course, for this purpose, is defined as any feature, either natural or man-made, which conveys water during any time of year. The limitation on asphalt use near waterways is restricted to shoulder backing.
- 8. Construction should be limited to the period outside of the bird nesting season, from September 1 to February 1. If work is conducted during the nesting bird season (February 1 to September 1), the District Biologist should be notified 1 week in advance of work and nesting bird surveys by a qualified biologist must be conducted a minimum of 3 days before commencement of work. For songbirds and raptors, if there are active nests, a buffer zone of 150 feet or 500 feet, respectively, must be established with no work in the buffer zone until the fledglings can flee the project area.
- 9. Clearing and grubbing is not anticipated for this project. If clearing and grubbing is conducted during the nesting bird season (February 1 to September 1), nesting bird surveys will be necessary before any clearing and grubbing can be conducted. A qualified biologist should be notified 1 week prior to clearing and grubbing to conduct nesting bird surveys a maximum of 3 days before clearing and grubbing commences.

Cultural Resources

This project has no potential to affect historic properties eligible for or listed in the National Register of Historic Places, and is exempt from further review pursuant to the Section 106 PA. No additional studies are required and the Section 106 compliance process, CEQA cultural resources component, and PRC 5024 compliance are

EA: 34660 Page **3** of **7**



complete. This assessment could change if there are any changes to the proposed activities or if additional locations are added. If there are such changes to the proposed undertaking, an additional review by the cultural resources unit will be required. If previously unidentified cultural materials are unearthed during construction, work shall be halted in that area until a qualified archaeologist can assess the significance of the find.

Air Quality

This project is considered exempt from conformity requirements pursuant to 40 CFR 93.126 under "Safety" and classification "Pavement resurfacing and/or rehabilitation" It is unlikely that the project will result in an adverse impact to ambient CO, PM10, or PM2.5. The project is not anticipated to contribute to an increase in mobile source air toxic (MSAT) emissions impacts relative to the no-build alternative and does not require an analysis or discussion of MSAT.

The proposed project is not anticipated to result in increase in operational GHG emissions as no additional roadway capacity will be added. However, per Executive Order B-30-15, Caltrans requires that construction GHG emissions be quantified.

Caltrans DEA Office of Environmental Management developed a GHG Reduction Measures Toolbox

(https://env.onramp.dot.ca.gov/downloads/env/managedfiles/caltrans-ghg- reduction-measures-jun-2021-a11y.pdf) for use in project development. It is recommended that the PDT review, evaluate, and consider project measures in Tables 1 and 3 of the Toolbox and that the project commit to include all feasible and relevant measures identified from the Tables. If any measures are proposed outside the tables, the PDT shall ensure that those measures are biddable, buildable, and can be successfully implemented. All identified reduction measures shall be carried forward in the ECR.

The proposed project is located within the jurisdiction of the South Coast Air Quality Management District (SCAQMD) and therefore must comply with the SCAQMD Fugitive Dust Rule 403 to minimize temporary emissions during construction of the project as applicable and appropriate. While construction equipment on site would generate some objectionable odors primarily arising from diesel exhaust, these emissions would generally be limited to the project site and would be temporary in nature. Objectionable odors should also be minimized by conducting certain construction activities in areas at least 500 feet from the sensitive receptors as feasible. The AQB will coordinate for approval of NSSP 14.9-.05 to mandate contractors' compliance with the applicable air district rules including measure related to dust control.

The AQB should be informed of any changes to the proposed scope or the class of action determination for this project. Such changes may require an update or reassessment of air quality issues for the proposed project.

Hazardous Waste

Material Containing Hazardous Waste Concentrations of Aerially Deposited Lead (ADL)

EA: 34660 Page **4** of **7**



Per OEE's review of the scope of work, excess soil, potentially containing hazardous waste concentrations of ADL, will be generated from said improvements/excavation work at unpaved areas. OEE recommends a Project-specific Aerially Deposited Lead (ADL) site investigation (SI) to be conducted in PS&E phase to evaluate and to determine the extent of the ADL contamination. Furthermore, the ADL SI data will assist the General Contractor (GC) to develop task-specific Lead Compliance Plans (LCPs) and to implement lead awareness trainings in conformance with 8CCR, Section 1532.1, "Lead" and Cal-OSHA Construction Safety Order prior to commencement of ADL excavation work. For the PR Cost Estimate, it is recommended to assume all excess excavated soils at the unpaved areas to be classified as California hazardous waste (Roadway/Structural Excavation Type Z-2) and shall be disposed at a permitted Class I hazardous waste disposal facility within the State of California.

Minimum Disturbance of Material Containing ADL

The Project will require installation of temporary stationary mounted construction area signposts and minor landscape/irrigation restoration at existing unpaved areas. These works are considered "minimal soil disturbance" and will not generate excess/surplus potential ADL soil that requires special handling and/or waste management. According to Caltrans' ADL guidance document (2010), US EPA allows certain discrete areas of generally dispersed contamination (AOCs) to be considered as individual waste management unit. An AOC is equated to a single unit, and therefore movement, consolidation, or in-situ treatment of hazardous waste within the AOC does not create a new point of hazardous waste generation. For an AOC, contamination must be contiguous but can have various concentrations. The Department of Toxic Substances Control (DTSC) allows Caltrans to apply AOC approach to projects that will only cause minimal disturbances of soil containing hazardous waste concentrations of aerially deposited lead. All soil disturbed must remain in the immediate area of disturbance and not be transported elsewhere. Health and safety precautions and dust control for hazardous waste must be implemented. It is important to notify the General Contractor (GC) that lead is present and allow for preparation of a task-specific Lead Compliance Plan (LCP) and implement lead awareness training as required by Title 8, Section 1532.1 of the California Code of Regulations (8CCR) and Cal-OSHA Construction Safety Order.

Remove Existing Yellow Traffic Stripes & Pavement Marking With Hazardous Residue

Application of yellow thermoplastic material containing high concentrations of lead was phased out during 2004 to 2006. The lead concentrations in the older yellow paint and yellow thermoplastic are high enough to make these materials hazardous wastes when they are removed. In addition, in many areas there are new low lead concentration paints on top of older yellow high lead concentration paints. The GC is required to properly manage removed stripe and pavement marking as a hazardous waste and to have and implement an LCP prepared by a Certified Industrial Hygienist (CIH). The LCP shall be prepared in conformance with 8CCR, Section 1532.1 and Cal-OSHA Construction Safety Order. The GC is also required to submit a work plan for the removal, containment, storage, and disposal of yellow thermoplastic and yellow painted traffic stripe and pavement marking.

EA: 34660 Page **5** of **7**



Remove Existing Traffic Stripes & Pavement Marking Containing Lead (Non-yellow & Non-hazardous)

Residues from the removal of existing white (non-yellow) thermoplastic and lead-based painted traffic stripe/pavement marking can be classified as non-hazardous and does not require disposal at a permitted Class I hazardous waste disposal facility. The GC is required to develop a task-specific LCP as required in 8CCR, section 1532.1, Cal-OSHA Construction Safety Order, and training program to ensure worker safety at the construction site prior to commencement of work.

Temporary Construction Easements, Highway Easements, and Partial Fee Acquisition

Based on OEE's discussion with the Project Engineer, two locations/5 parcels will require temporary construction easements (TCEs), highway easements (HEs) and/or partial fee (F) acquisitions. Refer to the map locations with potential new right of way acquisitions attached to the HWA dated 3/25/24. Initial site assessments (ISAs) will be required to assess all new commercial/industrial parcels/properties that will be acquired for the project. The objective of the ISA is to identify recognized environmental conditions (RECs) presence or likely presence of any hazardous substances or petroleum products in, on, or at a property (1) due to any release of the environment; (2) under conditions indicative of a release to the environment; or (3) under conditions that pose a material threat of a future release to the environment.

Noise

Based on the scope of work listed above, this is not a Type I project as defined in the 2020 Traffic Noise Analysis Protocol and it is not expected to raise traffic noise levels or cause a substantial permanent noise increase. Therefore, a detailed traffic noise impact study is not required for this project. However, since there are sensitive land uses in the vicinity where construction work will take place, potential construction noise impacts would need to be addressed. Section 13-8.02, Sound Control Requirements, of Caltrans Standard Specifications states that overnight construction noise levels should not exceed sustained 86 dBA at 50 feet from the job site activities. These requirements also state that noise levels generated during construction shall comply with applicable local, state, and federal regulations. Incorporating the standard Sound Control Requirements previously mentioned into the Project Standard Specifications and Special Provisions would address any temporary construction noise-related potential impacts.

Visual

A Questionnaire to Determine Visual Impact Assessment (VIA) was completed on 3/8/24 and found the following:

- The project will not impact the surrounding aesthetics or visual resources.
- The project will not introduce a new major light source.
- The project is not within a scenic vista, and the route is not eligible for designation as a state scenic highway at the time of this assessment.

No further assessment is required unless the project scope changes.

EA: 34660 Page **6** of **7**



Section 4(f)

There are a few park and recreational facilities in the vicinity of SR-213 within the project limits:

- Deane Dana Friendship Park
- Peck Park
- Navy Field Sports Complex

Due to the nature and location of the activities associated with this project, there will be no "use" of the properties.

EA: 34660 Page **7** of **7**

STORM WATER DATA REPORT SIGNED COVER SHEET – Attachment G



	Dist-County-Rou	ite: 0	/-LA-213			
	Post Mile Limits	: 0.00	0/10.00			
	Type of Work:	CAPM	& ADA CURB F	AMPS		
	Project ID (EA):	0718	3000076 (346	600)		
Caltrans						
	Phase: ☐ PID		⊠ PA/ED	☐ PS&E		
Applicable Caltrans Post Constr	iction Treatment I	Peguire	ment: 2012	20′	22 🖂	
		-			22 X	
Regional Water Quality Control E	· · · · · · · · · · · · · · · · · · ·		Region 4)			
Total Disturbed Soil Area: 6.2	5 Acres	PCTA:	0.93 Acres			
Alternative Compliance (acres):	0.32 Acres	ATA 2 (5	50% Rule)?	Ye	s 🗌	No ⊠
Estimated Const. Start Date:	11-23-2026	Estimate	ed Const. Comple	tion Date:	01-3	1-2029
Risk Level: RL 1 ☐ F	RL2⊠ RL	3 🗌	WPCP □	Other:		
ls (M)WELO applicable?	,	Yes □		No ⊠		
Is the Project within a TMDL wat	ershed?	Yes ⊠		No □		
Does the project require trash tr	reatment?	Yes □		No ⊠		
Notification of ADL reuse (if yes,	provide date):	 Yes □	Date:	_		No ⊠
This Report has been prepared und attests to the technical information conclusions, and decisions are bas PS&E only.	n contained herein a sed. Professional En	and the d ngineer o	late upon which r Landscape Arc	recommend	lations,	•
Kin Seng We Kin Seng Wong, Registered Project	ing				06/0	03/2024
Kin Seng Wong, Registered Project	Engineer/Landscap	e Archite	ect			Date
l have reviewed the stormwater qu accurate:	ality design issues a	and find	this report to be	complete, c	urrent	and
Fo	Mehdi Sa	alehin	rik		06/	/03/2024
	Nader Abdelmalek	, Project	Manager			Date
	Avre Con	~	intenance Storm		6/1	12/2024
	Jose Villasenor, Di	strict Ma	intenance Storm	water Coord	linator	Date
	Kathleen S	Han	ner		6/1	3/2024
	Kathleen Hamer, D Representative	Designat	ed Landscape Ar	chitect		Date
	S1:	۸			6/	13/2024
[Stamp Required at PS&E only]	Shao-Chiang Liu, Designee	District/R	egional Design S	SW Coordina		Date

PPDG July 2023 1 of 27

1. Project Description

- This project report (PR) presents a roadway preservation project on Route 213 in and near the cities of Los Angeles, Rancho Palos Verdes, Lomita, and Torrance, from West 25th Street to Route 405. This project is programmed in the 2022 State Highway Operation and Protection Program (SHOPP) under 20.XX.201.121 Roadway Preservation Program for delivery in the 2023/2024 fiscal year. The project proposes to rehabilitate pavement (cold plane and overlay), upgrade guardrail, upgrade existing nonstandard ADA curb ramps facilities to Americans with Disabilities Act (ADA) standards, construct concrete bus pads at transit stops, construct retaining walls for the addition of sidewalk segments, relocate some traffic signals, upgrade some pedestrian push-buttons, replace loop detectors, reduce some medians to allow for placement of Class II bike lanes, place Class II bike lanes, install bicycle loop detectors, upgrade existing drainage inlet grates with bicycle friendly grates, and install guide, warning and bicycle signs.
- This project also proposes design and installation of treatment Best Management Practice (BMP) for implementation of Total Maximum Daily Loads (TMDL) along segments of SR-213 (PM 10.00) and I-405 (PM 14.9) based on recommendations of the Corridor Stormwater Management Studies for the I-405.
- The scope of work for the programmable project alternative is as follows:
 - Cold plane 0.25 feet of the existing asphalt concrete pavement and overlay with 0.10 feet of HMA-Type A and 0.15 feet of rubberized hot mix asphalt gap graded (RHMA-G).
 - Dig-outs: Dig-out and replace failed pavement.
 - Upgrade 64 existing ADA curb ramps to the current American Disabilities Act standards. Ramps are located at various locations within project limits.
 - Upgrade existing 478 ft. Metal Beam Guardrail (MBGR) with Midwest Guardrail System (MGS).
 - Place 42 concrete bus pads (JPCP-RSC).
 - Place 2 retaining walls: total length of 533 ft.
 - Place 1,125 LF of sidewalk.
 - Place accessible pedestrian pushbuttons (PBA pole) at location of ADA curb ramp upgrades.
 - Upgrade 11 existing drainage inlets with bicycle friendly grates.
 - Replace all traffic loop detectors within limits of pavement rehabilitation.
 - Install bicycle loop detectors at all signalized intersections.
 - Include protection for State fiber optics within the roadway.
 - At six intersections, as required due to ADA curb ramp upgrades, replace 7 traffic signals, and relocate 5 electrical boxes.
 - The construction of 2 Biofiltration Device (Bioswale).
- The construction cost for this project is estimated to be \$48,481,437.
- The project Limit is within Los Angeles County MS 4 area.

PPDG July 2023 2 of 27

• The Total disturbed soil area (DSA) of this project is 6.25 acres, based on the following work:

Construction Work Item	Disturbe	ed Soil Are	a
Bus Pads (Full Structural Section)	40,320 ft ²	0.93	acres
Curb Ramps	25,600 ft ²	0.59	acres
Dig Outs (3% of Cold-Plane Area)	158,400 ft ²	3.64	acres
MGS with Vegetation Control	1,434 ft ²	0.03	acres
Traffic Signals	34 ft ²	0.0007	acres
Sidewalks	6,750 ft ²	0.15	acres
Medians	33,298 ft ²	0.76	acres
Retaining Walls	5,330 ft ²	0.12	acres
Total	271,166 ft ²	6.23	acres

	Construction of BMPs							
ВМР	ВМР	Length	Width	Area	Area (ac)			
Site	Туре	(ft)	(ft)	(sf)	Area (ac)			
3	Bioswale	100	6.5	650	0.015			
5	Bioswale	50	6	300	0.007			
			Total	950	0.022			

- The total new impervious surface (NIS) for this project is about 0.93 acres.
 - NIS=NNI+RIS
 - Net New Impervious (NNI)= 0.00 acre
 - Replaced Impervious Surface (RIS) is 0.93 acre
 - Bus Pads (Full Structural Section) = 0.93 acres
 - The area of sidewalks, curb, and gutter are not incorporated into the RIS because the structural section is not being removed.
 - The area of curb ramp sidewalk concrete cutout is not included as RIS because the full structural section is not being removed and it is not a roadway item.
- The existing impervious area for this project is estimated to be 121 acres.
 - There is no Net New Impervious Area (NNI) and there are no existing Treatment BMPs to be removed or modified as a part of the project. Therefore, Additional Treatment Area (ATA) is not applicable.
 - There are no existing Treatment BMPs being removed as part of this project; thus, ATA Condition 1 = 0.00 acres (PPDG 4-4-2).
 - NNI for this project has been found to be 0.00 acres, making it less than 25% of the total post-project impervious area; thus, ATA Condition 2 = 0.00 acres (PPDG 4-4-2).
- The Post Construction Treatment Area (PCTA) is 0.00 acres.
 - PCTA = NIS + ATA 1 + ATA 2 = 0.93 acres + 0.00 acres + 0.00 acres = 0.93 acres.
- The Corridor Stormwater Management Study (May 2013) recommended four permanent treatment Best Management Practice (BMP) devices. Implementation and applicability of treatment BMPs have been studied as part of this report. It has been determined that two of the recommended permanent BMPs are not feasible. See Section 6 Treatment Permanent BMPs.

PPDG July 2023 3 of 27

• This project does not include irrigated landscape area; therefore, the project conditions do not require compliance with the Model Water Efficient Landscape Ordinance (MWELO).

2. Site Data and Stormwater Quality Design Issues

The project limits on State Route 213 – Western Ave are from 25th Street (PM 0.00) to the I-405 (PM 10.00). The project limits are within the Santa Monica Bay, Los Angeles Harbor, Machado Lake, and Dominquez Channel Total Maximum Daily Load (TMDL) Watershed Boundaries. The TMDLs are as follows:

Santa Monica Bay

Pollutant(s)	Effective	LA RWQB	Categorical Implementation Requirements ¹²
	Date	Resolution	
		No.	
Title: Santa Mon	ica Bay Bead	hes Dry- and	d Wet-Weather Bacteria TMDLs
Indicator bacteria	07/15/2003	2002-004	Dry-weather non-storm water and wet-weather storm water discharges may
		(dry-	significantly increase bacteria loading to receiving waters. Caltrans shall
		weather)	implement control measures and/or BMPs to prevent the discharge of bacteria
		2002-022	from its R/W. Source control measures include street sweeping, illegal dumping
		(wet-	clean-up, public education on littering. BMPs include devices which treat storm
		weather)	water through retention/detention, infiltration and/or diversion.
Title: Santa Monica Bay Nearshore and Offshore Debris TMDL			
Debris (trash and	03/20/2012	R10-010	Discharge of trash to receiving waters from Caltrans R/W is prohibited. Caltrans
plastic pellets)			is assigned a WLA and compliance schedule in the Trash TMDL.
			Installation/retrofit of Gross Solid Removal Devices (GSRDs) and/or full capture
			systems at existing drainage outfalls within Caltrans R/W are required for TMDL
			compliance. Existing projects with GSRDs do not require additional
			implementation.
Title: Santa Mon	ica Bay TMD	Ls for DDT a	and PCBs
Dichlorodiphenyl-	03/26/2012	US EPA	Caltrans shall implement control measures and/or treatment BMPs to prevent
trichloroethane		established	the discharge of sediments which may contain toxic pollutants as listed in the
(DDT), total		TMDL	TMDL. Possible treatment options include the interception and infiltration of
polychlorinated			runoff which will allow water to percolate into soil.
biphenyls (PCBs)			

¹ Refer to §4 of the PPDG to determine the specific impervious threshold for stormwater Treatment BMP requirements.

PPDG July 2023 4 of 27

² General TMDL Requirements can be found in Attachment IV of the NPDES Statewide Storm Water Permit.

Los Angeles River

Pollutant(s)	Effective	LA RWQB	Categorical Implementation Requirements ¹²
	Date	Resolution	
		No.	
Title: Los Angele	s River Trash	TMDL	
Trash	12/24/2008,	R15-006	Discharge of trash to receiving waters from Caltrans R/W is prohibited. Caltrans
	revised		is assigned a WLA and compliance schedule in the Los Angeles River Trash
	06/30/2016		TMDL. Installation/retrofit of Gross Solid Removal Devices (GSRDs) and/or full
			capture systems at existing drainage outfalls within Caltrans R/W are required
			for TMDL compliance. Existing projects with GSRDs do not require additional
			implementation.
Title: TMDL for N	Netals for the	e Los Angele	s River and its Tributaries
Metals (Cu, Pb)	12/22/2005,	R15-004	Caltrans shall implement control measures and/or treatment BMPs to prevent
	revised		the discharge of sediments which may contain metals. Possible treatment
	12/12/2016		options include the interception and infiltration of runoff which will allow
			water to percolate into soil. Compliance of the TMDL will be achieved through
			implementation of BMPs.
Title: TMDL for I	ndicator Bac	teria for the	Los Angeles River Watershed
Indicator bacteria	03/23/2012	R10-007	Dry-weather non-storm water and wet-weather storm water discharges may
			significantly increase bacteria loading to receiving waters. Caltrans shall
			implement control measures and/or BMPs to prevent the discharge of bacteria
			from its R/W. Source control measures include street sweeping, illegal dumping
			clean-up, public education on littering. BMPs include devices which treat storm
			water through retention/detention, infiltration and/or diversion.
Title: Dominguez			s Angeles and Long Beach Harbor Waters Toxic Pollutants TMDL
Toxic pollutants	03/23/2012	R11-008	Targeted pollutants are to be monitored in the water column in the channel
(dichlorodiphenyl-			and harbors as well as the sediment in the harbors. The TMDL requires the
trichloroethane			dischargers of the Los Angeles River and the San Gabriel River to monitor water
(DDT), polycyclic			quality at the mouth of each river. Caltrans shall implement control measures
aromatic			and/or treatment BMPs to prevent the discharge of sediments which may
hydrocarbons			contain toxic pollutants as listed in the TMDL. Possible treatment options
(PAHs), total			include the interception and infiltration of runoff which will allow water to
polychlorinated			percolate into soil.
biphenyls (PCBs),			
metals (Cu, Pb,			
Zn))			

[|] Zn)) | | 1 Refer to §4 of the PPDG to determine the specific impervious threshold for stormwater Treatment BMP requirements.

PPDG July 2023 5 of 27

² General TMDL Requirements can be found in Attachment IV of the NPDES Statewide Storm Water Permit.

Machado Lake

Pollutant(s)	Effective Date	LA RWQB Resolution No.	Categorical Implementation Requirements ¹²
Title: Machado L	.ake Trash TN	ЛDL	
Trash	03/06/2008 (currently in the revision process)	R19-004	Discharge of trash to receiving waters from Caltrans R/W is prohibited. Caltrans is assigned a WLA and compliance schedule in the Machado Lake Trash TMDL. Installation/retrofit of Gross Solid Removal Devices (GSRDs) and/or full capture systems at existing drainage outfalls within Caltrans R/W are required for TMDL compliance. Existing projects with GSRDs do not require additional implementation.
Title: Machado I	ake Nutrient	s TMDL	
Nutrients (algae, ammonia, eutrophic and odor)	03/11/2009	2008-006	Caltrans shall implement control measures to prevent or minimize erosion and sediment discharge. Control efforts may include protecting hillsides, intercepting and filtering runoff, avoiding concentrated flows and not modifying natural runoff flow patterns.
Title: Machado I	ake Toxics TI	MDL	
Toxics (Chem A (chlordane, dieldrin), total polychlorinated biphenyls (PCBs))	03/20/2012	R10-008	Responsible Agencies, including Caltrans must implement actions to reduce pollutant loadings by weight in order to achieve the final wasteload allocations. Caltrans shall implement control measures and/or treatment BMPs to prevent the discharge of sediments which may contain toxic pollutants as listed in the TMDL. Possible treatment options include the interception and infiltration of runoff which will allow water to percolate into soil.

¹ Refer to §4 of the PPDG to determine the specific impervious threshold for stormwater Treatment BMP requirements.

Dominguez Channel

Pollutant/s)	Effective	LA RWQB	Catagorical Implementation Requirements 12
Pollutant(s)	Effective		Categorical Implementation Requirements ¹²
	Date	Resolution	
		No.	
Title: Dominguez	Channel an	d Greater Lo	s Angeles and Long Beach Harbor Waters Toxic Pollutants TMDL
Toxic pollutants	03/23/2012	R11-008	Targeted pollutants are to be monitored in the water column in the channel
(dichlorodiphenyl-			and harbors as well as the sediment in the harbors. The TMDL requires the
trichloroethane			dischargers of the Los Angeles River and the San Gabriel River to monitor water
(DDT), polycyclic			quality at the mouth of each river. Caltrans shall implement control measures
aromatic			and/or treatment BMPs to prevent the discharge of sediments which may
hydrocarbons			contain toxic pollutants as listed in the TMDL. Possible treatment options
(PAHs), total			include the interception and infiltration of runoff which will allow water to
polychlorinated			percolate into soil.
biphenyls (PCBs),			
metals (Cu, Pb,			
Zn))			

¹ Refer to §4 of the PPDG to determine the specific impervious threshold for stormwater Treatment BMP requirements.

PPDG July 2023 6 of 27

² General TMDL Requirements can be found in Attachment IV of the NPDES Statewide Storm Water Permit.

 $^{{\}bf 2}~{\bf General}~{\bf TMDL}~{\bf Requirements}~{\bf can}~{\bf be}~{\bf found}~{\bf in}~{\bf Attachment}~{\bf IV}~{\bf of}~{\bf the}~{\bf NPDES}~{\bf Statewide}~{\bf Storm}~{\bf Water}~{\bf Permit}.$

• The following are the Hydrologic Units, Hydrologic Sub-Area, 303(d) listed receiving water bodies, and pollutants that are near the project limits.

Hydrologic Unit	Hydrologic Sub-Area #
SANTA MONICA BAY	404.70
DOMINGUEZ CHANNEL	411.02
DOMINGUEZ CHANNEL	411.01

Receiving Water Bodies	Pollutant
TORRANCE CARSON CHANNEL	Copper
	Indicator Bacteria
	Lead
LOS ANGELES/LONG BEACH INNER HARBOR	Benthic Community Effects
	Benzo(a)pyrene
	Chrysene (C1-C4)
	Copper (sediment)
	DDT (tissue & sediment)
	PCBs
	Toxicity
	Zinc (sediment)

- The topography of the project site is generally flat and primarily under 3% grade. It is an urbanized area, and the local land use is mainly commercial and residential.
- There is no presence of any or anticipated persistent dry weather flow within the project limits.
- The Los Angeles Regional Water Quality Control Board (RWQCB) has the jurisdiction of these project limits.
- 401 Certification is not required for this project.
- The project limits are within the Los Angeles County Municipal Separate Storm Sewer Systems (MS4) area.
- Per-Caltrans Storm Water Quality Handbook Construction Site BMPs Manual (dated March 1,2003), the rainy season is defined as October 1st through May 1st.
- Per-National Oceanic & Atmospheric Administration (National Climate Data Center), the annual average precipitation totals for the project location are 13.67".
- There are no local agency requirements or concerns.
- There are no known areas with present slope stabilization concerns.
- No aerially deposited lead (ADL) soil is expected to be reused within the project limits.
- This project has multiple watersheds with multiple K and LS factors. Therefore, a risk level analysis was made for each watershed. The most conservative risk level (Santa Monica Bay Watershed) was chosen to represent this project.

PPDG July 2023 7 of 27

- The project risk level determination for this project was determined as follows: sediment risk is medium, receiving water risk is high, and the combined risk is level 2. The parameters of the determination were based on: R-factor = 94.55, K-factor = 0.32, LS-factor = 1.26, which were obtained from the Caltrans Water Quality Planning Tool Website, District 7 GIS Website, and the Construction Rainfall Erosivity Waiver, under the guidance of Caltrans Project Risk Level Determination Guidance.
- The construction of this project will utilize measures to avoid or reduce potential storm water impacts by disturbing existing slopes only when necessary and minimizing cut and fill areas to reduce slope lengths.
- Construction is to be scheduled or phased to minimize soil-disturbing work during the rainy season. The rainy season is defined as October 1st through May 1st.
- It is anticipated that this project will be Categorically Exempt/Categorically Excluded by California Environmental Quality Act (CEQA) and National Environmental Policy Act (NEPA)guidelines, respectively.
- There are no drinking water reservoirs or recharge facilities within the project limits.

3. Construction Site BMPs to be used on Project

- This project requires a Storm Water Pollution Prevention Plan (SWPPP) since the disturbed soil area (DSA) of this project is more than 1 acre.
- The project will disturb the underlying soil when reconstructing existing curb ramps and bus pads.
- During construction, the following temporary construction site BMPs will be considered in the project special provisions and incorporated in a separate bid item line.
- The following construction site BMPs that will be included as contract bid items are:
 - Job Site Management (130100)
 - Storm Water Pollution Prevention Plan (SWPPP) (130301)
 - Stormwater Sampling and Analysis Day
 - Stormwater Annual Report
 - Temporary Cover
 - Temporary Drainage Inlet Protection
 - Temporary Fiber Roll
 - Temporary Gravel Bag Berm
 - Street Sweeping
 - Temporary Concrete Washout
- Job Site Management lump sum costs include the following items:
 - Paving, Sealing, Saw Cutting, and Grinding Operations
 - Concrete Curing
 - Concrete Finishing
 - Vehicle and Equipment Fueling
 - Vehicle and Maintenance
 - Concrete Waste Management
 - Hazardous Waste Management
 - Stockpile Management

PPDG July 2023 8 of 27

- Spill Prevention and Control
- Solid Waste Management
- Wind Erosion Control
- Water Control and Conservation
- Sanitary/Septic Waste Management
- Material Delivery and Storage
- Material Use
- Illegal Connection and Illegal Discharge Detection and Reporting
- Supplemental work items for this project include:
 - Water Pollution Control Maintenance Sharing
 - Additional Water Pollution Control
 - Stormwater Sampling and Analysis
- Department Furnished Materials and Expenses for this project include:
 - Annual Construction General Permit Fee
- Dewatering will not be needed for the project.
- Temporary construction site BMPs have been estimated at \$402,290 in accordance with the guidelines of Appendix F, 2023 PPDG.
- Project specific BMP measures will be specified and quantified during the design phase.
- Additional information will be provided during the PS&E phase.
- On April 08, 2024, Arthur Hedayati, District 7 Construction Stormwater Coordinator, agrees to the temporary construction site BMP strategy used (at PAED phase) for the scope of work of this project.

4. Maintenance BMPs

- No maintenance BMPs are required for this project but drain inlets will require stenciling within this project.
- There are existing features (chain link fence with gate) that will assist with maintaining the BMP.
- The existing delegated maintenance agreement(s) between Caltrans and local cities will be assessed and possibly amended in the next project phase. If agreement(s) can't be amended, maintenance may withdraw support for the construction of the proposed TBMP for the project and construct in an alternate location.

5. Other Water Quality Requirements and Agreements

- The Los Angeles Regional Water Quality Control Board (RWQCB) requires all new/major reconstruction projects that increase impervious area to evaluate the feasibility of post construction treatment BMPs as a condition of permit process. It has been determined that this project will not be required to construct any treatment BMPs, due to it being a CAPM project and not exceeding one or more acres of NIS.
- Since the Environmental Document of the project is expected to be Categorically Exemptional requirement from other permits.

PPDG July 2023 9 of 27

6. Treatment Permanent BMPs

In accordance with Deputy Directive DD-92 dated March 17, 2008, this project is required to implement all treatment BMPs recommended in the Corridor Stormwater Management Study (Corridor Study) for State Route 213 (Western Ave) from 25th Street to I-405 (PM 0.00 to PM 10.00) completed in December 2013.

Rapid Stability Assessment

- Not applicable.
- The Caltrans Permit mandates that a Rapid Stability Assessment (RSA) be conducted during
 planning and design for all projects that will include 1 acre or more of Net New Impervious
 (NNI). The Net New Impervious (NNI) for this project is 0.00 acres. Therefore, an RSA will not
 be required for this project.

Design Pollution Prevention (DPP) BMP Strategy

- There will be no increase of velocity or volume of downstream flow within the project limits.
 This Capital Preventive Maintenance Project will not add or modify the existing grade,
 alignment, or profile of the roadway.
- The project will not discharge to lined channels.
- There are no hydraulic changes that may affect the downstream channel stability.
- The existing slopes are stable and vegetated within the project limits. This project will not create new slopes or modify existing slopes.
- Per Caltrans policy, all landscape that is disturbed due to construction will be replaced following Caltrans policy and procedure.
- All runoffs will be directed to the existing road drainage system. Any damaged curb and gutters will be repaired at some locations.
- This project will minimize impacts to the existing vegetation. All disturbed vegetation resulted from construction activities will be replaced following Caltrans policy and procedure.
- Any landscaping that is removed or disturbed by construction related activities will be replaced following Caltrans Replacement Highway Planting Policy.

Treatment BMP Strategy

• The Treatment BMP strategy is to consider the existing site constraints and determine the feasibility of BMP implementation at the site-specific location. The goal for the BMPs is to retain and treat the paved area runoff to the maximum extent practicable (MEP). Treatment BMPs have been evaluated individually for implementation on the project in accordance with the guidelines provided in the Project Planning and Design Guide (PPDG).

PPDG July 2023 10 of 27

Biofiltration Swales

- The biofiltration swale identified by the corridor study at Site #2 has recently been developed into a new housing development and resulted in the widening of a portion of Western Ave. A bioswale behind the back of sidewalk would require a highway easement purchased from the property landowner.
- The biofiltration swale identified by the corridor study at Site #3 may require a highway easement. Further investigation will occur during the PS&E phase.
- The implementation of biofiltration swale identified by the corridor study at Site #5 may require a highway easement. Further investigation will occur during the PS&E phase.
- The biofiltration swale identified by the corridor study at Site #6 is not feasible. The parkway between the sidewalk and curb is too narrow, and the placement of the bioswale behind the back of sidewalk would require a highway easement on private property.

Treatment BMP Strategy - Checklist T-1, Part 1

The pervious vs impervious area breakdown is as follows:

Treated Drainage Area (TDA) Table		
Impervious, w/in Caltrans ROW	1.25	ac
Pervious, w/in Caltrans ROW	0.02	ac
Impervious, not w/in Caltrans ROW	0	ac
Pervious, not w/in Caltrans ROW	0	ac
Total	1.27	ac

Biofiltration Swales - Checklist T-1, Parts 1 and 3

- Site No. 3 biofiltration swale will be incorporated into the project. The paved tributary area for the biofiltration swale is 0.89 acres. The total tributary area for unpaved surfaces is 0.01 acres.
- Site No. 5 biofiltration swale will be incorporated into the project. The paved tributary area for the biofiltration swale is 0.36 acres. The total tributary area for unpaved surfaces is 0.01 acres.

PPDG July 2023 11 of 27

	Table E-1. Overall Project Treatment Summary To	able ¹
	PCTA (ac) ²	A=0.93
	Treated Impervious Area (CT RW) (ac)	B=1.25
	Treated Impervious Area (Outside CT RW) (ac) ³	C=0
Total Area to be Treated	Treated Pervious Area (CT RW) (CUs) (ac)	D=0.02
	Treated Pervious Area (Outside CT RW) (CUs) (ac) ³	E=0
	Stabilized Area (ac) ⁵	G=0
	Alternative Compliance (ac) ⁴	F=(B+C) - A=0.32

- ¹ This table is provided as an example. The table may be edited, altered, or removed as applicable or as directed by the District/Regional Design Stormwater Coordinator.
- ² Provide treatment for ATA 1 even if NIS is less than 10,000 ft².
- Requires Regional Water Quality Control Board approval. Coordinate with District/Regional NPDES Coordinator.
- ⁴ Available Alternative Compliance
 - Negative Value amount of treatment needed through Alternative Compliance.
 - Positive Value amount of treatment available for Alternative Compliance (within the same watershed) as determined by the district.
- 5 surface area disturbed during construction and stabilized through method that is not an impervious surface.


Required Attachments

- Vicinity Map
- Evaluation Documentation Form (EDF)
- Risk Level Determination Documentation
- SWDR Summary Spreadsheets

Supplemental Attachments

- BMP Cost Summary
- Plans showing BMP deployment

PPDG July 2023 12 of 27



13 of 27 PPDG July 2023

DATE: 05/31/2024

Project ID (EA): 0718000076 (346600)

No.	Criteria	Yes	No ✓	Supplemental Information for Evaluation
1.	Begin Project evaluation regarding requirement for implementation of Treatment BMPs		✓	Continue to 2.
2.	Is the scope of the Project to install Treatment BMPs (e.g., Alternative Compliance or TMDL requirement)?		✓	If Yes , go to 8. If No , continue to 3.
3.	Is there a direct or indirect discharge to surface waters?	✓		If Yes , continue to 4. If No , go to 9.
4.	As defined in the WQAR or ED, does the project: a. discharge to areas of Special Biological Significance (ASBS), or		✓	If Yes to any , contact the District/Regional Design Stormwater Coordinator or District/Regional NPDES Coordinator to discuss the Department's obligations, go to 8 or 5.
	b. discharge to a TMDL watershed where Caltrans is named stakeholder, or	✓		
	c. have other pollution control requirements for surface waters within the project limits (e.g. STGA)?	✓		If No to all, continue to 5.
5.	Are any existing Treatment BMPs partially or completely removed?		✓	If Yes , go to 8 AND continue to 6.
	(ATA Condition 1, Section 4.3.1)			If No , continue to 6.
6.	Is this a Routine Maintenance Project?		✓	If Yes , go to 9. If No , continue to 7.
7.	Does the project result in an increase of 10,000 ft ² or more (or 5,000 ft ² for "nonhighway facilities projects") of new impervious surface (NIS)?	~		If Yes , go to 8. If No , go to 9.
8.	Project is required to implement Treatment BMPs.	Complete C	Checklist T-1,	Part 1.
9.	Project is not required to implement Treatment BMPs(Dist./Reg. Design SW Coord. Initials)(Project Engineer Initials)(Date)	Document (for Project Fi	les by completing this form and attaching it to the SWDR.

PPDG July 2023 14 of 27

Rainfall Erosivity R Factor

Construction Project Span: 11/23/26 to 01/31/29

Facility Information

Start Date: 11/23/2026	Latitude: 33.7895	
End Date: 11/22/2027	Longitude: -118.3076	

Calculation Results

Rainfall erosivity factor (R Factor) = 39.43

A rainfall erosivity factor of 5.0 or greater has been calculated for your site's period of construction.

Facility Information

Start Date: 11/23/2027	Latitude: 33.7895
End Date: 11/22/2028	Longitude: -118.3076

Calculation Results

Rainfall erosivity factor (R Factor) = 39.43

A rainfall erosivity factor of 5.0 or greater has been calculated for your site's period of construction.

Facility Information

Start Date: 11/23/2028	Latitude: 33.7895
End Date: 01/31/2029	Longitude: -118.3076

Calculation Results

Rainfall erosivity factor (R Factor) = 15.69


A rainfall erosivity factor of 5.0 or greater has been calculated for your site's period of construction.

The site's overall R factor between November 23, 2026, and January 31, 2029, would be: Overall R Factor = 39.43 + 39.43 + 15.69 = 94.55.

PPDG July 2023 15 of 27

June 2024


K Factor



Project Limit: SR-213 PM 0.00 / PM 10.00

16 of 27 PPDG July 2023

LS Factor



Project Limit: SR-213 PM 0.00 / PM 10.00

PPDG July 2023 17 of 27


Risk Level Determination Documentation

 This project has multiple watersheds with multiple K and LS factors. Therefore, a risk level analysis was made for each watershed. The most conservative risk level (Santa Monica Bay Watershed) was chosen to represent this project.

Sediment Risk Factor Worksheet Entry A) R Factor Analyses of data indicated that when factors other than rainfall are held constant, soil loss is directly proportional to a rainfall factor composed of total storm kinetic energy (E) times the maximum 30-min intensity (I30) (Wischmeier and Smith, 1958). The numerical value of R is the average annual sum of El30 for storm events during a rainfall record of at least 22 years. "Isoerodent" maps were developed based on R values calculated for more than 1000 locations in the Western U.S. Refer to the link below to determine the R factor for the project site. http://cfpub.epa.gov/npdes/stormwater/LEW/lewCalculator.cfm 94.55 R Factor Value B) K Factor (weighted average, by area, for all site soils) The soil-erodibility factor K represents: (1) susceptibility of soil or surface material to erosion, (2) transportability of the sediment, and (3) the amount and rate of runoff given a particular rainfall input, as measured under a standard condition. Fine-textured soils that are high in clay have low K values (about 0.05 to 0.15) because the particles are resistant to detachment. Coarse-textured soils, such as sandy soils, also have low K values (about 0.05 to 0.2) because of high infiltration resulting in low runoff even though these particles are easily detached. Medium-textured soils, such as a silt loam, have moderate K values (about 0.25 to 0.45) because they are moderately susceptible to particle detachment and they produce runoff at moderate rates. Soils having a high silt content are especially susceptible to erosion and have high K values, which can exceed 0.45 and can be as large as 0.65. Silt-size particles are easily detached and tend to crust, producing high rates and large volumes of runoff. Use Site-specific data must be submitted. Site-specific K factor guidance 0.32 K Factor Value C) LS Factor (weighted average, by area, for all slopes) The effect of topography on erosion is accounted for by the LS factor, which combines the effects of a hillslope-length factor, L, and a hillslope-gradient factor, S. Generally speaking, as hillslope length and/or hillslope gradient increase, soil loss increases. As hillslope length increases, total soil loss and soil loss per unit area increase due to the progressive accumulation of runoff in the downslope direction. As the hillslope gradient increases, the velocity and erosivity of runoff increases. Use the LS table located in separate tab of this spreadsheet to determine LS factors. Estimate the weighted LS for the site prior to construction. LS Table 1.26 LS Factor Value Waters hed Erosion Estimate (=RxKxLS) in tons/acre 38.12256 Site Sediment Risk Factor Low Sediment Risk: < 15 tons/acre Medium Medium Sediment Risk: >=15 and <75 tons/acre High Sediment Risk: >= 75 tons/acre

PPDG July 2023 18 of 27

Receiving Water (RW) Risk Factor Worksheet	Entry	Score
A. Watershed Characteristics	yes/no	
A.1. Does the disturbed area discharge (either directly or indirectly) to a 303(d)-listed waterbody impaired by sediment (For help with impaired waterbodies please visit the link below) or has a USEPA approved TMDL implementation plan for sediment?: http://www.waterboards.ca.gov/water_issues/programs/tmdl/integrated2010.shtml		
OR A.2. Does the disturbed area discharge to a waterbody with designated beneficial uses of SPAWN & COLD & MIGRATORY? (For help please review the appropriate Regional Board Basin Plan)	no	Low
http://www.waterboards.ca.gov/waterboards_map.shtml		e
Region 1 Basin Plan		
Region 2 Basin Plan		
Region 3 Basin Plan		
Region 4 Basin Plan		
Region 5 Basin Plan		
Region 6 Basin Plan		
Region 7 Basin Plan		
Region 8 Basin Plan		
Region 9 Basin Plan		



Project Sediment Risk:	Medium
Project RW Risk:	Low
Project Combined Risk:	Level 2

PPDG July 2023 19 of 27

ody ody	(0)
TMD	Yes
DSA (ac)	6.25
Risk Level	RL2
Long	Yes
Project Long Risk DSA TMDL Phase SWDR Level (ac) Waterbo	PA/ED Yes RL2 6.25
D County Route Beg_PM End_PM Project Project Long Risk DSA TMDL Description Phase SWDR Level (ac) Waterbody	Capital Preventative Maintenance Project (CAPM)
End_PM	LA 213 0.00 10.00
Beg_PM	0.00
Route	213
County	ΓĄ
SWDR District EA/ Project ID Signed Date	346600/ 0718000076
District	
SWDR Signed Date	

TST		0
Infiltration Infiltration GSRD IS GSRD LR Capture Trash Net		0
Capture	Housing	0
GSRD LR		0
GSRD IS		0
Infiltration	Gallery	0
Infiltration	Trench	0
Infiltration	Basin	0
Detention		0
Bio	Retention	0
Bio	Swale	2
Bio	Strip	0

Net New	Impervious	area (NNI)	(ac)	0.00
New	Impervious Impervious	Surface (NIS) area (NNI)	(ac)	0.93
Est. Est. Const New	_Comp			1/31/2029
	BMP Const_Start _Comp			11/23/2026 1/31/2029 0.93
Other	BMP			0
OGFC				0
DPPIA				0
Compost DPPIA OGFC Other	Media			0
ustin Vault Delaware Austin/Del C	Sand Filter			0
Delaware	Media			0
Austin Vault	Med Filter Media Sand Filter			0

N/A	No	No No	00'0	0.02	0.32	1.25	0.93	00'0	0.93
					(ac)				
					Balance				
				Area (ac)	Area	Area (ac)	Area (ac)	(ATA) (ac)	Surface (RIS) (ac)
Comment			Area (ac)	Pervious	Impervious Impervious Pervious Area (ac)	Impervious	Treatment	Treatment Area	Impervious
SW	RSA	MWELO	Stabilized	Treated	Post Const Treated Treated Treated Stabilized MWELO RSA	Treated	Post Const	Additional	Replaced

20 of 27 PPDG July 2023

	d d	340		340	
	Longitude (d.ddddd	-118.3098		-118.3088	
LocEPM End Latitude	(a.aaaaa)	33.781640 -118.309840		33.821520 -118.308840	
LocEPM		4.50		7.26	
Begin	Longitude (d.ddddd)	33.781640 -118.309840		213 7.26 33.821520 -118.308840	
-	Latitude (d.ddddd)	33.781640		33.821520	
LocBPM		4.50)	7.26	
Route		213		213	
County		LA		ΓA	
District		2		2	
EA/ Project ID BMP Type (IMMS District County Route LocBPM	Abbreviation)	Biofiltration Swale	(BIOSWL)	346600/ 346600/ Biofiltration Swale	(BIOSWL)
EA/ Project ID		346600/	0718000076	346600/	0718000076
ONGI		/009978	0718000076-1 0718000076	346600/	0718000076-2 0718000076 (BIOSWL)

WQF (cfs)	0.18	0.07
WQV (cf)	2,448	1,005 0.07
Treated Pervious Area (ac Outside CT R/W)	00'0	00.00
Treated Pervious Area (ac CT R/W)	0.01	0.01
ed Impervious Treated Impervious Treated Pervious Treated Pervious (ac CT R/W) Area (ac Outside CT R/W) Area (ac Outside CT R/W) CT R/W)	00'0	00.00
Direction Sand Trash Storage BMP Treated Impervious Treated Impervious Treated Impervious Treated Pervious Treated Pervious Treated Pervious WQV (cf) WQF (cfs) Storage Volume (cyd) Specific Area (ac CT R/W) Area (ac Outside ac CT R/W) CT R/W)	0.89	0.36
BMP Specific Comments	BSW 3	BSW 5
Sand Trash Storage BMP Treate Storage Volume (cyd) Specific Area Volume Comments	00'0	00'0
Sand Storage Volume (cyd)	00'0	00'0
Direction	S	S

FCV (cf)	FCF (cfs)	FCV (cf) FCF (cfs) Basis of BMP Stabilized	Stabilized	TMDL	BMP Capital Cost	BMP Capital Cost Watershed (HSA & #)	RWB
		(non 402)	Alea (ac)	waterboury			
00.00	00.0	N/A	00'0	Yes	\$73,440	Frontal Santa Monica Los Angeles	Los Angeles
						Bay-San Pedro Bay (Region 4)	(Region 4)
00.00	0.00 0.00	N/A	00'0	Yes	\$30,150	Dominguez Channel Los Angeles	Los Angeles
							(Region 4)

21 of 27 PPDG July 2023

Project Name:	Capital Preventative Maintenance Project
District:	7
Project ID (EA):	0718000076 (34660)
County:	Los Angeles
Route:	SR-213
Postmile:	0.00
End Postmile:	10.00

Permanent Storm Water BMPs

Treatment	\$ 103,590
Design Pollution Prevention	\$ -
Total	\$ 103,590
Construction Site BMPs	
Soil Stabilization	\$ -
Sediment Control	\$ 85,000
Wind Erosion Control	\$ 21,000
Tracking Control	\$ -
Waste Management & Materials Handling	\$ 35,000
Non-Storm Water Management	\$ -
Miscellaneous	\$ 39,200
Supplemental Items	\$ 115,000
Total	\$ 298,700
TOTAL STORM WATER BMPs	\$ 402,290

PPDG July 2023 22 of 27

Project ID (EA): 0718000076 (07-34660)

Treatment BMPs

BEES	Pollution Prevention BMPs PPDG Appendix A	Quantity	Unit	Unit Cost (\$/Unit)	Cost	(\$)
	Biofiltration Strip					
	Biofiltration Swale	2	LS		\$	103,590
	Dry Weather Diversion					
	Infiltration Devices (Trench)					
	Infiltration Devices (Basin)					
	DPP Infiltration Area					
	Detention Devices					
	Gross Solid Removal Devices					
	LR-1-(4'-0") GSRD	0	EA	\$0	\$	-
	LR(HV)-3-(6'-0") GSRD	0	EA	\$0	\$	-
	INCLINED SCREEN TYPE D GSRD	0	EA	\$0	\$	-
	Traction Sand Traps					
	Media Filters (Austin)					
	S-3500-3	0	EA	\$0	\$	-
	Media Filters (Delaware)					
	Wet Basins					
	Multi Chamber Treatment Train (MCTT)					

Total \$ 103,590

Design Pollution Prevention BMPs

<u>J</u>	Pollution Prevention BMPs			Unit Cost	Cost
BEES	PPDG Appendix A	Quantity	Unit	(\$/Unit)	(\$)
	Downstream Effects/Increased Flow Mitigation				
	Slope/Surface Protection Systems- Hard Surfaces				
	Slope/Surface Protection Systems- Vegetated Surfaces				
	Concentrated Flow Conveyance Systems				

Total \$ -

Total Permanent Storm Water BMPs \$ 103,590

PPDG July 2023 23 of 27

Project ID (EA): 0718000076 (07-34660)

Construction Site BMPs

BEES	Temporary Soil Stabilization BMPs	Quantity	Unit	Unit Cost (\$/Unit)	Cost (\$)
Soil Stal	bilization BMPs	_			
	Scheduling		EA		
130505	Move-In/Move-out (Temporary Erosion Control)		EA		\$ -
	Preservation of Exist Vegetation		EA		
141000	Temporary Fence (Type ESA)		LF		\$ -
	Hydraulic Mulch		EA		
130520	Temporary Hydraulic Mulch		SQYD		\$ -
130550	Temporary Hydroseed		SQYD		\$ -
	Hydroseeding		SQFT		
	Compost (Incorporate)		SQYD		\$ -
	Soil Binders				
130560	Temporary Soil Binder		SQYD		\$ -
	Temporary Soil Stabilizer		SQYD		\$ -
	Straw Mulch				
130540	Temporary Tacked Straw		SQYD		\$ -
	Geotextiles, Mats/Plastic Covers & Erosion Control Blankets				
130500	Erosion Control Blankets/Mats		SQYD		\$ -
130570	Temporary Cover		SQYD		\$ -
	Wood Mulching		CY		
130510	Temporary Mulch		SQYD		\$ -

PPDG July 2023 24 of 27

	Storm water biving	, Janinin	u. y			
BEES	Temporary Soil Stabilization BMPs	Quantity	Unit	Unit Cost (\$/Unit)		Cost (\$)
Sedimen	t Control BMPs					
	Silt Fence					
130680	Temporary Silt Fence		LF		\$	-
	Sediment/Desilting Basin					
	Sediment Trap					
	Check Dams					
130610	Temporary Check Dams		LF		\$	-
	Fiber Rolls					
130640	Temporary Fiber Rolls	1000	LF	\$5	\$	5,000
130660	Temporary Large Sediment Barrier		LF		\$	-
	Gravel Bag Berm					
130650	Temporary Gravel Bag Berm		LF		\$	-
	Street Sweeping and Vacuuming					
130730	Street Sweeping	1	LS	\$50,000	\$	50,000
	Sandbag Barrier					
	Straw Bale Barrier					
130690	Temporary Straw Bale Barrier		LF		\$	-
	Storm Drain Inlet Protection					
130620	Temporary Storm Drain Inlet Protection	100	EA	\$300	\$	30,000
					\$	85,000
Wind Ero	osion Control BMPs					
	Wind Erosion Control					
130720	Temporary Construction Roadway		CY	. –	\$	-
130570	Temporary Cover	3000	SQYD	\$7	\$	21,000
Tracking	Control BMPs				\$	21,000
Tuoking	Stabilized Construction Entrance/Exit					
130710	Temporary Construction Entrance		EA		\$	_
100710	Stabilized Construction Roadway				*	
130720	Temporary Construction Roadway		LS		\$	-
100.20	Entrance/Outlet Tire Wash				+	

\$ -

PPDG July 2023 25 of 27

JSM* C JSM* F JSM* V JSM* V JSM* C	Dewatering Operations Paving & Grinding Operations Temporary Stream Crossing Vehicle and Equipment Cleaning Vehicle and Equipment Fueling Concrete Curing Material & Equipment Use Over Water Structure Demolition/Removal Over or Adjacent to Water Street Sweeping		LS		\$	-
JSM* F JSM* V JSM* V JSM* C	Paving & Grinding Operations Temporary Stream Crossing Vehicle and Equipment Cleaning Vehicle and Equipment Fueling Concrete Curing Material & Equipment Use Over Water Structure Demolition/Removal Over or Adjacent		LS		\$	<u>-</u>
JSM* \\ JSM* \\ JSM* \\ JSM* \C	Temporary Stream Crossing Vehicle and Equipment Cleaning Vehicle and Equipment Fueling Concrete Curing Material & Equipment Use Over Water Structure Demolition/Removal Over or Adjacent to Water		LS		\$	-
JSM* \\ JSM* \\ JSM* \C	Vehicle and Equipment Cleaning Vehicle and Equipment Fueling Concrete Curing Waterial & Equipment Use Over Water Structure Demolition/Removal Over or Adjacent to Water		LS		\$	-
JSM* V	Vehicle and Equipment Fueling Concrete Curing Material & Equipment Use Over Water Structure Demolition/Removal Over or Adjacent to Water					
JSM* C	Concrete Curing Material & Equipment Use Over Water Structure Demolition/Removal Over or Adjacent to Water					
	Material & Equipment Use Over Water Structure Demolition/Removal Over or Adjacent to Water					
JSM* N	Structure Demolition/Removal Over or Adjacent to Water					
	o Water					
	Street Sweeping					
130730 5						
					\$	-
	nagement & Materials Handling BMPs	1				
	Material Delivery and Storage					
	Material Use					
JSM* S	Spill Prevention and Control					
JSM* S	Solid Waste Management					
JSM* C	Concrete Waste Management					
T	Temporary Concrete Washout (Portable)	1	LS	\$35,000	\$	35,000
Т	Temporary Concrete Washout Bin		EA		\$	-
JSM* S	Sanitary/Septic Waste Management		LS			
JSM* L	Liquid Waste Management		LS			
Miscellane	ous Items				\$	35,000
	Job Site Management	1	LS	\$10,000	\$	10,000
	Prepare Water Pollution Control Program		LS	4107000	\$	-
	Prepare Storm Water Pollution Prevention Plan	1	LS	\$10,000	\$	10,000
	Rain Event Action Plan	10	EA	\$1,000	\$	10,000
	Storm Water Annual Report	2	EA	\$3,000	\$	6,000
	Storm Water Sampling and Analysis Day	1	EA	\$3,200	\$	3,200
	Temporary Active Treatment System		LS	+5,200	\$	-
	Water Quality Sampling and Analysis Day		EA		\$	_
	Water Quality Monitoring Report		EA		\$	_
	Water Quality Annual Report		EA		\$	_
F	Relations With California Regional Water Quality Control Board				*	
	Order of Work					

\$ 39,200

PPDG July 2023 26 of 27

BEES	Temporary Soil Stabilization BMPs	Quantity	Unit	Unit Cost (\$/Unit)	Cost (\$)
Supplem	ental Items				
066596	Additional Water Pollution Control	1	LS	\$10,000	\$ 10,000
066595	Water Pollution Control Maintenance Sharing	1	LS	\$100,000	\$ 100,000
066597	Storm Water Sampling and Analysis	1	LS	\$5,000	\$ 5,000
	Receiving Water Bioassessment (RL 3)		LS		\$ _
					\$ 115,000
Departme	ent Furnished Materials and Expenses				
066916	Annual Construction General Permit Fee	1	LS	\$3,500	\$ 3,500

\$ 3,500

Total Construction Site BMPs \$ 298,700

PPDG July 2023 27 of 27

Appendix O Summary of Hydraulics of Flow Based BMPs along the SR-213 Corridor

													WQF				٥	Ω ₂₅	
Top Bottom	Top Bottom	Bottom	Bottom	Bottom		Side							Water					Water	
Future Recommended Length ¹ Width ²	Recommended Length Width Width Slope Slope Runoff C	Length ¹ Width ² Width ³ Slope ⁴ Slope ⁵ Runoff C	Width ² Width ³ Slope ⁴ Slope ⁵ Runoff C	Width ³ Slope ⁴ Slope ⁵ Runoff C	Slope ⁴ Slope ⁵ Runoff C	Slope ⁵ Runoff C	Runoff C		Runoff C	<u>_</u>		WQF	Depth ¹⁰	Velocity ¹¹	HRT ¹²	10min 13	Ω ₂₅ ¹	Depth ₁₀	Velocity ¹⁵
	BMP (ft) (ft) (ft) % (paved) ⁶ (unpaved) ⁷	(ft) (ft) (H:V) % (paved) ⁶ (unpaved) ⁷	(ft) (ft) (H:V) % (paved) ⁶ (unpaved) ⁷	(ft) (H:V) % (paved) ⁵ (unpaved) ⁷	(H:V) % (unpaved) ⁷	% (paved) ⁶ (unpaved) ⁷	(unpaved) ⁷	(unpaved) ⁷	7	(in/hr)		(ft³/s)	(ft)	(£Ą\$)	(min)	(in/hr)	(ft³/s)	(ft)	(ft/s)
Avenue Aprenda Y Biofitration Swale 50.0 11.5 4.0 4.0 0.30 1.00 0.90 0.20	50.0 11.5 4.0 4.0 0.30 1.00 0.90	50.0 11.5 4.0 4.0 0.30 1.00 0.90	11.5 4.0 4.0 0.30 1.00 0.90	4.0 4.0 0.30 1.00 0.90	4.0 0.30 1.00 0.90	0.30 1.00 0.90	1.00 0.90	06:0		0.20		0.43	0.41	0.16	5.0	2.04	4.37	0.61	96'0
Leesdale Ave Y Biofiltration Swale 100.0 6.5 4.0 3.0 4.00 1.00 0.90 0.2	100.0 6.5 4.0 3.0 4.00 1.00 0.90	100.0 6.5 4.0 3.0 4.00 1.00 0.90	6.5 4.0 3.0 4.00 1.00 0.90	4.0 3.0 4.00 1.00 0.90	3.0 4.00 1.00 0.90	4.00 1.00 0.90	1.00 0.90	06:0		0	0.20	0.18	0.14	0.31	5.0	2.17	1.96	0.22	1.97
Lincoln Ave N Biofiltration Swale 50.0 6.0 2.0 4.0 1.00 1.00 0.90 0.	50.0 6.0 2.0 4.0 1.00 1.00 0.90	50.0 6.0 2.0 4.0 1.00 1.00 0.90	6.0 2.0 4.0 1.00 0.90	2.0 4.0 1.00 0.90	4.0 1.00 0.90	1.00 1.00 0.90	1.00 0.90	06:0		٥	0.20	70.0	0.17	0.16	5.0	2.24	0.83	0.27	1.01
220th St Y Biofiltration Swate 50.0 6.0 2.0 4.0 1.00 1.00 0.90 0	50.0 6.0 2.0 4.0 1.00 1.00 0.90	50.0 6.0 2.0 4.0 1.00 1.00 0.90	6.0 2.0 4.0 1.00 1.00 0.90	2.0 4.0 1.00 0.90	4.0 1.00 0.90	1.00 1.00 0.90	1.00 0.90	0.90		0	0.20	0.04	0.13	0.14	0.9	2.25	0.47	0.20	0.85

1. For biofiltration strips, the length is the distance along the shoulder or lateral length. For biofiltration swales, the length is the distance along the shoulder or lateral length. For biofiltration swales, the length is 0.5 ft. For biofiltration swale be top width is the distance along the sheet flow direction. For biofiltration swales, it is the top width of the channel.

3. For a trapezoidal bioswale, bottom width is 2.0 ft to 10 ftper PPDG Table B-1.

4. Side sope ratio should be 14/4/H) or flatter per PPDG Table B-1.

5. Slope in the direction of flow, Minimum 0.25%, maximum 6%, with 1 to 2% preferred per PPDG Table B-1.

6. Runoff coefficient for paved area set as 1.0 per the Shipulation and Order for the Conridor Stormwaler Management Studies, dated January 17, 2008.

7. Runoff coefficient for paved area from Highway Design Manual Table 819.2A, taken as the upper limit of the "Normal" classification.

7. Runoff coefficient for paved area from Highway Design Manual Table 819.2A, taken as the upper limit of the "Normal" classification.

8. Ratial Inhamstyl) is 0.2Phri in Region 4. Low Angeles), PPOG Seedon 2.4.2.2

9. Water Quality Flow (WOF) = C_{20x} 1 "Area _{20xe} 4" C_{20xe} 1" Area _{20xe} 4" C_{20xe} 4" Area _{20xe} 4

11. Velocity = WQFA, where A is the cross sectional area. Maximum velocity is 10fts per PPDG Table B-1.

12. Hydraulic Residence Time (HRT) is the time during which the WQF travels in the swale or sirp. Minimum HRT is 5 min for boilitration swales per PPDG Table B-1; no HRT requirement for biofitration sirps per PPDG Table B-1.

13. Rankal Intensity of 10 min and 25-year return per Los Angeles County Hydrology Manual.

14. Qa. S_{count} 1 from "Artega_{woot} + C_{counter}" 1 from "Artega_{woot} + C_{counte}



Figure 3 Site 3, Biofiltration Swale, North View





Figure 4 Site 3, Biofiltration Swale, North View




Figure 5 Site 5, Biofiltration Swale, North View



Figure 6 Site 5, Biofiltration Swale, South View





TRANSPORTATION MANAGEMENT PLAN DATA SHEETAttachment H

TRANSPORTATION MANAGEMENT PLAN DATA SHEET (Revised TMP Elements and Costs)

Co-Rte-PM	LA-213-0.0/10.0 EA/EFIS 346600/0718000076	Alt. No. PA&ED	
Project Limit	Route 213 (Western Ave) from 25th Street to Route 405	•	
Project Descri	ption CAPM and ADA curb-ramps upgrade project		
I) Pub	olic Information		
a. Brochures and Mailers		\$	
	🔀 b. Press Release		
C. Paid Advertising		\$150,000	
d. Public Information Center/Kiosk		\$	
	f. Telephone Hotline		
	g. Internet		
	h. Others Fact sheets and fliers	\$	
2) Mo	torists Information Strategies		
	a. Changeable Message Signs (Fixed)	\$	
	b. Changeable Message Signs (Portable)	\$185,500	
	c. Ground Mounted Signs	\$	
·	d. Highway Advisory Radio	\$	
	e. Caltrans Highway Information Network (CHIN)	•	
	f. Others	\$	
3) Inci	dent Management		
	a. Construction Zone Enhanced Enforcement		
	Program (COZEEP)	\$84,000	
	b. Freeway Service Patrol	\$	
	c. Traffic Management Team		
	d. Helicopter Surveillance	<u>\$</u>	
•	e. Traffic Surveillance Stations	¢.	
	(Loop Detector and CCTV) f. Others	<u> </u>	
		\$	

b. Others	\$
a. Application of New Technology	\$
7) Other Strategies	
e. Others	\$
d. Parking Restrictions	Ψ
c. Traffic Control Officers	\$
b. Street Improvement (widening, traffic signal etc)	\$
a. Add Capacity to Freeway Connector/Ramps	\$
6) Alternative Route Strategies	*
h. Others	\$
g. Ramp Metering (Modify Existing)	<u>\$</u>
f. Ramp Metering (Temporary Installation)	\$
e. Telecommute	
d. Variable Work Hours	Ψ
c. Rideshare Incentives	\$
b. Park and Ride Lots	\$ \$
a. HOV Lanes/Ramps (New or Convert)	\$
5) Demand Management	Φ
k. Others	\$ \$
j. Moveable Barrier	\$
i. Incentive and Disincentive	\$
h. Connector and Ramp Closures	\$Design to include
g. Reduced Speed Zone	
f. Truck Traffic Restrictions	\$
d. Extended Weekend Closure e. Contra Flow	
c. Total Freeway Mainline Closure	
b. Reversible Lanes	
a. Lane Closure Chart	

1. Project Information:

The approved TMP Data Sheet dated February 23, 2024 has been revised to reflect Design's decision to place temporary barrier systems in both direction of Route 213 in segments where the raised median island will be reconstructed.

The following project information was provided by the Office of Design on February 9, 2024:

- Estimated total project cost: \$26,000,000
- Estimated begin construction date: 11/23/2026
- Estimated construction duration: 26 months

2. Public Information:

David White from the Office of Public Affairs & Media Relations determined on March 13, 2024 that the Public Awareness Campaign (PAC) will involve press releases, possible fact sheets, fliers, web notices and possible paid advertising. Include The PAC cost estimate of \$150,000 for possible paid advertising in State Furnished Materials, BEES Item #066063. Construction will notify Caltrans' Office of Public Affairs & Media Relations a minimum of one month prior to the start of construction to commence the PAC. Additionally, all project road closure information will be made available to the public via the Caltrans internet website at http://www.dot.ca.gov > Click "Travel" > Click "Lane Closures."

3. Motorists Information Strategies:

Portable changeable message signs (PCMS) will be utilized to inform motorists prior to and during construction activities along Route 213. Funding for PCMS cost estimate of \$185,500 should be added to Traffic Control System in BEES Item #120100.

4. Incident Management:

The Construction Traffic Advisor Joe Hernandez provided a Construction Zone Enhanced Enforcement Program (COZEEP) cost estimate of \$84,000 on March 21, 2024. Include COZEEP funding in State Furnished Materials, BEES Item #066062.

5. Construction Strategy:

To improve worker and public safety on State Highway System, Caltrans' policy issued on April 19, 2019 requires a ten miles per hour (10 mph) speed limit reduction in the work zones. Design should perform an assessment and allocate necessary funds for any construction work zone speed limit reduction bid items.

- The Office of District Traffic Manager will notify the Cities of Los Angeles, Rancho Palos Verdes, Lomita and Torrance about this project during Design phase.
- 7. Work shall conform to the lane requirement charts that will be included in the Maintaining Traffic Specifications. Any changes to the scope of the project that will result in different types of traffic lane closures than anticipated will require a re-evaluation of TMP cost and strategies.

PREPARED BY	Julio C. Valdez, Transportation Engineer	DATE	03/21/2024
APPROVAL RECOMMENDED BY	Alam	DATE	03/21/2024
APPROVED BY	Mohammad Islam, Acting Senior Transportation Engineer	DATE	03/22/2024
	Kenneth Young, Distrct Traffic Manager		

Page 3 of 3



March 13, 2024 EFIS 0718000076 EA 346600

Public Awareness Campaign

SR-213 Resurfacing Project Between I-405 & 25th Street Revised II

1. Press Release:

Announcing upcoming project may be sent to local media outlets, elected officials & others if needed. Press Release may include:

- Start of work
- · Explanation of project
- Lane closures
- Completion
- 2. Fact Sheets, Fliers or Web Notices
 - · May be utilized as needed
- 3. Possible Caltrans PY Hours 30
- 4. Possible Paid Advertising
- 5. Funding Elements
 - Advertising \$150,000

David P. White Office of Public Affairs & Media Relations (213) 897-3656

MEMORANDUM

TO:

JULIO VALDEZ

FROM:

JOE HERNANDEZ, CONSTRUCTION TRAFFIC ADVISOR

SUBJECT:

COZEEP COST ESTIMATE, PROJECT # EA 346600

LA-213 - PM 0/10.0

INSTALL ADA RAMPS, AC PAVEMENT OVERLAY AND OTHER

IMPROVEMENTS

DATE:

3/21/2024

CC:

TMP ESTIMATE FILES

After reviewing the project plans and scope of work including the proposed changes of Krail and as indicated in the memo dated February 13, 2024, the estimated \$84,000 will be sufficient for COZEEP services.

The estimate will provide approximately 640 hours of COZEEP services for the project. The estimate is derived by estimating 40 shifts at 16 hours per shift and 100% of the COZEEP resourcing will be for nighttime closures.

640 hrs. @ \$130.00 per hour = \$83,200.00 call it \$84,000.00.

If you have any questions or comments, please call me at (213) 793-9065.

MATERIALS ENGINEERING RECOMMENDATION – Attachment I

Memorandum

To: JOSEPH REYNOZA Date: March 29, 2024

Senior Transportation Engineer, PE District 7 Maintenance Engineering West Region

West Region File: 07-LA-213 PM 0.0/10.0 Attn: Kin Seng Wong EA 07-34660

EFIS 0718000076

Sona Juharyan Transportation Engineer, Range D Materials Engineering Office Engineering Services

Subject: MATERIALS RECOMMENDATION UPDATED SCOPE OF CHANGE

This Materials Recommendation supersedes to the recommendation provided on January 9, 2024. Materials has reviewed the above-mentioned project and has the following recommendation:

- 1. The proposed pavement section Type 2 on the Typical Cross Sections X-1 and X-2 shall reflect the following information.
 - A. For existing AC layers more than or equal to 0.30'

Cold plane 0.15' of the existing AC layer Overlay with 0.15' of Rubberized Hot Mix Asphalt Gap Graded (RHMA-G)

B. For existing AC layers more than or equal to 0.35',

Cold plane 0.20' of the existing AC layer

Overlay with 0.20' of Rubberized Hot Mix Asphalt – Gap Graded (RHMA-G)

C. For existing AC layer less than 0.30'

Cold plane the full depth of the existing AC layer Overlay with Hot Mix Asphalt – Type A (HMA-A).

GENERAL NOTES:

- After cold planning, the existing AC layer must remain at least 0.15' thick for stability.
- Digouts not exceeding 20 percent of the CAPM pavement costs may be included. Please see attached construction details for digout
- Transition Taper Slopes should be 200:1 or flatter, follow HDM Section 673.1 for tapering into existing pavement or structure.

[&]quot;Provide a safe and reliable transportation network that serves all people and respects the environment"

December 21, 2023 EA 34660 (EFIS 0718000076) Page 2 of 2

2. Pavement Section for Raised Island Removal and reconstruction:

TI = 10: R-Value = 15

0.20' Rubberized Hot Mix Asphalt – Gap Graded (RHMA-G)

0.25' Hot Mix Asphalt, Type A (HMA-A)

0.50' Lean Concrete Base (LCB)

0.90' Aggregate Base, Class 3 (AB, Cl3)

1.85' Total

- Lean Concrete Base Rapid Setting (LCB-RS) can be used as a substitute for LCB to satisfy the construction window.
- The newly replaced HMA section should be at least 2 feet in width from the edge of the curb ramp gutter.
- Extend the base and subbase layers of the new pavement section underneath the new constructed curb ramp gutter (modified curb ramp gutter recommended below).
- Where the proposed curb ramps do not impact the grading of the adjacent pavement, Materials highly recommends saw cutting the existing pavement to the exact footprint of the curb ramp/curb and gutter and constructing the new curb ramps/curb and gutter to match the existing pavement grade as closely as possible. It is recommended to not disturb the adjacent pavement wherever possible.
- 3. Modified Curb Ramp Gutter

0.50' Minor Concrete

0.50' Lean Concrete Base (LCB)

0.90' Aggregate Base, Class 3 (AB, Cl3)

1.90' Total

- The above modified gutter section should be used at locations where it
 is anticipated that vehicles may off-track into the gutter. This section is
 recommended at ADA curb ramp locations.
- Gutters in other areas where off-tracking of vehicles is not expected to occur (not expected for use on this project) may be constructed with 0.50' Minor Concrete over 0.50' AB, Cl3.
- **4.** Revise the proposed pavement section Type 1 on the Typical Cross Sections X-1 and X-2 to read as follows for sidewalk.

0.35' minor Concrete 0.35' AB, Class 3

 AB Class 3 may be removed if native soil has sand equivalent of 20 or more determined by CT 217F.

[&]quot;Provide a safe and reliable transportation network that serves all people and respects the environment"

December 21, 2023 EA 34660 (EFIS 0718000076) Page 3 of 2

- **5.** Curb Ramp at pedestrian 0.35' Minor Concrete 0.35' AB, Class 3
- 6. Curb Ramp at Driveway
 0.50' Minor Concrete
 0.50' AB, Class 3
- **7.** Bus Pad

0.85' Jointed Plain Concrete Pavement (JPCP) 0.50' AB, Class 3

Please submit the design plans include Typical Cross Sections and corresponding construction details for our next review during PS&E stage.

If you have any questions, please email me at sona.juharyan@dot.ca.gov or call me at (213) 269-0866. This project was peer reviewed by Min Deng.

Sona Juharyan, PE Materials Engineering

PAVEMENT CONDITION SURVEY – Attachment J

PaveM Scenario Used: #3625 APCS Data Year: 2021 Using: Prior-Treatment Distresses

Caltrans Pavement Program Pavement Condition Detailed Report (PaveM)

District: 7; County: Los Angeles (LA); Route: 213 From PM: 0.000 To PM: 9.984

Year: 2021 (Current) R-Length: 9.984. L-Length: 9.984
R-Lane Miles: 20.898. L-Lane Miles: 21.968 (Unknown lane miles: 0.000)

			Concrete				Asphalt			144D 24			Estimated
Pavement Segment	Lane	Type			- 1	Alligator IRI in		IRI in/mi				Lane	
-			1st%	3rd%	Fault%	A%	В%	Rut (in)		Condition	Condition	Class	Mile
Post Mile: 0.000 to 1.700	L1	Flexible				11.30	1.00	0.13	165	Fair	Yellow	2	1.76
Post Mile: 0.000 to 1.769 Length: 1.769	L2	Flexible				5.70	1.00	0.11	124	Fair	Yellow	2	1.76
9	R1	Flexible				13.10	1.00	0.13	154	Fair	Yellow	2	1.76
Estimated Lane Mileage: 7.076	R2	Flexible				18.40	2.00	0.12	151	Fair	Yellow	2	1.76
Post Mile: 1.769 to 3.458	L1	Flexible				16.60	0.00	0.14	189	Fair	Blue	2	1.6
Length: 1.689	L2	Flexible				23.20	1.00	0.13	154	Fair	Yellow	2	1.6
Estimated Lane Mileage: 6.756	R1	Flexible				12.90	0.00	0.13	183	Fair	Blue	2	1.6
Estimated Lane Mileage. 6.756	R2	Flexible				20.10	3.00	0.15	160	Fair	Yellow	2	1.68
Post Mile: 3.458 to 5.085	L1	Flexible				9.40	0.00	0.23	168	Fair	Yellow	2	1.6
	L2	Flexible				6.20	1.00	0.21	159	Fair	Yellow	2	1.6
Length: 1.627 Estimated Lane Mileage: 6.508	R1	Flexible				4.60	0.00	0.21	187	Fair	Blue	2	1.6
Estimated Lane Mileage. 0.308	R2	Flexible				2.60	0.00	0.18	198	Fair	Blue	2	1.6
Post Mile: 5.085 to 5.667	L1	Flexible				3.80	0.00	0.21	166	Fair	Green	2	0.5
Length: 0.582	L2	Flexible				1.90	0.00	0.20	151	Fair	Green	2	0.5
Estimated Lane Mileage: 2.328	R1	Flexible				1.50	0.00	0.21	177	Fair	Blue	2	0.5
Estimated Lane Mileage. 2.328	R2	Flexible				2.20	0.00	0.21	159	Fair	Green	2	0.5
Post Mile: 5.667 to 6.996	L1	Flexible				3.60	0.00	0.18	175	Fair	Blue	2	1.3
Length: 1.329	L2	Flexible				2.70	0.00	0.18	138	Fair	Green	2	1.3
Estimated Lane Mileage: 5.316	R1	Flexible				2.00	0.00	0.21	204	Fair	Blue	2	1.3
Estimated Lane Willeage. 5.510	R2	Flexible				7.70	0.00	0.20	166	Fair	Yellow	2	1.3
Post Mile: 6.996 to 7.984	L1	Flexible				2.10	0.00	0.20	165	Fair	Green	2	0.9
Length: 0.988	L2	Flexible				4.30	0.00	0.22	132	Fair	Green	2	0.9
Estimated Lane Mileage: 3.952	Lane	0.9											
ŭ .	R2	Flexible				4.00	0.00	0.21	132	Fair	Green	2	0.9
Post Mile: 7.984 to 9.054 Length: 1.070	R1	Flexible				4.20	1.00	0.25	216	Fair	Blue	2	1.0
Estimated Lane Mileage: 2.140	R2	Flexible				10.80	4.00	0.26	209	Fair	Blue	2	1.0
Post Mile: 7.984 to 9.984	L1	Flexible				3.90	1.00	0.22	175	Fair	Blue	2	2.0
Length: 2.000	L2	Flexible				2.60	1.00	0.23	236	Fair	Blue	2	2.0
Estimated Lane Mileage: 6.000	L3	Flexible				7.40	5.00	0.23	277	Fair	Blue	2	2.0
Post Mile: 9.054 to 9.984	R1	Flexible				3.70	0.00	0.20	189	Fair	Blue	2	0.9
Length: 0.930	R2	Flexible				1.00	0.00	0.22	199	Fair	Blue	2	0.9
Estimated Lane Mileage: 2.790	R3	Flexible				2.70	0.00	0.22	252	Fair	Blue	2	0.9
						7.00	0.05	0.10	170				42.8

VALUE ANALYSIS SPRINT REPORT – Attachment K



Final Value Analysis Sprint Report



D-7 LA-213 Capital Preventive Maintenance Project

EA 07-34660 PN 0718000076 07-LA-213 (PM 0.0/9.8)

Contract No. 53A0248

Task Order No. 1405



January 2024

Prepared by Value Management Strategies, Inc.





Date: January 17, 2024

To: Ryan Nai, District 7 DVAC

Subject: Final VA Study Report

D7 LA-213 Capital Preventive Maintenance Project Sprint (T.O 1405)

Dear Mr. Nai,

Value Management Strategies, Inc. is pleased to submit this Final VA Sprint Report for the referenced project. This report summarizes the results of the virtual sprint conducted January 8-9, 2024, using the WebEx virtual meeting platform, for District 7 in Los Angeles, California.

It was a pleasure working with District 7 on this project, and I look forward to the next one. If you have any questions or comments concerning this final report, please do not hesitate to contact me at 206-679-8029 or email eric.trimble@vms-inc.com.

Sincerely,

Value Management Strategies, Inc.

Eric Trimble, CVS, MBA, PMP

VA Study Team Leader


Copy: (PDF) Nader Abdelmalek, Project Manager

(PDF) Suzie Kearns, Project Designer

(PDF) Jaroslaw Kusz, HQ VA Program Manager (PDF) Erika Barrick, HQ VA Program Administrator


VA SPRINT SUMMARY REPORT1
Project Summary
VA Study Timing
Project Purpose and Need
VA Study Objectives
Key Project Issues
Evaluation of Baseline Concept
Final VA Sprint Results
Rejected VA Alternatives – Reason for Rejection
VA Sprint Team
VA ALTERNATIVES7
Proposed VA Alternatives
Other Considerations
Summary of Performance Improvements
 Proposed
 Accepted
Alignment with Safe System Objectives
VA Alternative Documentation
PROJECT ANALYSIS30
Summary of Analysis
Key Project Factors
 Project Issues
Cost Model
Function Analysis
 Random Function Identification
IDEA EVALUATION36
Evaluation Process
Idea Summary
Idea Summary List
VA PROCESS39
VA Sprint Agenda
VA Sprint Meeting Attendees
APPENDIX 42
Cost Estimate

D-7 LA-213 CAPM Project Table of Contents



VA Sprint Summary Report – Final Results D-7 LA-213 Capital Preventive Maintenance Project

PN 0718000076 EA 07-34660 07-LA-213 PM 0.0/9.8



A virtual Value Analysis (VA) sprint, sponsored by the California Department of Transportation (Caltrans) District 7 and facilitated by Value Management Strategies, Inc. (VMS), was conducted for the LA-213 Capital Preventive Maintenance (CAPM) Project located in Los Angeles County, California. The workshop was facilitated on January 8-9 using the WebEx virtual meeting platform. This *VA Sprint Summary Report – Final Results* provides an overview of the project, key findings, the alternatives developed by the VA team and the final implementation decisions made by the project stakeholders regarding the six recommended VA alternatives.

PROJECT SUMMARY

This VA sprint—an abbreviated two-day VA study for SB-1 projects—was performed for this CAPM project for State Route 213 (SR-213) in Los Angeles County. The facility passes through the cities of Los Angeles, Rancho Palos Verdes, Lomita, and Torrance from West 25th Street to Route 405. This project is programmed in the 2022 State Highway Operation and Protection Program (SHOPP) under the Roadway Preservation Program for delivery in the 2023/2024 fiscal year. The project proposes to rehabilitate pavement (cold plane and overlay); upgrade guardrail; upgrade existing nonstandard ADA curb ramps facilities to Americans with Disabilities Act (ADA) standards; construct concrete bus pads at transit stops; construct retaining walls for the addition of sidewalk segments; relocate some traffic signals; upgrade some pedestrian push-buttons; replace loop detectors; reduce some medians to allow for placement of Class II bicycle lanes; place Class II bicycle lanes; install bicycle loop detectors; upgrade existing drainage inlet grates with bicycle friendly grates; and install guide, warning, and bicycle signs.

The detailed scope is as follows:

- Cold plane 0.25 ft. of the existing asphalt concrete pavement and overlay with 0.10 ft. of HMA-Type A and 0.15 ft. of rubberized hot mix asphalt gap graded (RHMA-G).
- Dig-outs: Dig-out and replace failed pavement.
- Upgrade 64 existing ADA curb ramps to the current ADA standards. Ramps are located at various locations within project limits.
- Upgrade existing 478 ft. Metal Beam Guardrail (MBGR) with Midwest Guardrail System (MGS).
- Place 42 concrete bus pads (JPCP-RSC).
- Place three retaining wall: total length of 1,157 ft.
- Place 1,860 LF of sidewalk.
- Place accessible pedestrian pushbuttons at location of ADA curb ramp upgrades.
- Upgrade 11 existing drainage inlets with bicycle friendly grates.
- Replace all traffic loop detectors within limits of pavement rehabilitation.
- Install bicycle loop detectors at all signalized intersections.
- Include protection for State fiber optics within the roadway.
- At six intersections, as required due to ADA curb ramp upgrades, replace traffic signals and relocate five electrical boxes.
- Replace/repair southbound sidewalk (PM 0.326 to PM 0.388) approximately 330 LF.
- Replace 3,000 LF curb and gutter.

The current total project cost is estimated to be \$73,400,000 – including support and escalation.

VA STUDY TIMING

The VA sprint was conducted midway through the PA&ED phase which is scheduled to be completed by June 2024. PS&E is schedule for completion in January 2026. The project is scheduled for Ready to List (RTL) in April 2026 and Construction Completion in October 2028.

PROJECT PURPOSE AND NEED

The purpose of the project is to extend pavement life, improve ride quality, and reduce extraordinary maintenance. Previously, several pavement related projects rehabilitated the pavement within the projects limits as found in the PAVE M Highway H-Chart database. Four of these were cold plane and overlay projects implemented between PM 7.0/8.0, 3.4/7.0, 3.4/8.0, 0.0/0.3, and 0.3/3.4 in 1999, 2001,2009, 2010, and 2013 respectively. The current pavement condition survey justifies the need to program this project for pavement rehabilitation.

VA STUDY OBJECTIVES

The objectives of the VA study were to:

- 1. Utilize a condensed VA study process by referencing previous Caltrans VA alternatives for similar project types
- 2. Analyze the current project design, estimate, and schedule
- 3. Provide cost and/or schedule saving recommendations
- 4. Provide performance improvement recommendations

KEY PROJECT ISSUES

The items listed below are the key drivers, constraints, or issues being addressed by the project and considered during this VA sprint to identify improvements.

Project Scope and Budget – The escalated cost for the project completion has far exceeded the original programmed amount (PA), mainly due to market conditions and the additional scope items since included in the project such as retaining walls, right-of-way (R/W), and median removal. Completing the rehabilitation work of the anchor asset while incorporating the more essential satellite assets (curb ramps, guardrail, ITS elements, etc.) will be a challenge for this project.

Construction Process – Contractor means and methods will be integral to the project minimizing impacts to the traveling public and local communities. During the daytime, all lanes need to be open to accommodate traffic volumes. The 600-working-day schedule appears more than adequate to complete work while achieving this with nighttime work. However, this period of work will generate unwanted noise in the residential areas.

Public Partnership – Building rapport for public engagement with the City of Los Angeles, Rancho Palos Verdes, Lomita, and Torrance will be important to the success of the project as well as for coordinating future maintenance of the facilities. Also, a significant level of additional public engagement will be needed for the project with the local community (businesses and residents) and the traveling public, including drivers, bicyclists, pedestrians, and equestrians to help the project reach completion with as little community disruption as possible.

EVALUATION OF BASELINE CONCEPT

During the VA sprint, the VA team was comprised mainly of members of the Project Development Team (PDT) as this process does not require an independent VA team. Therefore, most VA team members were already familiar with the project. During the Information Phase, the design teams provided an in-brief presentation and there were opportunities for VA team members to discuss the baseline concept.

Overall, the VA team concluded that these baseline concepts were typical for similar pavement rehabilitation projects. The team recognized that the value improvement opportunities would focus on cost reductions to help mitigate rising project costs.

FINAL VA SPRINT RESULTS

Two of the six VA alternatives proposed for consideration were accepted. Below are the two accepted VA alternatives along with their associated potential initial cost savings, potential change in schedule, a brief discussion of each, and the rationale for their acceptance. The four rejected VA alternatives and the rationale for rejection are in the following section.

Alternative No. and Description	Initial Cost Savings	Change in Schedule
1.0 Use 0.20 ft. RHMA-G in lieu of 0.25 ft. HMA/RHMA-G mix	\$3,956,000	60-day reduction

The baseline concept proposes to cold plane 0.25 ft. of the existing asphalt concrete pavement and overlay with 0.10 ft. of HMA-Type A and 0.15 ft. of rubberized hot mix asphalt gap graded (RHMA-G). The alternative concept proposes to use 0.20 ft. RHMA-G pavement strategy in lieu of the 0.25 ft. pavement structural section. There will be no HMA portion in this proposal.

This alternative was accepted based on initial feasibility and cost savings represented.

4.0 Use appropriate bus pad length

\$474,000

12-day reduction

The baseline concept proposes to include 42 concrete bus pads constructed of JPCP-RSC and 115 ft. in length (8-9 panels of roughly 14 ft. length). The alternative concept proposes to reduce the length of the bus pads by approximately 2 panels for a total length of 98 ft. (roughly seven panels).

This alternative was accepted for implementation as it seems to be a reasonable design for the bus pad which will provide cost and time savings while still meeting the intended function of the bus pad – provided that the pad meets the 1:1.2 criteria and avoids placing any wheel tracks on pavement joints.

Rejected VA Alternatives - Reason for Rejection

2.0 Use 0.15 ft. RHMA-G in lieu of 0.25 ft. HMA/RHMA-G mix

\$8,430,000

60-day reduction

The baseline concept proposes to cold plane 0.25 ft. of the existing asphalt concrete pavement and overlay with 0.10 ft. of HMA-Type A and 0.15 ft. of rubberized hot mix asphalt gap graded (RHMA-G). The alternative concept proposes to use 0.15 ft. RHMA-G pavement strategy in lieu of the 0.25 ft. pavement structural section throughout the facility. There would be no HMA portion in this proposal.

This alternative was rejected in favor of VA Alternative 1.0 which provides a more durable pavement section. This should be considered a fallback position if the project is short of funding and the pavement is at least 0.30 ft. thick.

3.0 Reduce number of bus pads to reduce conflicts with fiber optic line

\$454,000

12-day reduction

The baseline concept proposes to include 42 concrete bus pads constructed of JPCP-RSC. There are several of these planned bus pads between PM 2.0 and 5.0 that will conflict with existing fiber optic line. The alternative concept proposes to reduce the total number of bus pads for this section by six (or where appropriate) to reduce the potential fiber conflict. The total number bus stops will not be changed, but the construction of new JPCP bus pads will be reduced.

This alternative was rejected at this time as it was determined that additional investigation (potholing) needs to be completed and depth of fiber lines verified before removing any bus pads from the project.

5.0 Eliminate one segment of retaining walls

\$3,116,000

40-day reduction

The baseline concept proposes to include sidewalks along the facility at two separate locations (Locations 1 and 2). The sidewalks will require retaining walls to be constructed at these locations. The necessary R/W for the retaining wall at Location 1 (SB on SR-213 between West Weymouth Place and Bynner Drive) has not yet been acquired. The alternative concept proposes to eliminate the two retaining walls needed for Location 1.

This alternative was rejected at this time to provide more time to allow the potential inclusion of the sidewalk and necessary retaining walls at Location 1 in the project – dependent on more funding and R/W acquisition.

6.0 Eliminate permanent BMPs from project

\$377,000

No change

The baseline concept proposes to include three BMPs for storm water management within the project limits. The alternative concept proposes to eliminate these three treatment BMPs as there is currently no available R/W for placement within the project limits.

This alternative was rejected at this time to provide more time to allow the potential inclusion of BMPs in the project – dependent on more funding and R/W acquisition.

VA SPRINT TEAM

VA Sprint Team

Name	Organization	Title
Eric Trimble	VMS, Inc.	VA Study Team Leader
Suzie Kearns	Caltrans	Project Designer
Kinseng Wong	Caltrans	Project Engineer
Kevin Nguyen	Caltrans	Design - ADA
Wendel Davidson	Caltrans	Construction/Field Office Resident Engineer
Joseph Reynoza	Caltrans	Design Manager

Key Project Contacts

Name	Organization	Title
Ryan Nai	Caltrans	DVAC
Nader Abdelmalek	Caltrans	Project Manager



The results of this study are presented as individual alternatives to the baseline concept. Each alternative consists of a summary of the baseline concept, a description of the suggested change, a listing of its advantages and disadvantages, a cost comparison, change in performance and value, discussion of schedule and risk impacts (if applicable), and a brief narrative comparing the baseline concept with the alternative. Sketches, calculations, and performance attribute ratings are also presented where applicable. The cost comparisons reflect a similar level of detail as in the baseline estimate.

PROPOSED VA ALTERNATIVES

Alternative No. & Description	Initial Cost Savings	Schedule Savings	Initial Disposition
1.0 Use 0.20 ft. RHMA-G in lieu of 0.25 ft. HMA/RHMA-G mix	\$3,956,000	60-day reduction	Accept
2.0 Use 0.15 ft. RHMA-G in lieu of 0.25 ft. HMA/RHMA-G mix	\$8,430,000	60-day reduction	Reject
3.0 Reduce number of bus pads to avoid fiber optic line conflict	\$454,000	12-day reduction	Reject
4.0 Use appropriate bus pad length	\$474,000	12-day reduction	Accept
5.0 Eliminate one segment of retaining walls	\$3,116,000	40-day reduction	Reject
6.0 Eliminate permanent BMPs from project	\$377,000	No change	Reject

Note: Please refer to the alternative form for reason of Acceptance or Rejection

OTHER CONSIDERATIONS

The VA team identified the following observations and design suggestions, relatively general in nature, for consideration by the Project Development Team (PDT). More detailed descriptions can be found in the *Idea Evaluation* portion of this report.

CS-2 Eliminate replanting from project

This concept would seek to eliminate the proposed planting work from the project as the trees currently identified within the project area are located in the sidewalk areas of the facility and are causing sidewalk pavement uplift. The proposed tree removal and replanting elements of the project are not currently included in the project estimate. A project currently in construction may be better suited for the immediate removal of the planted trees in lieu of attempting to include them in this project. The future replanting can be pursued later once an aesthetic and maintenance plan has been discussed with the cities. Different types of trees and/or root protection design elements can be placed in the future to help reduce the ongoing maintenance burden on either Caltrans or the cities.

CS-3 Determine balance between bicycle lane, parking, and median

This concept would explore where several conflicting facility elements should be located for the betterment of the entire corridor. The facility elements in question include the proposed bicycle lane, parking lane, and raised median structure. There simply is not enough space along the facility to support all of these design elements while also allowing for travel lanes, shoulders, turn lanes, and drainage. A meeting with the involved cities should be held to determine the overall priorities of these items in relation to the entire facility.

CS-4 Coordinate with railroad for two crossings

This concept would continue discussions with the railroads which currently have tracks crossing the facility in two locations. A determination needs to be made with the input of the railroads about the proposed roadway work and how the required traffic management plan will affect railroad operations. It is possible that flaggers will be required, or other special arrangements or restrictions will need to be in place. It would also be beneficial to reach a shared understanding with the railroads over the current R/W and each entities responsibilities in terms of the limits of the finished pavement.

CS-5 Determine construction staging options

This concept would explore the available staging options open for the contractor to construct the project. Currently, it is assumed that the project will rely heavily on night work as day work is not allowable due to traffic volumes and city preference. However, it is expected that some work will need to be completed during daylight hours or will be of significant duration that daytime traffic impacts or prolonged closures (sidewalks and ramps) cannot be avoided. Defining what is or is not allowable (weekend work periods, multiple locations, detours, longer directional night work closures, etc.) with the aid of the District Traffic Manager and city representatives will help to identify the total number of workdays needed as well as providing better information for potential contractor bids.

CS-6 Reduce lane width in lieu of median reduction for bicycle lane

This concept would explore the use of reduced width travel lanes (from 12 ft. to 11 ft.) to allow for more roadway space to accommodate bicycle lanes.

CT-1 Widen sidewalks where appropriate

This concept would seek to widen the existing sidewalks in several locations. The additional width would make better use of existing slivers of unused land and would be helpful for pedestrians. There are currently several locations where the current tree planting areas result in a sidewalk width that is not per current pedestrian/ADA design standards.

CT-2 Detour traffic to avoid railroad crossing near Sepulveda Ave.

This concept would address the potential for significant traffic and railroad operational disruptions from the work being conducted near the two railroad crossings near Sepulveda Blvd. and Western Ave. (SR-213) and which are in relatively close proximity to each other. A planned detour may be a potential solution to route traffic away from the Sepulveda Blvd. and Western Ave. and, thereby, reduce the potential traffic conflicts while this portion of the facility is completed.



SL-2 Use RAP for RHMA-G mix

This concept would seek to use the waste material from the cold planing/milling pavement process and recycle it as reclaimed asphalt pavement (RAP) within the needed RHMA-G mixture. An allowance of 10%-15% use of this material is permitted by Caltrans in its RHMA mixtures (and the contractor is anticipated to do it anyway); however, this concept would simply require the use of RAP

and would reflect the lower cost in the project estimate. The approval of the use of RAP in an RHMA-G pavement mixture would need to be verified.

TW-2 Determine drainage inlet design for removed median areas

This concept needs to determine an appropriate design for drainage inlets in locations where the median is proposed to be removed or modified as there are several locations stormwater is currently directed to the center of the roadway. If these medians are removed, the drainage flow pattern may be significantly impacted and will need to be redesigned to avoid potential drainage issues, future maintenance and/or possible traffic conflicts.

MB-1 Reduce paving limits

This concept would seek to focus the rehabilitation work only on those pavement areas of the project that need it. This determination would be made with the aid of recent pavement condition surveys and would aim to reduce the overall total cost of the project. Areas of pavement not rehabilitated at this time would be addressed in a subsequent CAPM project eight to 12 years further in the future. Please reference the *D7 APCS Data Sheet*, accessible from the PDT, which details the current pavement condition for each lane of the facility.

SUMMARY OF PERFORMANCE IMPROVEMENTS

The Caltrans HQ VA Program requires the following information to enable reporting of performance to the FHWA. Only the six standard Caltrans performance attributes, shown in the table below, are to be documented. Caltrans does not require reporting of the performance of any other attributes utilized in this study.

SUMMARY OF PROPOSED VA ALTERNATIVE PERFORMANCE IMPROVEMENTS

Alt. No.	Connectivity	Long-Term Impacts	Maintainability	Construction Impacts	Traffic Ops	Project Schedule
1.0		Improved	Improved	Improved	Improved	Improved
2.0				Improved		Improved
3.0				Improved		Improved
4.0			Improved	Improved		Improved
5.0		Improved	Improved	Improved		Improved
6.0			Improved	Improved		

SUMMARY OF ACCEPTED VA ALTERNATIVE PERFORMANCE IMPROVEMENTS

Alt. No.	Connectivity	Long-Term Impacts	Maintainability	Construction Impacts	Traffic Ops	Project Schedule
1.0		Improved	Improved	Improved	Improved	Improved
4.0			Improved	Improved		Improved

Alignment with Safe System Objectives

The VA process considers the degree to which the baseline concept and VA alternatives align with and support the five USDOT Safe System objectives for all road users. These objectives include:

Safe Road Users focuses on people and behaviors with the goal to support safe, responsible behavior by people who use the roads; this prioritizes their ability to reach the destination unharmed. This often takes the form of improvement through clear signage, roadway facilities that are consistent with expectations, and items that affect driver behavior and predictability.

Safe Vehicles expands the availability of vehicle systems and roadway features that facilitate the operation of safer vehicles; this additionally aims to help prevent crashes and minimize the impact of crashes for both occupants and non-occupants. This currently focuses primarily on transportation management systems (TMS) and their communication with drivers in addition to shoulder width accommodations for law enforcement, EMS, and distressed vehicles.

Safe Speeds promotes safer speeds in all roadway environments through a combination of thoughtful, context-appropriate roadway design, targeted education and outreach campaigns, and enforcement. This category often includes aspects such as signage, traffic management, and road characteristics including speedbumps, roundabouts, crosswalks, etc.


Safe Roads aims to mitigate human mistakes and account for injury tolerances, encourage safer behaviors, and facilitate safe travel for the most vulnerable users. This encompasses the geometry and logistics of a roadway with items such as roadway sight distance, stopping sight distance, shoulder and buffer widths, and roadway delineation.


Post-Crash Care provides roadway features that support post-crash care and enhances the survivability of crashes through expedient access to emergency medical care while simultaneously creating a safe working environment for vital first responders. This also helps prevent secondary crashes through robust traffic incident management practices. This category often encompasses features such as shoulder width suitable for supporting first responders and emergency vehicle turnarounds, pullouts, or other access points.


Each VA alternative was assessed by the VA team with respect to its influence on alignment with Safe System objectives and is included in each VA alternative form.

		I			
VA Alt. No. 1.0		VA Alt. Title: Use 0.20 ft	t. RHMA-G in lieu of 0.2	.5 ft. F	IMA/RHMA-G mix
Initial Cost Savings: Initial LCC Savings:		\$3,956,000 TBD			
Change in Schedule:		60-day reduction (3 mor			
Description of Baseline		, , , , , , , , , , , , , , , , , , , ,	ittisj		
· ·		-	of the existing asphalt o	oncrei	te pavement and overlay with
		0.15 ft. of rubberized hot			
Description of Alternat			data di di di	<u> </u>	
The alternative concept	t prop	oses to use 0.20 ft. RHM	IA-G pavement strategy	in lieu	u of the 0.25 ft. pavement
<u> </u>	e will	be no HMA portion in th			
Advantages:			Disadvantages:		
=	vide a more dependable face and structure. Ride				
Construction Impacts – Will require less work by the contractor. Less material handling, fewer lifts, and fewer days (less traffic disruption). Better productivity; assume 20-25% saving on paving effort.					
Long-Term Impacts – V recycle of material.	/ill all	ow for more use of			
durable pavement stru	cture.	e a more consistent and Will require less longer pavement lifespa			
Discussion:					
	thin t	o provide a durable stru	· · · · · · · · · · · · · · · · · · ·	-	nent section. The 0.10 ft. HMA e pavement cracking and
Performance Assessmer	nt		Alignment with Safe Sy	stem	Objectives
Connectivity	0	No change	Safer People	0	No change
Long-Term Impacts	Δ	Improved	Safer Roads	0	No change
Maintainability	Δ	Improved	Safer Vehicles	0	No change
Construction Impacts		Improved	Safer Speeds	_	No change
Traffic Ops.		Improved	Post-Crash Care		No change
'		Improved	i ost crasii care		i to change
Risk Assessment: This alternative should					
risk due to the improve			sk while also having a m	ninor r	eduction on future operational
risk due to the improve Additional Comments:	d pav		isk while also having a m	ninor r	eduction on future operational
Additional Comments: This alternative present paving approach would regarding the current paving rehabilitation ag	ts a be I make avem oproac	etter pavement approach construction much easi ent condition and should	h than the baseline cond ier. Further coring samp d confirm that this alterr	cept. T les wi native	The use of one homogenous Il provide more information will provide an appropriate
Additional Comments: This alternative present paving approach would regarding the current paving rehabilitation ag	ed pavets a bell make pavem oproace	ement durability. etter pavement approach e construction much easi ent condition and should	h than the baseline cond ier. Further coring samp d confirm that this alterr	cept. T les wi native	The use of one homogenous Il provide more information will provide an appropriate

Concept Images









Images of existing/proposed pavement between PM 0.0 to PM 9.98


CONSTRUCTION ELEMENT			SELINE CONC	Г	ALTERNATIVE CONCEPT						
Description	Unit	Quantity		Cost/Unit		Total	Quantity	Cost/Unit		Total	
ROADWAY ITEMS											
					\$	-				\$	-
Cold Plane Asphalt Concrete Pavement	SY	427,953	\$	5	\$	2,139,765	342,362	\$	5	\$	1,711,810
Mot Mix Asphalt (Type A)	Ton	27,924	\$	130	\$	3,630,120				\$	-
Rubberized Hot Mix Asphalt (Gap Graded)	Ton	41,886	\$	150	\$	6,282,900	55,848	\$	150	\$	8,377,200
					\$	-				\$	-
Traffic Management	LS	1	\$	280,000	\$	280,000	1	\$	252,000	\$	252,000
					\$	-				\$	-
					\$	-				\$	-
ROADWAYSUBTOTAL					\$	12,332,785				\$	10,341,010
ROADWAY MARK-UP	79%				\$	9,792,231				\$	8,210,762
ROADWAY TOTAL					\$	22,125,016				\$	18,551,772
TIME RELATED OVERHEAD (TRO) ITEMS											
Time Related Overhead	Ea	360	\$	4,328	\$	1,558,080	300	\$	4,328	\$	1,298,400
TRO SUBTOTAL					\$	1,558,080				\$	1,298,400
TRO MARK-UP	47%				\$	736,972				\$	614,143
TRO TOTAL					\$	2,295,052				\$	1,912,543
R/W or OTHER MATERIALS and EXPENSES											
					\$	-				\$	-
					\$	-				\$	-
					\$	-				\$	-
R/W or OTHER SUBTOTAL					\$	-				\$	-
R/W or OTHER MARK-UP	57%				\$	-				\$	-
R/W or OTHER TOTAL					\$	-				\$	-
TOTAL		\$				24,420,068	\$				20,464,315
TOTAL (Rounded)		~				\$24,420,000	7				\$20,464,000
TOTAL (Nounded)						324,42U,UUU					32U,404,UUU

VA Alt. No. 2.0		VA Alt. Title: Use 0.15' F	HMA-G in lieu of 0.2	5' HMA	/RHMA-G mix
Initial Cost Savings:		\$8,430,000			
Initial LCC Savings:		TBD			
Change in Schedule:		60-day reduction (3 mor	ths)		
Description of Baselin	e Cond	cept:			
	-	es to Cold plane 0.25 fee 0.15 feet of rubberized			rete pavement and overlay with RHMA-G).
Description of Alterna	tive Co	oncept:			
The alternative concep	t prop	ooses to use 0.15' RHMA-			of the 0.25' pavement structural
Advantages:	2 IaCIII	ty. There would be no HN	Disadvantages:	JOSai.	
	_ \//ill	require less work by the	1	t s – Ma	y discover pavement areas
contractor. Less mater	ial har disrup	ndling, fewer lifts and otion). Better productivity	where a full rehab is		•
reduction in project du workdays).		_			
Discussion:					
structure to resist pote can work in conjunctio This pavement rehabili	ential f n with itation	VA Alt 1.0, which reduce	and provide the designs as the pavement structure before within the dis	red pav tural se	thin to provide a durable rement lifespan. This alternative ection from 0.25' to 0.20'. In similar facilities and has proven
Performance Assessm	ent		Alignment with Safe	Syster	n Objectives
Connectivity		No change	Safer People	TO	No change
Long-Term Impacts	0	No change	Safer Roads	0	No change
Maintainability	0	No change	Safer Vehicles	0	No change
Construction Impacts	Δ	Improved	Safer Speeds		No change
-	\bigcirc	-	·		
Traffic Ops. Risk Assessment:		No change	Post-Crash Care		No change
			sk while having a mind	or incre	ase on future operational risk
Additional Comments	:				
paving approach would regarding the current p	d make pavem e struc	e construction much easi ent condition, but Altern tural depth throughout t	er. Further coring sam ative 1 is a superior o	nples wi ption co	The use of one homogenous ill provide more information ompared to this – especially if oring samples show that the
			-		nich provides a more durable ort of funding and the pavement
Resolution of Alternat	ive:		Audit date (milestor	nes)	

Concept Images







Images of existing/proposed pavement between PM 0.0 to PM 9.98

CONSTRUCTION ELEMENT			SELINE CON	т	А	LTE	RNATIVE CO	NC	PT		
Description	Unit	Quantity		Cost/Unit	Total		Quantity	Cost/Unit		Total	
ROADWAY ITEMS											
					\$	-				\$	-
Cold Plane Asphalt Concrete Pavement	SY	427,953	\$	5	\$	2,139,765	256,772	\$	5	\$	1,283,860
Mot Mix Asphalt (Type A)	Ton	27,924	\$	130	\$	3,630,120		\$	130	\$	-
Rubberized Hot Mix Asphalt (Gap Graded)	Ton	41,886	\$	150	\$	6,282,900	41,886	\$	150	\$	6,282,900
					\$	-				\$	-
Traffic Management	LS	1	\$	280,000	\$	280,000	1	\$	280,000	\$	280,000
					\$	-				\$	-
					\$	-				\$	-
ROADWAYSUBTOTAL					\$	12,332,785				\$	7,846,760
ROADWAY MARK-UP	79%				\$	9,792,231				\$	6,230,327
ROADWAYTOTAL					\$	22,125,016				\$	14,077,087
TIME RELATED OVERHEAD (TRO) ITEMS											
Time Related Overhead	Ea	360	\$	4,328	\$	1,558,080	300	\$	4,328	\$	1,298,400
TRO SUBTOTAL					\$	1,558,080				\$	1,298,400
TRO MARK-UP	47%				\$	736,972				\$	614,143
TRO TOTAL					\$	2,295,052				\$	1,912,543
R/W or OTHER MATERIALS and EXPENSES											
					\$	-				\$	-
					\$	-				\$	-
					\$	-				\$	-
R/W or OTHER SUBTOTAL					\$	-				\$	-
R/W or OTHER MARK-UP	57%				\$	-				\$	-
R/W or OTHER TOTAL					\$	-				\$	-
TOTAL		\$				24,420,068	\$				15,989,631
TOTAL (Rounded)						\$24,420,000					\$15,990,000
									SAVINGS	Ş	8,430,000

		1			
VA Alt. No. 3.0		VA Alt. Title: Reduce nu	mber of bus pads to ave	oid fi	ber optic line conflict
Initial Cost Savings:		\$454,000			
Initial LCC Savings:		TBD			
Change in Schedule:		12-day reduction			
Description of Baseline		=		c . = =	
					P-RSC. There are several of
these planned bus pads	s betv	veen PM 2.0 and 5.0 that	will conflict with existin	ig tibe	er optic line.
Description of Alternat	tive C	oncept:			
-		ooses to reduce the total			The state of the s
	•		e total number bus stop	s will	not be changed, but the
construction of new JP	CP bu	s pads will be reduced.			
Advantages:			Disadvantages:		
_		ıld reduce the amount of	Maintainability – Will	poter	ntially increase the amount of
		bus pads. Less material	-		e work to keep the bus stop
handling, less construct			areas in good operatio	nal c	ondition.
fewer workdays. Will re					
Caltrans-owned fiber co	OHILICI	t connicts.			
Discussion:			<u> </u>		
The main benefit of thi	s altei	rnative is to help avoid tir	me-consuming and cost	ly cor	nflicts with the existing Caltrans-
I				-	n the bus pad locations. The
IF		= -			CP bus pads would be placed to
I .			s may be between 1.8 ft	t. to 3	3.0 ft. which may create conflicts
dependent on the spec	itic se	paration criteria.			
The current estimate de	oes no	ot yet include the cost of p	ootential fiber optic utili	tv rel	ocation.
		, , , , , , , , , , , , , , , , , , ,		-,	
					olidated and the number of
I .	uced	in the PM 2.0 to 5.0 locat	ion which would require	e few	er bus pads to be constructed
for the project.			lan		
Performance Assessme	ent	1	Alignment with Safe S	yster	Ť
Connectivity	\bigcirc	No change	Safer People	<u>O</u>	No change
Long-Term Impacts	\circ	No change	Safer Roads	0	No change
Maintainability	\triangleright	Degraded	Safer Vehicles	\bigcirc	No change
Construction Impacts	Δ	Improved	Safer Speeds	\bigcirc	No change
Traffic Ops.	\circ	No change	Post-Crash Care	\bigcirc	No change
Risk Assessment:			•		
This alternative represe	ents a	reduction in construction	n-related risk but will ha	ive a	slight increase on operational
risk due to the reduced	l dura	bility of the areas with re	gular bus stop pavemer	ıt.	
Additional Comments:					
			•	-	the depth of the fiber optic lines
under the pavement in	the s	houlder and determine th	ne separation criteria wi	ith IT.	
		=			d that additional investigation
(potholing) needs to be	comp	pleted and depth of fiber	lines verified before rem	oving	g any bus pads from the project.
Resolution of Alternati	ve:		Audit date (milestone	s)	

Concept Images

PCC or PM NB-AC SB-AC PCC or AC Intersection AC 0.022 1 AC NA NA W 25th St No Intersection (Dash Station) 0.166 AC NA NA 1 0.293 1 AC NA NA 19th St 2.025 AC Summerland 1 AC 1 2.23 1 AC 1 AC Crestwood 2.369 1 AC 1 Park Western AC 2.484 Trudie Dr / Capital Dr 1 AC 1 AC 2.786 1 Caddington Dr AC 1 AC Toscanini Dr 2.971 1 1 AC AC WB Delasonde Dr & EB 1 3.19 AC 1 AC Westmont Dr. 3.454 1 AC 1 PCC Avenue Aprenda 3.699 0 PCC 0 PCC Green Hills St

List of proposed bus pad locations with potential fiber conflicts (highlighted)

CONSTRUCTION ELEMENT	ı	BAS	ELINE CONCE	Ρī	Г	ALTERNATIVE CONCEPT						
Description Unit			it Quantity Cost/Unit Total				Quantity Cost/Uni			it Total		
ROADWAYITEMS	,											
					\$	-				\$	-	
Bus Pads	Ea	42	\$	35,000	\$	1,470,000	36	\$	35,000	\$	1,260,000	
					\$	-				\$	-	
					\$	-				\$	-	
					\$	-				\$	-	
Traffic Management	LS	1	\$	280,000	\$	280,000	1	\$	280,000	\$	280,000	
					\$	-				\$	-	
					\$	-				\$	-	
ROADWAY SUBTOTAL					_	1,750,000				\$	1,540,000	
ROADWAY MARK-UP	79%				_	1,389,500				\$	1,222,760	
ROADWAY TOTAL					\$	3,139,500				\$	2,762,760	
TIME RELATED OVERHEAD (TRO) ITEMS												
Time Related Overhead	Ea	360	\$	4,328	\$	1,558,080	348	\$	4,328	\$	1,506,144	
TRO SUBTOTAL					\$	1,558,080				\$	1,506,144	
TRO MARK-UP	47%				\$	736,972				\$	712,406	
TRO TOTAL					\$	2,295,052				\$	2,218,550	
R/W or OTHER MATERIALS and EXPENSES												
					\$	-				\$	-	
					\$	-				\$	-	
					\$	-				\$	-	
R/W or OTHER SUBTOTAL					\$	-				\$	-	
R/W or OTHER MARK-UP	57%				\$	-				\$	-	
R/W or OTHER TOTAL			L		\$	-				\$	-	
TOTAL		\$				5,434,552	\$				4,981,310	
TOTAL (Rounded)						\$5,435,000					\$4,981,000	
	•	-							SAVINGS		\$454,000	

VA Alt. No. 4.0		VA Alt. Title: Use appro	opriate bus pad length								
Initial Cost Savings:		\$474,000									
Initial LCC Savings:		TBD									
Change in Schedule:		2-day reduction									
Description of Baseline The baseline concept p panels of roughly 14 ft.	ropos	es to include 42 concre	te bus pads constructe	d of JPC	P-RSC and 115 ft. in length (8-9						
Description of Alternat	t ive C o t prop	oncept: oses to reduce the leng	th of the bus pads by a	pproxir	nately two panels for a total						
Advantages: Construction Impacts - effort by the contractor less traffic disruption, a Maintainability – Will r maintenance with rega	r. Less and fer reduce	materials, fewer panel wer workdays. e the amount of future			to introduce some buckling of nent prior to bud pad location.						
bus pad design. The Higft.; however, the actual existing/proposed facilithe the w	ghway I desig ity. It i vidth c	Design Manual (HDM) on is left to the discretion	provides a recommend n of each district and t gth of 98 ft. will provid	ded leng he uniq	also provide a more efficient th of 115 ft. and a width of 14 ue aspects of the equate length for bus activity on						
Performance Assessme	ent		Alignment with Safe	Systen	n Objectives						
Connectivity	0	No change	Safer People	0	No change						
Long-Term Impacts	\circ	No change	Safer Roads	0	No change						
Maintainability	Δ	Improved	Safer Vehicles	0	No change						
Construction Impacts	Δ	Improved	Safer Speeds	0	No change						
Traffic Ops.	0	No change	Post-Crash Care	0	No change						
measurable impact on	opera	tional risk.			sk but will not have any ble given that the HDM provides						
wheel paths with the p Final Determination: <i>Th</i>	avemo	ent joints and will need ernative was accepted f	to conform with the 1: for implementation as i	1.2 ration	to be a reasonable design for						
		the 1:1.2 criteria and av	_		ed function of the bus pad – on pavement joints.						
Resolution of Alternati	ive:		Audit date (milestor	nes)							

Concept Images

(3) Bus Pads. Bus pads are subjected to similar stresses as intersections; however, it is not practical to engineer rigid bus pads according to the Traffic Index, or according to bus counts. The minimum pavement structure for bus pads should be 0.85 foot JPCP with dowel bars at transverse joints on top of 0.5 foot lean aggregate subbase. Type III soil should be treated in accordance with Index 614.4. Where local standards are more conservative than the pavement structures mentioned above, local standards should govern.

Relative slab dimensions for bus pads should be approximately 1:1 to 1:1.25, transverse-to-longitudinal. The width of the bus pad should be no less than the width of the bus plus 4 feet. If the bus pad extends into the traveled way, the rigid bus pad should extend for the full width of the lane occupied by buses. The minimum length of the bus pad should be 1.5 times the length of the bus(es) that will use the pad at any given time. This will provide some leeway for variations in where the bus stops. Additional length of rigid pavement should be considered for approaches and departures from the bus pad since these locations may be subjected to the same stresses from buses as the pad. A 115-foot length of bus pad (which is approximately 250 percent to 300 percent times the length of typical 40-foot buses) should provide sufficient length for bus approach and departure. The decision whether to use rigid pavement for bus approach and departure to/from bus pads is the responsibility of the District.

A JPCP end anchor is not required, but may improve long-term performance at the flexible-to-rigid pavement transition. Doweled transverse joints should be perpendicular to the longitudinal joint at maximum 14 feet spacing, but consider skewing (at 1:6 typical) entrance/exit transverse flexible-to-rigid transitions, note that since acute corners can fail prematurely, acute corners should be reinforced or rounded (see Figure 626.4). Special care should be taken to assure skid resistance in conformance with current Standard Specifications in the braking area, especially where oil drippage is concentrated.

Highway Design Manual (HDM) Bus Pad guidance

Round Acute Corner Perpindicular to Longitudinal Joint Rigid Bus Pad Flexible Pavement ETW or Edge of Lane Line (Typ) Skew Transverse Flexible to Rigid Transition Rigid Bus Pad

Figure 626.4

Example plan sheet of Bus Pad from HDM

(1) Not all details shown

CONSTRUCTION ELEMENT	ı	BASE	LINE CONCE	P	Г	ALTERNATIVE CONCEPT					
Description	Unit	Quantity	(Cost/Unit		Total	Quantity	Cost/Unit		Total	
ROADWAY ITEMS											
					\$	-				\$	-
Bus Pads	Ea	42	\$	35,000	\$	1,470,000	42	\$	29,750	\$	1,249,500
					\$	-				\$	-
					\$					\$	-
					\$					\$	
Traffic Management	LS	1	\$	280,000	\$,	1	\$	280,000	\$	280,000
					\$					\$	-
					\$					\$	-
ROADWAY SUBTOTAL					H.	1,750,000				\$	1,529,500
ROADWAY MARK-UP	79%				·	1,389,500				\$	1,214,423
ROADWAY TOTAL					\$	3,139,500				\$	2,743,923
TIME RELATED OVERHEAD (TRO) ITEMS											
Time Related Overhead	Ea	360	\$	4,328	\$	1,558,080	348	\$	4,326	\$	1,505,448
TRO SUBTOTAL						1,558,080				\$	1,505,448
TRO MARK-UP	47%				\$	•				\$	712,077
TRO TOTAL					\$	2,295,052				\$	2,217,525
R/W or OTHER MATERIALS and EXPENSES											
					\$	-				\$	-
					\$	-				\$	-
					\$	-				\$	-
R/W or OTHER SUBTOTAL					\$					\$	-
R/W or OTHER MARK-UP	57%				\$					\$	-
R/W or OTHER TOTAL					\$	-		L		\$	-
TOTAL		\$				5,434,552	\$				4,961,448
TOTAL (Rounded)						\$5,435,000					\$4,961,000
									SAVINGS		\$474,000

VA Alt. No. 5.0		VA Alt. Title: Eliminate one segment of retaining walls									
Initial Cost Savings:		\$3,116,000									
Initial LCC Savings:		TBD									
Change in Schedule:		40-day reduction									
The sidewalks will requ	ropos ire ret	es to include sidewalks al taining walls to be constru	ucted at these locations	s. The	ate locations (Locations 1 and 2). necessary R/W for the retaining) has not yet been acquired.						
Description of Alternat The alternative concep		oncept: oses to eliminate the two	retaining walls neede	d for l	ocation 1.						
Advantages:			Disadvantages:								
excavation, fewer work disruption. Long-Term Impacts – R acquisition required. Ro vegetation disturbance	contra days, Require eprese to the retain	ctor. Less materials, less and less traffic es less permanent R/W ents less soil and	Multi-Modal Connecti connectivity by elimina more traffic conflicts t	ating s	sidewalk. Creates potential for						
currently included (or r needed to support the this portion of the facil	not ind retain ity.		. The District is still pur of the retaining walls a	suing nd sic	the funding to acquire the R/W lewalk originally intended for						
Performance Assessme	ent		Alignment with Safe S	ysten	n Objectives						
Connectivity	∇	Degraded	Safer People	\circ	No change						
Long-Term Impacts	Δ	Improved	Safer Roads	0	No change						
Maintainability	Δ	Improved	Safer Vehicles	\bigcirc	No change						
Construction Impacts	Δ	Improved	Safer Speeds	\bigcirc	No change						
Traffic Ops.	\circ	No change	Post-Crash Care	\bigcirc	No change						
		ative will reduce the cons t by not providing a sidev		the p	roject but will increase the						
enough funding in the pand included in the est Final Determination: <i>Th</i>	projec imate his alte	t included for additional I ernative was rejected at t.	R/W acquisitions despithing time to provide more	te the	owever, there currently is not retaining walls being identified e to allow the potential inclusion ent on more funding and R/W						
Resolution of Alternati	ve:		Audit date (milestone	<u>s)</u>							

Concept Images



Overhead image of the proposed sidewalk and retaining wall location on the SB side of SR-213



Street level image of the proposed sidewalk and retaining wall location on the SB side of SR-213

			-	St Estillia	-						
CONSTRUCTION ELEMENT	1	BAS	ELINE CONCE	PΊ	Г	ALTERNATIVE CONCEPT					
Description Unit		Quantity		Cost/Unit	Total		Quantity	Cost/Unit		Total	
ROADWAY ITEMS											
					\$	-				\$	-
Retaining Wall (Segment 1)	LS	1	\$	1,574,405	\$	1,574,405				\$	-
					\$	-				\$	-
Traffic Management	LS	1	\$	280,000	\$	280,000	1	\$	260,000	\$	260,000
					\$	-				\$	-
					\$	-				\$	
					\$	-				\$	-
					\$	-				\$	-
ROADWAY SUBTOTAL					_	1,854,405				\$	260,000
ROADWAY MARK-UP	79%				_	1,472,398				\$	206,440
ROADWAYTOTAL					\$	3,326,803				\$	466,440
TIME RELATED OVERHEAD (TRO) ITEMS											
Time Related Overhead	Ea	360	\$	4,328	\$	1,558,080	320	\$	4,328	\$	1,384,960
TRO SUBTOTAL					\$	1,558,080				\$	1,384,960
TRO MARK-UP	47%				\$	736,972				\$	655,086
TRO TOTAL					\$	2,295,052				\$	2,040,046
R/W or OTHER MATERIALS and EXPENSES											
					\$	-				\$	-
					\$	-				\$	-
					\$	-				\$	-
R/W or OTHER SUBTOTAL					\$	-				\$	-
R/W or OTHER MARK-UP	57%				\$	-				\$	-
R/W or OTHER TOTAL					\$	-				\$	-
TOTAL		\$				5,621,854	\$				2,506,486
TOTAL (Rounded)						\$5,622,000					\$2,506,000
									SAVINGS	\$	3,116,000

VA Alt. No. 6.0		VA Alt. Title: Eliminate	permanent BMPs fro	m proje	ct
Initial Cost Savings:		\$377,000	•	<u> </u>	
Initial LCC Savings:		TBD			
Change in Schedule:		No change			
Description of Baseline The baseline concept p		-	Ps for storm water mai	nageme	nt within the project limits.
Description of Alterna	tive Co	oncept: poses to eliminate these			re is currently no available R/W
Advantages:			Disadvantages:		
worked required in the	proje	ect.	stormwater water p	ollution	ces the ability to receive credits. There will still be a nent until R/W is acquired.
possible to pursue. The be placed and no addit The need for proper sto project does not currer staffing resources to m	ere is r ional p ormwantly ha aintai	no R/W available within project resources to acc ater treatment within t ave the resources to inc	the project limits whe quire more property. he project limits is still lude it. The District (an vater BMPs for the facil	desirable desira	that is that currently not tormwater treatment BMPs can be for the facility; however, the does not currently have the maintenance agreement with any completed BMPs.
Performance Assessme			Alignment with Saf		· · · ·
Connectivity		No change	Safer People		No change
Long-Term Impacts	∇	Degraded	Safer Roads	0	No change
Maintainability	Δ	Improved	Safer Vehicles	0	No change
Construction Impacts	Δ	Improved	Safer Speeds	0	No change
Traffic Ops.	0	No change	Post-Crash Care	0	No change
Risk Assessment: The oler than the control of the	perat	tional risk will be margi	nally increased due to	the redu	action in overflow relief at this
limited by the availabili Final Determination: <i>Tl</i>	ity of a	appropriate property ai ernative was rejected a	nd the funding for prop t this time to provide n	erty aco	ojective, but it is understandably quisition. e to allow the potential inclusion
		endent on more funding		•	
Resolution of Alternat	ive:		Audit date (milesto	nes)	

CONSTRUCTION ELEMENT	ı	BASELINE CONCI	EPT		ALTERNATIVE CONCEPT					
Description	Description Unit		Cost/Unit		Total	Quantity	Cost/Unit		Total	
ROADWAY ITEMS										
				\$	-				\$	-
Water Pollution Control	Ea	1	\$ 360,000	\$	360,000	1	\$	150,000	\$	150,000
				\$	-				\$	-
				\$	-				\$	-
				\$	-				\$	-
				\$	-				\$	
				\$	-				\$	-
				\$	-				\$	-
ROADWAYSUBTOTAL				\$	360,000				\$	150,000
ROADWAY MARK-UP	79%			\$	285,840				\$	119,100
ROADWAYTOTAL				\$	645,840				\$	269,100
TIME RELATED OVERHEAD (TRO) ITEMS										
Time Related Overhead				\$	-				\$	-
TRO SUBTOTAL				\$	-				\$	-
TRO MARK-UP	47%			\$	-				\$	-
TRO TOTAL				\$	-				\$	-
R/W or OTHER MATERIALS and EXPENSES										
				\$	-				\$	-
				\$	-				\$	-
				\$	-				\$	-
R/W or OTHER SUBTOTAL				\$	-				\$	-
R/W or OTHER MARK-UP	57%			\$	-				\$	-
R/W or OTHER TOTAL				\$	-				\$	-
TOTAL		\$			645,840	\$				269,100
TOTAL (Rounded)					\$646,000					\$269,000
	•						SAV	INGS		\$377,000



PROJECT ANALYSIS

SUMMARY OF ANALYSIS

The following analysis tools were used to study the project:

- Key Project Factors
- Cost Model
- Function Analysis

KEY PROJECT FACTORS

The first day of the VA study included meetings with the project stakeholders. The following summarizes key project issues and site visit observations identified during these sessions.

Project Issues

The following are some of the issues and concerns associated with the project:

Project Scope and Budget – The escalated cost for the project completion has far exceeded the original PA, mainly due to market conditions and the additional scope items since included in the project such as retaining walls, R/W, and median removal. Completing the rehabilitation work of the anchor asset while incorporating the more essential satellite assets (curb ramps, guardrail, ITS elements, etc.) will be a challenge for this project.

Construction Process – Contractor means and methods will be integral to the project minimizing impacts to the traveling public and local communities. During the daytime, all lanes need to be open to accommodate traffic volumes. The 600-working-day schedule appears more than adequate to complete work while achieving this with nighttime work. However, this period work will generate unwanted noise in the residential areas.

Public Partnership – Building rapport for public engagement with the City of Los Angeles, Rancho Palos Verdes, Lomita, and Torrance will be important to the success of the project as well as for coordinating future maintenance of the facilities. Also, a significant level of additional public engagement will be needed for the project with the local community (businesses and residents) and the traveling public including drivers, bicyclists, pedestrians, and equestrians to help the project reach completion with as little community disruption as possible.

COST MODEL


The VA team leader prepared a cost model from the cost estimated presented in the *Project Information* section of this report. The model is based on the updated project cost estimate dated October 18, 2023, which was made available during the VA study and is organized to identify major construction element or trade categories, the original estimated costs, and the percent of total project cost for the significant cost items. The cost model and Pareto chart below provide a concise perspective of where major cost items reside within the project cost estimate.

Cost Model

Item	Cost	% of Total	Cumulative %
Roadway Contingency	\$9,621,900	19.1 %	19.1 %
Pavement Structural Section - RHMA	\$6,282,900	12.5 %	31.6 %
Specialty Items - Median Reduction	\$5,624,058	11.2 %	42.7 %
Traffic Items	\$4,728,700	9.4 %	52.1 %
Pavement Structural Section - Hot Mix Asphalt	\$3,630,120	7.2 %	59.3 %
Roadway Mobilization	\$3,116,200	6.2 %	65.5 %
Right-of-Way	\$2,286,300	4.5 %	70.0 %
Pavement Structural Section - Cold Plane	\$2,139,765	4.2 %	74.3 %
Supplemental Work	\$1,831,500	3.6 %	77.9 %
Specialty Items - Retaining Wall 1	\$1,574,405	3.1 %	81.0 %
Time-Related Overhead	\$1,558,100	3.1 %	84.1 %
Pavement Structural Section - Bus Pads	\$1,540,000	3.1 %	87.2 %
Minor Items	\$1,483,900	2.9 %	90.1 %
Specialty Items - Retaining Wall 2	\$1,458,554	2.9 %	93.0 %
Pavement Structural Section - ADA Curb Ramps	\$960,000	1.9 %	94.9 %
State Furnished	\$820,300	1.6 %	96.5 %
Pavement Structural Section - Digouts	\$819,000	1.6 %	98.2 %
Environmental	\$511,100	1.0 %	99.2 %
Specialty Items - Other	\$216,250	0.4 %	99.6 %
Pavement Structural Section - Tack Coat	\$150,000	0.3 %	99.9 %
Drainage	\$27,500	0.1 %	100.0 %
Earthwork	\$15,000	0.0 %	100.0 %
TOTAL	\$50,395,552		

For VA alternative development, additional percentage-based cumulative mark-ups not included in the initial cost of construction are reflected within the total project estimate. These mark-ups include 5% for Minor Items, 10% for Mobilization, 4% for Supplemental Work, 2% for State Furnished Materials and Expenses, 25% for Roadway Contingency, and 18% for escalation. The mark-up for each initial construction cost items cumulatively amounts to 79.4% for Roadway Construction items, 47.3% for Time Related Overhead, and 56.7% for R/W items. This mark-up total was used for the purpose of developing initial construction costs for analyzing individual practical design VA alternatives.

Pareto Chart



FUNCTION ANALYSIS

Function analysis was performed, and a Function Analysis System Technique (FAST) diagram was produced which revealed the key functional relationships for the project. This analysis provided a greater understanding of the total project and how the project's performance, cost, time, and risk characteristics are related to the various functions identified. The FAST diagram arranges the functions in logical order so that when read from left to right, the functions answer the question "How?" If the diagram is read from right to left, the functions answer the questions "Why?" Functions connected with a vertical line are those that happen at the same time as, or are caused by, the function at the top of the column (a "When?" relationship).

FUNCTION ANALYSIS

Function analysis was performed, and a Function Analysis System Technique (FAST) diagram was produced which revealed the key functional relationships for the project. This analysis provided a greater understanding of the total project and how the project's performance, cost, time, and risk characteristics are related to the various functions identified. The FAST diagram arranges the functions in logical order so that when read from left to right, the functions answer the question "How?" If the diagram is read from right to left, the functions answer the questions "Why?" Functions connected with a vertical line are those that happen at the same time as, or are caused by, the function at the top of the column (a "When?" relationship).

Random Function Identification

Project Element	Function
Drainage	Collect Water
Drainage	Connect Stormwater
Drainage	Convey Water
Drainage	Remove Water
Drainage	Resist Erosion
Drainage	Treat Water
Earthwork	Acquire Fill
Earthwork	Investigate Conditions
Earthwork	Prepare Site
Earthwork	Remove Existing
Earthwork	Remove HAZMAT
Electrical	Collect Data
Electrical	Control Signals
Electrical	Control Traffic
Electrical	Decrease Delay

Project Element	Function
Electrical	Enhance Safety
Electrical	Enhance Visibility
Electrical	Illuminate Space
Electrical	Increase Delay
Electrical	Inform Public
Electrical	Manage Traffic
Electrical	Optimize
Electrical	Transportation
Electrical	Sense Traffic
Electrical	Store Data
Electrical	Transmit Data
Pavement Structural	Enhance Durability
Pavement Structural	Enhance Ride
Pavement Structural	Increase Longevity
Pavement Structural	Increase Traction
Pavement Structural	Match Existing

Function
Smooth Pavement
Support Load
Advertise Project
Complete Milestones
Coordinate
Stakeholders
Engage Public
Ensure Scope
Maintain Schedule
Manage Contract
Manage Cost
Manage Expectations
Manage Risk
Meet Standards
Obtain Approvals
Obtain Funding
Play Nice

Project Element	Function
Project Management	Protect Environment
Project Management	Stage Construction
Project Requirement	Accommodate Bicycles
Project Requirement	Accommodate Pedestrians
Project Requirement	Accommodate Vehicles
Project Requirement	Create Separation
Project Requirement	Enhance Public Trust
Project Requirement	Enhance Safety
Project Requirement	Extend Life
Project Requirement	Improve Mobility
Project Requirement	Maintain Assets
Project Requirement	Reduce Maintenance
Project Requirement	Rehabilitate Pavement
Project Requirement	Separate Traffic
r roject nequirement	· ·

The study team concluded that the higher-order function of the project is to *Improve Mobility* through the basic functions of *Rehabilitate Pavement and Accommodate Modes*. Key secondary functions include *Support Load, Enhance Durability, Reduce Maintenance, Treat Water, Convey Water, Engage Public, Manage Traffic, Transmit Data, Stage Construction, Enhance Safety, and <i>Recycle Materials*. Essential requirements included *Manage Estimate* and *Deliver Project*.



IDEA EVALUATION

The ideas generated by the VA team were carefully evaluated, and project-specific attributes were applied to each idea to assure an objective evaluation.

EVALUATION PROCESS

The VA team generated and evaluated ideas on how to perform the various project functions using other approaches. The idea list was grouped by function or major project element. Each idea was evaluated with respect to the functional requirements of the project. Performance, cost, time, and risk may also have been considered during this evaluation.

Once each idea was fully evaluated, it was rated to determine which ideas had the greatest potential for value improvement. Ideas identified for development as VA alternatives or as other considerations are documented in the VA Alternatives section of this report.

IDEA SUMMARY

All the ideas generated during the Creativity Phase using brainstorming techniques are recorded on the following pages. The team created and evaluated these ideas together using Miro. Each idea received an idea code based on the function statement under which it was brainstormed. The following table indicates the functions related to each idea code.

Idea Code	Related Function
AM	Accommodate Modes
CS	Coordinate Stakeholders
СТ	Control Traffic
MT	Manage Budget

Idea Code	Related Function
RE	Retain Earth
SL	Support Load
TW	Treat Water

IDEA SUMMARY LIST

Idea Code	Idea Description	Rating
AM-1	Reduce number of bus pads	DEV
AM-2	Optimize bus pad length	DEV
CS-1	Improve Maintenance Agreements	OC
CS-2	Eliminate replanting from project	OC
CS-3	Determine balance between bicycle lane, parking, and median	OC
CS-4	Coordinate with Railroad for two crossings	OC
CS-5	Determine construction staging options	OC
CS-6	Reduce lane width in lieu of median reduction for bicycle lane	OC

Idea Code	Idea Description	Rating
CT-1	Widen sidewalks	OC
CT-2	Detour traffic to avoid railroad crossing near Sepulveda Ave.	OC
CT-3	Drop parking adjacent to left turn lane	ABD
CT-4	Eliminate median reduction where parking must remain	COM
MB-1	Reduce paving limits	OC
MB-2	Eliminate city rail replacement	ABD
RE-1	Eliminate one segment of retaining walls	DEV
SL-1	Use 0.20 ft. RHMA-G in lieu of 0.25 ft.	DEV
SL-2	Use RAP for RHMA-G mix	OC
SL-3	Use 0.15 ft. RHMA-G where appropriate in lieu of 0.25 ft.	DEV
SL-4	Use crack sealant	ABD
SL-5	Request materials recommendation	ABD
SL-6	Use slurry seal	DIS
SL-7	Use alternative concrete method in lieu of JPCP at bus pads to reduce fiber optic conflict	DIS
TW-1	Eliminate permanent BMPs	DEV
TW-2	Determine drainage inlet design for removed median areas	OC

DEV: Develop as VA Alternative

OC: Other Consideration

ABD: Already Being Done (in the Baseline Concept)

DIS: Dismissed COM: Combine







Day 1 – Monday, January 8th 2024– via WebEx

8:00	Introductions
8:05	Proiect In-Brief


- Need & Purpose
- Overview of Current Project Status
- Review Project Cost Estimate & Schedule
- VA Sprint Goals

10:00	Break

- 10:15 Review Project Functions
- 11:00 Brainstorm New Ideas
- 12:00 Lunch
- 1:00 Review Applicable Caltrans VA Database Ideas
- 2:00 Evaluate Ideas
- 4:00 Adjourn

Day 2 – Tuesday, January 9th 2024– via WebEx

8:00 Review Shortlist of Top Ideas
8:15 Assign and Develop VA Alternatives
10:00 Break
10:30 Continue Development of VE Alternatives
12:00 Lunch
12:30 Development of VE Alternatives (cont.)
2:00 Presentation Prep
3:00 VA Sprint Presentation
4:00 Adjourn





VA STUDY MEETING ATTENDEES

11/6	1/3	1/8	1/9	Name	Position/Role	Telephone	E-mail
×	×	×	×	Eric Trimble	VA Study Team Leader	206-679-8029	Eric.trimble@vms-inc.com
×	×	×	×	Ryan Nai	DVAC		Ryan.Nai@dot.ca.gov
×		×	×	Joseph Reynoza	Design Manager	213-266-6121	Joseph.reynoza@dot.ca.gov
×	×	×	×	Kinseng Wong	Project Engineer	213-266-3705	Kin.Seng.Wong@dot.ca.gov
×	×	×	×	Suzie Kearns	Project Designer	213-266-3729	Suzie.kearns@dot.ca.gov
		×	×	Kevin Nguyen	Design - ADA		Kevin.q.nguyen@dot.ca.gov
		×	×	Wendel Davidson	Construction/Field Office Resident Engineer		Wendel.davidson@dot.ca.gov
	×	×		Nader Abdelmalek	Project Manager	213-598-6789	Nader.abdelmalek@dot.ca.gov
×				Jesse Ornelas	Asst. Project Manager		
×				Mehdi Salehinik	Office Chief		
		×	×	Benjamin Medina	Complete Streets		Benjamin.medina@dot.ca.gov
		×		George Olguin	Landscape Architecture - South Region/Sr.	213-266-6588	George.olguin@dot.ca.gov
		×	×	Nader Gobran	Engineering Services – Materials/Sr.	213-269-1357	Nader.gobran@dot.ca.gov
		×		Wing-Yan (Karen) Lee	Hydraulics/Sr.	213-269-1861	Wing.y.lee@dot.ca.gov
		×		Carly Corona	Right-of-Way		Carly.corona@dot.ca.gov
		×		Mario Zamorano	Right-of-Way/Railroad	213-266-3576	Mario.zamorano.jr@dot.ca.gov
		×		Maximilio Chavez	Office of District Traffic Manager		Maximiliano.chavez@dot.ca.gov
		×	×	Jose Martinez	Office of Intelligent Transportation Systems, ITS Infrastructure Development - Electrical	213-266-6047	Jose.flores.martinez@dot.ca.gov
		×		Fatemeh Ansari	Office of Traffic Design, Electrical Sys. Design/Sr.	213-598-1671	Fatemeh.ansari@dot.ca.gov
		×	×	Erick Morales	Office of Traffic Design, Electrical Sys. Design		Erick.morales@dot.ca.gov
		×	×	Godfrey Nzeogu	Maintenance		
		×		Ara Jitechian	Hydraulics		



PROJECT

PLANNING COST ESTIMATE®

EA: DS-123456 PID: DS1234567

PID: DS1234567 District-County-Route: 00-XXX-X-000

PM: 00.0 - 00.0

Escalated Cost

Type of Estimate : Project Scope Summary Report

Program Code: STIP

EA: DS-123456

Project Limits: X street west of a highway to y street east of route b.

Project Description: Freeway widening, bridge widen/replace and maintenance structure.

Scope: Freeway Widening and Building Work - Not a real example.

Alternative: Alternative # 1

SUMMARY OF PROJECT COST ESTIMATE

Current Year Cost

	•					
	TOTAL ROADWAY COST	\$	48,109,300	\$	56,677,878	
7	OTAL STRUCTURES COST	\$	-	\$	-	
	SUBTOTAL CONSTRUCTION COST	\$	48,109,300	\$	56,677,878	
т	OTAL RIGHT OF WAY COST	\$	2,286,300	\$	3,583,500	
TOTA	L CAPITAL OUTLAY COSTS	\$	50,396,000	\$	60,262,000	
	PA/ED SUPPORT	\$	4,037,128	\$	4,079,233	
	PS&E SUPPORT	\$	3,049,041	\$	3,369,774	
ĺ	RIGHT OF WAY SUPPORT	\$	139,688	\$	152,914	
	CONSTRUCTION SUPPORT	\$	4,464,060	\$	5,463,298	
٦	TOTAL SUPPORT COST	\$	11,690,000	\$	13,066,000	
тот	TAL PROJECT COST	\$	62,100,000	\$	73,400,000	
-			Programmed Amount	\$	250,000,000	
			Month /	Year		
	Date of Estimate (Month/Year)		1 /			
	Estimated Construction Start (Month/Year)		1_/	2025		
		Ν	Number of Working Days =	600		
Estima	ted Mid-Point of Construction (Month/Year)		7_ /	2024		
	Estimated Construction End (Month/Year)		12 /	2026		
	Numbe	er of P	lant Establishment Days	261		
	Estimated Project Schedule					
	PID Approval		1/15/2014			
	PA/ED Approval		12/10/2017			
	PS&E		6/25/2023			
	RTL		12/18/2023			
	Begin Construction		1/19/2023			
Reviewed by District O.E. or Cost Estimate Certifier			xx/xx/xxxx		(xxx) xxx-xxxx	
SSS ESTIMATE SOLUTION	Office Engineer / Cost Estimate Certifier		Date		Phone	
Approved by Project Manager			xx/xx/xxxx		(xxx) xxx-xxxx	
	Project Manager		Date		Phone	

Page 1 1/8/2024

PROJECT COST ESTIMATE

EA: DS-123456 PID: DS1234567

I. ROADWAY ITEMS SUMMARY

	Section		Cost
1	Earthwork	\$	15,000
2	Pavement Structural Section	\$	15,521,800
3	Drainage	\$	27,500
4	Specialty Items	\$	8,873,300
5	Environmental	\$	511,100
6	Traffic Items	\$	4,728,700
7	Detours	\$	
8	Minor Items	\$	1,483,900
9	Roadway Mobilization	\$	3,116,200
10	Supplemental Work	\$	1,831,500
11	State Furnished	\$	820,300
12	Time-Related Overhead	\$	1,558,100
13	Total Roadway Contingency	\$	9,621,900
	TOTAL ROADWAY ITEMS	\$	48,109,300
	TOTAL NOADWAT TILMO	•	40,100,000
timate Prepared B	y: Name and Title	Date	Phone
	паше апо пое	Date	Prione
timate Reviewed B	Name and Title	Date	Phone

By signing this estimate you are attesting that you have discussed your project with all functional units and have incorporated all their comments or have discussed with them why they will not be incorporated.

Page 2 1/8/2024

SECTION 1: EARTHWORK

Item code		Unit	Quantity		Unit Price (\$)		Cost
190101	Roadway Excavation	CY		Х		=	\$ -
19010X	Roadway Excavation (Insert Type) ADL	CY		Х		=	\$ -
19801X	Imported Borrow	CY/TON		Х		=	\$ -
194001	Ditch Excavation	CY		Х		=	\$ -
192037	Structure Excavation (Retaining Wall)	CY		Х		=	\$ -
193013	Structure Backfill (Retaining Wall)	CY		Х		=	\$ -
193031	Pervious Backfill Material (Retaining Wall)	CY		Х		=	\$ -
17010X	Clearing & Grubbing	LS/ACRE	1	Х	15,000.00	=	\$ 15,000
100100	Develop Water Supply	LS		Х		=	\$ -
19801X	Imported Borrow	CY/TON		Х		=	\$ -
21012X	Duff	CRE/SQF	Γ	Х		=	\$ -
XXXXXX	Some Item	Unit		Х		=	\$ -

TOTAL EARTHWORK SECTION ITEMS	\$	15,000
-------------------------------	----	--------

SECTION 2: PAVEMENT STRUCTURAL SECTION

Item codeUnitQuantityUnit Price (\$)Cost401050Jointed Plain Concrete PavementCYx=\$400050Continuously Reinforced Concrete PavementCYx=\$	-
	-
390132 Hot Mix Asphalt (Type A) TON x = \$	-
26020X Class 2 Aggregate Base TON/CY x = \$	-
250401 Class 4 Aggregate Subbase CY x = \$	-
	9,765
414240 Isolation Joint Seal (Asphalt Rubber) LF x = \$	· -
414241 Isolation Joint Seal (Silicone) LF x = \$	-
280010 Rapid Strength Concrete Base CY x = \$	-
410096 Drill and Bond (Dowel Bar) EA x = \$	-
390137 Rubberized Hot Mix Asphalt (Gap Graded) TON x 130.00 = \$	-
391006 Aspiral Direct (Geosynthetic Favernett TON x = \$	-
290201 Asphalt Treated Permeable Base CY x = \$	-
374002 Asphaltic Emulsion (Fog Seal Coat) TON x = \$	-
	0,000
377501 Slurry Seal TON x = \$	-
374493 Polymer Asphaltic Emulsion (Seal Coat) TON x = \$	-
370001 Sand Cover (Seal) TON x = \$	-
731530 Minor Concrete (Textured Paving) CY x = \$	-
731502 Minor Concrete (Miscellaneous Construction) CY x = \$	-
39407X Place Hot Mix Asphalt Dike (Insert Type) LF x = \$	-
398100 Remove Asphalt Concrete Dike LF x = \$	-
420201 Grind Existing Concrete Pavement SQYD x = \$	-
398300 Remove Base and Surfacing CY x = \$	-
390095 Replace Asphalt Concrete Surfacing CY x = \$	-
41800X Remove Concrete Pavement SQYD/CY x = \$	-
394090 Place Hot Mix Asphalt (Miscellaneous Area) SQYD x = \$	-
398200 Cold Plane Asphalt Concrete Pavement SQYD x = \$	-
846046 6" Rumble Strip (Asphalt Concrete Pavement) STA x = \$	-
846049 6" Rumble Strip (Concrete Pavement) STA x = \$	-
846051 12" Rumble Strip (Asphalt Concrete Pavement) STA x = \$	-
846052 12" Rumble Strip (Concrete Pavement) STA x = \$	-
420102 Groove Existing Concrete Pavement SQYD x = \$	-
394095 Roadside Paving (Miscellaneous Areas) SQYD x = \$	-
390136 Minor Hot Mix Asphalt TON x = \$	-
390132 Hot Mix Asphalt (Type A) TON 27,924 x 130.00 = \$ 3,63	0,120
	9,000
390137 Rubberized Hot Mix Asphalt (Gap Graded) TON 41,886 x 150.00 = \$ 6,28	2,900
	0,000
	0,000
XXXXXX Some Item Unit x = \$	-

TOTAL PAVEMENT STRUCTURAL SECTION ITEMS \$ 15,521,800

EA: DS-123456 PID: DS1234567

SECTION 3: DRAINAGE

Item code		Unit	Quantity		Unit Price (\$)			Cost	
71013X	Remove Culvert	EA/LF	•	х	*.,	=	\$	-	
710240	Modify Inlet	EA		х		=	\$	-	
710370	Sand Backfill	CY		х		=	\$	-	
71010X	Abandon Culvert	EA/LF		х		=	\$	-	
710196	Adjust Inlet	LF		х		=	\$	-	
710262	Cap Inlet	EA		х		=	\$	-	
510501	Minor Concrete	CY		х		=	\$	-	
510502	Minor Concrete (Minor Structure)	CY		х		=	\$	-	
731627	Minor Concrete (Curb, Sidewalk, and Curb Ramp)	CY		х		=	\$	-	
6101XX	XX" Alternative Pipe Culvert (Insert Type)	LF		х		=	\$	-	
6411XX	XX" Plastic Pipe	LF		х		=	\$	-	
65XXXX	XX" Reinforced Concrete Pipe (Insert Type)	LF		х		=	\$	-	
6811XX	XX" Plastic Pipe (Edge Drain)	LF		х		=	\$	-	
6901XX	XX" Corrugated Steel Pipe Downdrain (0.XXX" Thick)	LF		х		=	\$	-	
7006XX	XX" Corrugated Steel Pipe Inlet (0.XXX" Thick)	LF		х		=	\$	-	
7032XX	XX" Corrugated Steel Pipe Riser (0.XXX" Thick)	LF		х		=	\$	-	
7050XX	XX" Steel Flared End Section	EA		х		=	\$	-	
703233	Grated Line Drain	LF		х		=	\$	-	
72XXXX	Rock Slope Protection (Type and Method)	CY/TON		х		=	\$	-	
72901X	Rock Slope Protection Fabric (Insert Class)	SQYD		х		=	\$	-	
721420	Concrete (Ditch Lining)	CY		х		=	\$	-	
721430	Concrete (Channel Lining)	CY		х		=	\$	-	
750001	Miscellaneous Iron and Steel	LB		х		=	\$	-	
150820	Modify Inlet	EA	11	х	2,500.00	=	\$	27,500	
XXXXXX	Additional Drainage	LS		Х		=	\$	-	
					тот	AL	DRAI	NAGE ITEMS \$	27,500

SECTION 4: SPECIALTY ITEMS

Item code		Unit	Quantity		Unit Price (\$)			Cost	
520103	Bar Reinforced Steel (Retaining Wall)	LB	•	х		=	\$	-	
5100XX	Structural Concrete	CY		х		=	\$	-	
510060	Structural Concrete, Retaining Wall	CY		х		=	\$	-	
5201XX	Bar Reinforcing Steel	LB		х		=	\$	-	
080050	Progress Schedule (Critical Path Method)	LS		х		=	\$	-	
582001	Sound Wall (Masonry Block)	SQFT		х		=	\$	-	
510530	Minor Concrete (Wall)	CY		х		=	\$	-	
60005X	Remove Sound Wall	LF/LS/SQFT	-	х		=	\$	-	
190110	Lead Compliance Plan	LS	1	х	20,000.00	=	\$	20,000	
141120	Treated Wood Waste	LB		х		=	\$	-	
839750	Remove Barrier	LF		х		=	\$	-	
839752	Remove Guardrail	LF		х		=	\$	-	
710167	Remove Flared End Section	EA		х		=	\$	-	
8000XX	Chain Link Fence (Insert Type)	LF		х		=	\$	-	
80XXXX	XX" Chain Link Gate (Type CL-X)	EA		х		=	\$	-	
832007	Midwest Guardrail System	LF	478	х	75.00	=	\$	35,850	
839301	Single Thrie Beam Barrier	LF		х		=	\$	-	
839310	Double Thrie Beam Barrier	LF		х		=	\$	-	
839521	Cable Railing	LF		х		=	\$	-	
839566	Terminal System (Type CAT)	EA		х		=	\$	-	
839584	Alternative In-line Terminal System	EA		х		=	\$	-	
839585	Alternative Flared Terminal System	EA		х		=	\$	-	
4906XX	XX" Cast-In-Drilled-Hole Concrete Piling	LF		х		=	\$	-	
8396XX	Crash Cushion (Insert Type)	EA		х		=	\$	-	
8331XX	Concrete Barrier (Insert Type)	LF		х		=	\$	-	
475010	Retaining Wall (Segment 1 Type- 6A & 5) & Sidewalk	LS	1	х	1,574,405.00	=	\$	1,574,405	
	Retaining Wall (Segment 2 - Type 6A) & Sidewalk	LS	1	х	1,458,554.00		\$	1,458,554	
839701	Concrete Barrier (Type 60)	LF	144	х	350.00	=	\$	50,400	
780460	Anti-Graffiti Coating	SQFT		х		=	\$	-	
780450	Rock Stain	SQFT		х		=	\$	-	
4730XX	Reinforced Concrete Crib Wall (Insert Type)	SQFT		х		=	\$	-	
83954X	Transition Railing (Insert Type)	EA		х		=	\$	-	
780440	Prepare and Stain Concrete	SQFT		х		=	\$	-	
839561	Rail Tensioning Assembly	EA		х		=	\$	-	
839581	End Anchor Assembly (Type SFT)	EA	4	х	2,500.00	=	\$	10,000	
	Median Reduction and Pavement Replacement at median	LS		х		=	\$	5,624,058	
XXXX	Side Walk, Raised island and Curb repair	LS	1	х	100,000.00	=	\$	100,000	
					TOT	AL S	PE	CIALTY ITEMS	\$ 8,873,300

Effective immediately, districts must input estimated item quantities in blue text above in the PRSM database for the pay items listed in the Design Memo, dated April 9, 2018, when Project Report is approved (Milestone 200).

Page 4 1/8/2024

SECTION 5: ENVIRONMENTAL

5A - ENV	IRONMENTAL MITIGATION								
Item code		Unit	Quantity		Unit Price (\$)			Cost	
	Biological Mitigation (on-site)	LS		х	(.,)	=	\$	-	
80010X	Temporary Fence (Insert Type)	LF		х		=	\$	-	
130670	Temporary Reinforced Silt Fence	LF		х		=	\$	=	
					Subtotal E	Envi	ronme	ental Mitigation	\$
5B - LAN	DSCAPE AND IRRIGATION								
Item code		Unit	Quantity		Unit Price (\$)			Cost	
	Highway Planting	LS		Х		=	\$	-	
	Irrigation System	LS		Х		=	\$	-	
	Plant Establishment Work	LS		Х		=	\$	=	
	Follow-up Landscape Project	LS		X		=	\$	-	
	Remove Irrigation Facility Maintain Existing Planted Areas	LS LS		X X		_	\$ \$	-	
	Check and Test Existing Irrigation Facilities	LS		X		=	\$	_	
	Imported Topsoil	CY/TON		X		=	\$	_	
	Rock Blanket	SQFT/SQYD		Х		=	\$	_	
	Vegetation Control (Minor Concrete)	SQYD	300	Х	47.00	=	\$	14,100	
	Water Pollution Control	EA	1	х	360,000.00	=	\$	360,000	
2087XX	XX" Conduit (Use for Irrigation x-overs)	LF		х		=	\$	-	
20890X	Extend X" Conduit (Use for Extension of Irrigation	LF		х		=	\$	-	
					Subtotal L	and	scap	e and Irrigation	\$ 374,100
5C - ERO	SION CONTROL								
Item code		Unit	Quantity		Unit Price (\$)			Cost	
211111	Permanent Erosion Control Establishment Work	LS		X		=	\$	-	
210010	Move-In/Move-Out (Erosion Control)	EA	4 000	X	5.00	=	\$	-	
	Fiber Rolls	LF	1,000	X X	5.00	_	\$	5,000	
	Compost Sock Rolled Fracion Control Braduet (Insert Type)	LF		X		=	\$ \$	-	
	Rolled Erosion Control Product (Insert Type) Bonded Fiber Matrix	SQFT/ACRE		X		=	э \$	-	
	Hydromulch	SQFT		Х		=	\$ \$	_	
210420	-	SQFT		Х		=	\$	- -	
	Hydroseed	SQFT		х		=	\$	_	
	Compost	CY		Х		=	\$	-	
210610	Compost Incorporate Materials	CY SQFT		Х		=	\$	-	
210610 210630	Incorporate Materials			Х				- Erosion Control	\$ 5,000
210610	Incorporate Materials	SQFT		Х					\$ 5,000
210610 210630 5D - NPD Item code	Incorporate Materials ES	SQFT <i>Unit</i>	Quantity		Unit Price (\$)	Subt	otal E	Cost	\$ 5,000
210610 210630 5D - NPD Item code 130300	Incorporate Materials ES Prepare SWPPP	SQFT <i>Unit</i> LS	Quantity 1	x		Subt	otal E		\$ 5,000
210610 210630 5D - NPD Item code 130300 130200	Incorporate Materials ES Prepare SWPPP Prepare WPCP	SQFT <i>Unit</i> LS LS	1	x x	Unit Price (\$) 10,000.00	Subt = = =	s \$ \$	Cost 10,000	\$ 5,000
210610 210630 5D - NPD Item code 130300 130200 130100	Incorporate Materials ES Prepare SWPPP Prepare WPCP Job Site Management	SQFT Unit LS LS LS LS	1	x x x	Unit Price (\$) 10,000.00	Subt = = =	sotal E	Cost 10,000 - 10,000	\$ 5,000
210610 210630 5D - NPD Item code 130300 130200 130100 130330	Incorporate Materials ES Prepare SWPPP Prepare WPCP Job Site Management Storm Water Annual Report	SQFT Unit LS LS LS EA	1 1 2	x x x x	Unit Price (\$) 10,000.00 10,000.00 6,000.00	= = = = =	\$ \$ \$ \$	Cost 10,000 - 10,000 12,000	\$ 5,000
210610 210630 5D - NPD Item code 130300 130200 130100 130330 130310	Prepare SWPPP Prepare WPCP Job Site Management Storm Water Annual Report Rain Event Action Plan	SQFT Unit LS LS LS EA EA	1	x x x x	Unit Price (\$) 10,000.00	= = = = = =	\$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$	Cost 10,000 - 10,000	\$ 5,000
210610 210630 5D - NPD Item code 130300 130200 130100 130330 130310 130320	Prepare SWPPP Prepare WPCP Job Site Management Storm Water Annual Report Rain Event Action Plan Storm Water Sampling and Analysis Day	SQFT Unit LS LS LS EA EA	1 1 2	x x x x x	Unit Price (\$) 10,000.00 10,000.00 6,000.00	= = = = = =	\$ \$ \$ \$ \$ \$ \$ \$ \$	Cost 10,000 - 10,000 12,000	\$ 5,000
210610 210630 5D - NPD Item code 130300 130200 130100 130330 130310 130320 130520	Incorporate Materials ES Prepare SWPPP Prepare WPCP Job Site Management Storm Water Annual Report Rain Event Action Plan Storm Water Sampling and Analysis Day Temporary Hydraulic Mulch	Unit LS LS EA EA EA SQYD	1 1 2	x x x x x x	Unit Price (\$) 10,000.00 10,000.00 6,000.00	= = = = = =	\$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$	Cost 10,000 - 10,000 12,000	\$ 5,000
210610 210630 5D - NPD Item code 130300 130200 130100 130330 130310 130320 130520 130550	Prepare SWPPP Prepare WPCP Job Site Management Storm Water Annual Report Rain Event Action Plan Storm Water Sampling and Analysis Day	SQFT Unit LS LS LS EA EA	1 1 2	x x x x x	Unit Price (\$) 10,000.00 10,000.00 6,000.00	= = = = = = =	\$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$	Cost 10,000 - 10,000 12,000	\$ 5,000
210610 210630 5D - NPD Item code 130300 130200 130100 130330 130310 130320 130520 130550	Incorporate Materials ES Prepare SWPPP Prepare WPCP Job Site Management Storm Water Annual Report Rain Event Action Plan Storm Water Sampling and Analysis Day Temporary Hydraulic Mulch Temporary Hydroseed	Unit LS LS EA EA EA SQYD SQYD	1 1 2	x x x x x x	Unit Price (\$) 10,000.00 10,000.00 6,000.00	= = = = = = =	\$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$	Cost 10,000 - 10,000 12,000	\$ 5,000
210610 210630 5D - NPD Item code 130300 130200 130100 130330 130310 130320 130520 130550 130505 130640	Incorporate Materials ES Prepare SWPPP Prepare WPCP Job Site Management Storm Water Annual Report Rain Event Action Plan Storm Water Sampling and Analysis Day Temporary Hydraulic Mulch Temporary Hydroseed Move-In/Move-Out (Temporary Erosion Control)	Unit LS LS EA EA SQYD SQYD EA	1 1 2 10	x x x x x x x	Unit Price (\$) 10,000.00 10,000.00 6,000.00 1,000.00	= = = = = = = = = = = = = = = = = = =	\$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$	Cost 10,000 - 10,000 12,000 10,000 - - -	\$ 5,000
210610 210630 5D - NPD Item code 130300 130200 130100 130330 130310 130320 130520 130550 130505 130640 130900	Incorporate Materials ES Prepare SWPPP Prepare WPCP Job Site Management Storm Water Annual Report Rain Event Action Plan Storm Water Sampling and Analysis Day Temporary Hydraulic Mulch Temporary Hydroseed Move-In/Move-Out (Temporary Erosion Control) Temporary Fiber Roll	Unit LS LS EA EA SQYD SQYD EA LF	1 1 2 10	x x x x x x x x x x x x x x x x x x x	Unit Price (\$) 10,000.00 10,000.00 6,000.00 1,000.00	= = = = = = = = = = = = = = = = = = =	**************************************	Cost 10,000 - 10,000 12,000 10,000 - - - 5,000	\$ 5,000
210610 210630 5D - NPD Item code 130300 130200 130100 130330 130310 130320 130520 130550 130505 130640 130900 130710	Prepare SWPPP Prepare WPCP Job Site Management Storm Water Annual Report Rain Event Action Plan Storm Water Sampling and Analysis Day Temporary Hydraulic Mulch Temporary Hydroseed Move-In/Move-Out (Temporary Erosion Control) Temporary Fiber Roll Temporary Concrete Washout	Unit LS LS EA EA SQYD SQYD EA LF LS	1 1 2 10	x x x x x x x x x x x x x x x x x x x	Unit Price (\$) 10,000.00 10,000.00 6,000.00 1,000.00	= = = = = = = = = = = = = = = = = = =	**************************************	Cost 10,000 - 10,000 12,000 10,000 - - - 5,000	\$ 5,000
210610 210630 5D - NPD Item code 130300 130200 130100 130330 130310 130520 130550 130550 130640 130900 130710 130610 130620	Prepare SWPPP Prepare WPCP Job Site Management Storm Water Annual Report Rain Event Action Plan Storm Water Sampling and Analysis Day Temporary Hydraulic Mulch Temporary Hydroseed Move-In/Move-Out (Temporary Erosion Control) Temporary Fiber Roll Temporary Concrete Washout Temporary Construction Entrance Temporary Drainage Inlet Protection	Unit LS LS EA EA SQYD SQYD EA LF LS EA LF EA	1 1 2 10	x x x x x x x x x x x x x x x x x x x	Unit Price (\$) 10,000.00 10,000.00 6,000.00 1,000.00	= = = = = = = = = = = = = = = = = = =	otal E	Cost 10,000 - 10,000 12,000 10,000 - - - 5,000	\$ 5,000
210610 210630 5D - NPD Item code 130300 130200 130100 130330 130310 130320 130550 130550 130505 130640 130900 130710 130610 130620	Prepare SWPPP Prepare WPCP Job Site Management Storm Water Annual Report Rain Event Action Plan Storm Water Sampling and Analysis Day Temporary Hydraulic Mulch Temporary Hydroseed Move-In/Move-Out (Temporary Erosion Control) Temporary Fiber Roll Temporary Concrete Washout Temporary Construction Entrance Temporary Check Dam	Unit LS LS EA EA SQYD SQYD EA LF LS EA LF	1 1 2 10	x x x x x x x x x x x x x x x x x x x	Unit Price (\$) 10,000.00 10,000.00 6,000.00 1,000.00	= = = = = = = = = = = = = = = = = = =	otal E	Cost 10,000 - 10,000 12,000 10,000 - - - 5,000	\$ 5,000
210610 210630 5D - NPD Item code 130300 130200 130100 130330 130310 130520 130550 130550 130640 130900 130710 130610 130620	Prepare SWPPP Prepare WPCP Job Site Management Storm Water Annual Report Rain Event Action Plan Storm Water Sampling and Analysis Day Temporary Hydraulic Mulch Temporary Hydroseed Move-In/Move-Out (Temporary Erosion Control) Temporary Fiber Roll Temporary Concrete Washout Temporary Construction Entrance Temporary Drainage Inlet Protection	Unit LS LS EA EA SQYD SQYD EA LF LS EA LF EA	1 1 2 10 1,000 1	x x x x x x x x x x x x x x x x x x x	Unit Price (\$) 10,000.00 10,000.00 6,000.00 1,000.00 5.00 35,000.00	= = = = = = = = = = = = = = = = = = =	otal E	Cost 10,000 - 10,000 12,000 10,000 5,000 35,000	\$ 5,000
210610 210630 5D - NPD Item code 130300 130200 130100 130330 130310 130320 130550 130550 130505 130640 130900 130710 130610 130620	Prepare SWPPP Prepare WPCP Job Site Management Storm Water Annual Report Rain Event Action Plan Storm Water Sampling and Analysis Day Temporary Hydraulic Mulch Temporary Hydroseed Move-In/Move-Out (Temporary Erosion Control) Temporary Fiber Roll Temporary Concrete Washout Temporary Construction Entrance Temporary Drainage Inlet Protection	Unit LS LS EA EA SQYD SQYD EA LF LS EA LF EA	1 1 2 10 1,000 1	x x x x x x x x x x x x x x x x x x x	Unit Price (\$) 10,000.00 10,000.00 6,000.00 1,000.00 5.00 35,000.00	= = = = = = = = = = = = = = = = = = =	otal E	Cost 10,000 - 10,000 12,000 10,000 5,000 35,000 50,000	
210610 210630 5D - NPD Item code 130300 130200 130100 130330 130310 130320 130550 130550 130505 130640 130900 130710 130610 130620	Prepare SWPPP Prepare WPCP Job Site Management Storm Water Annual Report Rain Event Action Plan Storm Water Sampling and Analysis Day Temporary Hydraulic Mulch Temporary Hydroseed Move-In/Move-Out (Temporary Erosion Control) Temporary Fiber Roll Temporary Concrete Washout Temporary Construction Entrance Temporary Drainage Inlet Protection	Unit LS LS EA EA SQYD SQYD EA LF LS EA LF EA	1 1 2 10 1,000 1	x x x x x x x x x x x x x x x x x x x	Unit Price (\$) 10,000.00 10,000.00 6,000.00 1,000.00 5.00 35,000.00	= = = = = = = = = = = = = = = = = = =	otal E	Cost 10,000 - 10,000 12,000 10,000 5,000 35,000	\$ 5,000
210610 210630 5D - NPD Item code 130300 130200 130100 130330 130310 130320 130550 130550 130505 130640 130900 130710 130610 130620	Prepare SWPPP Prepare WPCP Job Site Management Storm Water Annual Report Rain Event Action Plan Storm Water Sampling and Analysis Day Temporary Hydraulic Mulch Temporary Hydroseed Move-In/Move-Out (Temporary Erosion Control) Temporary Fiber Roll Temporary Concrete Washout Temporary Construction Entrance Temporary Drainage Inlet Protection	Unit LS LS EA EA SQYD SQYD EA LF LS EA LF EA	1 1 2 10 1,000 1	x x x x x x x x x x x x x x x x x x x	Unit Price (\$) 10,000.00 10,000.00 6,000.00 1,000.00 5.00 35,000.00	=	otal E	Cost 10,000 - 10,000 12,000 10,000 5,000 35,000 50,000	
210610 210630 5D - NPD Item code 130300 130200 130100 130330 130320 130550 130550 130550 130640 130900 130710 130610 130620 130730	Prepare SWPPP Prepare WPCP Job Site Management Storm Water Annual Report Rain Event Action Plan Storm Water Sampling and Analysis Day Temporary Hydraulic Mulch Temporary Hydroseed Move-In/Move-Out (Temporary Erosion Control) Temporary Fiber Roll Temporary Concrete Washout Temporary Construction Entrance Temporary Drainage Inlet Protection	Unit LS LS EA EA SQYD SQYD EA LF LS EA LF EA	1 1 2 10 1,000 1	x x x x x x x x x x x x x x x x x x x	Unit Price (\$) 10,000.00 10,000.00 6,000.00 1,000.00 5.00 35,000.00	=	otal E	Cost 10,000 - 10,000 12,000 10,000 5,000 35,000 50,000	\$ 132,000
210610 210630 5D - NPD Item code 130300 130200 130100 130330 130320 130550 130550 130550 130640 130900 130710 130610 130620 130730	Prepare SWPPP Prepare WPCP Job Site Management Storm Water Annual Report Rain Event Action Plan Storm Water Sampling and Analysis Day Temporary Hydraulic Mulch Temporary Hydraulic Mulch Temporary Fiber Roll Temporary Construction Entrance Temporary Construction Entrance Temporary Drainage Inlet Protection Street Sweeping Pental Work for NPDES Water Pollution Control Maintenance Sharing*	SQFT Unit LS LS LS EA EA SQYD EA LF LS EA LF EA LS LS	1 1 2 10 1,000 1	x x x x x x x x x x x x x x x x x x x	Unit Price (\$) 10,000.00 10,000.00 6,000.00 1,000.00 5.00 35,000.00 TOTA	= = = = = = = = = = = = = = = = = = =	otal E	Cost 10,000 - 10,000 12,000 10,000 5,000 35,000 50,000 cototal NPDES	\$ 132,000
210610 210630 5D - NPD Item code 130300 130200 130100 130330 130310 130520 130550 130550 130640 130710 130610 130620 130730	Prepare SWPPP Prepare WPCP Job Site Management Storm Water Annual Report Rain Event Action Plan Storm Water Sampling and Analysis Day Temporary Hydraulic Mulch Temporary Hydroseed Move-In/Move-Out (Temporary Erosion Control) Temporary Fiber Roll Temporary Concrete Washout Temporary Construction Entrance Temporary Check Dam Temporary Drainage Inlet Protection Street Sweeping Pental Work for NPDES Water Pollution Control Maintenance Sharing* Additional Water Pollution Control**	SQFT Unit LS LS LS EA EA SQYD EA LF LS EA LF EA LS LS LS LS LS LS	1 1 2 10 1,000 1	x x x x x x x x x x x x x x x x x x x	Unit Price (\$) 10,000.00 10,000.00 6,000.00 1,000.00 5.00 35,000.00	= = = = = = = = = = = = = = = = = = =	otal E	Cost 10,000 - 10,000 12,000 10,000 5,000 35,000 50,000 cototal NPDES	\$ 132,000
210610 210630 5D - NPD Item code 130300 130200 130100 130330 130320 130550 130550 130505 130640 130710 130610 130620 130730	Prepare SWPPP Prepare WPCP Job Site Management Storm Water Annual Report Rain Event Action Plan Storm Water Sampling and Analysis Day Temporary Hydraulic Mulch Temporary Hydroseed Move-In/Move-Out (Temporary Erosion Control) Temporary Fiber Roll Temporary Concrete Washout Temporary Construction Entrance Temporary Drainage Inlet Protection Street Sweeping ental Work for NPDES Water Pollution Control Maintenance Sharing* Additional Water Pollution Control** Storm Water Sampling and Analysis***	SQFT Unit LS LS LS EA EA SQYD EA LF LS EA LF EA LS LS LS LS LS LS	1 1 2 10 1,000 1	x x x x x x x x x x x x x x x x x x x	Unit Price (\$) 10,000.00 10,000.00 6,000.00 1,000.00 5.00 35,000.00 TOTA	= = = = = = = = = = = = = = = = = = =	otal E	Cost 10,000 - 10,000 12,000 10,000 5,000 35,000 50,000 cototal NPDES	\$ 132,000
210610 210630 5D - NPD Item code 130300 130200 130100 130330 130320 130550 130550 130550 130640 130710 130610 130620 130730	Prepare SWPPP Prepare WPCP Job Site Management Storm Water Annual Report Rain Event Action Plan Storm Water Sampling and Analysis Day Temporary Hydraulic Mulch Temporary Hydroseed Move-In/Move-Out (Temporary Erosion Control) Temporary Fiber Roll Temporary Concrete Washout Temporary Construction Entrance Temporary Check Dam Temporary Drainage Inlet Protection Street Sweeping Pental Work for NPDES Water Pollution Control Maintenance Sharing* Additional Water Pollution Control**	SQFT Unit LS LS LS EA EA SQYD EA LF LS EA LF EA LS LS LS LS LS LS	1 1 2 10 1,000 1	x x x x x x x x x x x x x x x x x x x	Unit Price (\$) 10,000.00 10,000.00 6,000.00 1,000.00 5.00 35,000.00 TOTA	= = = = = = = = = = = = = = = = = = =	otal E	Cost 10,000 - 10,000 12,000 10,000 5,000 35,000 50,000 cototal NPDES COMMENTAL 100,000 10,000	\$ 132,000

 $^{^{\}star}$ Applies to all SWPPPs and those WPCPs with sediment control or soil stabilization BMPs.

Page 5 1/8/2024

^{**}Applies to both SWPPPs and WPCP projects.

^{***} Applies only to project with SWPPPs.

SECTION 6: TRAFFIC ITEMS

6A - Traff	ic Electrical								
Item code		Unit	Quantity		Unit Price (\$)			Cost	
870200	Lighting System	LS	-	Х		=	\$	-	
870300	Sign Illumination System	LS		Х		=	\$	-	
870400	0 0,	LS		Х		=	\$	-	
870510	Ramp Metering System	LS		Х		=	\$	-	
87181X	Interconnection Conduit and Cable	LF/LS		Х		=	\$	_	
5602XX	Furnish Sign Structure (Insert Type)	LB		Х		=	\$	_	
5602XX	Install Sign Structure (Insert Type)	LB		Х		=	\$	_	
4980XX	XX" CIDHC Pile (Sign Foundation)	LF		Х		=	\$	_	
87011X	Inductive Loop Detector	EA/LS		Х		=	\$	_	
870600	Traffic Monitoring Station System	LS		Х		=	\$	_	
56804X	Remove Sign Structure	EA/LS		Х		=	\$	-	
568054	Reconstruct Sign Structure	EA		Х		=	\$	-	
568060	Modify Sign Structure	EA		Х		=	\$	-	
870009	Elements During Construction	LS	1	Х	100,000.00	=	\$	100,000	
86XXXX	Protect Fiber Optic Conduit System	LS	1	х	160,000.00	=	\$	160,000	
872130	Relocate Signal Structures/ Pull Boxes, and Loop	LS	1	Х	1,500,000.00	=	\$	1,500,000	
	Some Item	Unit		Х	, ,	=	\$	-	
					Su	ıbtoi	al Tı	raffic Electrical	\$ 1,760,000
6B - Traff	ic Signing and Striping								
Item code		Unit	Quantity		Unit Price (\$)			Cost	
820840	Roadside Sign - One Post	EA	1	Х	10,000.00	=	\$	10,000	
820850	Roadside Sign - Two Post	EA		х		=	\$	· <u>-</u>	
5602XX	Furnish Sign Structure (Insert Type)	SQFT		х		=	\$	_	
820890	Install Sign Panel on Existing Frame	SQFT		х		=	\$	_	
846020	Remove Painted Traffic Stripe	LF		Х		=	\$	-	
141102	Remove Yellow Painted Traffic Stripe (Hazardous	LF	1,040,600	Х	2.00	=	\$	2,081,200	
846025	Remove Painted Pavement Marking	SQFT		х		=	\$	-	
820250	Remove Roadside Sign	EA		Х		=	\$	_	
820530	3	EA		х		=	\$	_	
820610	Relocate Roadside Sign	EA		х		=	\$	_	
820101	Delineator (Marker)	EA	970	х	10.00	=	\$	9,700	
840502	, ,	LF	160,600	х	3.00	=	\$	481,800	
846012		SQFT	•	х		=	\$	· -	
120090	Construction Area Signs	LS	1	х	100,000.00	=	\$	100,000	
	Permanent Pavement Delineation	LS		Х	•	=	\$	-	
					Subtotal Traff	fic S	ignin	ng and Striping	\$ 2,682,700
CC T==ff	in Managamant Plan								
	ic Management Plan	1.1-14	Our matitus		Linit Duine (A)			04	
Item code	Deutahla Channachla Massana Cian	Unit	Quantity		Unit Price (\$)		ф	Cost	
12805X	Portable Changeable Message Sign	EA/LS	4	Х	\$ 1,500	=	\$	6,000	
					Subtotal Tra	affic	Man	nagement Plan	\$ 6,000
6C - Stag	e Construction and Traffic Handling								
Item code		Unit	Quantity		Unit Price (\$)			Cost	
120198	Plastic Traffic Drums	EA		Х		=	\$	-	
12016X	Channelizer (Insert Type)	EA		Х		=	\$	-	
120116	Type II Barricade	EA		Х		=	\$	-	
120120	Type III Barricade	EA		Х		=	\$	-	
	Temporary Crash Cushion Module	EA		Х		=	\$	-	
	Traffic Control System	LS	1	Х	280,000.00	=	\$	280,000	
	Temporary Crash Cushion	EA		Х		=	\$	-	
129000	Temporary Railing (Type K)	LF		Х		=	\$	-	
	Temporary Pavement Marking (Paint)	SQFT		Х		=	\$	-	
	Temporary Pavement Marking (Tape)	SQFT		Х		=	\$	-	
8101XX	Delineator (Insert Class)	EA		Х		=	\$	-	
			Subto	tal S	tage Construction	on a	nd T	raffic Handling	\$ 280,000
					TC	OTA	L TF	RAFFIC ITEMS	\$ 4,728,700

SECTION 7: DETOURS

Includes constructing, maintaining, and removal

Item code		Unit	Quantity	Unit Price (\$)	Cost	
190101	Roadway Excavation	CY	;	(=	\$	-
19801X	Imported Borrow	CY/TON	,	=	\$	-
390132	Hot Mix Asphalt (Type A)	TON	,	(=	\$	-
26020X	Class 2 Aggregate Base	CY/TON	,	(=	\$	-
250401	Class 4 Aggregate Subbase	CY)	(=	\$	-
130620	Temporary Drainage Inlet Protection	EA)	(=	\$	-
129000	Temporary Railing (Type K)	LF		(=	\$	-
128601	Temporary Signal System	LS)	(=	\$	-
120149	Temporary Pavement Marking (Paint)	SQFT)	(=	\$	-
80010X	Temporary Fence (Insert Type)	LF)	(=	\$	-
XXXXXX	Some Item	LS)	=	\$	-

TOTAL DETOURS \$ -

SUBTOTAL SECTIONS 1 through 7 \$ 29,677,400

SECTION 8: MINOR ITEMS

8A - Americans with Disabilities Act Items 1.0% 296,774 ADA Items \$ 8B - Bike Path Items Bike Path Items 1.0% \$ 296,774 8C - Other Minor Items 3.0% Other Minor Items \$ 890,322 Total of Section 1-7 \$ 29,677,400 5.0% \$ 1,483,870

TOTAL MINOR ITEMS \$ 1,483,900

SECTIONS 9: ROADWAY MOBILIZATION

Item code

999990 Total Section 1-8 \$31,161,300 x 10% = \$3,116,130

TOTAL ROADWAY MOBILIZATION \$ 3,116,200

SECTION 10: SUPPLEMENTAL WORK

Item code		Unit	Quantity		Unit Price (\$)		Cost
066670	Payment Adjustments For Price Index Fluctuations	LS	1	х	300,000.00	=	\$ 300,000
066094	Value Analysis	LS		Х		=	\$ -
066070	Maintain Traffic	LS	1	Х	150,000.00	=	\$ 150,000
066919	Dispute Resolution Board	LS	1	х	25,000.00	=	\$ 25,000
066921	Dispute Resolution Advisor	LS		х		=	\$ -
066015	Federal Trainee Program	LS		х		=	\$ -
066610	Partnering	LS		Х		=	\$ -
066204	Remove Rock and Debris	LS		х		=	\$ -
066222	Locate Existing Crossover	LS		Х		=	\$ -
XXXXXX	Some Item	Unit		х		=	\$ -

Cost of NPDES Supplemental Work specified in Section 5D = \$ 110,000

Total Section 1-8 \$ 31,161,300 4% = \$ 1,246,452

TOTAL SUPPLEMENTAL WORK \$ 1,831,500

EA: DS-123456 PID: DS1234567

SECTION 11: STATE FURNISHED MATERIALS AND EXPENSES

Item code		Unit	Quantity		Unit Price (\$)		Cost
066105	Resident Engineers Office	LS	1	Х	150,000.00	=	\$150,000
066063	Traffic Management Plan - Public Information	LS	1	Х	5,000.00	=	\$5,000
066901	Water Expenses	LS		Х		=	\$0
8609XX	Traffic Monitoring Station (X)	LS		Х		=	\$0
066841	Traffic Controller Assembly	LS		Х		=	\$0
066840	Traffic Signal Controller Assembly	LS		Х		=	\$0
066062	COZEEP Contract	LS	1	Х	42,000.00	=	\$42,000
066838	Reflective Numbers and Edge Sealer	LS		Х		=	\$0
066065	Tow Truck Service Patrol	LS		Х		=	\$0
066916	Annual Construction General Permit Fee	LS		Х		=	\$0
XXXXXX	Some Item	Unit		Х		=	\$0
	Total Section 1-8		\$ 31.161.300		2%	=	\$ 623.226

TOTAL STATE FURNISHED \$820,300

SECTION 12: TIME-RELATED OVERHEAD

Total of Roadway and Structures Contract Items excluding Mobilization

\$31,161,300 (used to calculate total TRO)

Estimated Time-Related Overhead (TRO) Percentage (0% to 10%) = 5%

Item code	Unit	Quantity		Unit Price (\$)		Cost
090100 Time-Related Overhead	WD	360	Х	\$4,328	=	\$1,558,100

TOTAL TIME-RELATED OVERHEAD \$1,558,100

SECTION 13: ROADWAY CONTINGENCY*

Risk Amount from Risk Register		(for Known Risks)	5%		\$2,000,000	
Additional or Residual Contingency	(for Unknow	vn/Undefined Risks	s)	20%		\$7,621,850	
Total Section 1-12	\$	38,487,400	х	25%	=	\$9,621,850	

TOTAL CONTINGENCY* \$9,621,900

II. STRUCTURE ITEMS

	Bridge 1	Bridge 2		
DATE OF ESTIMATE	00/00/00	00/00/00		00/00/00
Bridge Name	xxxxxxxxxxxxxxxxx	xxxxxxxxxxxxxxxxx	xxxx	xxxxxxxxxxx
Bridge Number	57-XXX	57-XXX		57-XXX
Structure Type	xxxxxxxxxxxxxxxx	xxxxxxxxxxxxxxxx	xxxx	xxxxxxxxxxx
Width (Feet) [out to out]	LF	LF	c) LF
Total Bridge Length (Feet)	LF	LF	c	- -
Total Area (Square Feet)	0 SQFT	0 SQFT	c	SQFT
Structure Depth (Feet)	0 LF	0 LF	C) LF
Footing Type (pile or spread)	xxxxxxxxxxxxxxxx	xxxxxxxxxxxxxxxx	XXXX	XXXXXXXXXXXXX
Cost Per Square Foot	\$150	\$150		\$0
COST OF EACH	\$0	\$0	<u> </u>	\$0
	Building 1	1	I	
DATE OF ESTIMATE	00/00/00	00/00/00		00/00/00
Building Name	xxxxxxxxxxxxxxxx	xxxxxxxxxxxxxxxxx	xxxx	xxxxxxxxxxx
Bridge Number	57-XXX	57-XXX		57-XXX
Structure Type	xxxxxxxxxxxxxxxx	xxxxxxxxxxxxxxxx	xxxx	xxxxxxxxxxx
Width (Feet) [out to out]	LF	0 LF	C) LF
Total Building Length (Feet)	LF	0 LF	c) LF
Total Area (Square Feet)	0 SQFT	0 SQFT	c	
Structure Depth (Feet)	0 LF	0 LF	C) LF
Footing Type (pile or spread)	xxxxxxxxxxxxxxx	xxxxxxxxxxxxxxx	xxxx	XXXXXXXXXXXXX
Cost Per Square Foot	\$300	\$0		\$0
COST OF EACH	\$0	\$0		\$0
		TOTAL COST OF B	RIDGES	\$0
		TOTAL COST OF BU	JILDINGS	\$0
		Time-Related Overhead	10%	\$0
		STRUCTURES MOBILIZATION	10%	\$0
		STRUCTURES CONTINGENCY*	25%	\$0
	TO.	TAL COST OF STRUCTURES		\$0

XXXXXXXXXXXXXXXX ----- Division of Structures

Page 9 1/8/2024

Date

EA: DS-123456 PID: DS1234567

III. RIGHT OF WAY

Fill in all of the available information from the Right of Way Data Sheet.

ı ııı ııı aıı	of the available information in	om the Right of Way Data Sheet.	(Current Value Future Use		Escalated Value
A)	A1) Acquisition, incl Damages, Goo	uding Excess Land, Fees,	\$		\$	74.40
	A2) SB-1210	uwiii	\$	1,661,058	\$	2,499,741
B)	B1) Utility Relocatio	n (State Share)	\$		\$	
	B2) Potholing (Design	gn Phase)	\$	486,000	\$	908,319
C)	Utility - Advance Engineeri (Encumber with State Only		\$	0	\$	0
D)	RAP and/or Last Resort Ho	pusing	\$	0	\$	0
E)	Clearance & Demolition		\$	0	\$	0
F)	Relocation Assistance (RA	P and/or Last Resort Housing Costs)	\$	0	\$	0
G)	Title and Escrow Reimbursed Appraisal Fee		\$ \$	71,721 67,500	\$ \$	107,932 67,500
H)	Environmental Review		\$	0	\$	0
I)	Condemnation Settlements	0%	\$	0	\$	0
J)	Design Appreciation Facto	n0%_	\$	0	\$	0
K)	Utility Relocation (Construc	ction Cost)	\$	0	\$	0
L)		TOTAL RIGHT O	F WAY E	ESTIMATE		\$2,286,300
M)		TOTAL R/W EST	IMATE:	Escalated		\$3,583,500
N)		RIGHT OF V	VAY SUF	PPORT		\$44,721
	Cost Estimate	oject Coordinator ¹		Phone		_
Utility Esti	mate Prepared	ility Coordinator ²		Dhono		_
	, (1	inty Coolullator		Phone		
D.04/ *	isition Estimate					

Note: Items G & H applied to items A + B

Page 10 1/8/2024

¹ When estimate has Support Costs only

 $^{^{2}\,\}mathrm{When}$ estimate has Utility Relocation $^{-3}\,\mathrm{When}$ R/W Acquisition is required

EA: DS-123456 PID: DS1234567

IV. SUPPORT COST ESTIMATE SUMMARY Run a <u>Support Cost Estimate Summary</u> report (D1

report (D11 Project Management Support onramp) for component data.

Total by FY <2015/16 E 2016/17 E 2017/18 E		PARED	PS&F	MG	CON	Total \$	PA&ED	DCRE	WA	CON	Total \$
	I							1 50			
	Expended										
	ETC										
	Expended										
	ETC										
	Expended	\$2,000,000				000 000 00	\$2,000,000				000 000 00
_	ETC					22,000,000					\$4,000,000
2018/19	Expended					64 040 440					64 040 440
	ETC	\$1,019,440				044,610,14	\$1,019,440				91,019,440
2019/20	Expended					6000					¢047 E07
	ETC	\$909,402				4903,40Z	\$947,597				4947,097
2020/21	Expended					64 647 479					64 788 773
	ETC	\$8,286	\$1,633,898	\$5,295		011,170,19	\$8,996	\$1,774,028	\$5,749		011,001,10
2021/22	Expended					\$1 320 275					\$1 493 715
	ETC		\$1,287,021	\$33,254		61,520,19		\$1,456,092	\$37,623		01,400,10
2022/23	Expended					64 945 434					69 257 707
	ETC		\$28,122	\$1,015	\$1,885,987	41,515,124		\$33,152	\$1,196	\$2,223,359	\$2,237,707
2023/24	Expended					64 522 836					64 000 004
	ETC			\$124	\$1,532,712	¢1,002,000			\$153	\$1,882,778	41,002,001
2024/25	Expended					\$540.254					\$691.516
	ETC				\$540,251					\$691,516	21.20
2025/26	Expended					\$228 100					\$304 229
	ETC				\$228,100					\$304,229	
2026/27	Expended					\$173.826					\$241 578
	ETC				\$173,826					\$241,578	
2027/28	Expended					\$3.184					\$4.610
	ETC				\$3,184					\$4,610	
2028/29	Expended										
02/02/02	EIC									Ī	
	Lyberided										
FAC (Exnended + FTC)	+ 110	£3 937 128	\$2 949 041	639 688	\$4 364 060	£44 200 047	63 976 033	£3.263.272	SAA 721	&£ 348 070	642 622 006
1 - 1 - 1 - 1 - 1 - 1 - 1 - 1 - 1 - 1 -	in the contraction of	000 0000	000 0074	9700 000	200,000,000	116,602,114	000 0074	1 1 0 0 1 0	4400 400	0.000.000	000,200,310
KISK AMOUNT TOM KISK REGISTER	ISK Register	\$100,000	000,001\$	000,000¢	000,001\$	\$100,000 Escalated Risk Amount	\$103,200	Z0C,001¢	\$1.08,193	\$77,611\$	\$433,124
Support Escalation Rate	on Kate	3.2%	3.2%	3.2%	3.2%						
Duration to mid-point component	t component	1.00	2.00	2.50	4.50						
Total including Risk Amount	sk Amount	\$4,037,128	\$3,049,041	\$139,688	\$4,464,060	\$4,464,060 Total Esc. Support Cost	\$4,079,233	\$3,369,774	\$152,914	\$5,463,298	\$13,065,220
Approved Budget (PRSM)	t (PRSM)										
Difference (Budget - EAC)	et - EAC)	-\$3,937,128	-\$2,949,041	889'68\$-	-\$4,364,060	-\$11,289,917	\$4,079,233	-\$3,263,272	-\$44,721	-\$5,348,070	-\$4,576,830
Support Ratio (EAC / Cap Cost)	/ Cap Cost)	%9'9	4.9%	0.1%	7.2%	18.7%	%9'9	5.4%	0.1%	8.9%	21.0%

60,262,000	Cost: 13,065,220	ost: 21.7%
Total Capital Cost:	Total Capital Outlay Support Cost:	Overall Percent Support Cost:

workplan hours/costs verified	against approved MWA:
RSN	

Approved by:

Office Chief -

Date

Project Control -

Date

DO NOT PRINT THIS SHEET AS PART OF COST ESTIMATE ATTACHMENT TO PROJECT INITIATION OR APPROVAL DOCUMENTS.

PIR Input Table: Provided here to facilitate input into the PIR Programmable Alternative Table in PIR document.

Gray cells are not in PIR Table	in PIR Table	Blu	e cells are fo	Blue cells are for Input from elsewhere	elsewh	ere					
Column Headings in the PIR Table	in the PIR Table										
Component or Sub-phase	(C) Base Estimate (Total Most Likely Amount)	Ris	(D) Risk Amount	(E) Total Including Risk (C+D) (Total Current		(F) # of Years to mid-point of Component	(G) Escalation Rate	ш '	(H) Escalation Amount	Pro	(1) Program Amount (E+H) (Total Escalated Cost)
Support					П						
PA&ED	\$ 3,937,128	\$	100,000	\$ 4,037,128	,128	1.0	3.2%	\$	129,188	\$	4,079,233
PS&E	\$ 2,949,041	❖	100,000	\$ 3,049,041	,041	2.0	3.2%	φ.	198,261	❖	3,369,774
Right of Way	\$ 39,688	❖	100,000	\$ 139	139,688	2.5	3.2%	❖	11,445	\$	152,914
Construction	\$ 4,364,060	\$	100,000	\$ 4,464,060	090′1	4.5	3.2%	\$	679,794	\$	5,463,298
Support Total	\$ 11,289,917	\$	400,000	\$ 11,690,000	000′(0 \$	\$	1,018,688	\$	13,066,000
	Current Year Base Estimate with Total Contengency less	Ris	Risk Amount	Total Including Risk (Total Current	ding						
Capital	Risk Amount			Year Cost)	it)						
Right of Way	\$ 2,286,300	\$	1,000,000	\$ 3,286,300	300,	1.5	3.2%	\$	1,297,200	\$	3,583,500
Construction	\$ 46,109,300	⊹	2,000,000	\$ 48,109,300	300 (1.5	3.2%	φ.	2,327,623	φ.	50,436,923
Capital Total	\$ 48,396,000	\$	3,000,000	\$ 51,396,000	000′			\$	3,624,823	\$	54,021,000
Total Project Cost	\$ 60,000,000	\$	3,400,000	\$ 63,100,000	000′(\$	4,643,511	\$	68,000,000
				7						1	

Note: See the notes in red comment marks at the top right of cells.

158,998

Rounded Amounts

RISK REGISTER – Attachment L

RISK REGISTER CERTIFICATION (ACCOUNTABILITY CHECKPOINTS) FORM

PPM-D07-0001 (REV 05/2022)

The risk register is to be approved and signed-off by the District Deputies listed below for all scalability levels. By signing this form, you are certifying that you have reviewed the risks documented in the register and agree that they have been managed to the extent possible by the PDT.

<u>Project Information</u> ■Capital Project □Major	Maintenance Project(Check One) Total Capital Cost: \$44,494,000
Project ID/District-EA:	Project ID: 0718000076/ EA-07-346600
Project Description/ Route/ Post-Mile:	Roadway Preservation/ LA-213-0/10
Project Manager:	Carlos Loera
Project Risk Manager:	Syed A. Huq
□ No Risk Register Certification Required Check box if proform with PID, PA&ED, PS&E submittal, and RE Handoff F	oject is less than \$1 million in total cost and risk register not prepared. Sign below and submit this File (as applicable).
Project Manager Signature	Date:
PID (Required for Capital Projects)	
Project Manager	Date:
Deputy District Director, Planning	Date:
Deputy District Director, Design	Date:
Deputy District Director, Rightof Way	Date:
Deputy District Director, Environmental	Date:
Deputy District Director,Traffic Operations	Date:
Deputy District Director, Maintenance	Date:
Deputy District Director, Project Management	Date:
PA&ED (Required for Capital Projects)	C 1
Project Manager	Date: 06/19/2024
Deputy District Director, Design	Brezory Fan Date: 06/20/2024
Deputy District Director, Construction	Assam Abumuhor Date: 06/21/2024
Deputy District Director, Rightof Way	Wayne D. Lee
Deputy District Director, Environmental	Date: 06/19/2024
Deputy District Director, Traffic Operations	Date: 06/20/2024
Deputy District Director, Maintenance	Hamid Saadatnejadi Date: 06/26/2024
Deputy District Director, Project Management	Ngim N. Pe
Prior to PS&E (Required for Capital Projects)	
Project Manager	Date:
Deputy District Director, Design	Date:
Deputy District Director, Construction	Date:
Deputy District Director, Rightof Way	Date:
Deputy District Director, Environmental	Date:
Deputy District Director, Traffic Operations	Date:
Deputy District Director, Maintenance	
Deputy District Director, Project Management	
Dopar, Diotrior Director, Froject Management	

EA-07-346600, EFIS ID: 0718000076			Milestones			Duration	Base RW Cap Est (k): \$949	PM: Carlos Loera
Route & Post Mile: LA-275-Q/N	Q	PA&ED	PS&E	Ш	CCA	Con Working Days: 600	Base Con Cap Est (k): \$37,865	DM: Joseph Reynoza
Desized Transfellow: Develous Desessanding is and east the office of 1 or Annaba Dascha Discha Undes 1 smith and Tomenon from Mass 95th Stead in Dasta 485	(MO10)	(MZ00)	(M380)	(M460)	(M600)	Plant Est Days: 0	Base Contingency (k): \$5,680	RM: Syed A. Huq
AL TIMEN NORTH THE REAL HOUR WAS A TIMEN TO A TIMEN AND A TIMEN TO A TIMEN AND A T	06/23/2021 A	06/25/2024 T 03/26/2026 T		04/20/2026 T	01/31/2029 T	Total Con Days: 600	Total Con Days: 600 Base Total Capital Est (k): \$44,494	
Scope Summary. The orded processe to cold plane and overlaw the actissing such all ownered and cloud damaged structural conclours have been with new structural sections and ownerent markers.	kers. upgrade 64 exist	ing nonstandard ADA	curb-ramos, construct	42 concrete pads at tra	nsit bus stops, constru	ct sidewalk to create a continuous sidewalk between intersection, redi	concises of stratific constanted AD curbonness, constant of Concernal tous constant is contract steemal to create a confinous steemal to create a confinous steemal to create a confinous steemal to content a steemal to create a confinous steemal to content a ste	blete the bikeway throughout the route.

				EA-07-346600, EFIS ID: 0718000076	920			Milestones				Duration		Base RW Cap Est (k):	(k): \$349		PM: Carlos Loera	
Route & Post Mile: LA-213-0/10	LA-213-0/10					Old Old	PA&ED	PS&E	RIF	CCA			Con Working Days: 600	Days: 600 Base Con Cap Est (k):	(k): \$37,865		DM: Joseph Reynoza	loza
						(MO10)	(MZ00)	(M380)	(M460)	(M600)			Plant E	Plant Est Days: 0 Base Contingency (k):	(k): \$5,680		RM: Syed A. Huq	
Project Description	n: Roadway Pr	reservation in a	and near the cities of Los Ar	Project Description: Roadway Preservation in and near the cities of Los Argeles, Rancho Palos Verdes, Lomita, and Torrance, from West 28th Street to Route 405	e, from West 25th Street to Route 405	<	06/25/2024 T	03/26/2026 T	D4/20/2026 T	01/31/2029 T			Total Con	Fotal Con Days: 600 Base Total Capital Est (k):	(k): \$44,494			
Scope Summary: 1	The project pro	roposes to cold	I plane and overlay the exist	ing asphalt pavement and dig-out damaged structu	Sope Summay. The project propose to cold plans and overlay the solding applial powerent and do-oil changed structural powerent sections, applied the will new structural sections and powerent markers, upgrade 54	rkers, upgrade 64 exi	ting nonstandard AD	4 curb-ramps, constru	ct 42 concrete pads at to	ransit bus stops, const	truct sidewalk to cre	ate a continuous sik	dewalk between into	in the content of the contents, content of contents but stops, construct adewalt to trate a continuous adewalt between intersection, reduce line widths and medians to place Class II bits lanes integrated into the roadway to complete the bitsway throughout the roads.	place Class II bils	relanes integrated into the roadway to compl	lete the bikeway thr	oughout the route
e de	S four num film	enfie pr	ate signate, reprace toop on	ierora, consulor, recanning waits, upgrade extension	transge mes graces with oxyder menuty gates, and extends meets been good transfer.	O Separate of Sports	tardians (mod).		Risk Impaci	Risk Impact Assessment								
				Risk Identification		Š	Contingency (@70th Percentile):	ij .	45	13%	Risk Impact on N	Risk Impact on Working Days* (@70th Percentile):	Percentile):	428		Response Strategy		
Risk No. Status	Type	Category	Risk Title	Risk Statement	Risk Defails with Current Status/Assumptions	Probability of Occurrence	Low (\$)	Most Likely (\$)	Hgh (\$)	Cost Impact	P.O.	Most Libely	High	Time Impact Rationale	Strategy	Response Actions	Risk Owner	Updated
1 Active	Threat	DGN	Scope Change	As a result of scope changes to the project during its development, a requirement for additional work may occur, which would lead to increased project ocet and achedise delera.	The accept may be refreed during PS&E Phase, Length and height of relatining walls may be need to be increased. Obser may ask for street (phingslents), K-raik at medians to perform median work ofc.		\$750,000	\$1,000,000	\$1,250,000	000'009	82	04	8	24 By firmly establishing an acceptable scope the cost of the project will be more reliable	e the Mitigate	Work with all fur the scope durin	6.0	June 12, 2024
2 Active	Threat	NO	Scope Change due to request from Rancho Palos Verdes	As a result of Paos Verder (POV) request to include elements has from the beautifaction properly, additional design rifer from you control to the conded, staffing in proper accept ording profiled proper development leading to through child properly consequent leading to through control and additional control to the control of the control and additional control ordinary and a control ordinary and the control ordinary and control ordinary control ordinary c	IPO's repeat to include element from the heading and repeat on the abothes some the lite week interpretation and the about the control of the control of the control of the control of the control of the control of the control of the control of the control of	*68	\$500,000	\$750,000	\$1,000,000	480,000	8	â	8	Polyect plans would be abuned with RPV and CIO of A forthing people despenses and other may or a forthing people despense and other may recover elements from their beautification project. In the modified in this registed. By firmly, establishing an exceptible accope the cost of the project will be more relatible.	and City V may project Mitgate t of the		Project Engineer Project Manager	June 19, 2024
3 Active	Threat	DGN	Utilities at ADA Curb Ramps	As a result of upgrading ADA curb ramps, conflicts with existing power poles and underground utilities may occur, which would lead to increased project costs and schedule delays.	19 Underground utilities and other field conditions al tome project boalfons may grewert ADA curb d ramps from being constituted to standards.	802	\$400,000	000'009\$	000'008\$	450,000	82	9	8	Exeting utilities at ADA ramps will be studied to avoid conflicts during construction.	led to Mitgate	UBHy Engineer will coordinate with UBHy Dwner for any conflicting utities. The cost estimate includes extra funds for utility relocation and portholing early in the PS&E Phase.	Project Engineer/ Utility Engineer	June 12, 2024
4 Active	Threat	拓	Signal Replacement	Bucasse the project is on a State conventional highway, part of the proposed work is located within the local and City. But of statements with peak to comply with cbt signal and lighting distributeds and requirements, which may lead to increased project costs and schedule delaye.	Proposed excitation region was not have surpressed control collars. Specialists. The counted deep will be submitted to LACIT and the Shaward CSMed Lighting Specialists. The control deep will be submitted to LACIT and the Shaward CSMed Lighting The Committed of the Specialists	\$60	\$500,000	\$600,000	\$700,000	000'086	us	7	p	Maintain communication with a clear understanding of expeditions with the City would minimize the impact of the risk.	Mitgate		A Traffic Electrical Engineer & Project Manager	June 12, 2024
5 Active	Threat	CON	Differing Site Conditions	As a result of differences between design data and actual field conditions, design modifications may occur, which would lead to increased project costs and duration.	Variations in also conditions may be possible.	%09	\$600,000	\$700,000	000'008\$	380,000	w	۲	9	Adequately characterizing the project site will reduce the cost uncertainty.	Mtigate	Conduct an appropriate site visit and comprehensive site investigation. Expect to use contingency funds to pay for work increases antixing in from site condition variations after conducting site visits and investigations.	g Resident Engineer	June 12, 2024
6 Active	Threat	DGN	Viability of English BMP Locations	As a nearl of a lening survey, influence, and gotherhorist lent feature and extra control of the	A warried involver of the IV of soft on an exten on the pUSIC was inflamed the inflame line recommend for any proper as set inflamed are surpoom. Inflamen 1984 in short the recommend for the proper as set inflamen 1984 in short Proposition sample the 1985 in the state of detuning the veiled of the fair Proposition sample the 1985 in the state of detuning the veiled of the fair Proposition sample the 1985 in the state of detuning the veiled of the fair proper and the state of the public purpose the state of the state of the public and the state of the state of the public does not be some enterined. (In EL SST) & EL SSSI & EL SSSI (ARS MED MAIL LINE proper it be deferred to the same enterined. (In EL SST) & EL SSSI & EL SSSI (ARS MED MAIL LINE proper it be deferred to the same enterined. (In EL SST) & EL SSSI & EL SSSI (ARS MED MAIL LINE proper it be deferred to the same enterined. (In EL SST) & EL SSSI & EL SSSI (ARS MED MAIL LINE proper it be deferred to the same enterined. (In EL SST) & EL SSSI & EL SSSI & ARS MED MAIL LINE proper it be deferred to the same enterined. (In EL SST) & EL SSSI & EL SSSI & ARS MED MAIL LINE proper it be deferred to the same enterined.	¥01.	000'006\$	\$500,000	\$700,000	000'058	01.	\$1	52	The Resibility of dorivios was properly studied during the PAED Press.	Mtigate	Propose to modify nativity distings systems to concless the fow form several signated outfills or concless the fow form several signated outfills or the outcome of borning sification tests will determine the type of Start, will complete surveys and all functions the surveys and all functions the surveys and all functions the surveys and start of the services of the services of the services and start of the services and confine proposed denics lessibility. BMP types, and locations.	Project Engineer	June 10, 2024
7 Active	Threet	DGN	Phose and Economic Confibons	As a read of designs in the demand and supply of maturities the transfer of the conference from the conference and the conference and the conference from the conference and conference and conference designs increased project codes and schools designs.	In the part of the part when the non-constructions he has quide, contribution contribution of the part	%55	\$400,000	000'009\$	000'0088	000'006	v	~	9	1 to committy of known whether the material of processes a control of the committee of the	riels. MREgate	The Project Eigheer will not with the Controlled Effective Section For Fold Effective the determinant The September of the The Project and with great that information.	So Project Engineer	\$202°, e amp
8 Active	Threat	DGN	Differing Site Conditions Due to Lack of f Survey	As a result of differences due to lack of survey data and actual field conditions, design modifications may be required, which would lead to increased project costs and duration.	Additional survey chis may to needed.	%09	\$400,000	\$500,000	000'0088	000'000	ю	7	9	h the PS&E Phase, the project site will be characterized to reduce the potential for unknown, hidden, conceated, or blent physical conditions that offer materially from the project plans.	ysical Mitigate	Expect to use confingency funds to pay for work increases arising from site condition variations.	Resident Engineer	June 4, 2024
9 Active	Threat	ROW	Additional Parcels	As a neut of more detailed right of way studies performed during the PS&E prese, additional parcels may need to be acquired later in the project, which would lead to capitalisupport cost increases and schedule delays.	Additional parcel requirements will be identified during PRAE phase	40%	\$500,000	\$750,000	000'006\$	288,333	10	15	z	Mentifying the number and type of parcels needed will increase the estimate relability.	s Mitgate	Evaluate the right of way impacts early in the Design phase.	Project Engineer / R/W Agent / R/W Engineering	June 12, 2024
10 Active	Threat	DGN	Right of Way Acquisition	As a result of the extension of Right of Why acquisition activities past the contract award class, obstruction of construction suivities may occur, which would lead to increased project codes and schedule delays.	RW requirement requirement and the second on the beneated in released during PSAE Phase. Also, there is consistent with regularized the regularized for the observation was compared for the possible of the possible of the regularized for the regul	¥07.	\$200,000	\$400,000	\$600,000	280,000	20	40	99	Cear all propertes before construction sants to minimae the interruption of Right of Way 28 acquisition no construction. Identifying the number and type of spracks needed will increase the cost estimate reliability.	arts to Mitgate crease	During the PS&E Phase, identify the necessary percode and conduct the necessary studies and clearances. Liptake the code estimate to reflect the necessary changes to the acquisition.	Project Engineed RW Agent	June 12, 2024
11 Active	Threat	ROW	Railroad Crossing Gate Requirement	As a nest of a requirement by CPUC to have 35% plans reviewed by UFRR, additional requirements may need to be implemented into the project, which can lead to additional delay from the review and additional costs to the project.	Requirements from rational agency may reach thinwing to come up with aggrades for a probaction safe bacilly at Tomace Bind interaction. Altering the RRI crossing may figure the need for the additional RR crossing gates.	%05	\$400,000	\$500,000	\$600,000	250,000	30	09	8	CPUC will not give a formal position on the crossing guards (gates) until UPRR reviews th 35% Plans. In striker projects, pedestrain crossing gates had been requested.	e Megale Megale		RNV Agent & Project Engineer	June 12, 2024
12 Active	Threat	ROW	Unknown Utility Relocation	As a result of utilies not being identified at this stage of the project, utility conflicts may occur, and these conflicts may lead to delays to the project schedule and increased project costs.	Conduct through utility investigation during PS&E phase and include any relocation cost in the opject report.	40%	\$400,000	\$600,000	\$700,000	233,333	20	30	9	Because no potholing has been completed at 12 this phase, it is crucial to complete pothoking during the PS&E phase to identify any potential utility confids.	ng Mtgate	During the PS&E Phase, request for potholing as soon as possible and develop plans that reflect what is identified through the result from potholing.	Uffly Engineer	June 12, 2024
13 Active	Threat	CON	Construction Inconvenience / Public Accommodation	As a result of the need to reduce construction impacts due to notes, accord, vehicled, cuts, taffic delays and other construction-resilied inconveniences, charges to construction methods and traing near, which would test to increased project costs and schools delays.		%0±	\$200,000	\$300,000	\$400,000	210,000	us	۲	t t	Project is on a Conventional Highway in an urban area with businesses adjacent to the facility.	n Mitgale		Project Engineer Resident Engineer	May 24, 2024
14 Active	Threat	785	Traffic Management and Handling	Because public traffic and emergency access need to be martismed throughout the contribution strong, and existing 1 feetin resupports agrees some to be probleded using contribution, modification to the self-in-senting plans are coord, which would must in additional project costs and achievable oblegs.	Trust, from the boundment of the or mention, etc. on proceedings of the order periods would be produced in period of the order periods would be produced in period or direct periods or the order periods or the order period or the order periods or the order periods or the order period or the order periods or the order period or the order periods or t	%09	\$200,000	\$400,000	\$600,000	200,000	0.	20	8	Traffic, aimes through the construction zone 10 would be maintained except as allowed in the closure charts to minnine traffic oblings during construction.	the Mtgate uring	During the PS&E Phase update the cod estimate and tells hending plans is include the best approach for tellife handing during construction.	DTM Traffic Engineer & Resident Engineer	June 12, 2024
15 Active Threat Or-selb Rey Region 06-19-2024 John 10-	Threat 19-2024.visb, RR_Lov	ROW	Temporary Construction Easement (TCE)	Because Caltura RW is limited on a conventional inginety, indicated in a feedom of Tempora Constructural Exemption (Tempora Constructural Exemption (Tempora Constructural Exemption Security and Constructural Exemption Security and Constructural Exemption Security and Constructural Exemption Security Exemption Security and Constructural Exemption Security Security Exemption Security Securit	Out to solitous lespony contractor esserenticoses is not levertical in the place. Calment acting the wath is 100 fectives and 90% 10 however, improm Collectoric illumination (CO) and be request to reconstruct some direct increasing a CO) and the request to reconstruct some direct increasing a CO) and the request to reconstruct some direct increasing a CO) and the request to reconstruct some direct increasing a CO) and the region of	50% *Risk impact on constrino	\$200,000 dion schedulo is estimated us	\$300,000 sang Menia Carlo simulation w	\$500,000 Bhout consideration of overlaps	158,333 pingtonourent activities.	æ	30	â	The need for construction essement has been featured out-ing PARED Praise as survey data become available.	been Witigate Wydate	identify which locations need TCE and start permit-beasement application early at the PG&E phase.	Project Engineer/ RW Agent or Engineer	June 12, 2024

EA-07-346600, EFIS ID: 0718000076			Milestones			Duration	Base RW Cap Est (k): \$949	PM: Carlos Loera	
Roule & Post Mile: LA-215.0/10	0 <u>L</u>	PARED	PS&E	RIL	CCA	Con Working Days: 600	Base Con Cap Est (k): \$37,865	DM: Joseph Reynoza	
belos Descindos Descinsolas la sad escriba cilias al La bendas Descis Delas Vestas I ambs nas Tasasas, from Mad 1988 Chests Desis Me	(MO10)	(MZ00)	(M380)	(M460)	(M600)	Plant Est Days: 0	Base Contingency (k): \$5,680	RM: Syed A. Huq	_
espolybusi. Nashing reservati ili alu iraa ule cutes ul Lio Aligesa, halicini r'ado verues, Lullias, alu l'unaine, llulli res, Lull destu u nuute vu	06/23/2021 A	06/25/2024 T	03/26/2026 T	04/20/2026 T	01/31/2029 T	Total Con Days: 600	Total Con Days: 600 Base Total Capital Est (k): \$44,494		_

10 10 10 10 10 10 10 10	Project Des	:ription: Road:	dway Preserva	ervation in and n	Project Description: Roadway Preservation in and near the cities of Los Angeles, Rancho Palos Verdes, Lomits, and Torrancs, from West 25th Street to Route 405	e, from West 25th Street to Route 405	(M010)	(MZ00)	(M380)	(M460)	(Weoo)			Plant Est	Plant Est Days: 0 Base Conti	Base Contingency (k): \$5,680	089	2	KM: Syed A. Huq	
The contract of the contract		.	.				06/23/2021 A	06/25/2024 T	03/26/2026 T	04/20/2026 T	D1/31/2029 T			Total Con Da			7691			
1 1 1 1 1 1 1 1 1 1	Scope Surr. install guid	mary. The pro , warning and	roject propose d bicycle sign:	oses to cold pla. igns, relocate si	ane and overlay the existing asphalt pavement and dig-out damaged struct. ignals, replace loop detectors, construct retaining walls, upgrade existing t	tural pavement sections, replace them with new structural sections and pavement mari drainage inlet grates with bicycle friendly gates, and existing metal beam guardrall (M	rkers, upgrade 64 e. NBGR) to Midwest 6	isting nonstandard Al uardrails (MGS).	DA curb-ramps, const.	ruct 42 concrete pads .	at transit bus stops, cons	truct sidewalk to crea	te a continuous sidewa	k between inters	section, reduce lane widths and m.	dians to place Clax	ss II bike lanes integrat	sted into the roadway to complete	the bikeway thro	ughout the route,
1. 1. 1. 1. 1. 1. 1. 1.										Risk Impa	act Assessment									
1 1 1 1 1 1 1 1 1 1					Risk Identification		ď	inthigency (@70th Percei	ntile):		13%	Risk Impact on W	orking Days* (@78th Perc	utte):	428		Respor	Response Strategy		
				Category		Risk Details with Current Status/Assumptions	Probability of Occurrence	Low (5)	Most Likely (\$)	High (\$)	Cost Impact	Low						Response Actions	Risk Owner	Updated
1 1 1 1 1 1 1 1 1 1				ROW		The character sproving possible and see at a will as character of the paper of the	*00	000'000\$	\$400,000	000'005\$	120,000	8	8	120				Start the negotiators promptly and holide an estimate for "legging" for the period during which the Restands will be misseled by construction advilles. In addition, add a cost for the review process.	Project Engineer R/W Rairosd Coordinator	June 12, 2024
1. 1. 1. 1. 1. 1. 1. 1.					Became of the project continution may cause importery became of the project continues and important control hunding it benegated can good continues or continues to the original proposed funds continued and continues to the original properties that the project costs and problems or continues or continues or continues or continues project costs and problems or continues or continues or continues or continues project costs and problems or continues or continues or continues or continues project costs and problems or continues or continues or continues or continues project costs and project costs and pro		*02*	\$200,000	000'008\$	000′00+\$	120,000	8	30	40		_		Funds for Maintain Traffir has been included in Rel the Engineer Estimate to pay for any measuremy changes or modifications needed to address the Mai boal traffic conditions and demand during construction.	Resident Engineer & Dist Traffic Manager & Comdor Manager	June 3, 2024
1. 1. 1. 1. 1. 1. 1. 1.					Sequest for using Aluminum As a result of inquest to use Aluminum Conductors (vites), Conductors project may nour additional cost and deby.		×500	\$125,000	\$175,000	\$200,000	102,500	\$	54	9				Project may need additional funding if request is made before PS&E is finalized, and/or may need to PS use contingency fund if the request is made after RN the project has gone to construction.	Project Engineer / Resident Engineer	June 12, 2024
1. 1. 1. 1. 1. 1. 1. 1.				CON			%08	\$150,000	\$200,000	000'092\$	100,000	5	\$	09				Project may need additional funding if request is made before PS&E is finished, and/or may need to Ps outs contringency fund if the request is made after Ribe project has gone to construction.	Project Engineer / Resident Engineer	June 12, 2024
1.						In PARETD phase, DES had posiminarly distribed for the two retaining usets (SOV total length) to be ideagened by District. In PSME upon further study, the two walls may need to be designed by DES. If this is dependent on the results from the gookstrancel study.	35%	\$150,000	\$250,000	\$350,000	87,500	w	۴	10				PM will work with DES and provide the necessary Eresources	Project Engineen/Project Managen' DES	June 12, 2024
1. 1. 1. 1. 1. 1. 1. 1.	72			CON	As the result of construction starting during the winter and rain Weather Delays - Rain seeson, Contractor's nability to perform work in inclument weeting may court, winter would lead to increased project cooks and schedule delays.	Try Revise the construction schedule so that work starts after the winter and ratiny season.	%0S	000'08\$	\$160,000	\$240,000	80,000	8	8	9		_		Allow for approximately 20 weather or rainy days in Rachedule.	Resident Engineer	May 8, 2024
Lange Table Tabl					As a result of the catch basin hostion next to the curb, Catch Basin Relocation - Catanges to the curb geometric may result in relocation of catch basin, which may richous additional cost.	ch Existing field condition is unknown at this stage and will be evaluated during Design Phase	40%	\$100,000	\$200,000	000'006\$	80,000	so.	Đ	15				identity the need early on in design phase.	Project Engineer	May 14, 2018
Fig. 12 13 13 13 13 13 13 13					As a result of changes to stormwater requirements, Beet Management Practices (BMPs) design changes may occur. Storm Water Requirements which would lead to increased project costs and schedule debigs.	p project may need to comply with additional new stomwaster treatment requirements. I Commod Sum waster Management Book (CSMS) to 75ae is Roule 215 from 25th Si Long 2004 and 445 (Part 0010 PM 10.0 recommended four BMP sites. However, only 2 BMP sites intended that are within Catharas Right of Virgy.	20%	\$200,000	\$400,000	\$600,000	80,000	ıo	7	10					Project Engineer	June 12, 2024
The company of the	×			DGN		Permits will be needed from City of LA and LA County for drainage systems and Traffic agnal poles.	3038	\$100,000	\$200,000	\$300,000	60,000	10	\$2	20				In the PS&E Phase, coordinate with the necessary clies and/or agencies to obtain the permits in a timely manner.	Electrical, Hydraulics & Project Engineer.	June 12, 2024
Actor The control of the control						Vestion to the site acceptor services are serviced enough to the service of the construction of the tay open services are serviced to the service of the ser	308	\$100,000	\$200,000	\$300,000	000'09	80	8	60					Project Engineer	June 12, 2024
Actor The Part Coor Name the Coor Name and control (and cont					As a result of Decivical internation reproposed to the be- constructed in the project requiring both seat the bonds: Bedrical librars and a standown of materials is ableen from the Contractor's growing in project materials and project reproductive to the project and pro	Electrical farms, spocially against and galt pales mequine forg lead (set much a set montha) firms to by celest. If sharing set staken form Contractor passession, contractor may need to galt ex-approval from "Be the design which could delay project completion due to Coordination with LA-BSL and permit application."	20%	\$250,000	000'008\$	\$350,000	60,000	82	8	40					Project Engineer	June 12, 2024
This Col Washer being Col Washer being Continued to protect be				DGN		Sons the project proposes evaluate, execution for the reconstruction of markets, construction of board and reversely, and construction of the construction of the construction of the reversely of the construction of the construction of the construction of any required of properties are constructed and the construction of the construction of addressed during the drings place of the project.	%09	000'05\$	\$100,000	000'002\$	54,167	5	30	45	7.2			monocologistics of the cologistics of the cologistic of the	HW EngineerProject Engineer	June 12, 2024
Active The Late of the Control Early Control							%09	000'08\$	\$100,000	\$120,000	900'09	0	8	30	Some weather expected.			RE to work with Contractor to minimize the non- working days.	Resident Engineer	May 8, 2024
Active Tried To New Tried Tried To New Tried Tried To New Tried Tr							%09	000'05\$	\$75,000	\$100,000	000'08	5	źī	50		-	A coordination c specifications. T Migate coordinate with Engineers to ad avoiding conflict	A coordination chains will be included in the project characterism. This factorist ingrees we the control of the control of the control of the Engineer's beginning to control of the characterist in profession in	Resident Engineer/Project Manager	May 15, 2024
Active Triant CDN Virtualistra-Time CDN Virtualistra-Time Virtualistra-Time CDN Virtualistra-Time Virtuali				DGN			30%	\$50,000	\$75,000	\$100,000	22,500	so	7	10				The PE needs to coordinate with Environmental staff to ensure confact sensibility is included early in Pithe project and funded in the project cost estimate.	Project Engineer	June 12, 2024
	-				Vandalism/Theft of As a result of vandalism or theft of the newly constructed impation/Electrical System impation/Electrical system, regains may be required, which components would leaf to increased costs.		20%	000'05\$	\$100,000	\$150,000	20,000	NO.		01				Contract specifications will include provisions for Contractor to miligate the polential for vandalism of P the irrigation system during the Construction period.	Project Engineer	June 12, 2024

EA-07-346600, EFIS ID: 0718000076			Milestones			Duration	Base RW Cap Est (k): \$949	PM: Carlos Loera	
Route & Post Mile: LA-2/5-0/10	OL OL	PA&ED	PS&E	RIL	CCA	Con Working Days: 600	Base Con Cap Est (k): \$37,865	DM: Joseph Reynoza	_
Danked Parachellen: Dacksandlen is and excellen, alles all as dendes Dacks Direct Louis, and Towness, from World 19th Chees in Daries Alle	(MO10)	(MZ00)	(M380)	(M460)	(M600)	Plant Est Days: 0	Base Contingency (k): \$5,680	RM: Syed A. Huq	_
rujen, creacipum: Noamely reservatini mailus un cues ur kas Algess, handur ruos veuts, kullis al uniant, mul res. kou oues tu nuo un desta de la cultura de	06/23/2021 A	06/25/2024 T	03/26/2026 T	04/20/2026 T	01/31/2029 T	Total Con Days: 600	Base Total Capital Est (k): \$44,494		_
One Common The analysis control and the contro	e de constante esta esta esta esta esta esta esta es	ADA brahaman nai	de la company de	ent to about about the	and the	of eldesself to constant and eldesself hadrone detection and	and large and modians to shoo Clees Il bile loons interroted late the readons to	also the biloness throughout the courts	_

	_						_						
oughout the route,			Updated	June 16, 2024	June 12, 2024	June 12, 2024	June 12, 2024	May 8, 2024	May 8, 2024	June 12, 2024	June 17, 2024	May 24, 2024	May 24, 2024
te the bikeway th			Risk Owner	Resident Engineer, Geolochmical Engineer & Hazardous Waste Engineer	Project Engineer	Project Manager	Project Engineer	Project Engineer & Resident Engineer	Project Engineer & Resident Engineer	Project Manager & Project Engineer	Coastal Permit Liaison & Resident Engineer		
lanes integrated into the roadway to comple		Response Strategy	Response Actions	Only on the SECT make deliment which broadens are excess the promotive from the properties of the section of the production and section of the section of the section of the reconstruct, its benefit of the reconstruct the section of the concentration of the section of the section of the section of the section of the section of the concentration of the section of the section of the conceptual pair for the section of the continues and continues are decimal and con- petition of the section of the section of the continues decimals. The action of the properties continues of the section of the properties of the section of the section of the continues decimals. The section of the section of the properties of the section of the	Coordinate with the approving agency (State Water Baser) to observine the appropriate addons needed for the project.	Project Mrager will work with Management to addresse shortings in staffing and if need be utilize Consultants as and if needed.	Early in the Design Phase, coordinate with the necessary clies and agencies to mitgate any potential problems and develop any agreements, if necessary.	Before beginning construction activities, the Resident programment or Captioners will work Maintenance to Calescury browsless excentrements and remove personal property per Calescus policy (MFD-1001 dieso Off WERD). The public specifications because the construction to shoot the calculate singuises for the Contractor to steep the area clear of any new homeless encampments.	Bution bagining construction activities, the Restort regioners will and out with Maintenance to clear-up formeries encampreneuts and remove personal property per Calerare policy (MCP-LOID) general property per Calerare policy (MCP-LOID) alead off MCD(10). The prodest specifications lack-date singuings for the Contractor to keep the area orient of any new homeless encampments.	Montar design progress in conforming to the QMS process and essues complete submitties are provided for review.	The frestent Engineer will inform the Coastal Permit Liaison of any dange in construction meanstendbods during construction and initials the the-entastion process to update the CDP ₹ necessary.	Risk Retined based on PDT decision during Risk Workshop held on May 24, 2024.	Risk Refined based on PDT decision during Resk Workshop held on May 24, 2024.
lass II bike I			Strategy	Mfigate	Mitgate	Mitigate	Milgate	Mitgate	Mitgate	Milgato	Milgate		
Species of activiting normal ADA curb-crops, construct & concrete pads at farnal bus abops, construct atdewalk to create a continuous atdewalk between intersection, notice laws widths and midlan to place Class 10he laws integrated into the roadway to complete the billwaysy throughout the roadway.			Rationale	Connotation discovers as possible feet establishment as required Location of approximate to be confirmed by geodechrical and years.	This is a new required document and there has not been an approved ACP yet throughout the state.	Staffing and productivity are the main conflictions to Support Costs. Since this is a Support Cost risk, it isn't captured in the recommended confingency calculations.	Coordination of the Department's effort with the cities and different agencies in a timely manner will help mitigate the risk.	in the event homeless enclampments are encountered uting controlled askilled by Contractor ray be evilibled to built he project for Time-Relating Overhead delay cooks while they are removed. The Times to verify presence of Usahelberd damps in the project erea during RS&E Phase.	in early 2020, new protocologuidelines were issued regarding the proper handing of underheadhormetes encampments (MPD 20-20 dated 00014 420.00). PDT need to verify presence of Unshribited camps in the project area during	By felowing the Quality Management System (UMS) process, the cost and scholds impacts on the project could be minimized.	CDP will be required prior to construction begins.		
ntersection		82	Time Impact	-	×	m	w	-	-	-	N N		
sidewalk between i		6th Percentile):	High	0t	921	5	10	10	10	đ	â		
o create a continuous		Risk Impact on Working Days* (@76th Percentile):	Most Likely	۴	98	۰	7	۲	۲	۲	8		
uct sidewalk to		Risk Impac	Low	w	8	in.	6	us	w	us	ŧ		
ansit bus stops, constr	Risk Impact Assessment		Cost Impact	15,000	14,000	12,333	11,375	7,000	900'9	900'5	267		
ct 42 concrete pads at tr	Risk Impact	13%	High (5)	\$100,000	000'09\$	\$40,000	\$25,000	\$45,000	\$40,000	000'08\$	\$10,000		
A curb-ramps, constru		(eg	Most Likely (\$)	\$75,000	\$40,000	000'06\$	\$15,000	\$35,000	\$30,000	\$25,000	\$5,000		
pgrade 64 existing nonstandard AD to Midwest Guardralls (MGS).		Contingency (@78th Percentile)	Low (\$)	000'05\$	000°02\$	\$25,000	\$12,500	\$25,000	000'02\$	000'02\$	\$2,000		
arkers, upgrade 64 exi (MBGR) to Midwest G		8	Probability of Occurrence	502	%SS	%O#	2022	20%	20%	%02 ************************************	86		
Sope Surmary. The project proposes to cold plane and contray the staining apphal powement and dis-out damaged structural powement sections, regular processes to cold plane and contray the staining and blog-cle signs, rescent alignats, replace loop detections, construct restaining walls, apprated scaling drainings intell plane with blog-cle felterly grained and plane and a plane with blog-cle felterly grains and existing metal beam guaranted (MBGR);			Risk Details with Current Status/Assumptions	Thes as a see intersection requiting the epitocenet includes control to the expension all not be preferred the new places of the production report as to based on shoot state. These is producted to a control of the production of the pr	I pommonet BMPs are not leasible along flouis 213, alemanive treatment BMP busilions may need to be deedled. This is a rear process that increvise other: 1. horsynching Chemisteri BMPs on other propietal has feed feed to the same watershoot or 2. horsynching Chemisteri BMPs on one busilions process promised BMPs outded charant Reflect of reg. 2. horsynching Chemisteria Ch	Clitters staff may not be available to perform work on this project as needed, negatively impacting the project support costs and solvedule. Also, there may be staff source related to believerfring, references, and new-times.	As the project limits are within multiple clies, the construction of bike larnes, bus peds and installation of new agrial poles shoulding loop debodors for bloycles, may require new agreements with the Olises and bus operating agencies.	As a seaf of underbard people sating up exterprete in or fee 49th 24th 24th state of underbard people sating up exterprete in or fee 49th 24th 24th state of the 25th state of	The POT has desirated that the project does not have unsubshared encomprenses, but the may change when the project pose into construction. This is a time probability risk.	The project will complete SIN Quality Review (0772202), see the SIN Quality Review is with opinion to complete or 10720202 washed through and objective that will be excessed of any quantities. The special project was the story of all process are all other special committees that the transfer special review of the story of the project occurrent and relations for special review (1971).	Despit had welled find good of the project that it bounded within the Cheated Zhou. The interaction of Zhou Miller and pull of the State of the Stat	Implementation of VA Study recommendators will be considered.	Foundation design is based on comprehensive geotlechnical exploration.
ng asphalt pavement and dig-out damaged structur ctors, construct retaining walls, upgrade existing d		Risk Identification	Risk Statement	sleep arpuse pur pero pubul pamenung apa (au upun "upamena Burg pagunosa si dan alapunosa "upameng pubu ay pamban ongazana dan ang ang	Re a result of a new requirement of Abarnahve Compliance Plen (ACP), f proposed BAPF is not possible to be constituted by Proposed policy and promisely be between BAPF Ocations may need but be denified resulting in deby and/or cost increase and 1. possibly initiating a expertable project.	As a result of hiring new shalf and shalf retirements, the availability of in-house personnel (or shalf augmentation consultations) with the proper experience to complete all required basis may be limited, which would lead to increased conjust closis and daration.	As a result of work that impacts local agencies and utilities, agreements addressing additional project requirements and constraints may be needed, which would lead to increased project costs and duration.	As a real of unabelland people setting up encemprents in or source free works are dring, construction, construction source free works to stop, which would lead to increase achieve may seek to stop, which would lead to increase Contractor Time-Nestead Overfreed (TRO) costs and achieve	If unableted or humbles encampments are encourated within the project think of this contractor, additional effort and minima may be required for that emonal or possible indication which would lead to increased project costs and survivolate obeys.	Could project information (Plans, Speca, Chamilton, or Constitution (Plans) in an universal processing of the Constitution (Plans) in a constitution of the Constituti	As a near of the project lating with it ho State and Local consonail junctions. A Costal Desponent Famil (CDT) is proposed to the cost of the cost of the cost of the cost control with the cost of the cost of the cost cost with cost of the cost of the cost of the cost cost of the cost of the cost of the cost cost of the cost of the cost of the cost cost of the cost of the cost of the cost cost of the cost of the cost of the cost cost of the cost of the cost of the cost cost of the cost of the cost of the cost cost of the cost of the cost of the cost cost of the cost of the cost of the cost cost of the cost of the cost of the cost cost of the cost of the cost cost of the cost of the cost cost of the cost of the cost cos	As a result of a Value Analysis Study during PS&E, project changes may occur, which would lead to cost and schedule changes.	As a result of geolectrical and other existing conditions different than plans, a requirement for construction of retaining which may could have a which would lead to increased project costs and archerists delease.
vane and overlay the existi signals, replace loop deter			Risk Tibe	Groundwater Dewatering g	Meeting Atternative P Complance Plan a Requirement n	Limited StaffFunctional a Support	Agreements	TRO Costs Related to a Removing Homeless a Encampments of	Unshekend/ Homeless W Encampments W	Quality, Constructability, & O Safety	Coastal Development Permit (CDP)	Value Analysis Study c	Retaining Walls o
ses to cold pi			Category	CON	BW	38	NO	CON	CON	NO	BA.	DGN	DGN
project propo and bicycle si			Type	Threat	Threat	Threat	Threat	Threat	Threat	Threat	Threat	Threat	Threat
ummary: The ide, warning			Status	Active	Active	Active	Active	Active	Active	Active	Active	Retired	Retired
Scope St install gu			Risk No.	8	8	8	Я	8	37	8	8		

EA 346600 Risk Register Certification

Final Audit Report 2024-06-26

Created: 2024-06-20

By: Ryan Nai (s148568@dot.ca.gov)

Status: Signed

Transaction ID: CBJCHBCAABAAd8djWO9EjE0XnXBM1BzW5PcEPlbJN6cl

"EA 346600 Risk Register Certification" History

- Document created by Ryan Nai (s148568@dot.ca.gov) 2024-06-20 0:52:17 AM GMT- IP address: 149.136.33.249
- Document emailed to Carlos Loera (carlos.loera@dot.ca.gov) for signature 2024-06-20 0:54:23 AM GMT
- Document emailed to Greg Farr (greg.farr@dot.ca.gov) for signature 2024-06-20 0:54:23 AM GMT
- Document emailed to Issam Abumuhor (issam.abumuhor@dot.ca.gov) for signature 2024-06-20 0:54:23 AM GMT
- Document emailed to Angela Perez (angela.perez@dot.ca.gov) for approval 2024-06-20 0:54:24 AM GMT
- Document sent to Wayne Lee (wayne.d.lee@dot.ca.gov) and Zoltan Elo (zoltan.elo@dot.ca.gov) for signature. One of them to sign

 2024-06-20 0:54:24 AM GMT

Document emailed to Dawn Montano (dawn.kukla@dot.ca.gov) for signature

2024-06-20 - 0:54:24 AM GMT

- Document emailed to Son Dao (son.dao@dot.ca.gov) for signature 2024-06-20 0:54:24 AM GMT
- Document emailed to Shawn Enjily (shawn.enjily@dot.ca.gov) for approval 2024-06-20 0:54:25 AM GMT
- Document emailed to Hamid Saadatnejadi (hamid.saadatnejadi@dot.ca.gov) for signature 2024-06-20 0:54:25 AM GMT
- Document emailed to Mehdi Salehinik (mehdi.salehinik@dot.ca.gov) for approval 2024-06-20 0:54:25 AM GMT



- Email viewed by Carlos Loera (carlos.loera@dot.ca.gov) 2024-06-20 0:55:50 AM GMT- IP address: 149.136.33.251
- Document e-signed by Carlos Loera (carlos.loera@dot.ca.gov)

 Signature Date: 2024-06-20 0:56:36 AM GMT Time Source: server- IP address: 149.136.33.251
- Email viewed by Angela Perez (angela.perez@dot.ca.gov) 2024-06-20 1:15:58 AM GMT- IP address: 172.226.186.18
- Email viewed by Wayne Lee (wayne.d.lee@dot.ca.gov) 2024-06-20 - 1:23:26 AM GMT- IP address: 149.136.17.251
- Email viewed by Mehdi Salehinik (mehdi.salehinik@dot.ca.gov) 2024-06-20 2:35:11 AM GMT- IP address: 172.226.212.0
- Email viewed by Dawn Montano (dawn.kukla@dot.ca.gov) 2024-06-20 2:45:53 AM GMT- IP address: 149.136.33.247
- Document e-signed by Dawn Montano (dawn.kukla@dot.ca.gov)

 Signature Date: 2024-06-20 2:47:00 AM GMT Time Source: server- IP address: 149.136.33.247
- Email viewed by Hamid Saadatnejadi (hamid.saadatnejadi@dot.ca.gov) 2024-06-20 3:26:09 AM GMT- IP address: 146.75.146.0
- Email viewed by Shawn Enjily (shawn.enjily@dot.ca.gov) 2024-06-20 2:13:53 PM GMT- IP address: 149.136.33.247
- Document approved by Shawn Enjily (shawn.enjily@dot.ca.gov)

 Approval Date: 2024-06-20 2:14:27 PM GMT Time Source: server- IP address: 149.136.33.247
- Document approved by Mehdi Salehinik (mehdi.salehinik@dot.ca.gov)

 Approval Date: 2024-06-20 2:55:29 PM GMT Time Source: server- IP address: 149.136.33.251
- Email viewed by Son Dao (son.dao@dot.ca.gov) 2024-06-20 - 4:05:26 PM GMT- IP address: 149.136.33.248
- Document e-signed by Son Dao (son.dao@dot.ca.gov)

 Signature Date: 2024-06-20 4:05:35 PM GMT Time Source: server- IP address: 149.136.33.248
- Document approved by Angela Perez (angela.perez@dot.ca.gov)

 Approval Date: 2024-06-20 6:04:50 PM GMT Time Source: server- IP address: 47.148.166.197
- Email viewed by Zoltan Elo (zoltan.elo@dot.ca.gov) 2024-06-20 7:42:52 PM GMT- IP address: 172.226.6.6
- Email viewed by Greg Farr (greg.farr@dot.ca.gov) 2024-06-21 - 0:50:25 AM GMT- IP address: 149.136.33.248



- Document e-signed by Greg Farr (greg.farr@dot.ca.gov)

 Signature Date: 2024-06-21 0:55:59 AM GMT Time Source: server- IP address: 149.136.33.248
- Document e-signed by Issam Abumuhor (issam.abumuhor@dot.ca.gov)

 Signature Date: 2024-06-21 3:41:27 PM GMT Time Source: server- IP address: 149.136.17.253
- Email viewed by Hamid Saadatnejadi (hamid.saadatnejadi@dot.ca.gov) 2024-06-22 2:18:15 AM GMT- IP address: 104.28.85.132
- Email viewed by Zoltan Elo (zoltan.elo@dot.ca.gov) 2024-06-22 6:33:54 PM GMT- IP address: 172.226.7.3
- Email viewed by Wayne Lee (wayne.d.lee@dot.ca.gov) 2024-06-25 5:06:27 PM GMT- IP address: 149.136.17.250
- Document e-signed by Wayne Lee (wayne.d.lee@dot.ca.gov)

 Signature Date: 2024-06-25 5:06:38 PM GMT Time Source: server- IP address: 149.136.17.250
- Email viewed by Hamid Saadatnejadi (hamid.saadatnejadi@dot.ca.gov) 2024-06-25 5:31:26 PM GMT- IP address: 149.136.33.252
- Email viewed by Hamid Saadatnejadi (hamid.saadatnejadi@dot.ca.gov) 2024-06-26 6:26:26 PM GMT- IP address: 149.136.33.253
- Document e-signed by Hamid Saadatnejadi (hamid.saadatnejadi@dot.ca.gov)

 Signature Date: 2024-06-26 6:26:33 PM GMT Time Source: server- IP address: 149.136.33.253
- Document emailed to Nancy Pe (nancy.n.pe@dot.ca.gov) for signature 2024-06-26 6:26:37 PM GMT
- Document e-signed by Nancy Pe (nancy.n.pe@dot.ca.gov)

 Signature Date: 2024-06-26 6:36:25 PM GMT Time Source: server- IP address: 149.136.33.248
- Agreement completed. 2024-06-26 - 6:36:25 PM GMT



SHOPP PROJECT PERFORMANCE MEASURES – Attachment M

SHOPP Project - Accomplishment - Performance Measures - Benefits

Save to Excel

 District:
 07
 Tool ID:
 19243
 Project ID:
 0718000076
 EA:
 34660
 Co-Rte-PM:
 LA-213-0/9.984 (Primary Location)

 Res In PID WP:
 10/27/17
 Project Manager:
 Nade: Abdelmalek, 213-588-6789

						ı						1	
8	Bridge Pavement Drainage Facilities	Signs and Lighting Mobility	Roadside	Bicycle and Pedestrian Infrastructure	360	Sustainability (Climate Change	N	Advance Mitigation /Mitigation	Major Damage & Betterments		house Gase	Green-house Gases Relinquishment	uishment
		Per	Performance &	Accomplishments (PPC)	ts (PPC)								
ActiD	HD Activity Detail	Performance Objective	Unit of Measurement	Quantity Pre-Good	Pre-Fair	Pre-Poor	New Po	Post-Good Post-Fair Post-Poor	HQ Program Post-Poor Review - Agree with District?	Agree Comment	Review Date	Performance Change Date After Review	Comment
1 B2	B25 Asphalt Pavement Minor Rehab (CAPM)	Pavement Class II	Lane Miles	42.866	42.888			42.888	-				
2 E07	N Guard Rail (201.010, 015)	No Performance Objective in the SHSMP	Linear Feet	478.000		478.000		478.000				255	Upgrade MBGR to MGS
2 E23	Collisions Reduced (201.015)	Collision Severity Reduction	Fatal/Serious Injury Collisions	7.000		7.000		7.000				m ≒ E	Based upon the new methodology
4 E55	Proactive Safety Vehicles	Proactive Safety	Annual Fatal & Serious Injury Collisions	0.840		0.640		0.640				mak	Based upon the new methodology
5 E86	Wider Edge Lines from 4 to 6 Inches	No Performance Objective in the SHSMP	Linear Miles	8.900			8.900						
6 F01	Oensus Station (201.315)	No Performance Objective in the SHSMP	Each	2.000			2.000						
1 124	ADA - Repair/Upgrade Curb Ramp (201.381)	No Performance Objective in the SHSMP	Each	84.000		64.000		64.000				a.I.	Per Sarah Horn
8 F25	35 ADA - Install Accessible Pedestrian Signal (201,381)	No Performance Objective in the SHSMP	Each	38.000		38.000		38.000				o. T	Per Sarah Horn
B F43	18 ADA - Deficient Elements	ADA Pedestriar Infrastructure	Deficient Elements	102.000		102.000		102.000					
10 F45	TMS Structure Component	Transportation Management System Structures Each	res Each	2:000			2.000	A	5=0				
11 F48	TMS Technology Component	Transportation Management Systems	Each	2.000			2.000			-			
12 H08	D8 Bikeway Class II	No Performance Objective in the SHSMP	Linear Feet	44502.000		44	44502:000		.B				
13 H10	10 Conflict Zone Green Paint	No Performance Objective in the SHSMP	Each	132.000			132.000						
14 H1	H13 Crosswalks	No Performance Objective in the SHSMP	Linear Feet	9792.000 6,656.000	1,971,000	965.000	200.000	9.592.000					
15 HZ7	77 Transit Stop Improvements	No Performance Objective in the SHSMP	Each	42.000			42.000					0 6	concrete bus pads
16 H32	32 Is any Location Within the Project Limits Ped/Bike Accessible?	No Performance Objective in the SHSMP	Yes/No	Yes								*	res
17 H35	35 Bicycle Detection Loops	No Performance Objective in the SHSMP	Each	80.000		360	90.000			_			
18 H37	37 Bicycle-Tolerable Drainage Grates	No Performance Objective in the SHSMP	Each	11.000			11.000						
19 H63	33 Bicycle and Pedestrian Infrastructure	Bicycle and Pedestrian Infrastructure	Linear Feet	54294.000 8.656.000	1,971,000	965.000 44	44702.000 9	9.592.000					
	20 HB9 Other Bloycle and Pedestrian Infrastructure Activity	No Performance Objective in the SHSMP		46154,000	4	45.029.000 1	1126.000 45,028,000	026,000				¥ 6.8 C M C W C W C	46029 pre- poor bike poor bike included in 30861, 1125 new inclusion into state invertiory
21 10	101 Total Maximum Daily Load (TMDL) Mitigation	Storm Water Mitigation	Acres	1.270		1.270		1.270					0

4200.000

MTC02e

No Performance Objective in the SHSMP

N02 Quantitative - Proposed Mitigated

GEOTECHNICAL SERVICES SUBSURFACE INFORMATION – Attachment N

Memorandum

Making Conservation a California Way of Life

To: Division of Environmental Planning

District 7

Date: February 23, 2024

File: 07-LA-213 PM 1.072-1.47

0718000076 (07-34660) 1 Retaining Wall

From: Geotechnical Services

Office of Geotechnical Design South

Branch D

Subject: REVISED CATEGORICAL EXEMPTION/CATERGORICAL EXCLUSION (CE/CE) REQUEST FOR SUBSURFACE INVESTIGATION

Please process the revised CE/CE request for the subject project. The Office of Geotechnical Design is proposing three borings for one proposed retaining wall along southbound State Route 213 in Los Angeles County. Reference attached plans depicting the subsurface exploration area. Your response is requested by March 22, 2024.

If you have any questions, please contact Pamela Brutzkus at (915) 296-1895 or James Majors at (213) 200-4188.

Prepared by:

Pamela Brutzkus, GIT

Engineering Geologist

Office of Geotechnical Design South


Branch D

Supervised by:

James Majors, PE, GE Transportation Engineer

Office of Geotechnical Design South

Branch D



PROJECT CHANGE REQUEST – Attachment O

Project Change Request



Submitted on 01-SEP-2023 12:00:00 AM

Project ID: 0718000076

District: 07 **EA5:** 34660 **PPNO:** 5371 **Pgm Doc:** SHOPP **Pgm Del Fy:** 2026 **Prog Code:** 20.XX.201.121

County: LA **Route:** 213 **Postmile:** 0.000/10

Project Scope Description

In and near the cities of Los Angeles, Rancho Palos Verdes, Lomita, and Torrance, from West 25th Street to Route 405. Rehabilitate pavement, upgrade guardrail, and upgrade facilities to Americans with Disabilities Act (ADA) standards.

Type of Request

Split No Combine No Outputs No Description Yes Documentation No Fund Type No

Cost Yes Schedule No Scope Yes Delete No

Components

Note: Highlighted cells indicate phase allocated for SHOPP projects.

(\$ in 1,000s)

Existing (Programmed)		Proposed		Cost Expended to Date %Complete			Cost Change				
	Value	FY	Value (EAC)	FY	Expended	Pct Expended	Pct Complete	Value	Value%	Yrs	Туре
PA&ED	\$ 910	22/23	\$ 1,189	22/23	\$ 583	64.1%	52.4%	\$ 279	30.66%	0	D
PS&E	\$ 2,420	22/23	\$ 2,805	22/23	\$ 0	0%	0%	\$ 385	15.91%	0	D
R/W SUP	\$ 775	22/23	\$ 830	22/23	\$ 0	0%	0%	\$ 55	7.1%	0	D
CON SUP	\$ 4,010	25/26	\$ 4,828	25/26	\$ 0	0%	0%	\$ 818	20.4%	0	Р
R/W CAP	\$ 839	25/26	\$ 999	25/26	\$ 0	0%	0%	\$ 160	19.07%	0	Р
CON CAP	\$ 20,060	25/26	\$ 26,441	25/26	\$ 0	0%	0%	\$ 6,381	31.81%	0	Р
Totals	\$ 29,014		\$ 37,092		\$ 583			\$ 8,078	125%		

Change Type	Description
Р	Programming Cost Change: Per Senate Bill 1, any cost change subject to a CTC action.
D	Documentation: Not a programming change; it does not involve CTC action. For internal documentation only.
G12	G12: The change is within the delegated G-12 capacity. No PCR is required for this change; needs a G-12 Approval Memo.
NA	Not Applied/Blank: There is no cost change.

PRE-PGM DELIVERY YR	Yes	PGM DELIVERY YR & PRE VOTE	No	POST VOTE	No	
---------------------	-----	----------------------------	----	-----------	----	--

New Project Description (Only if revised)

County	LA	Route	213	Post Mile	0.0/10		
Description	In and near the cities of Los Angeles, Rancho Palos Verdes, Lomita, and Torrance, from West 25th Street to Route 405. Rehabilitate pavement, upgrade guardrail, upgrade facilities to Americans with Disabilities Act (ADA) standards, and install Complete Streets elements including: bike lanes, and crosswalks.						

Outputs (Project Performance)

Performance Measure (CTIPS) (Include counts of bridges and culverts)

	Value	Units
Programmed (from CTIPS)	42.9	Lane Miles(201.121)
Proposed in this PCR	42.9	Lane Miles(201.121)
Change	0	

Primary Asset Information (for Pavement, Bridge, Culvert, or TMS)

Primary and Supplementary Asset:	Pavement
Units :	Lane miles

Existing Condition (Pre Project)	Good	Fair	Poor	Total
Programmed (from CTIPS)	0	42.9	0	42.9
Proposed in this PCR	0	42.9	0	42.9
Change	0	0	0	0

Expected Post-Construction Condition	Good	Fair	Poor	New	Total
Programmed (from CTIPS)	42.9	0	0	0	42.9
Proposed in this PCR	42.9	0	0	0	42.9
Change	0	0	0	0	0

1.) WHAT IS THE PROPOSED CHANGE?

Augmenting project with available IIJA program funding for Complete Streets as follows:

- A. Increase Construction Capital by \$6,381K.
- B. Increase Construction Support by \$818K.
 C. Document Increase in PS&E Support by \$385K.
- D. Document increase in PA/ED Support cost by \$279K.
 E. Document RW Support cost increase by \$55K.
- F. Increase RW capital by \$160K.

G. Make scope and description change for complete streets elements.

2.) COMPLETE THE FOLLOWING REGARDING THE LATEST TWO COST ESTIMATES. (\$'s in 1,000's.)

Con Cap Est Date		Con Capital \$	RW Cap Est Date	RW Capital \$	
Current	22-Aug-23	26,441	22-Aug-23	999	
Previous	22-Jun-21	20,060	22-Jun-21	839	

3.) WHAT CHANGED SINCE THE PREVIOUS PROGRAMMING ACTION? WHAT NEW INFORMATION WAS NOT AVAILABLE WHEN THE PROJECT WAS PROGRAMMED OR AMENDED?

The original scope of work entails rehabilitate pavement, upgrade guardrail, and upgrade facilities to Americans with Disabilities Act (ADA) standards.

The Infrastructure Investment and Jobs Act (IIJA) has provided increased federal funding for transportation system projects in California. This Project Change Request (PCR) documents the additional scope and associated cost to an existing 2022 State Highway Operation and Protection Program (SHOPP) project made possible by the IIJA funding for Complete Street items for EA 34660. Adding Complete Street elements to the project will enhance bicycle awareness and usage.

A. Adding Complete Street elements to the project to enhance bicycle awareness and usage. These elements will Increase Construction Capital with IIJA funding as follows:

- 1- Class II/Class II Buffered Bike Lanes \$5,492,230.
- 2- Conflict zone green paint \$19,786.
- 3- Enhanced Visibility Paint Crosswalk \$412,200.
- 4- Bicycle Detection Loops \$102,292.
- 5- Bike Boxes & Two-Stage Left turn Queue Boxes \$26,106.
- 6- Bicycle and Pedestrian Signage \$328,386.

Total Estimated Cost is \$6,381,000 from IIJA.

- B. Increase Construction Support with IIJA funding for the added work.- The additional work listed above will necessitate the need for further funding for support to accommodate the additional inspection and coordination that is anticipated. The additional scope of work will increase the working days for the project by approximately 120 days. Total Amount Needed: \$818,000
- C. Document the increase in PS&E Support with IIJA funding for the added work. The additional work listed above will necessitate the need for further funding for support to accommodate the required design and coordination efforts. This phase has an approved time extension and an allocation greater than 100% will be requested. Total amount from IIJA is \$385,000.
- D. Document the increase in PA/ED Support of \$279K from IIJA fund for the added work. As this phase has been allocated, we are documenting in this PCR that we'll be making a request for supplemental funds for the additional funds. The additional bike lane will require field surveys, outreach effort with local agencies and communities, and additional studies during the PAED phase.
- E. Document the increase in Right of Way Support with IIJA funding for added work. This support cost for the estimated potholing to cover the added scope of work. This phase has an approved time extension and an allocation greater than 100% will be requested. Total Amount Needed: \$55,000.
- F. Increase Right of Way Capital with IIJA funding for the added work. The additional work listed above will necessitate the need for further potholing to accommodate the additional design, environmental studies, and required coordination efforts. Total Amount Needed: \$160,000
- G. We are adding the above mentioned complete street elements to enhance bicycle awareness and usage and updating the project description to include the new scope of work.

4.) WHEN WAS THE CHANGE DISCOVERED?

The change was discovered on May 2023, when District identified this project for IIJA funding.

5.) WHAT HAS BEEN DONE TO MANAGE ANY CHANGE? (ie. Field Reviews)

Field reviews have been conducted to determine the feasibility of the added scope. Additional coordination and outreach will be conducted with local agencies in the project area to ensure consistency and support. Funding augmentation with complete street improvements to the programmed project will enhance transportation assets and increase bicycle safety within the corridor limits.

6.) IF THIS IS A COST INCREASE, WHAT IS THE PLAN IF THIS PCR IS DENIED?

If the PCR is denied, there would not be additional funding to enhance the project's transportation assets and increase bicycle safety within the corridor limits. The Complete Street Elements will not be added to the project scope.

7.) IF THE SCOPE IS REDUCED OR SPLIT, WOULD THE REMOVED WORK NEED TO BE REPROGRAMMED OR ADDED TO ANOTHER PROJECT? No

n/a

8.) IS A SUPPLEMENTAL SCOPING DOCUMENT NEEDED? Yes IF YES STATUS?

CT will work on the Supplemental PIR to add the additional complete street elements for the project scope of work, the estimated date for this Supplemental PIR will be 11/16/2023. The Project is currently in PAED. The added scope will be documented in the PR for the project, which is scheduled to be completed in 06/07/2024.

9.) WAS A VALUE ANALYSIS STUDY CONDUCTED? No EXPLAIN THE RESULTS OF THE STUDY OR WHY A STUDY WAS NOT CONDUCTED.

The value analysis will be done during the PA/ED phase.

10.) COST - WHERE WILL THE REQUIRED FUNDS COME FROM?

The required funds for all the above mentioned elements will come from the Infrastructure Investment and Job Act (IIJA) complete streets funding allocated by headquarters.

11.) PRIOR PCRs LIST OTHER PCRs PREVIOUSLY APPROVED.

N/A

12.) (A) (STIP-RIP) WHEN DID THE DISTRICT OBTAIN CONCURRENCE FROM THE HEADQUARTERS STIP PROGRAM MANAGER AND THE RTPA OR COUNTY TRANSPORTATION COMMISSION STAFF?

N/A

(B) (STIP-IIP) WHEN DID THE DISTRICT OBTAIN CONCURRENCE FROM HEADQUARTERS STIP PROGRAM MANAGER?

N/A

(C) (SHOPP) IS THE HQ PROGRAM MANAGER'S RECOMMENDATION CONSISTENT WITH THE DISTRICT'S REQUEST? PROVIDE A NAME, DATE, AND SHORT SUMMARY OF THE DISCUSSION WITH THE PROGRAM MANAGER.

The HQ Program Manager (Complete Streets), Joshua Davis concurred with this PCR on 08/24/23. The HQ Program Manager (CAPM), Long Huynh concurred with this PCR on 08/24/23.

13.) LESSONS LEARNED, NEW STRATEGIES

(What new information pertaining to this project could be beneficial to others?)

Early in the project development process, look for opportunities for funding augmentation through different grants and programs. Identifying unprogrammable opportunities in the PID helps to quickly manage change when funding becomes available. Complete Street Elements should be identified during the development of the Project Initiation Report.

14.) HOW WAS THE CAUSE OF THE PROPOSED CHANGE DESCRIBED IN THE RISK REGISTER?

The opportunity was not identified in the risk register. This is an opportunity and could not have been foreseen as an opportunistic risk since new funding programs typically are not known at the time of project programming.

District PM: Nader Abdelmalek			Ph: (213) 598-6789			
Deputy District Director: Susan Chang						
HQ Project Delivery: Robert Navarro						
Concurrence: Y	Objections:n/a					
District Director: Gloria Roberts		Date:				
HQ Division PM Chief: JEFFREY N. WILEY			Date:			
HQ Division Chief Financial Programm	ming: JAMES R. ANDERSON	Date				



Project ID: 0718000076

Project Change Request Signature Page

Print Date: Mon Aug 28 2023 17:08:06 GMT-0700 (Pacific Daylight Time)

District: 07	EA5: 34660	PPNO: 5371	Pgm Doc: SHOPP	
County: LA Pgm Del Fy:2026	Route: 213	Postmile: 0.000/10	Prog Code: 20.XX.201.121	
District Project N	 Manager:	Nader Abdelmalek	Date	08/28/2023 a:
Deputy District I Program/Project	Director t Managemer	Susan Chang nt: Susan Chang	Date	08/29/2023 e:
HQ Project Coor	dinator:	Robert Navarro	Date	08/30/2023 2:
District Director:	Dregory Fam	Gloria Roberts	Date	09/01/2023 e:
		Approve Den	No HQ Action	
		Cost Scope Schedule Split/Combine Other And Resubmit		
HQ Division Chie Project Managen	f nent:	For Simply Phys		e: 10/2/23
HQ Division Chie		Lyls Stockto	n Date	10-24-2023 م

State Highway Operation and Protection Program

Los Angeles County
Document Year 2022, Version Number 3 PPNO: 5371 (Dollars in Thousands)

DIST: PPNO: EA: CTIPS ID: TCRP NO.: 34660 109-0000-4710 07 5371

CT PROJECT ID: 0718000076

COUNTY: ROUTE:

Los Angeles County 213

PM: 0.000 / 9.984 TITLE (DESCRIPTION):

(In and near the cities of Los Angeles, Rancho Palos Verdes, Lomita, and Torrance, from West 25th Street to Route 405. Rehabilitate pavement, upgrade guardrail, and upgrade facilities to Americans with Disabilities Act

(ADA) standards.)

ELEMENT: SHOPP Major Const.

MPO ID: LAW: 22

SPONSOR: Caltrans

MPO: Southern California Association of

Governments

CORRIDOR: PRJ MGR:

PHONE: EMAIL:

ASSEMBLY: 64,66,70 SENATE: 26,35 CONGRESS: 33,43,44

IMPLEMENTING AGENCIES:

PAED

PSE

RW

CON

Program Code	Quantity	Performance Measure			Asset Class
201.121	42.9	Lane mile(s)			Primary
	<u>Unit</u>	Good/operational	<u>Fair</u>	Poor/non-operational	<u>Quantity</u>
Existing Condition	Lane mile(s)	0.0	42.9	0.0	42.9
Post Condition	Lane mile(s)	42.9	0.0	0.0	42.9

PROJECT VERSION HISTORY (Printed Version is Shaded) (Last 9 versions displayed)

Programmed Dollars in Thousands - Total for Project

Version	Status	Date	Updated By	Change Reason	Amend No.	Vote	Cum Award	Prog Con	Prog RW	PA & ED	PS & E	RW Sup	Con Sup
3	Official		GBAINS	Time Extension - Allocation		910		20,060	839	910	2,420	775	4,010
2	Official	06/29/2022	GBAINS	Allocation - CTC Vote	FP-21-92	910		20,060	839	910	2,420	775	4,010
1	Official	03/16/2022	LSTOCKTO	Approved - New Project	22H-000			20,060	839	910	2,420	775	4,010

Fund Source 1 of 1 SHOPP -**Roadway Preservation**

20.XX.201.121 - Pavement Preservation (CAPM) Fund Type

Allocation Time Extensions National Hwy System Phase_ Deadline **Funding Agency** PSE 08/31/2024 23-72

AMOUNT 910	PA&ED PS&E R/W SUP CON SUP	PRIOR	22-23 910 2,420 775	23-24	<u>24-25</u>	<u>25-26</u> 4.010	26-27	<u>27-28</u>	FUTURE	TOTAL 910 2,420 775 4,010
Extensions	R/W CON					839 20.060				839 20,060
<u>Waiver</u>	Total:		4,105			24,909				29,014

07/12/2023 Made official fourteen month time extension for PS& and R/W Sup approved under Waiver 23-72; June 2023; expiring August 2024 -GB

VOTE DATE

PAED 06/29/2022

RW Sup 08/31/2024

******* Version 3 - 07/06/2023 *******

Entered Time Extension- NM

6/30/22: Made COS allocation (PA&ED) official - GB ******** Version 2 - 06/28/2022 ******* Entered COS allocation (PA&ED) ? RS ****** Version 1 - 03/16/2022 ***** New 2022 SHOPP project

Products of CTIPS 09/01/2023 04:50:43 Page 1

From: Bains, Harsimran@DOT

To: Abdelmalek, Nader H@DOT

Cc: Salehinik, Mehdi@DOT; Kuoch, Chan Q@DOT; Romero Jr, Leon@DOT; Sanchez, Noah R@DOT; Navarro, Robert

M@DOT

 Subject:
 RE: 07-34660 Exec PCR Outcome

 Date:
 Friday, September 29, 2023 11:33:17 AM

Good morning Nader,

I appreciate you getting back to me. Thanks a lot for sharing this information.

Hope you have a great weekend!

Regards,
-Harsimran Bains (Simran)
Cell (916) 956-9688

From: Abdelmalek, Nader H@DOT <nader.abdelmalek@dot.ca.gov>

Sent: Friday, September 29, 2023 11:18 AM

To: Bains, Harsimran@DOT < Harsimran.Bains@dot.ca.gov>

Cc: Salehinik, Mehdi@DOT <mehdi.salehinik@dot.ca.gov>; Kuoch, Chan Q@DOT

<chan.kuoch@dot.ca.gov>; Romero Jr, Leon@DOT <leon.romero@dot.ca.gov>; Sanchez, Noah
R@DOT <noah.sanchez@dot.ca.gov>; Navarro, Robert M@DOT <robert.navarro@dot.ca.gov>

Subject: 07-34660 Exec PCR Outcome

Good morning Harsimran,

Per the HQ PCR Exec review meeting on 09/22/23, please find the project information below along with the attached updated PCR:

EA 07-34660

The original scope of work:

In and near the cities of Los Angeles, Rancho Palos Verdes, Lomita, and Torrance, from West 25th Street to Route 405. Rehabilitate pavement, upgrade guardrail, and upgrade facilities to Americans with Disabilities Act (ADA) standards.

Added scope of work:

Adding Complete Street elements to the project to enhance bicycle awareness and usage. These elements are:

- 1- Class II/Class II Buffered Bike Lanes
- 2- Conflict zone green paint
- 3- Enhanced Visibility Paint Crosswalk
- 4- Bicycle Detection Loops
- 5- Bike Boxes & Two-Stage Left turn Queue Boxes
- 6- Bicycle and Pedestrian Signage

Please contact us if you need any further information and I really appreciate if you may reply that you received this email.

Thank you so much for all your help,

Nader Abdelmalek, PE Project Manager Division of Program/Project Management Cell: (213) 598-6789

				SHOPP Project =	Accomplishment - Performance Measures - Benefits	ormance M	easure	s - Be	nefits								
Distric	District: 07 To	Tool ID: 19243 ▼	Project ID:	▶ 0718000076 ▶	EA: 34660 \	Co-Rte-PM:	LA-21	3-0/9.984	(Primary L	LA-213-0/9 984 (Primary Location) 🗸				View/Prir	nt PIR (Per	View/Print PIR (Performance) Report	ort
Bridge		Pavement Drainage	nage Facilities	Signs and Lighting	Mobility Roadside	Complete Streets		Sustainability /Climate Change	oility Change	Advanc /Mitigat	Advance Mitigation /Mitigation		Major Damage & Betterments		en-house	Green-house Gases Relinquishment	linquishme
					Performance & Accomplishments (TYP V	ments (TYP	िद										
ActID			Activity Detail		Performance Objective	Unit of Quantity Good Fair	Quantity	Pre- Good F	air Pre-I	Pre-Poor New	Post- Good	t- Post	HQ Program Post- Review - Fair Poor Agree With District?	am HQ w- Comment	Revie ent Date	Review Performance Change Date Date After Review	Comment
1 B05 Mair	line Existing Asphalt	CAPM (e.g. 2" Thin Overlay	with or without Wearing Surface	Mainline Existing Asphalt CAPM (e.g. 2" Thin Overlay with or without Wearing Surface, Cold in Place, Digouts, Etc.) (201.121)	21) Pavement Class II	Lane Miles	42.866	39	39.796 3	3.070	42.1	42.866					2027 MAP-21 Condition
2 E07 Gua	2 E07 Guard Rail (201.010, .015)				No Performance Objective in the SHSMP Linear Feet	AP Linear Feet	880,000		880	880.000	880,000	000					
3 F24 ADA	F24 ADA - Repair/Upgrade Curb Ramp (201.361)	rb Ramp (201.361)			No Performance Objective in the SHSMP Each	AP Each	45.000		45	45.000	45.0	45.000					
4 F32 AD/	۱- Install New Detecta	4 F32 ADA - Install New Detectable Warning Surface (201,361)	161)		No Performance Objective in the SHSMP Square Feet	AP Square Feet	70.000			70.000	8						Implement truncated domes
5 F43 ADA	F43 ADA - Deficient Elements				ADA Pedestrian Infrastructure	Deficient Elements	45.000		45	45.000	45.0	45.000					
6 H13 Crosswalks	sswalks				No Performance Objective in the SHSMP Linear Feet	AP Linear Feet	3840.000			3840.000	00						New continental crosswalk
7 H56 Con	H56 Complete Streets Fix Existing	ting			Complete Streets Fix Existing	Linear Feet					L						
8 H57 Corr	H57 Complete Streets Build New	we			Complete Streets Build New	Linear Feet	3840,000		3840.000	000	3840.000	000					
9 N02 Qua	9 N02 Quantitative - Proposed Mitigated	itigated			No Performance Objective in the SHSMP MTCO2e	AP MTCO2e	4200.000										
(Last Save	(Last Saved - 08/22/18 @ 11:21 AM by Charles Lau)	AM by Charles Lau)															

Programming Performance Summary (All Locations)

42.9	0:0	0:0	42.9	0000	42.9	42.9	3.1	39.8	0.0	Lane mile(s)	Lane mile(s)	42.9	Pavement	Primary	Pavement - Pavement Preservation	201.121
Post-Total	Post-Poor	Post-Fair	Post Good+New	New	Post Good	Pre-Total	Pre-Poor	Pre-Fair	Pre-Good	Unit	Performance Measure	Performance Value	Asset	Asset Class	Activity Category	0

- 1. The crosswark for reporting performance in the "Programming Performance Summary" was developed to assist the districts on performance reporting requirements for CTC and PCRs. For discrepancies or errors, please notify AM Tool admins via e-mail at CT-TAM@dot.ca.gov.
 - 2. The data summarized in the table represents the performance reported or to be reported in CTIPS.

- Programming only requires the breakdown of Good. Fair and Poof for Primary and Supplementary Asset Classes.
 Reporting on bridge pre and post conditions may contain errors if the project RTL is before 2024/25.
 Reporting of bridge pre and post conditions may contain errors if the project RTL is before 2024/25.
 Reporting of the post good may differ whenever projects contain abandoned/removed culverts as the culvert no longer exists at post constitution is deleted from the pre-total value for a post of may differ whenever projects will empropriate the professional post projects will empropriate the professional post projects. When the reporting requirements for CTC changes, the logic in the AM Tool will change.
 Duractive Salety solicitive is be performance output for projects with a primary activity category of Proactive Salety (under program codes 015, 112, or 235) will continue to be presented here in the units of measure corresponding to the activities historically reported to date. A change in units to "Annual Fatal and Serious Injury Collisions" for future programming requests is being planned.

		SHOPP Project -	 Accomplishment - Performance Measures - Benefits 	ment -	· Perfor	mance	Measu	ires - B	enefits						
Dist	District: 07 Tool ID: 19243 V	Project ID: 0718000076 ✓	EA: 34660	>	O	Co-Rte-PM:		4-213-0/9.98	LA-213-0/9.984 (Primary Location) 🗸	cation) 🗸			View/Print I	View/Print PIR (Performance) Report	nce) Report
	Bridge Pavement P Drainage	Facilities Signs and Lighting	Mobility TMS	Roadside		Complete Streets	Streets	Sustain /Climate	Sustainability /Climate Change	Advance Mitigation /Mitigation	itigation	Major Damage & Betterments		Green-house Gases	Relinquishment
			Performance & Accomplishments (PRG 🗢	& Accor	nplishm	ents (PR	© <								
ActiD	ID Activity Detail	Performance Objective	Unit of Measurement	Quantity	Pre-Good F	re-Fair Pre	Poor Ne	w Post-Go	ood Post-Fa	ir Post-Poor	Quantity Pre-Good Pre-Fair Pre-Poor New Post-Good Post-Fair Post-Poor Review - Agree with District?	HQ Comment Review Date Change Date After Review	Review Date	Performance Change Date After Review	Comment
1 B2!	B25 Asphalt Pavement Minor Rehab (CAPM)	Pavement Class II	Lane Miles	42.866		42.866		42.866	366						
2 E07	7 Guard Rail (201.010, .015)	No Performance Objective in the SHSMP	Linear Feet	880.000		88	880.000	880.000	000						Upgrade MBGR to MGS
3 F01	1 Census Station (201.315)	No Performance Objective in the SHSMP	Each	2.000			2.0	2.000							
4 F24	4 ADA - Repair/Upgrade Curb Ramp (201.361)	No Performance Objective in the SHSMP	Each	61.000		9	61.000	61.000	000					1	Per Sarah Horn
5 F25	5 ADA - Install Accessible Pedestrian Signal (201.361)	No Performance Objective in the SHSMP	Each	39.000		36	39.000	39.000	000					1	Per Sarah Horn
6 F43	3 ADA - Deficient Elements	ADA Pedestrian Infrastructure	Deficient Elements	100.000		10	100.000	100.000	000						
7 F45	F45 TMS Structure Component	Transportation Management System Structures	Each	2.000			2.0	2.000							
8 F46	6 TMS Technology Component	Transportation Management Systems	Each	2.000			2.0	2.000							
9 H27	7 Transit Stop Improvements	No Performance Objective in the SHSMP	Each	44.000		4	44.000	44.000	000					1	Per CSDD
10 H32	H32 Is any Location Within the Project Limits Ped/Bike Accessible?	No Performance Objective in the SHSMP	Ves/No	Yes										,	Yes
11 H37	7 Bicycle-Tolerable Drainage Grates	No Performance Objective in the SHSMP	Each	11.000			11.000	000						1	Per CSDD
12 NO.	12 N02 Quantitative - Proposed Mitigated	No Performance Objective in the SHSMP	MTCO2e	4200.000											
(Last	(Last Saved - 08/17/21 @ 10:59 AM by AMT Admin)														

Programming Performance Summary (All Locations)

m Code	Activity Category	Asset Class	Asset	Performance Value	Performance Measure	Unit	Pre-Good	Pre-Fair	Pre-Poor	Pre-Total	Post Good	New	Post Good+New	Post-Fair	Post-Poor	Post-Total
144	Pavement - Pavement Preservation	Primary	Pavement	42.9	Lane mile(s)	Lane mile(s)	0.0	42.9	0.0	42.9	42.9	0.000	42.9	0.0	0:0	42.9

- 1. The crosswalk for reporting performance in the "Programming Performance Summary" was developed to assist the districts on performance reporting requirements for CTC and PCRs. For discrepancies or errors, please notify AM Tool admins via e-mail at CT-TAM@dot.ca.gov. 2. The data summarized in the table represents the performance reported or to be reported in CTIPS.

 - 3. Programming only requires the breakdown of Good, Fair and Poor for Primary and Supplementary Asset Classes.

4. Reporting of bridge pre and post conditions may contain errors if the project RTL is before 2024/25.

- 5. Reporting dainage pre-lotal and post good may differ whenever projects contain abandoned/removed culvert as the culvert no longer exists at post construction, is deleted from the pre-lotal value for posting of the post good value, and gets deleted from the statewide CIP inventory database.

 6. Reactive Safety projects will temporally use the same performance output for projects. When the reporting requirements for CTC changes, the logic in the AM Tool will change.

 7. Annual preta than sold to the new Proparative. The performance output for projects with a primary activity category of Proactive Safety (under program codes 015, 112, or 235) will continue to be presented here in the units of measure corresponding to the activities historically reported to date. A change in units to "Annual preta farial she intogramming requests is being planned."

PIR/PA&ED COST ESTIMATE COMPARISON – Attachment P

ROADWAY ITEMS			PAED				뎶		REASON OF COST (+/-)
SECTION 1: EARTHWORK									
Item code	Unit	Quantity	Unit Price (\$)	Cost	Quantity	Unit Price (\$)	e (\$)	Cost	The addition of sidewalk segment
190101 Roadway Excavation	C	3,380	x 200,000 =	\$ 676,000					requires a retaining wall.
19010X Roadway Excavation (Insert Type) ADL	C	250	x 250.00 =	\$ 62,500					
192037 Structure Excavation (Retaining Wall)	CY	3,660	x 225.00 =	\$ 823,500					Reduction of median for bike lanes
192053 Structure Excavation (Type Z-2)	C	640	x 450,00 =	\$ 288,000					and predicted dig out locations
193013 Structure Backfill (Retaining Wall)	C	3,320	x 100,000 =	\$ 332,000					requires roadway excavation.
193031 Pervious Backfill Material (Retaining Wall)	C	90	x 250,00 =	\$ 12,500					
17010X Clearing & Grubbing	rs	1	x 15,000,000 =	\$ 15,000	1	x 15000	\$ = 0	15,000,00	
TOTAL				\$ 2,209,500			\$	15,000.00	\$ 2,194,500.00
SECTION 2: PAVEMENT STRUCTURAL SECTION									
Item code	Unit	Quantity	Unit Price (\$)	Cost					
260303 Class 3 Aggregate Base	Ç	2,040	x 175.00 =	\$ 357,000					Increase is due to price and
153103 Cold Plane Asphalt Concrete Pavement	SQYD	427,900	x 5,00 =	\$ 2,139,500	410	x 2.2	П	902,000.00	quantity increase and addition of
397005 Tack Coat	TON	100	= 00.008 ×	\$ 80,000	\$	× 150,000	\$ 00	150,000.00	approximately 1,200 ft of
360200 Base Bond Breaker	SQYD	5,490	x 3,00 =	\$ 16,470					sidewalk.
731521 Minor Concrete (Sidewalk)	ζ	09	x 1,500,000 =	\$ 90,000					
731504 Minor Concrete (Curb and Gutter)	C	70	x 100.00 =	\$ 7,000					Reducing the median for bike lane
7318940 Remove Concrete (Curb and Gutter)	4	200	× 30.00 =	\$ 15,000					requires new structural section
730020 Minor Concrete (Curb)	ζ	006	x 1,000,00 =	\$ 900,000					in addtioon to predicted dig out
390095 Replace Asphalt Concrete Surfacing	ζ	100	x 450.00 =	\$ 45,000					locations.
390132 Hot Mix Asphalt (Type A) Dig out	NOT		x 130,00 =	€	6,300	× 90	\$ =	567,000.00	
390137 Rubberized Hot Mix Asphalt (Gap Graded)	NOT	57,800	x 150,00 =	\$ 8,670,000	65,200	× 94	H	6,128,800.00	
731502 ADA Curb Ramps	EA	64	x 13,000,00 =	\$ 832,000	45	× 5,500	П	247,500.00	
731502 Bus Pads	EA		x 35,000.00 =	€9	44	× 28,300	П	1,245,200.00	
401055 Jointed Plain Concrete Pavement (RSC)	≿	1,560	x 850,00 =	\$ 1,326,000					
280000 Lean Concrete Base	Ç	620	× 500,000 =	\$ 310,000					
280015 Lean Concrete Base (RS)	ζ	006	× 280.00 =	\$ 252,000					
TOTAL				\$ 15,040,000			❖	9,240,500.00	\$ 5,799,500.00
SECTION 3: DRAINAGE									
Item code	Unit	Quantity	Unit Price (\$)	Cost					
150820 Modify Inlet	EA	11	x 2,500,00 =	\$ 27,500	11	x 2,500	П	27,500.00	
TOTAL				\$ 27,500			\$	27,500.00	- \$
SECTION 4: SPECIALTY ITEMS									
	Unit	Quantity	Unit Price (\$)	Cost					
520103 Bar Reinforced Steel (Retaining Wall)	ΓB	33,016	x 3,00 =	\$ 99,048					Increase is due to adding additional
510530 Minor Concrete (Wall)	C	380	x 2,500,00 =	\$ 950,000					retaining wall items and
190110 Lead Compliance Plan	ST	_	x 20,000.00 =	(4	П	× 20,000	\$ = 0	20,000.00	modification of the median island.
839752 Remove Guardrail	4	478	x 20.00 =	\$ 9,560					
832007 Midwest Guardrail System	4	478	x 75,00 =		880		п	36,080.00	
839701 Concrete Barrier (Type 60)	4	144	x 350,00 =	\$ 50,400	144	x 350	\$ =	50,400.00	
	4	150	= 00'055 ×	\$ 82,500					
839581 End Anchor Assembly (Type SFT)	EA	4	x 2,500,00 =	\$ 10,000	4	× 780		3,120.00	
XXXX Side Walk, Raised island and Curb repair	ST	1	x 100,000,000 =	\$ 100,000	1	x 100,000	П	100,000.00	
TOTAL				\$ 1,357,400			\$	209,600.00	\$ 1,147,800.00

		\$ (256,410.00)	Addition of SWDR Items.		\$ 5,000.00	Addition of SWDR Items.	Items missed in PID.									\$ 180,200.00		Items missed in PID.			\$ 115,000.00					itenis not incladed in rio.		Additional Modifications needed	due to ADA curb ramp conflicts.	\$ 881,152.00		Increase due to the items price	increase.		Replacement of Roadside Signs	
		\$ 374,100.00																								×	100,000 = \$	00.000,001 ¢	1 x 1,500,000 = \$ 1,500,000.00	\$ 1,760,000.00			0.4 = \$ 41.840.00	x 2.5 = \$ 2,425.00		
Cost 73,440 30,150	14,100	117,690		5,000	5,000		Cost	10,000	000′9	10,000	3,200	5,000	35,000	30,000	50.000	180,200		100,000	2,000	10,000	115,000			Cost	80,000	10.000	000	1 186 152	740,000	2.641.152		Cost	208.120	9,700	300,000	
\$ \$. = = 0	x 47.00 = \$ x = \$	₩		<i>Unit Price (3)</i> × 5.00 = \$	\$		Unit Price (\$)	1 11	3,000,000 =	1,000,00 =	3,200,00 =	5.00 =	= 0	300.00 =	x 50.000.00 = \$			100,000,001	Ш	x 10,000,00 = \$	\$			(%)	x 80,000 = \$	10.000.00	00 000 004	x 400,000,00 = \$	740.000,00 =			Unit Price (\$)	2.00 =		1.50 =	
Quantity 1	300			1,000		; 	Quantity 1		2	10	_	1,000	- 6	000 2	3,000			_	-	-			,	Quantity			. ,		- ,-			Quantıty	104.060	970	200,000	
Unit LS LS	SQYD EA		577	JI.		:	Unit S	rs FS	EA	EA	EA	<u></u> ዜ !	S	EA CVCV	SQ7D I.S			ST	rs	rs				Unit	S S	3	LS I	S <u>S</u>	S S			Cuit C		SQYD	4	
SECTION 5: ENVIRONMENTAL 5B - LANDSCAPE AND IRRIGATION Item code 20XXXX Permanent BMP #1 20XXXX Permanent BMP #2	Vegetation Control (Minor Concrete) Water Pollution Control	TOTAL	5C - EROSION CONTROL	Fiber Rolls	TOTAL		Dronaro CM/DDD	Job Site Management	Storm Water Annual Report	Rain Event Action Plan	Storm Water Sampling and Analysis Day	Temporary Fiber Roll	Temporary Concrete Washout	Temporary Drainage Inlet Protection	Terriporary Cover	TOTAL	Supplemental Work for NPDES	Water Pollution Control Maintenance Sharing*	Storm Water Sampling and Analysis***	Additional Water Pollution Control**	TOTAL	SECTION 6: TRAFFIC ITEMS	<u>-lectrical</u>		Modifying Wireless Magnetometer Vehicle detection System	nanc Census Station Systems Maintaining Existing Traffic Management System Elements	During Construction	Protect Fiber Optic Conduit System Modify Signal and Light system	Relocate Signal Structures/ Pull Boxes, and Loop Detectors	TOTAL	6B - Traffic Signing and Striping	Roadside Sim - (One Doet & Two Doet)	Remove Yellow Painted Traffic Stripe (Hazardous Waste)	Delineator (Marker)	Temporary Traffic Stripe	
SECTION 5B - LANDSC Item code 20XXXX 20XXXX	XXXXXX 209801		5C EROSIC	210350		5D NPDES	Item code	130100	130330	130310	130320	130640	130900	130620	130570		Supplement	066595	066597	066596		SECTION	6A - Traffic Electrical	Item code	87XXXX	A108070	870009	86XXXX 872133	872130		6B - Traffic	Item code	141102	820101	840501	

not included in PID.	0 \$ 2,472,105.00	Add traffic control due to	median work.	\$ 185,500.00	d traffic control due to	median work.		0			0 \$ 1,274,620.00			\$ 540,000.00	0	0 \$ 11,046.00		0	1 443 500 00)	c	Items not included in PID.						0 \$ 490,600.00				0 0	- 0
15,000.00 78,450.00 28,000.00	165,715.00							280,000.00			280,000.00				386,400.00	386,400.00		1,245,900.00	1 245 900 00	7,210,000	00 000 867	6.001						498,400.00				150,000.00	5,000.00
15,000 = 1 = 0.5 =	\$							280,000 = \$			\$				3.20% = \$			10% = \$		}	\$ - %/	?						\$				\vdash	2000
1 × 104,600 × 56,000 ×								1 ×							ltem 1-7 12,072,500 x			Item 1-8 12,458,900 x			Item 1-8											т ,	
1,200,000	2,637,820		Cost 185,500	185,500		Cost 5 000	10,920	1,500,000	10,500	22,200	1,554,620	Cost	540,000	540,000	397,446	397,446		2.689.390	2 689 400	2,000,100	350 000	000,000	150,000	25,000	10,000	20,000	268,939	000'686		Cost	200,000	\$150,000	000,061\$
\$ \$ 00	\$	•	(\$)			(\$)	1 11	П	65 69		\$	(\$)	\$ =	\$	\$	₩		u II		€	(\$)	1 11	П	II	# # 	1 11	11	\$		(§)	П		=
3.00 100,000.00			Unit Price (\$) \$ 185,500			Unit Price (\$)		7,5	350.00			Unit Price (\$)			1.50%			0.10			Unit Price (\$)				10,000.00					Unit Price (\$)			00.000,061
400,000 x 1 x		:	Quantity 1 ×			Quantity x	42 ×		30 × ×			Ouantity	18,000 x		26,496,000 ×			26.893.900.00			Quantity ,	· ·	۲ ×		· ×	× ×	26,893,900 x			Quantity x	. .	- ·	-
T S T T		:	nut LS			Unit FA	EA	rs	SOYD	LF		Unit	LF					tem 1-8			Unit	LS LS	LS	rs	S]	r. S.	Item 1-8		S)	Unit S	FS FS	LS LS	2
Thermoplastic Traffic Stripe Construction Area Signs 6" Yellow Thermoplastic Traf 6" White Thermoplastic Traf	TOTAL	6C - Traffic Management Plan	Portable Changeable Message Sign		6C - Stage Construction and Traffic Handling	Channelizer (Insert Tyne)			Temporary Crash Cushion Module Temporary Pavement Marking (Paint)		TOTAL	V 7: DETOURS	Temporary Railing (Type K)	TOTAL	SECTION 8: MINOR ITEMS SUBTOTAL SECTIONS 1-7	TOTAL	SECTION 9: MOBILIZATION		TOTAI	SUPPLEMENTAL V	Davmant Adiretmante For Drica Inday Electristicus				Dispute Resolution Advisor			TOTAL	V 11: STATE FURNISHED MATERIALS AND EXPENSES	Railroad Work (Flanning)	Railroad Work (Pedestrian Gates)		raffic Management Plan - Public Information
840502 120090 840623 840623		3C Traffic	Item code 12865X		C - Stage (Item code	129100	120100	129110 120152	120320		SECTION 7:	129000		SECTION		SECTION	Item code 99990		SECTION 10:	Item code	066094	066070	066919	066921	066919			SECTION 11:	Item code	66020	066105	066063

066062 COZEEP Contract	ΓS	-	x 85,000.00	= \$85,000	1	x 4200	42000 = \$	42,000.00	
066916 Annual Construction General Permit Fee	rs	1	x 3,500,00	= \$3,500					
TOTAL SECTION 1-8	tem 1-8	26,893,900 x	x 0.01	= \$268,939		0 ×	\$ =	$12458900 \times 0 = $124,589.00$	
TOTAL				\$ 1,457,500			\$	321,600.00	\$1,135,900.00
SECTION 12: TIME-RELATED OVERHEAD									
Item code	Unit	Quantity	Unit Price (\$)	Cost					
090100 Time-Related Overhead	WD	(009	X \$2,241	= \$1,344,700	360	(1731	= \$	\times 1731 = \$ 623,000.00	
TOTAL				\$1,344,700			\$	\$ 00.000,629	721,700.00
SECTION 13: CONTINGENCY									
		\$ 33,374,500 X		15% = \$ \$ 5,006,200.00 15,147,800 x	15,147,800 x	25%	\$ =	25% = \$ 3,787,000.00	
TOTAL				\$ 5,006,200.00			\$	\$ 3,787,000.00 \$	1,219,200.00

19,561,000.00

\$ 18,934,800.00 \$

\$ 38,380,700.00

TOTAL PROJECT COST

TRAFFIC ELECTRICAL WORK – Attachment Q

		Description of Electrical	
Intersection/Location	Design Ramp #'s	Work: Type pole,	Notes
mersection, Escation	Design nump # 3	Pullbox, etc.	Notes
		4-Type 5 Pull Boxes	Hydrant might be in the way of the curb ramp
		2-Type 2 Post PBA	•Relocate 4 pullboxes
		2 Type 2 Tose 1 B/C	May need to install PBA posts
SW SEPULVEDA Blvd.	R-1 & R-2	-	· · · · · · · · · · · · · · · · · · ·
		2-Type 5 Pull Boxes	•Relocate Type 16-3-100 Pole
	_	1-Type 6 Pull Boxes	•Relocate 4 pullboxes
SE 213TH St	R-10 & R-11	Type 16-3-100 Pole	May need to install PBA posts
SW 213TH St	R-12 & R-13	4-Type 5 Pull Boxes	•Relocate 4 pullboxes
NE 213TH St	R-14 & R-15	4-Type 5 Pull Boxes	•Relocate 4 pullboxes
NW 213TH St	R-16 & R-17	3-Type 5 Pull Boxes	•Relocate 3 pullboxes
		4-Type 5 Pull Boxes	•Relocate Type 24-4-100 Pole
		Type 24-4-100 Pole	•Relocate 4 pullboxes
SE TORRANCE Blvd	R-19 & R-20	C-1-100 Pole	•Relocate C-1-100 Pole
SW TORRANCE Blvd	R-21	2-Type 5 Pull Boxes	•Relocate 2 pullboxes
NE TORRANCE Blvd	R-22	N/A	N/A
NW TORRANCE Blvd	R-23	2-Type 5 Pull Boxes	•Relocate 2 pullboxes
		3-Type 5 Pull Boxes	Relocate 3 pullboxes
SE DEL AMO Blvd	R-39 & R-40	2-Type 2 Post PBA	 May need to install PBA posts
		2-Type 5 Pull Boxes	•Relocate 2 pullboxes
		Type CD954 Pole	•Relocate Type CD954 Pole
SW DEL AMO Blvd	R-41 & R-42	2-Type 2 Post PBA	 May need to install PBA posts
		2-Type 5 Pull Boxes	•Relocate 2 pullboxes
		1-Type 6 Pull Boxes	•Relocate Type CD954 Pole
		Type 2 Post PBA	 May need to install PBA posts
		Type CD954 Pole	 Relocate 332 Controller Cabinet
NE DEL AMO Blvd	R-43	Type 332 Controller Cabinet	
		2-Type 5 Pull Boxes	•Relocate 2 pullboxes
NW DEL AMO Blvd	R-44	Type 2 Post PBA	 May need to install PBA post
SE FRANCISCO St	R-45	N/A	N/A
		2-Type 5 Pull Boxes	•Relocate 2 pullboxes
SW WESTERN Way	R-46	Type 2 Post PBA	 May need to install PBA post
		3-Type 5 Pull Boxes	•Relocate 3 pullboxes
		Type 2 Post PBA	•Relocate Type 17-3-100 Pole
NE FRANCISCO St	R-47 & R-48	Type 17-3-100 Pole	May need to install PBA post
NW WESTERN Way	R-49 & R-50	N/A	N/A
•		2-Type 5 Pull Boxes	•Relocate 2 pullboxes
SE 195TH St	R-51	Type 2 Post PBA	May need to install PBA posts
		2-Type 5 Pull Boxes	May need to install PBA post
		Type 2 Post PBA	•Relocate 2 pullboxes
SW 195TH St	R-52	Type 1A-Pole	•Relocate Type 1A Pole
		2-Type 5 Pull Boxes	•Relocate 2 pullboxes
NE 195TH St	R53 & R54	2-Type 2 Post PBA	May need to install PBA posts
NW 195TH St	R55 & R56	N/A	N/A
20000		5-Type 5 Pull Boxes	•Relocate 5 pullboxes
SE 190TH St	R57 & R58	2-Type 2 Post PBA	May need to install PBA posts
<u></u>	, \(\alpha\) 1.50	3-Type 5 Pull Boxes	May need to install PBA posts
		2-Type 2 Post PBA	•Relocate 3 pullboxes
SW 190TH St	R59 & R60	Type CD953C Pole	Relocate Type CD953C Pole
244 T301113f	172 K 1100	Type ebooder tile	- Neiocate Type CD303C Pole

ADA CURB RAMP LIST – Attachment R

		Location/	ADA Curb	Layout
PM	Intersection	Corner	Ramp #	Sheet #
6.984	Sepulveda Blvd.	SW	R-1	L-25
6.984	Sepulveda Blvd.	SW	R-2	L-25
7.127	228th St.	SE	R-3	L-26
8.063	216th St.	SE	R-4	L-29
8.07	216th St.	NE	R-5	L-29
8.13	215th St.	SE	R-6	L-29
8.14	215th St.	NE	R-7	L-29
8.196	214th St.	SE	R-8	L-29
8.202	214th St.	NE	R-9	L-29
8.263	213th St.	SE	R-10	L-30
8.262	213th St.	SE	R-11	L-30
8.261	213th St.	SW	R-12	L-30
8.262	213th St.	SW	R-13	L-30
8.27	213th St.	NE	R-14	L-30
8.272	213th St.	NE	R-15	L-30
8.273	213th St.	NW	R-16	L-30
8.275	213th St.	NW	R-17	L-30
8.404	212th St.	SE	R-18	L-30
8.441	Torrance Blvd.	SE	R-19	L-30
8.443	Torrance Blvd.	SE	R-20	L-30
8.432	Torrance Blvd.	SW	R-21	L-30
8.476	Torrance Blvd.	NE	R-22	L-30
8.459	Torrance Blvd.	NW	R-23	L-30
8.647	209th St.	SE	R-24	L-31
8.655	209th St.	NE	R-25	L-31
8.727	208th St.	SE	R-26	L-31
8.735	208th St.	NE	R-27	L-31
8.736	208th St.	NW	R-28	L-31
8.778	207th St.	SE	R-29	L-31
8.786	207th St.	NE	R-30	L-31
8.846	206th St.	SE	R-31	L-32
8.855	206th St.	NE	R-32	L-32
8.908	205th St.	SE	R-33	L-32
8.906	205th St.	SW	R-34	L-32
8.916	205th St.	NE	R-35	L-32
8.917	205th St.	NW	R-36	L-32
8.969	204th St.	SE	R-37	L-32
8.976	204th St.	NE	R-38	L-32
9.049	Del Amo Blvd.	SE	R-39	L-32
9.051	Del Amo Blvd.	SE	R-40	L-32
9.046	Del Amo Blvd.	SW	R-41	L-32
9.048	Del Amo Blvd.	SW	R-42	L-32
9.059	Del Amo Blvd.	NE	R-43	L-32
9.064	Del Amo Blvd.	NW	R-44	L-32

		Location/	ADA Curb	Layout
PM	Intersection	Corner	Ramp #	Sheet #
9.234	Western Way/Francisco St.	SE	R-45	L-33
9.238	Western Way/Francisco St.	SW	R-46	L-33
9.252	Western Way/Francisco St.	NE	R-47	L-33
9.254	Western Way/Francisco St.	NE	R-48	L-33
9.253	Western Way/Francisco St.	NW	R-49	L-33
9.255	Western Way/Francisco St.	NW	R-50	L-33
9.573	195th St.	SE	R-51	L-34
9.573	195th St.	SW	R-52	L-34
9.586	195th St.	NE	R-53	L-34
9.588	195th St.	NE	R-54	L-34
9.587	195th St.	NW	R-55	L-34
9.587	195th St.	NW	R-56	L-34
9.864	190th St.	SE	R-57	L-35
9.867	190th St.	SE	R-58	L-35
9.857	190th St.	SW	R-59	L-35
9.86	190th St.	SW	R-60	L-35
9.885	190th St.	NE	R-61	L-35
9.888	190th St.	NE	R-62	L-35
9.884	190th St.	NW	R-63	L-35
9.888	190th St.	NW	R-64	L-35

COMPLETE STREETS DECISION DOCUMENT – Attachment S

Complete Streets Decision Document (CSDD)

1)	Is the project located entirely on a facility where bicyclists and pedestrians are legally prohibited and the project does not involve a shared use path, pedestrian/bicycle structure or work impacting a local road crossing or interchange? (For example, a project including freeway mainline and ramp work, not including the ramp connection with the minor road, where the project freeway segment legally prohibits bicyclists and pedestrians.)
	x NO - Proceed to Question 2 YES - Stop here. The project is exempt from further complete streets evaluation. Sign and attach to the Project Initiation Document (PID).
2)	Is the primary project purpose to address assets that are outside of the roadbed where pedestrian and bicycle travel is not affected, and proposed project will not affect future pedestrian and bicycle facilities? Examples may include culvert outfalls, storm water treatment facilities, bridge substructure or scour mitigation, planting or vegetation removal, retaining walls, etc.
	_x NO - Continue to Question 3 YES - Stop here. The project is exempt from further complete streets evaluation. Sign and attach to PID.
3)	Has a Transportation Planning Scoping Information Sheet (TPSIS) been completed for this project?
	NO – Proceed to Question 4x YES – Skip to Question 5 (Note: TPSIS is attached to the PID)
4)	Which of the following planning documents were consulted to determine bicycle, pedestrian or transit needs? Select all that apply and proceed to Question 5. a. District Active Transportation Planb. Other Caltrans or local/regional agency bike/ped/transit/safe routes to school plansc. ADA Transition Plan/Grievances (consult with the District ADA Coordinator)d. Corridor planning documentse. Other (list here)
5)	Based on the reviews completed in Question 4 or identified in the TPSIS, after a review of the roadway geometrics, or identified by the PDT, are there any bicycle, pedestrian, or transit needs, deficiencies or opportunities for improvement identified for the project location?
	NO – Provide brief description of findings: Stop here. The project meets the requirements for consideration of Complete Streets elements. Sign and attach to the PID. X YES – Describe them here and proceed to Question 6:
	45 Existing curb ramps will be brought up to standard and new 16 additional dual curb ramps at signalized intersections. Additionally, it will provide pedestrian push buttons at locations where they do not currently exist. Also bicycle and pedestrian circulation, as well as roadway accessibility for all users will be studied in more detail
	in the next phase

6) Based on the needs identified in Question 5, what would be the preferred complete streets elements to address those needs (e.g. road diet, separated bikeway, reconstructed sidewalk, etc.)? Resources include the Complete Streets Elements Toolbox, the Contextual Guidance for Bikeway Facility

Selection, the Bikeway Facility Selection Guidance Memorandum, etc. List them in the table below and

provide a rough estimated cost to construct preferred project complete streets elements (including right-of-way and support costs) and proceed to Question 7.

FACILITY TYPE	UNIT	QUANTITY	ESTIMATED TOTAL COST
Bicycle Facilities - Existing inlet grate	Ea	11	\$27,500
Bicycle Facilities – Marking & Striping	Ea	LS	\$250,000
Transit Facilities – Concrete bus Pad	Ea	44	\$1,245,200
ADA curb ramps	Ea	61	\$335,500

7)	Was there any known public and stakeholder opposition t identified for the project? Provide response and proceed			ete streets elements		
	_xNO YES – Describe the opposition position here:					
					_	
8)	Does the programmable project alternative/project scope identified in Question 6?	include	all the comple	te streets elements		
	NO - Proceed to Question 9X_ YES - Stop here. The project has met the requirements for consideration of complete streets elements. Sign and attach to PID.					
9)	Does the project include any of the complete streets elements that are identified in Question 6? Or are there any proposed incremental improvements related to the complete streets elements in Question 6? Provide response and proceed to Question 10.					
	NO – The programmable project alternative does r and therefore does not address identified needs for comp YES – List them here:					
	FACILITY TYPE	UNIT	QUANTITY	ESTIMATED TOTAL COST		
	e.g. Class III Bike Route- Segment [PM xx.x- xx.x]	LF				
	e.g. Standard 8-foot shoulder- Segment [PM xx.x- xx.x]	LF				
10)	Does the project funding have constraints that would precomplete streets elements into the project (For example, Provide response and proceed to Question 11. NOYES – Describe the constraints here:	cannot (combine fundii		?	
11)	Provide a rationale and justification for not including all the into the project: (Consider the engineering justification, rig				s,	

Prepared by:	
Gu-Ging Chu	
Yu-Ying Chu, P.E. Office of Project & Special Studies	
, .	
Concurred by:	
7.1: 54 11	5/10/2021
Mine Struhl Mine Struhl	Date
District Complete Streets Coordinator	Date
Oinm,	
CRAMON	6/22/2021
Paul Marquez	Date
Deputy District Director, Planning	
Alh	
feel Com	06/21/2021
Jerrel Kam	Date
Deputy District Director, Design or	
Division Chief, Design/Project Development	
dation of CSDD at PA&ED	
Does the project scope defined in the project apidentified in Question 6 or 9 of this CSDD and the	
	swer Questions 1 through 11) replacing the original
CSDD, obtain all certified and concurrence sign	atures below, and attach the superseding CSE
project approval document. VES – Certify there are no changes to the	e scope of complete streets elements with only
project engineer certification signature below or	
the project approval document.	
Certified by:	
Kin. Sana Wona	06/24/2024
	OOI LTI LULT
Kin Seng Wong Name, Project Engineer	 Date

Name District Complete Streets Coordinator	Date
Name Deputy District Director, Planning	Date
Name Deputy District Director, Design or	 Date
Division Chief, Design/Project Developmen dation of CSDD at PS&E Does the project scope designed in the plan	s, specifications and estimate include the complete
Does the project scope designed in the plane elements identified in Question 6 or 9 of the PA&ED revalidation and the project approv NO – Prepare a Superseding CSDD was approved at PA&ED revalidation, obtain to the Supplemental PR. If a Supplemental YES – Certify there are no changes that temporary bike and pedestrian facilities	s, specifications and estimate include the complete CSDD (or Superseding CSDD, if applicable) certifical document? (answer Questions 1 through 11) replacing the CSD all certified and concurrence signatures below, an PR is not required, place in the project history file. To scope of complete streets elements in the project during construction have been considered. Include elow on the CSDD that was approved at PA&ED

07- LA - 213 - PM 8.0/9.984 EA 34660K – EFIS 0718000076

Name District Complete Streets Coordinator	Date
Name Deputy District Director, Planning	Date
Name Deputy District Director, Design or Division Chief, Design/Project Development	Date

FIBER OPTIC SYSTEMS TABLE – Attachment T

The following are locations of proposed bus pads in conflict with State-owned fiber optics:

)				-
	Route	Location	Direction	Δ	Type of ITS Work
1	LA-213	N/O Crestwood St	SB	2.23	Relocate 1 pull box Relocate 250 linear feet of fiber optic conduit
7	LA-213	N/O Park Western Dr	SB	2.37	Relocate 2 pull boxes, Relocate 250 linear feet of fiber optic conduit
m	LA-213	N/O Trudie Dr/Capitol Dr	SB	2.48	Relocate 1 pull box, Relocate 250 linear feat of fiber optic conduit
4	LA-213	S/O Caddington Dr	NB	2.79	Relocate 1 pull box Relocate 250 linear feet of fiber optic conduit
73	LA-213	N/O Caddington Dr	SB	2.79	Relocate 1 pull box Relocate 250 linear feet of fiber optic conduit
9	LA-213	S/O Toscanini Dr	NB	2.97	Relocate 1 pull box Relocate 250 linear feet of fiber optic conduit
7	LA-213	N/O Delasonde Dr/Westmont Dr	SB	3.19	Relocate 2 pull boxes Relocate 250 linear feet of fiber optic conduit
				Total:	Relocate 9 Pull Boxes Relocate 1750 linear feet of fiber optic conduit *Replace 9000 linear feet of fiber optic cable

*In order to restore communication along this route, the 60-strand single-mode fiber optic cable from Summerland Ave (PM 2.02) to the splice vault on Avenida Aprenda (PM 3.45) would be replaced. A total of about 9000 LF of fiber optic cable.

Project Approval/Environmental Document (PA/ED) QA/IQA Routing Slip

Office Lead: (OPSS, Maintenance, Operations, Design)

Lvl	Reviewer	Initials	Date Concurred	Comments
	Project Engineer preparing the PA/ED Name: Kin Seng Wong			
	Senior preparing the PA/ED Name: Joseph Reynoza		6/23/24	Please see attached approval email.
	District Program Advisor(s) Name: Shawn Enjily for MD Musa		6/25/24	Please see attached approval email.
	District Asset Manager Name: Roger Yoh		6/24/24	Please see attached approval email.
	District Program (or SB-1) Manager Name: Sona Juharyan (Acting)		6/21/24	Please see attached approval email.
	Office Chief of Environmental Planning Name: Dawn E. Kukla		6/19/24	Please see attached approval email.
1st	Office Chief of R/W Name: Zolton Elo		6/26/24	Please see attached approval email.
	Office Chief preparing the PA/ED Name: Asadour Terterian (Simon Kuo - Acting)		6/25/24	Please see attached approval email.
	Office Chief of Design Name: Asadour Terterian (Simon Kuo - Acting)		6/25/24	Please see attached approval email.
	Name: Asadour Terterian (Simon Kuo - Acting) Office Chief of Maintenance Name: Shawn Enjily Office Chief of Operations, Mobility		6/25/24	Please see attached approval email.
	Name: Siew Mei Tan		6/25/24	Please see attached approval email.
	Project Manager Name: Carlos Loera (Acting)		6/26/24	Please see attached approval email.
	Office Chief of Project Management Name: Mehdi Salehinik		6/24/24	Please see attached approval email.
	PPM Assistant Division Chief (Project Management)* Name: Nancy Pe	NP NP	07/03/2024	
	PPM Assistant Division Chief (Programming) Name: Chan Kuoch (Acting)	SW	06/28/2024	
	Design Assistant Division Chief Name: Andy Liao (Acting)	AL AL	06/27/2024	
	PA/ED Lead Assistant Division Chief Name: Andy Liao (Acting)	AL AL	06/27/2024	
	Deputy District Director preparing the PA/ED Name: Greg Farr	OF.	07/03/2024	
2nd	Deputy District Director of Environmental Planning Name: Kelly Ewing-Toledo	KET	07/08/2024	
	Deputy District Director of Right-of-Way Name: Dan Murdoch	DEM	07/03/2024	Dem
	Deputy District Director of Design Name: Greg Farr Deputy District Director of Maintenance	TP.	07/03/2024	
	Name: Godson Okereke			
	Name: Rafael Molina			
	Deputy District Director of Program & Project Management* Name: Kelly Lamare (Acting)	KL	07/15/2024	
	Chief Deputy District Director* Name: Monica Benavides		10/04/2024	
3rd	District Director* Name: Gloria Roberts	Signature		

^{*}When PR is delegated then PD DDD (Lead Division) signs the document after all other reviewers in level 2 have approved and level 3 review is not required.

Kearns, Suzie@DOT

Subject:

From: Kearns, Suzie@DOT

Sent: Wednesday, June 19, 2024 4:47 PM

To: Reynoza, Joseph E@DOT; Yoh, Roger@DOT; Juharyan, Sona@DOT; Kukla, Dawn

E@DOT; Elo, Zoltan@DOT; Kuo, Simon S@DOT; Enjily, Shawn@DOT; Tan, Siew Mei@DOT; Musa, Md@DOT; Loera, Carlos@DOT; Salehinik, Mehdi@DOT

[REQUEST FOR OFFICE CHIEF/MANAGER APPROVAL] PROJECT REPORT FOR EA 346600

Attachments: 0734660_LA_213_PR_6-19-24.pdf

Importance: High

Follow Up Flag: Follow up Flag Status: Flagged

Tracking:	Recipient	Read	Response
	Reynoza, Joseph E@DOT	Read: 6/19/2024 5:52 PM	Approve with Comments: 6/23/2024 6:04 PM
	Yoh, Roger@DOT	Read: 6/20/2024 9:08 PM	Approve with Comments: 6/24/2024 9:03 PM
	Juharyan, Sona@DOT	Read: 6/19/2024 5:27 PM	Approve with Comments: 6/21/2024 2:56 PM
	Kukla, Dawn E@DOT		Approve with Comments: 6/19/2024 7:55 PM
	Elo, Zoltan@DOT	Read: 6/25/2024 12:44 PM	Approve: 6/26/2024 11:00 AM
	Kuo, Simon S@DOT		Approve: 6/25/2024 11:17 AM
	Enjily, Shawn@DOT		
	Tan, Siew Mei@DOT	Read: 6/19/2024 4:53 PM	Approve with Comments: 6/25/2024 11:53 AM
	Musa, Md@DOT		
	Loera, Carlos@DOT		Approve with Comments: 6/26/2024 8:57 AM
	Salehinik, Mehdi@DOT	Read: 6/20/2024 7:58 AM	Approve with Comments: 6/24/2024 3:56 PM

Greetings Office Chiefs, Program Managers, and Project Managers;

The attached is the Project Report (PR) for Project EA 07-346600. The Project Manager and Project Engineer would like to request for your <u>approval/concurrence of this PR before Monday 6/24/2024</u>, to facilitate the Level 2 review and approval of District Director.

Requested 1st Level QA/QC Approval/Concurrence from:

Senior Preparing the PA/ED	Joseph Reynoza
	Shawn Enjily for MD Musa
District Program Advisor	(on vacation until 6/27/24)
District Asset Manager	Roger Yoh

District Program (or SB-1) Manager	Sona Juharyan	
Office Chief of Environmental Planning	Dawn Kukla	
Office Chief of R/W	Zoltan Elo	
	Simon Kuo (Acting for	
Office Chief preparing the PA/ED	Asadour Terterian)	
Office Chief of Maintenance	Shawn Enjily	
Office Chief of Operations	Siew Mei Tan	
Project Manager	Carlos Loera	
Office Chief of Project Management	Mehdi Salehinik	

Project Info Summary:

• Pavement Capital Preventative Maintenance Project

• Design Manager: Joseph Reynoza, (213) 269-6121

• Project Manager: Carlos Loera (213) 266-6202

Project Limits	07-LA-213-PM 0.0/10.0	
Number of Alternatives	2	
	Current Cost Estimate:	Escalated Cost Estimate:
Capital Outlay Support	\$8,933,000	\$13,079,000
Capital Outlay Construction	\$38,015,400	\$45,443,000
Capital Outlay Right- of-Way	\$949,000	\$1,286,000
Funding Source	SHOPP (20.XX.201.121)	
Funding Year	2026	
Type of Facility	4 to 6 lane conventional highway	
Number of Structures	None	
SHOPP Project Output	42.87 lane miles CAPM, 478 LF Guard Rail, 64 ADA Curb Ramps, and others. For complete list of performance measures See Attachment M.	
Environmental Determination or Document	Categorical Exemption/Categorical Exclusion (CE/CE)	
Legal Description	In and near the cities of Los Angeles, Palos Verdes, Lomita, and Torrance, from West 25th Street to Route 405. Rehabilitate pavement, upgrade guardrail, install complete streets elements, including bike lanes and crosswalk improvements, and upgrade facilities to American with Disabilities Act (ADA) standards.	
Project Development Category	5	

Attached please find the PR for your QA/QC approval/concurrence via Email Voting Button.

- By approving this request via email voting buttons, you are certifying that you have reviewed the PR and are recommending approval of the PR by the Executive Office, contingent on minor changes & updates, if any.
- You are also authorizing the use of the Approval Tracking Document printed from this email request inlieu of the wet signatures on the Project Report Signature Routing.

Voting:

- 1. To approve/concur the attached PR:
 - a. Select the vote button above (Approve, or Approve with Comments)
 - b. Select (edit the response before sending), if you select (Approve with Comments) and want to include a note for the Project Engineer or the Project Manager
 - c. Send
- 2. To reject the attached PR with comments:
 - a. Select the vote button above (Reject with comments)
 - b. Select (edit the response before sending) and provide your comments
 - c. Send

Should you have any questions or require additional information, please call me at 213-266-3679.

Thank you,

Suzic Kearns

Transportation Engineer (Civil)
District 7 – Division of Design – Office of Design A

Mobile: 213-266-3729

Ornelas, Jesse@DOT

From: Enjily, Shawn@DOT

Sent: Wednesday, June 26, 2024 10:00 AM

To: Kearns, Suzie@DOT

Cc: Loera, Carlos@DOT; Reynoza, Joseph E@DOT; Wong, Kin Seng@DOT; Musa, Md@DOT

Subject: RE: Status of Level 1 Vote

Hi Suzie

Md does not need to vote, since the level 1 approval is for office chiefs.

Md is the Program advisor and my approval is covering his review and concurrence.,

Thanks (\odot)



Shawn Enjily

Office Chief, Maintenance Engineering-SHOPP

Cell- 213-266-6134 Regions Boundary Map:

http://sv07lamaint.ct.dot.ca.gov/Maint/MS%20Station%20&%20Boundary%20Directory/D7%20Mtce%20Area%20Map.pdf

GIS Boundary Maphttp://sv07lamaint.ct.dot.ca.gov/gis/MTCEBN

http://sv07lamaint.ct.dot.ca.gov/GIS/MTCEBN

Statement of Ongoing Contracts | Caltrans

Caltrans 2020-2024 Strategic Plan 2-Page Summary

D7 Bridge and Pavement Condition Web Map (ca.gov)

From: Kearns, Suzie@DOT <suzie.kearns@dot.ca.gov>

Sent: Wednesday, June 26, 2024 9:56 AM

To: Enjily, Shawn@DOT <shawn.enjily@dot.ca.gov>

Cc: Loera, Carlos@DOT <Carlos.Loera@dot.ca.gov>; Reynoza, Joseph E@DOT <joseph.reynoza@dot.ca.gov>; Wong, Kin Seng@DOT

<Kin.Seng.Wong@dot.ca.gov> Subject: RE: Status of Level 1 Vote

Good morning Shawn,

May I request an email with your vote/approval on behalf of Md Musa?

Thank you,

Suzic Kearns

Transportation Engineer (Civil)

District 7 - Division of Design - Office of Design A

Mobile: 213-266-3729

From: Enjily, Shawn@DOT < shawn.enjily@dot.ca.gov >

Sent: Tuesday, June 25, 2024 9:38 AM

To: Kearns, Suzie@DOT < suzie.kearns@dot.ca.gov>

Cc: Reynoza, Joseph E@DOT <joseph.reynoza@dot.ca.gov>; Loera, Carlos@DOT <Carlos.Loera@dot.ca.gov>; Elo, Zoltan@DOT <zoltan.elo@dot.ca.gov>; Kuo, Simon S@DOT <simon.kuo@dot.ca.gov>; Tan, Jackie C@DOT <jackie.tan@dot.ca.gov>; Abdelhameid,

Ezzeldin@DOT < Ezzeldin.Abdelhameid@dot.ca.gov>; Chau, Eric D (D7)@DOT < eric.d.chau@dot.ca.gov>

Subject: RE: Status of Level 1 Vote

Hi Suzie

Thank you.

Most of my comments have been addressed. I saw a couple of minor editing issues, but not crucial. Cost estimate was corrected and revised. Thank you.

You can consider this as an approval from my side.

Thanks (\odot)



Shawn Enjily

Office Chief, Maintenance Engineering-SHOPP

Cell- 213-266-6134 Regions Boundary Map:

http://sv07lamaint.ct.dot.ca.gov/Maint/MS%20Station%20&%20Boundary%20Directory/D7%20Mtce%20Area%20Map.pdf

GIS Boundary Maphttp://sv07lamaint.ct.dot.ca.gov/gis/MTCEBN

http://sv07lamaint.ct.dot.ca.gov/GIS/MTCEBN

Statement of Ongoing Contracts | Caltrans

Caltrans 2020-2024 Strategic Plan 2-Page Summary

D7 Bridge and Pavement Condition Web Map (ca.gov)

From: Kearns, Suzie@DOT < suzie.kearns@dot.ca.gov >

Sent: Tuesday, June 25, 2024 9:05 AM

To: Enjily, Shawn@DOT <shawn.enjily@dot.ca.gov>

Cc: Reynoza, Joseph E@DOT <joseph.reynoza@dot.ca.gov>; Loera, Carlos@DOT <Carlos.Loera@dot.ca.gov>; Elo, Zoltan@DOT

<zoltan.elo@dot.ca.gov>; Kuo, Simon S@DOT <simon.kuo@dot.ca.gov>

Subject: RE: Status of Level 1 Vote

Good morning Shawn,

Please see attached PR, revised estimate as well as responses to your comments.

Thank you,

Suzic Kearns

Transportation Engineer (Civil)

District 7 - Division of Design - Office of Design A

Mobile: 213-266-3729

From: Enjily, Shawn@DOT <shawn.enjily@dot.ca.gov>

Sent: Tuesday, June 25, 2024 8:37 AM

To: Loera, Carlos@DOT <Carlos.Loera@dot.ca.gov>; Elo, Zoltan@DOT <zoltan.elo@dot.ca.gov>; Kuo, Simon S@DOT

<simon.kuo@dot.ca.gov>

Cc: Kearns, Suzie@DOT <suzie.kearns@dot.ca.gov>; Reynoza, Joseph E@DOT <joseph.reynoza@dot.ca.gov>

Subject: RE: Status of Level 1 Vote

Hi

Please respond to my comments, and I will approve it.

Thanks 😊



Shawn Enjily

Office Chief, Maintenance Engineering-SHOPP

Cell- 213-266-6134

Regions Boundary Map:

http://sv07lamaint.ct.dot.ca.gov/Maint/MS%20Station%20&%20Boundary%20Directory/D7%20Mtce%20Area%20Map.pdf

GIS Boundary Maphttp://sv07lamaint.ct.dot.ca.gov/gis/MTCEBN

http://sv07lamaint.ct.dot.ca.gov/GIS/MTCEBN

D7 Bridge and Pavement Condition Web Map (ca.gov)

From: Loera, Carlos@DOT < Carlos.Loera@dot.ca.gov >

Sent: Tuesday, June 25, 2024 8:20 AM

To: Elo, Zoltan@DOT <zoltan.elo@dot.ca.gov>; Kuo, Simon S@DOT <simon.kuo@dot.ca.gov>; Enjily, Shawn@DOT

<shawn.enjily@dot.ca.gov>

Cc: Kearns, Suzie@DOT <<u>suzie.kearns@dot.ca.gov</u>>; Reynoza, Joseph E@DOT <<u>joseph.reynoza@dot.ca.gov</u>>

Subject: FW: Status of Level 1 Vote

Hi Team,

Please either Approve or Approve with Comments by Noon today. Design needs to incorporate your comments and submit for Level 2 Vote today. If there is anything I can do on my end to help expedite the process then please let me know.

Carlos Loera, PE Acting Project Manager Caltrans, District 7 (213) 266-6202

From: Kearns, Suzie@DOT < suzie.kearns@dot.ca.gov>

Sent: Tuesday, June 25, 2024 8:11 AM

To: Ferrer, Kevin@DOT < Kevin.Ferrer@dot.ca.gov>

Cc: Wong, Kin Seng@DOT < Kin.Seng.Wong@dot.ca.gov; Loera, Carlos@DOT < Carlos.Loera@dot.ca.gov

Subject: FW: Status of Level 1 Vote

Sorry sent to you by mistake.

Suzic Kearns

Transportation Engineer (Civil)

District 7 – Division of Design – Office of Design A

Mobile: 213-266-3729

From: Kearns, Suzie@DOT

Sent: Tuesday, June 25, 2024 8:10 AM

To: Ferrer, Kevin@DOT < Kevin.Ferrer@dot.ca.gov>

Cc: Wong, Kin Seng@DOT < Kin.Seng.Wong@dot.ca.gov>; Loera, Carlos@DOT < Carlos.Loera@dot.ca.gov>

Subject: Status of Level 1 Vote

Recipient	Read
Reynoza, Joseph E@DOT	Read: 6/19/2024 5:52 PM
Yoh, Roger@DOT	Read: 6/20/2024 9:08 PM
Juharyan, Sona@DOT	Read: 6/19/2024 5:27 PM
Kukla, Dawn E@DOT	
Elo, Zoltan@DOT	
Kuo, Simon S@DOT	
Enjily, Shawn@DOT	
Tan, Siew Mei@DOT	Read: 6/19/2024 4:53 PM
Musa, Md@DOT	
Loera, Carlos@DOT	
Salehinik, Mehdi@DOT	Read: 6/20/2024 7:58 AM

Suzic Kearns

Transportation Engineer (Civil)
District 7 – Division of Design – Office of Design A

Mobile: 213-266-3729

Ornelas, Jesse@DOT

From: Enjily, Shawn@DOT

Sent: Tuesday, June 25, 2024 9:38 AM

To: Kearns, Suzie@DOT

Cc: Reynoza, Joseph E@DOT; Loera, Carlos@DOT; Elo, Zoltan@DOT; Kuo, Simon S@DOT; Tan, Jackie C@DOT; Abdelhameid,

Ezzeldin@DOT; Chau, Eric D (D7)@DOT

Subject: RE: Status of Level 1 Vote

Hi Suzie

Thank you.

Most of my comments have been addressed. I saw a couple of minor editing issues, but not crucial. Cost estimate was corrected and revised. Thank you.

You can consider this as an approval from my side.

Thanks (\odot)



Shawn Enjily

Office Chief, Maintenance Engineering-SHOPP

Cell- 213-266-6134 Regions Boundary Map:

http://sv07lamaint.ct.dot.ca.gov/Maint/MS%20Station%20&%20Boundary%20Directory/D7%20Mtce%20Area%20Map.pdf

GIS Boundary Maphttp://sv07lamaint.ct.dot.ca.gov/gis/MTCEBN

http://sv07lamaint.ct.dot.ca.gov/GIS/MTCEBN

Statement of Ongoing Contracts | Caltrans

Caltrans 2020-2024 Strategic Plan 2-Page Summary

D7 Bridge and Pavement Condition Web Map (ca.gov)

From: Kearns, Suzie@DOT <suzie.kearns@dot.ca.gov>

Sent: Tuesday, June 25, 2024 9:05 AM

To: Enjily, Shawn@DOT <shawn.enjily@dot.ca.gov>

Cc: Reynoza, Joseph E@DOT <joseph.reynoza@dot.ca.gov>; Loera, Carlos@DOT <Carlos.Loera@dot.ca.gov>; Elo, Zoltan@DOT

<zoltan.elo@dot.ca.gov>; Kuo, Simon S@DOT <simon.kuo@dot.ca.gov>

Subject: RE: Status of Level 1 Vote

Good morning Shawn,

Please see attached PR, revised estimate as well as responses to your comments.

Thank you,

Suzic Kearns

Transportation Engineer (Civil)

District 7 – Division of Design – Office of Design A

Mobile: 213-266-3729

From: Enjily, Shawn@DOT < shawn.enjily@dot.ca.gov >

Sent: Tuesday, June 25, 2024 8:37 AM

To: Loera, Carlos@DOT < Carlos.Loera@dot.ca.gov >; Elo, Zoltan@DOT < zoltan.elo@dot.ca.gov >; Kuo, Simon S@DOT

<simon.kuo@dot.ca.gov>

Cc: Kearns, Suzie@DOT <suzie.kearns@dot.ca.gov>; Reynoza, Joseph E@DOT <joseph.reynoza@dot.ca.gov>

Subject: RE: Status of Level 1 Vote

Please respond to my comments, and I will approve it.





Shawn Enjily

Office Chief, Maintenance Engineering-SHOPP

Cell- 213-266-6134 Regions Boundary Map:

http://sv07lamaint.ct.dot.ca.gov/Maint/MS%20Station%20&%20Boundary%20Directory/D7%20Mtce%20Area%20Map.pdf

GIS Boundary Maphttp://sv07lamaint.ct.dot.ca.gov/gis/MTCEBN

http://sv07lamaint.ct.dot.ca.gov/GIS/MTCEBN

Statement of Ongoing Contracts | Caltrans

Caltrans 2020-2024 Strategic Plan 2-Page Summary

D7 Bridge and Pavement Condition Web Map (ca.gov)

From: Loera, Carlos@DOT < Carlos.Loera@dot.ca.gov >

Sent: Tuesday, June 25, 2024 8:20 AM

To: Elo, Zoltan@DOT <zoltan.elo@dot.ca.gov>; Kuo, Simon S@DOT <simon.kuo@dot.ca.gov>; Enjily, Shawn@DOT

<shawn.enjily@dot.ca.gov>

Cc: Kearns, Suzie@DOT <suzie.kearns@dot.ca.gov>; Reynoza, Joseph E@DOT <joseph.reynoza@dot.ca.gov>

Subject: FW: Status of Level 1 Vote

Hi Team,

Please either Approve or Approve with Comments by Noon today. Design needs to incorporate your comments and submit for Level 2 Vote today. If there is anything I can do on my end to help expedite the process then please let me know.

Carlos Loera, PE Acting Project Manager Caltrans, District 7 (213) 266-6202

From: Kearns, Suzie@DOT <suzie.kearns@dot.ca.gov>

Sent: Tuesday, June 25, 2024 8:11 AM

To: Ferrer, Kevin@DOT < Kevin.Ferrer@dot.ca.gov >

Cc: Wong, Kin Seng@DOT < Kin.Seng.Wong@dot.ca.gov>; Loera, Carlos@DOT < Carlos.Loera@dot.ca.gov>

Subject: FW: Status of Level 1 Vote

Sorry sent to you by mistake.

Suzic Kearns

Transportation Engineer (Civil)

District 7 – Division of Design – Office of Design A

Mobile: 213-266-3729

From: Kearns, Suzie@DOT

Sent: Tuesday, June 25, 2024 8:10 AM

To: Ferrer, Kevin@DOT < Kevin.Ferrer@dot.ca.gov >

Cc: Wong, Kin Seng@DOT < Kin.Seng.Wong@dot.ca.gov ; Loera, Carlos@DOT < Carlos.Loera@dot.ca.gov

Subject: Status of Level 1 Vote

Recipient	Read
Reynoza, Joseph E@DOT	Read: 6/19/2024 5:52 PM
Yoh, Roger@DOT	Read: 6/20/2024 9:08 PM
Juharyan, Sona@DOT	Read: 6/19/2024 5:27 PM
Kukla, Dawn E@DOT	
Elo, Zoltan@DOT	
Kuo, Simon S@DOT	
Enjily, Shawn@DOT	
Tan, Siew Mei@DOT	Read: 6/19/2024 4:53 PM
Musa, Md@DOT	
Loera, Carlos@DOT	
Salehinik, Mehdi@DOT	Read: 6/20/2024 7:58 AM

Suzic Kearns

Transportation Engineer (Civil)
District 7 – Division of Design – Office of Design A

Mobile: 213-266-3729

Final Audit Report 2024-07-12

Created: 2024-06-27

By: Jesse Ornelas (s157087@dot.ca.gov)

Status: Canceled / Declined

Transaction ID: CBJCHBCAABAAMpWn68IR5h7q354n4sPxIVxiNoZAHgWB

"EA 34660: Project Report Approval" History

- Document created by Jesse Ornelas (s157087@dot.ca.gov) 2024-06-27 11:47:36 PM GMT- IP address: 149.136.33.247
- Document emailed to Chan Kuoch (chan.kuoch@dot.ca.gov) for approval 2024-06-28 0:18:27 AM GMT
- Document emailed to Andy Liao (andy.liao@dot.ca.gov) for approval 2024-06-28 0:18:27 AM GMT
- Document emailed to Nancy Pe (nancy.n.pe@dot.ca.gov) for approval 2024-06-28 0:18:27 AM GMT
- Email viewed by Andy Liao (andy.liao@dot.ca.gov) 2024-06-28 - 0:24:44 AM GMT- IP address: 216.165.250.117
- Email viewed by Nancy Pe (nancy.n.pe@dot.ca.gov)
 2024-06-28 2:31:00 AM GMT- IP address: 149,136,33,248
- Email viewed by Chan Kuoch (chan.kuoch@dot.ca.gov) 2024-06-28 5:44:06 AM GMT- IP address: 146,75,146.1
- Document approved by Andy Liao (andy.liao@dot.ca.gov)

 Approval Date: 2024-06-28 5:57:08 AM GMT Time Source: server- IP address: 216.165.250.117
- Document approved by Chan Kuoch (chan.kuoch@dot.ca.gov)

 Approval Date: 2024-06-28 3:22:14 PM GMT Time Source: server- IP address: 149.136.33.251
- Email viewed by Nancy Pe (nancy.n.pe@dot.ca.gov) 2024-06-29 - 2:43:37 PM GMT- IP address: 172.226.3.176
- Document approved by Nancy Pe (nancy.n.pe@dot.ca.gov)

 Approval Date: 2024-07-03 7:31:52 PM GMT Time Source: server- IP address: 149.136.33.253



- Document emailed to Kelly Ewing-Toledo (kelly.ewing-toledo@dot.ca.gov) for approval 2024-07-03 7:32:05 PM GMT
- Document emailed to Dan Murdoch (dan.murdoch@dot.ca.gov) for signature 2024-07-03 7:32:05 PM GMT
- Document emailed to Kelly Lamare (kelly.m.lamare@dot.ca.gov) for approval 2024-07-03 7:32:05 PM GMT
- Document emailed to Greg Farr (greg.farr@dot.ca.gov) for signature 2024-07-03 7:32:06 PM GMT
- Email viewed by Greg Farr (greg.farr@dot.ca.gov) 2024-07-03 8:19:58 PM GMT- IP address: 149,136,33,250
- Document e-signed by Greg Farr (greg.farr@dot.ca.gov)

 Signature Date: 2024-07-03 8:26:04 PM GMT Time Source: server- IP address: 149.136.33.250
- Email viewed by Dan Murdoch (dan.murdoch@dot.ca.gov) 2024-07-03 9:33:23 PM GMT- IP address: 172.226.7.8
- Document e-signed by Dan Murdoch (dan.murdoch@dot.ca.gov)

 Signature Date: 2024-07-03 9:36:05 PM GMT Time Source: server- IP address: 174,243,144,246
- Email viewed by Kelly Lamare (kelly.m.lamare@dot.ca.gov) 2024-07-05 1:46:45 PM GMT- IP address: 172.226.7.28
- Email viewed by Kelly Ewing-Toledo (kelly.ewing-toledo@dot.ca.gov) 2024-07-08 6:24:50 PM GMT- IP address: 149.136.33.251
- Document approved by Kelly Ewing-Toledo (kelly.ewing-toledo@dot.ca.gov)

 Approval Date: 2024-07-08 6:25:53 PM GMT Time Source: server- IP address: 149,136,33,251
- Document canceled by Jesse Ornelas (s157087@dot.ca.gov) 2024-07-12 8:10:57 PM GMT- IP address: 149.136.33.253



Final Audit Report 2024-07-16

Created: 2024-07-15

By: Jesse Ornelas (s157087@dot.ca.gov)

Status: Canceled / Declined

Transaction ID: CBJCHBCAABAAM-YrzwuBfjhFWoypInoPIQ3p743upe5a

"EA 34660: Project Report Approval" History

Document created by Jesse Ornelas (s157087@dot.ca.gov) 2024-07-15 - 10:58:13 PM GMT- IP address: 149.136.33.249

Document emailed to Kelly Lamare (kelly.m.lamare@dot.ca.gov) for approval 2024-07-15 - 11:13:53 PM GMT

Email viewed by Kelly Lamare (kelly.m.lamare@dot.ca.gov) 2024-07-15 - 11:31:19 PM GMT- IP address: 149,136,33,249

Document approved by Kelly Lamare (kelly.m.lamare@dot.ca.gov)

Approval Date: 2024-07-15 - 11:45:17 PM GMT - Time Source: server- IP address: 149.136.33,249

Document emailed to Monica Benavides (monica.benavides@dot.ca.gov) for approval 2024-07-15 - 11:45:31 PM GMT

Document canceled by Jesse Ornelas (s157087@dot.ca.gov) 2024-07-16 - 4:43:27 AM GMT- IP address: 149.136.33.249



Signa	tu	re	:
-------	----	----	---

Email:

Final Audit Report 2024-09-19

Created: 2024-08-09

By: Jesse Ornelas (s157087@dot.ca.gov)

Status: Canceled / Declined

Transaction ID: CBJCHBCAABAAOkS5GiS62xjL5-d_3v3ndLygEfz4fJsh

"EA 34660: Project Report Approval" History

Document created by Jesse Ornelas (s157087@dot.ca.gov) 2024-08-09 - 5:18:20 PM GMT- IP address: 149.136.33.252

Document emailed to Monica Benavides (monica.benavides@dot.ca.gov) for approval 2024-08-09 - 5:23:47 PM GMT

Email viewed by Monica Benavides (monica.benavides@dot.ca.gov)

Email viewed by Monica Benavides (monica.benavides@dot.ca.gov) 2024-08-19 - 5:53:49 AM GMT- IP address: 104,28,85,120

Document declined by Monica Benavides (monica.benavides@dot.ca.gov)

Decline reason: Please address my comments sent to the SFP. THank you.

2024-09-19 - 6:35:56 PM GMT- IP address: 149.136.17.253



Final Audit Report 2024-10-09

Created: 2024-09-24

By: Jesse Ornelas (s157087@dot.ca.gov)

Status: Signed

Transaction ID: CBJCHBCAABAA7zSFiQRrDuB1dRvg9NOYhOMYMt986CGg

"EA 34660: Project Report Approval" History

- Document created by Jesse Ornelas (s157087@dot.ca.gov) 2024-09-24 9:13:21 PM GMT- IP address: 149.136.33.253
- Document emailed to Monica Benavides (monica.benavides@dot.ca.gov) for approval 2024-09-24 9:31:56 PM GMT
- Email viewed by Monica Benavides (monica.benavides@dot.ca.gov)
- Email viewed by Monica Benavides (monica.benavides@dot.ca.gov)
 2024-10-04 3:27:08 AM GMT- IP address: 172,226,186,19
- Document approved by Monica Benavides (monica.benavides@dot.ca.gov)
 Approval Date: 2024-10-04 7:32:08 PM GMT Time Source: server- IP address: 149.136.17.250
- Document emailed to Gloria Roberts (gloria.roberts@dot.ca.gov) for signature 2024-10-04 7:32:21 PM GMT
- Email viewed by Gloria Roberts (gloria.roberts@dot.ca.gov) 2024-10-09 12:54:29 PM GMT- IP address: 104.28.85.131
- Document e-signed by Gloria Roberts (gloria.roberts@dot.ca.gov)

 Signature Date: 2024-10-09 12:57:50 PM GMT Time Source: server- IP address: 174,243,155,195
- Agreement completed.
 2024-10-09 12:57:50 PM GMT

